# COMBINED PRELIMINARY ASSESSMENT/SITE INSPECTION REPORT

Former Hulett Lagoon Site Camdenton, Missouri

March 30, 1999






Missouri Department of Natural Resources Division of Environmental Quality Hazardous Waste Program

### **NARRATIVE**

## COMBINED PRELIMINARY ASSESSMENT/SITE INSPECTION REPORT

### Former Hulett Lagoon Site Camdenton, Missouri

March 30, 1999





Missouri Department of Natural Resources Division of Environmental Quality Hazardous Waste Program

#### **TABLE OF CONTENTS**

1.0	Introdu	ction	1
2.0	Cito Do	a printing	4
2.0	2.1	scriptionLocation	ا 4
	2.1	Site Description	
	2.2	·	
	2.3	Operational History General Overview of Hulett Lagoon	د د
		Ownership History of Facility at 179 Sunset Drive	
		Operational History of 179 Sunset Drive Facility	د 1
		Operational History/Regulatory Compliance of Hulett Lagoon	
		DNR Inspection - September 7, 1978	
		DNR Geologic Investigation - September 12, 1978	5 ء
		Lagoon Sampling in 1984  Construction of Sundstrand's Pretreatment Plant in 1986	۰۰۰۰۰ ک
		Construction Permit for Lagoon to Replace Hulett Lagoon	
		Pretreatment Monitoring Report - April 30, 1987	۰۰۰۰۰ ء
	2.4	Hulett Lagoon ClosureSite History and Previous Investigations	
	2.4	Preliminary Assessment/Site Inspection at 179 Sunset Drive	0
		Facility	٥
		RCRA Corrective Action at 179 Sunset Drive Facility	Ο Ω
		Referral of Former Hulett Lagoon to Superfund Section	
	2.5	Waste Characteristics	
	2.5	Trichloroethene	
		The horoetherie	J
3.0	Waste/	Source Sampling	10
•••	3.1	Previous Sampling	
	3.2	PA/SI Sampling	
	3.3	PA/SI Analytical Results	
	3.4	Conclusions	
	•		,
4.0	Ground	water Pathway	14
	4.1	Hydrogeologic Setting	
		Stratigraphic Units	
		Aquifers	
		Aquifer Discontinuities	
		Wellhead Protection Area	
		Karst Features	
	4.2	Groundwater Targets	
		Public Drinking Water Wells	
		Private Drinking Water Wells	
	4.3	Previous Sampling	
		Monitoring Wells	21
		Public Drinking Water	21

#### TABLE OF CONTENTS, Cont'd.

	4.4	Private Wells	23
		Monitoring Wells 1 & 2  Monitoring Wells 3 & 4  Monitoring Well 5  Public Wells	23 23 24
	4.5	Analytical Results  Monitoring Wells  Public and Private Drinking Water Wells	24 25
	4.6	Conclusions	
5.0	Surface 5.1 5.2 5.3	Water Pathway Hydrologic Setting Surface Water Targets Surface Water Conclusions	26 28
6.0	Soil Exp 6.1 6.2 6.3	Posure and Air Pathways Physical Conditions Soil and Air Targets Soil and Air Conclusions	29 29
7.0	Summa	ry and Conclusions Waste/Source Sampling Groundwater Surface Water Soil and Air	31 31 32
8.0	Recomm	mendations	32
Refe	erences .		34
Tabl			
	Moo Table 2 Table 3 Table 4 Table 5 Forn Table 6	<ul> <li>Selected Analytical Results from Soil Samples Collected by Dames &amp; Fre in Hulett Lagoon on October 11, 1996</li> <li>Analytical Results from Soil Samples Collected In/Near the Hulett Lago</li> <li>Stratigraphic Column for Former Hulett Lagoon, Camden County</li> <li>Public Wells Within a 4-Mile Radius of the Former Hulett Lagoon Site</li> <li>Private Wells Registered with DNR Within a 4-Mile Radius of the ner Hulett Lagoon Site</li> <li>TCE Concentrations in Modine Groundwater Monitoring Wells 1-5</li> <li>TCE Results from Sampling at City of Camdenton's Public Drinking</li> </ul>	on13 18 20 20
			22

#### **TABLE OF CONTENTS, Cont'd.**

Table 8: Selected Groundwater Results from PA/SI Sampling at Modine  Monitoring Wells 1-5	.25
Table 9: Selected Groundwater Results from PA/SI Sampling at Public and Private Groundwater Wells	
Table 10: Estimated Population Within a 4-Mile Radius	.30
Appendix A, Figures Figure 1: Site Location Map, Former Hulett Lagoon Site, Camden County, MO Figure 2: Hulett Lagoon Site, Soil Sampling Locations Figure 3: Hulett Lagoon Site, Well Sampling Locations	

DATE: March 30, 1999

PREPARED BY: Valerie H. Wilder

Missouri Department of Natural Resources

SITE: Former Hulett Lagoon

**Camden County** 

C.A. NUMBER: V997381-98-0

EPA ID. NUMBER: N/A

#### 1.0 INTRODUCTION

Under the authority of the Comprehensive Environmental Response, Compensation and Liability Act of 1980 (CERCLA) and the Superfund Amendments and Reauthorization Act of 1986 (SARA), the Missouri Department of Natural Resources (DNR), through a cooperative agreement with the U.S. Environmental Protection Agency (EPA), conducted a combined Preliminary Assessment/Site Inspection (PA/SI) at the Former Hulett Lagoon site in Camden County, Missouri. The purpose of this investigation was to collect sufficient information concerning conditions at the site to assess the threat posed to human health and the environment, to determine the need for additional investigation under CERCLA/SARA or other authority, and if appropriate, support ranking the site using the Hazard Ranking System (HRS) for proposal to the National Priorities List (NPL). The scope of the investigation included review of previous file information, sampling of waste and environmental media to evaluate and document HRS factors, and collecting additional non-sampling information. Investigations included site visits on December 1, 16, 1998 and site sampling on January 6-7, 21,1999. The PA/SI was initiated on October 27, 1998.

#### 2.0 SITE DESCRIPTION

#### 2.1 Location

The Former Hulett Lagoon site is the location of a closed wastewater lagoon. The lagoon is located in the City of Camdenton, 500 feet northeast of the intersection of Dawson Road and Sunset Drive (Reference 3). Geographic coordinates for the site are 38°00'41.1" north latitude and 92°45'17.0" west longitude, as measured using the Garmin 12LX Global Positioning System (Reference 4). The lagoon is in the Southwest Quarter (SW 1/4) of the Southwest Quarter (SW 1/4) of Section 24, Township 38 North, Range 17 West in Camden County. Figure 1 is a site location map (Reference (Reference 3).

The site can be accessed from the intersection of U.S. Highway 54 and State Route 5 in Camdenton by taking State Route 5 northwest for 0.3 of a mile to East Mulberry; take a left onto East Mulberry and the first right onto West Mulberry. When the paved portion of West Mulberry curves to the left, continue straight onto a gravel driveway that leads behind the Ron Hulett Chev-Olds-Buick Jeep/Eagle Automobile Dealership. Stay to the left on a gravel road that leads down to the lagoon. This road is not regularly maintained; there are several severe ruts caused from washouts (Reference 5).

The Camdenton area receives an average of 42.32 inches of precipitation annually, and an average of 19 inches of snowfall annually (Reference 6, p. 2). The 2-year 24-hour rainfall estimated at 3.5 inches (Reference 7). The average daily temperature during the summer months is 77° F, and the average winter temperature is 35° F (Reference 6, p. 2). The average wind speed and direction is approximately 10 miles per hour from the south (Reference 8, p. 74).

#### 2.2 Site Description

The former Hulett lagoon is a closed wastewater sewage lagoon operated by the City of Camdenton from 1961 to 1988. The lagoon was approximately one acre in size (Reference 9, p. 12). Photos 1 and 2 were taken in October 1974 when the lagoon was operating. Photo 1 shows the north side of the lagoon where an influent pipe from a city sewer line entered the lagoon. Photo 2 shows the south side of the lagoon where an influent pipe from an industrial facility entered the lagoon. The wooden catwalk, also shown in photo 2, extended into the lagoon and supported the outlet pipe, which ran under the catwalk, and could be raised and lowered with a crank handle (the red apparatus on the end of the catwalk railing). More detailed operating conditions are discussed in the next section. A dirt road ran along the berm and surrounded the lagoon, as shown in photos 1 and 2.

In 1989, the lagoon was closed; the water was drained and the sludge was removed (Reference 9, p. 12). Photo 3 was taken during the dewatering process. The site is currently an open field area with grassy vegetation (Photos 4, 6-8). Remnants of the former berm and the road that surrounded the lagoon are still visible. The lagoon area is generally flat with surface runoff flowing to the northwest and entering an intermittent drainage that travels to the west. There is a monitoring well (MW), installed in July 1998, located just outside what would have been the southwest edge of the berm of the lagoon. This is known as MW-5 (Reference 5).

The lagoon is located in a mixed residential/commercial area of Camdenton. It is bordered on the north by an apartment complex (Photo 8); on the west by a strip of woods about 500 feet wide with Dawson Road on the other side; on the east by woods (Photo 7); and on the south by a strip of woods (Photo 6) and then residents. Access to the lagoon area is not restricted. There is no fencing or gates. The Ron Hulett car dealership personnel have

reported unauthorized dumping in the wooded area behind their facility that borders the road leading down to the lagoon (Reference 5).

#### 2.3 Operational History

#### General Overview of Hulett Lagoon

The City of Camdenton, Missouri has owned the former Hulett lagoon property since at least 1961 and retains ownership today. The lagoon was constructed in 1961 under the State of Missouri Grants Program. The lagoon was constructed of clay, and its berms were approximately 25 feet wide and 15 feet high (Reference 9, p. 12). The lagoon was named and most commonly referred to as the Hulett Lagoon due to its proximity to the Ron Hulett automobile dealership that is located at 249 N. Highway 5 (Reference 5). The lagoon was also referred to as the Factory Lagoon and Camdenton Lagoon #3 (Reference 10).

The Hulett lagoon was in operation from 1961 until its closure in late 1989. It was one of five municipal lagoons that serviced the City of Camdenton, however, it was the only lagoon that received industrial effluent in addition to domestic sewage. From 1967 through 1986 a nearby manufacturing facility released untreated wastewater and storm water into the lagoon through a series of "mudpits", or sumps, via a storm sewer. In 1986, the facility installed a pretreatment wastewater system that replaced the mudpits and lagoon system (References 9, p. 12; 11, p. 1).

The facility is located approximately 1,000 feet southeast of the lagoon at 179 Sunset Drive. Heat transfer components for commercial and automotive industries are manufactured at the facility. The untreated wastewater was known to have contained several hazardous waste streams including corrosive waste, wastewater treatment sludges from electroplating operations, and waste oil. In addition, residual contaminants associated with degreasing operations, including TCE, was discharged into the mud pits and ultimately into the Hulett lagoon (References 9, p. 12; 11, p. 1; 16, p. 8).

#### Ownership History of Facility at 179 Sunset Drive

The 179 Sunset Drive property was originally held by Dawson Metal Products, Inc., a Kansas Corporation ("Dawson-Kansas"), pursuant to a lease dated November 28, 1966 between Dawson-Kansas and the Camdenton Industrial Development Corporation. The lease had a term of ten years, which is believed to have commenced July 1, 1967, with an option for Dawson-Kansas to purchase (Reference 12, p. 3).

On June 12, 1972, Dawson Metal Products, Inc. was issued a Certificate of Incorporation in the State of Delaware (Reference 13). In 1972 Sundstrand Corporation incorporated Dawson Metal Products, Inc., a Delaware Corporation ("Dawson-Delaware"), as a wholly owned subsidiary of Sundstrand Corporation. On June 29, 1972, Dawson-Delaware acquired the business and assets of Dawson-Kansas. In connection with the acquisition Dawson-Delaware, by way of assignment, acquired a leasehold interest in the 179 Sunset Drive property (Reference 12, p. 3). On September 25, 1972, Dawson Metal Products, Inc.

(the Delaware Corporation) was authorized as a Foreign Corporation in the State of Missouri to carry on the business of sale and distribution of air conditioning equipment and related parts (Reference 14).

On May 25, 1977 Dawson Metal Products, Inc. (the Delaware Corporation) changed its corporate name in the State of Missouri to Sundstrand Tubular Products, Inc. (Reference 15).

On August 24, 1990, Sundstrand agreed to sell the business and assets of Sundstrand Tubular Products, Inc. to Modine Heat Transfer, Inc., a wholly owned subsidiary of Modine Manufacturing Company, a Wisconsin based corporation that operates and conducts business in the state of Missouri. This transaction was closed on October 18, 1990 (References 16, pp. 3, 4; 12, p. 3).

On November 27, 1990, Sundstrand Tubular Products, Inc. changed its name to Sundstrand Camdenton, Inc (Reference 12, p. 3). On April 18, 1991, Sundstrand Tubular Products, Inc., a Foreign Corporation, was formally withdrawn from the State of Missouri (Reference 17). On March 15, 1994 Sundstrand Camdenton, Inc. was liquidated (Reference 12, p. 3).

On April 1, 1997, Modine Heat Transfer, Inc. merged with Modine Manufacturing Company; thus, changing its name to Modine Manufacturing Company. Modine is the current owner/operator of the facility (Reference 16, pp. 3, 4).

#### Operational History of 179 Sunset Drive Facility

The facility at 179 Sunset Drive has always been used to manufacture air-conditioning coils and feeder parts from aluminum and copper tubing. According to Sundstrand personnel, the manufacturing process flowed as follows:

- copper and aluminum tubing were fed from rolls to benders to form U shapes and then cut off;
- parts were then immersed in alkaline cleaning lines to remove oil and chips;
- parts were degreased to remove any remaining oil;
- clean parts were assembled and small U shaped copper tubing and aluminum tubing ends were brazed to assembled cores using manual and automatic brazing systems;
- the assembled heat transfer components were degreased and/or alkaline cleaned and then tightness tested using refrigerant; and
- finally, the components were then painted if required by the customer and packaged for shipment (Reference 12, p. 4)

The manufacturing process consisted of aluminum etching, and a small amount of chromium electroplating (Reference 11, p. 2). According to an Environmental Site

Assessment conducted in November 1991 for Modine Manufacturing Company, the facility generated TCE waste during degreasing operations from the early 1970's to December 1990. In December 1990, they began using 1,1,1-trichloroethane (TCA) for degreasing operations (Reference 18, p. 1).

Four mudpits (sumps) were utilized by the facility from 1967 to 1986. The mudpits were connected by a six-inch steel line that delivered storm water (from 1979 to 1983, eliminated in 1983), boiler water and cleaning line waste to the Hulett lagoon. The mudpits were located adjacent to the manufacturing building on the west side. Each mudpit consisted of a 4' x 4' x 4' cement sump. Each sump received the previous sumps' wastes until discharged into the sewer. The southern most mudpit, #4, was an open pit that collected boiler water and storm water. Mudpit #3 collected aluminum cleaning line waste and storm water from mudpit #4. Mudpit #1 collected copper cleaning line waste in addition to aluminum cleaning line waste and storm water from the first two mudpits. Hulett lagoon potentially received hazardous waste from the facility's four mudpits and associated piping, identified by the following hazardous waste codes: F006 (wastewater treatment sludges from electroplating), D002 (corrosive waste) and D098 (waste oil). In addition, residual contaminants associated with degreasing operations, including TCE, did go through collection lines into the mud pits and ultimately into the Hulett lagoon (References 9, p. 13; 16, p. 8).

#### Operational History/Regulatory Compliance of Hulett Lagoon

The Hulett Lagoon operated with a National Pollutant Discharge Elimination System (NPDES) Permit (MO-0048577) issued under the Clean Water Act by the DNR's Water Pollution Control Program (WPCP) (Reference 10). The WPCP database shows the permit issued July 1985, although it is likely the permit was actually issued earlier. The permit was terminated February 29, 1988.

#### DNR Inspection - September 7, 1978

In September 1978, DNR personnel conducted an inspection of the operation and condition of the wastewater treatment facilities serving the City of Camdenton. The inspector noted that the Hulett Lagoon had a large problem with its industrial influent. The sewage from Sundstrand was entering the lagoon at the south end, which was the same end that the lagoon's discharge pipe was located. The retention time for the industrial waste was far too short a period to treat the waste. To correct the problem, it was recommended that the location of the influent pipe from Sundstrand be moved to the north end of the lagoon, or the sewage line be tied in to the other influent line already at the north end. The inspector also noted that the strength of the Sundstrand industrial sewage entering the Hulett Lagoon was apparently too great for the facility to handle. It was recommended to the city that they enforce their sewer use ordinance to prevent misuse of the sewers and sewage treatment facilities (Reference 19).

#### DNR Geologic Investigation - September 12, 1978

On September 12, 1978 DNR personnel from the Division of Geology and Land Survey (DGLS) conducted an investigation for an Engineering Geologic Report on the Collapse Potential of Camdenton Lagoons. The inspector noted that the problems at the Hulett lagoon appeared to be design related and not geologic. Like the previous inspectors, DGLS personnel noted the short circuiting problem. They observed effluent from the metal fabricating plant bubbling up approximately 40 feet from the discharge pipe. There was an area of thick floating effluent. An open channel existed directly from the inlet pipe to the discharge pipe. Discharge from the lagoon was dark green in color with thick white foam floating on the surface (similar to that in Photo 2) (Reference 20).

#### Lagoon Sampling in 1984

On May 22, 1984 the City of Camdenton collected samples of the Hulett lagoon water, Sundstrand's influent to the lagoon, housing influent to the lagoon, effluent from the lagoon, and water near Lake of the Ozarks. Results showed 41 parts per billion (ppb) TCE in the Sundstrand influent and 28 ppb TCE in the effluent from the lagoon (Reference 21).

On July 19, 1984 additional samples of Sundstrand's effluent and lagoon water were collected. This Sundstrand effluent sample showed 4,900 ppb TCE in addition to 7,600 ppb, total chromium, 29,000 ppb total copper, and 1,400 ppb total zinc. The sample from the lagoon showed 500 ppb TCE, 500 pbb total chromium, 200 ppb hexavalent chromium, 4100 ppb total copper and 230 ppb total zinc (Reference 22).

#### Construction of Sundstrand's Pretreament Plant in 1986

Sundstrand and the City of Camdenton joined efforts in 1986 to obtain a Community Development Betterment Grant (CDBG) from the state to construct a pretreatment plant at the Sundstrand facility. The plant was completed and on line as of April 14, 1986. The plant still operates today (Reference 23).

#### Construction Permit for Lagoon to Replace Hulett Lagoon

On September 23, 1986, DNR issued the City of Camdenton a Construction Permit for sewers, force mains and lift stations for transport of waste to the C.P. White Lagoon. The construction permit stated that these facilities were designed to allow for elimination of the existing factory lagoon (Hulett Lagoon) (Reference 24).

#### Pretreatment Monitoring Report - April 30, 1987

At the request of DNR's WPCP, a pretreatment monitoring survey was conducted of the industrial wastewater discharge of the Sundstrand Tubular Products factory. On April 30, 1987, DNR's Environmental Services Program (ESP) collected a grab sample of the effluent from the treatment system discharge weir. The sample was analyzed for cyanide, total metals (silver, cadmium, chromium, copper, hexavalent chromium, nickel, lead, zinc). The sample was also supposed to be analyzed for volatile organic compounds (VOCs), however, there were no results for VOCs due to analytical error. Results showed

chromium at 2,700 ppb, copper at 890 ppb, hexavalent chromium at 180 ppb, nickel at 50 ppb, and zinc at 110 ppb (Reference 25).

#### **Hulett Lagoon Closure**

In 1988, the City of Camdenton began closure of the Hulett Lagoon pursuant to an Industrial Development Grant overseen by DNR's WPCP. As per DNR guidelines for closing out municipal lagoons, sampling and analysis of the sludge in the lagoon was limited to metals and other parameters such as total solids. High levels of chromium, lead, and nickel were detected (Reference 26). DNR offered the City officials several options to consider in completing the closure of the lagoon (Reference 27). The option chosen and implemented by the city was subsurface application of the sludge from the lagoon to a sludge disposal site owned by the city. DNR approved the sludge disposal plan on February 22, 1989 (Reference 28).

The city's engineering consultant, Missouri Engineering Corporation, supervised the lagoon closure project. In June 1989, McCormick Gravel & Excavating of Versailles, Missouri was awarded the contract for the removal, stockpiling and disposal of sludge from the lagoon. The contract included lagoon dewatering, preparation, transportation, and stockpiling of the sludge, as well as disposal by land application at chosen site at the Camdenton Memorial Airport (CMA), four miles southeast of Camdenton (References 29; 30).

The specifications called for the contractor to pump the water from the lagoon and discharge it into the existing sewer manhole approximately 100 feet away (Reference 29). The process of removing the sludge at the lagoon began on July 11, 1989 and was completed sometime in late September 1989. Lime was added to the sludge at the lagoon to raise the pH and immobilize the metals. The project contract was originally written with an estimate of 1,500 cubic yards of sludge to be removed. However, due in part to an unusually high amount of rain during the removal process, the sludge did not dry out and shrink, as it should have. In addition, each time it would rain, the rain would cause the sludge to be spread across the lagoon contaminating more soil. The lagoon had to be pumped again and the sludge allowed to dry. A small amount of soil then had to be removed along with the sludge. When that portion of the project was completed, an estimated 2,395 cubic yards of sludge had been removed (References 31; 32; 33). The berms of the lagoon were turned in and mixed with a 1 to 1 ratio (Reference 34). No soil was brought in for the mixing. Some soil from the hillside southeast of the lagoon was scraped in to fill the void (Reference 5).

The sludge was deposited at the CMA from July through December 1989. The area at the CMA where the sludge was disposed of is being investigated as a separate site - the Camdenton Sludge Disposal Area. A Combined Preliminary Assessment/Site Inspection is being conducted at the site, and will be completed by April 1999.

#### 2.4 Site History and Previous Investigations

#### Preliminary Assessment/Site Inspection at 179 Sunset Drive Facility

In 1992, DNR conducted a PA and an SI of the facility at 179 Sunset Drive under the name Sundstrand site (MOD062439351). The investigations were initiated due to a complaint filed with DNR alleging that 4,500 gallons of TCE had been spilled at the facility. Neither the PA nor the SI included any off-site investigations of the former lagoon or sludge disposal area (References 35; 36).

In addition to the PA and SI conducted by DNR, there were several other investigations conducted at the Modine facility during that time period by EPA contractors and Modine consultants. In general, all of the investigations documented and/or confirmed the presence of chlorinated solvents, including TCE, in the soils and groundwater at the facility. At that time, the DNR determined that oversight authority of the facility was most appropriate under the Resource Conservation and Recovery Act (RCRA).

#### RCRA Corrective Action at 179 Sunset Drive Facility

Modine Manufacturing Company is currently negotiating a Corrective Action Abatement Order on Consent (AOC) through the Permits Section of DNR's Hazardous Waste Program (HWP). The objectives of the AOC include investigation to determine the nature and extent of any release of hazardous waste at the facility and to remediate any releases in order to protect human health and the environment (Reference 16). There have already been several investigations and a certain amount of remedial activities conducted by Modine at the facility and in the surrounding area. Detailed information regarding a subsurface investigation conducted at the Hulett lagoon in 1996 is included in Section 3.1 Previous Waste/Source Sampling. More information regarding groundwater sampling conducted in the area is included in Section 4.2 Previous Groundwater Sampling.

#### Referral of Former Hulett Lagoon to Superfund Section

On September 8, 1998 the Permits Section of the HWP formally referred investigation of the former Hulett Lagoon to the Superfund Section of the HWP. Investigation of the Hulett Lagoon is not included in the AOC with Modine due to the fact that, in addition to receiving wastewater from the facility at 179 Sunset Drive, the lagoon also received domestic sewage from the surrounding residences. A dye trace study of the City of Camdenton's sewer system performed by DNR's DGLS on August 5, 1998, verified that facility wastewater mixes with domestic sewage prior to entering city property (Reference 37).

According to 40 CFR 261.4(a)(1), domestic sewage and any mixture of domestic sewage and other wastes that pass through a sewer system to a publicly owned treatment works (POTW) are not considered solid wastes, and thus would not be considered hazardous wastes. The facility that disposes of such wastes is excluded from RCRA permitting requirements, which is why the Hulett Lagoon site was referred to Superfund to be addressed under CERCLA. CERCLA has no such exemption.

#### 2.5 Waste Characteristics

The primary contaminant of concern at the Former Hulett Lagoon site is the volatile organic compound (VOC) trichloroethene (TCE). Analytical results from soil and groundwater sampling show TCE at concentrations above Superfund Chemical Data Matrix (SCDM) health-based benchmarks as well as the Maximum Contaminant Level (MCL) for drinking water (Reference 38).

#### **Trichloroethene**

TCE is a nonflammable, colorless liquid at room temperature with a somewhat sweet odor and sweet, burning taste. The manmade chemical does not occur naturally in the environment. TCE is now mainly used as a solvent to remove grease from metal parts. It is also used as a solvent in other ways and is used to make other chemicals. TCE evaporates easily into the air but can persist in the soil and groundwater. Once TCE is in surface water, much of it will evaporate into the air. It will take days to weeks to break down in surface water; in groundwater, the breakdown is much slower because of the slower evaporation rate. Very little TCE breaks down in the soil, and it can pass through the soil into underground water (Reference 39, pp. 1, 2).

TCE can enter the body from breathing air or drinking water containing TCE. It can also enter through the skin, but not as easily as by breathing or drinking. If the chemical is inhaled, about half will enter the bloodstream and organs; the remaining is exhaled. If TCE is swallowed, most will be absorbed into the blood. The liver changes most of the TCE to other chemicals and the majority of these breakdown products leave the body in the urine within a day. Some of the common symptoms to TCE exposure (usually at high levels) are headaches, dizziness, and rashes. Laboratory animals that were exposed to moderate levels of TCE had enlarged livers, and high-level exposure caused liver and kidney damage. However, it is not known if these changes would occur in humans. TCE is considered an animal carcinogen (Reference 39, pp. 1-4).

TCE is known as a Dense Nonaqueous Phase Liquid (DNAPL). DNAPLs are separate-phase hydrocarbon liquids that are denser than water. DNAPLs can exist in the soil/aquifer matrix in free-phase form or in residual form. When released on the ground's surface, free-phase DNAPLs move downward through the soil matrix under the force of gravity or laterally along the surface of sloping fine-grained stratigraphic units. As free-phase DNAPLs move, residual amounts are trapped in pores and/or fractures by capillary forces. Trapped DNAPLs are known as residual saturation. This residual saturation is a function of the physical property of the DNAPL and the hydrogeologic characteristics of the soil/aquifer medium, which typically ranges from 5-50% of total pore volume (Reference 40).

Most DNAPLs undergo only limited degradation in the subsurface and persist for long periods of time, while slowly releasing soluble organic constituents to groundwater through

dissolution. Dissolution may continue for hundreds of years under natural conditions before the DNAPL is dissipated (Reference 40).

#### 3.0 WASTE/SOURCE SAMPLING

#### 3.1 Previous Sampling (Reference 41)

On October 11, 1996, on behalf of Modine Manufacturing Company, Dames & Moore conducted a subsurface investigation at the former Hulett lagoon. The purpose of the investigation was to determine the presence or absence of VOCs, in particular TCE, in soil at the former Hulett lagoon.

Four hydraulically driven probes were advanced in the area of the lagoon where the inlet pipe from the former Sundstrand facility and the outlet or discharge pipe from the lagoon were previously located. The soil within the probe cores was continuously sampled and field screened using a photoionization detector (PID). The soil sample exhibiting the highest indication of VOC content from each probe core was submitted for analysis. The samples were analyzed for VOCs only. The following table presents results for those samples.

TABLE 1: SELECTED ANALYTICAL RESULTS FROM SOIL SAMPLES COLLECTED BY DAMES & MOORE IN HULETT LAGOON ON OCTOBER 11, 1996						
Sample ID	Depth	Analyte Detected	Concentration (in ppm)			
GP-1	4' - 6'	chloroform	0.20			
		TCE	9.17			
GP-2	4' - 5.5'	TCE	1.94			
GP-3	4' - 5'	chloroform	0.0094			
		cis-1,2-dichloroethene,	0.0914			
		TCE	not detected			
GP-4	4' - 6'	TCE	not detected			

Although the majority of sludge from the lagoon was supposedly removed during closure, these sampling results indicated that TCE contamination was still present in the lagoon area. Dames & Moore and Modine have concluded that the TCE concentrations encountered in the soil at the lagoon supports their previous position that the former lagoon is the off-site source of the observed TCE impact to groundwater at the Modine facility. DNR RCRA Permits personnel hold the position that the nature, extent and source of the TCE groundwater contamination in the area has not been fully determined yet. That is one of the objectives of the AOC currently being negotiated. At least four waste management units on the 179 Sunset Drive property have been identified as potential contributors to TCE soil and groundwater contamination (Reference 16).

#### 3.2 PA/SI Sampling (Reference 38)

PA/SI soil sampling in the lagoon area was conducted on January 21, 1999. Figure 2 is a site map that shows collection location of all soil samples in the lagoon area. A membrane interface probe (MIP), equipped with a PID and a flame ionization detector (FID), was employed to generate soil gas data of the subsurface within and surrounding the boundaries of the former lagoon area.

Ten soil borings (Hulett-01 through Hulett-10) were drilled utilizing a track-mounted hydraulic soil probe. Eight soil grab samples were collected from the lagoon area and one background sample was collected from outside the lagoon. Based upon this sampling, the lagoon is estimated to have been approximately six feet deep. Previous sampling documented refusal, meaning bedrock was encountered, in drilling from a range of five to six feet below ground surface, depending on the boring location. The PA/SI background boring was drilled approximately 25 feet south of the lagoon's edge. The background sample was collected from a 10.5' to 11' depth, which was a similar depth zone as the majority of the source samples from the lagoon, correcting for the rise in elevation at the background sampling point.

#### 3.3 PA/SI Analytical Results (Reference 38)

Reference 38, Appendix B contains the MIP data logs generated for each boring. The logs indicate detections noted on the MIP's PID (identified as "Detector 1") and the FID ("Detector 2"). There were not any significant detections with the MIP for any of the borings.

Table 2, on page 13, presents the analytical results for all soil samples collected by DNR as part of the PA/SI. All soil samples were analyzed for total metals (arsenic, barium, cadmium, chromium, copper, lead, mercury, nickel, selenium, and silver) and VOGs. If any sample's total analyte levels exceeded 80% of 20 times the Toxicity Characteristic Leaching Procedure (TCLP) regulatory limit for a particular analyte, TCLP analysis was performed on that sample.

The last column in Table 2 lists the Missouri Cleanup Action Level (CALM) C<sub>LEACH</sub> level for each chemical. These values were listed for additional comparison. The Superfund Chemical Data Matrix (SCDM) benchmarks and MO Any-Use Soil Levels (ASLs) for chemicals only take into account human health effects related to exposure to the chemicals in the soil. They do not take into account the effect the chemicals have when they leach into the groundwater. The C<sub>LEACH</sub> value was calculated to approximate the physical processes involved in a soil contaminant leaching to the groundwater. The C<sub>LEACH</sub> value may be interpreted as a soil contaminant concentration, which (within the limitations of the formulas and assumptions used for calculation) if allowed to remain, would leach to the saturated zone and result in a groundwater concentration at or below the MCLs.

Three soil samples contained TCE at a detectable level. TCE was not detected in the background soil sample. The concentrations of TCE detected in the three samples from the lagoon exceed the  $C_{LEACH}$  value for TCE, which would indicate the potential exists for TCE to leach into the saturated zone and result in groundwater contamination above the MCL. This is, in fact, the situation at this site, as documented from groundwater samples collected from the monitoring well on-site (discussed in Section 4.5) (Reference 42).

The only sample that contained any metals significantly above background was 991471 from soil boring 4. Barium and cadmium were over three times the background levels, however neither metal was present above the SCDM benchmarks or MO ASLs.

#### 3.4 Conclusions

Although over 2,000 cubic yards of sludge were removed from the lagoon during closure in 1989, PA/SI sampling, as well as previous sampling, document that TCE contaminated soil still remains in the lagoon area. Three samples, collected for the PA/SI near the previous location of the outfall pipe, contained TCE at 9.5 ppm, 0.24 ppm and 0.12 ppm. These TCE concentrations are below health-based benchmarks protective of human exposure to the soil. However, the concentrations exceed the Missouri CALM C<sub>LEACH</sub> value, which was calculated as a value at which TCE would leach to the saturated zone and result in a groundwater concentration at or below the MCLs. The C<sub>LEACH</sub> value for TCE was calculated using specific formulas and assumptions that may not necessarily model site conditions at the Hulett lagoon.

One way of testing whether the TCE present in the soil at the lagoon has the potential to leach into groundwater at a level above the MCL would be to perform the Synthetic Precipitation Leaching Procedure on the soil samples. This may be necessary in future investigations.

to a decidence of the	TABLE	E 2: ANALY	TICAL RE	SULTS FRO	M SOIL SAI	MPLES COL	LECTED	N/NEAR TH	E HULETT LA	GOON		
All results in parts per r Underlined results are t				n level subsickground or				analyzed ground conc	NL - not lis entration is bel		ction limit	
	Hulett-01 4.5' - 5'	Hulett-02 6.5' - 7'	A STATE OF THE STA		Hulett-04 7.5' - 8'	Hulett-07 5.5' - 6'	Hulett-09 6' - 7'			SCDM Bnchmrk	MO ASL	MO CALM
	991469	991470	991467	991468	991471	991472	991473	991474 (replicate)	991475 (backgrnd)	-		C <sub>LEACH</sub>
METALS												
Arsenic, total	16.1	3.58	13.6	12.5	19.7	17.2	9.68	4.6	10.7	0.0043	11	NL
Barium, total	150	62.4	244	519	<u>750</u>	257	103	132	203	5500	3900	1650
Barium, TCLP	NA	NA	NA	0.442	0.628	NA	NA	NA	NA			
Cadmium, total	0.453	0.254	0.304	0.386	4.52	0.304	<0.2	0.204	0.651	39	28	11
Chromium, total	74.9	31.9	55.5	61.3	68.9	73.3	58.2	39.8	62.7	390	5600	38
Copper, total	39.9	15.7	33.6	37.5	64.3	38.8	6.47	8.56	36.8	NL	NL	NL
Lead, total	116	38.1	118	951	325	80.1	39.1	61.8	94.2	NL	240	NL
Lead, TCLP	< 0.025	NA	0.0772	0.143	<0.025	<0.025	NA	NA	<0.025			NL
Mercury, total	0.102	<0.04	0.107	0.139	0.195	0.141	<0.04	<0.04	0.0947	23	17	3.23
Nickel, total	43.3	12.5	49.4	69.6	90.1	36.2	9.76	12.4	32.5	1600	1100	170
Selenium, total	<1	<1	<1	<1	<1	<1	<1	<1	<1	390	280	4.37
Silver, total	<1	<1	<1	<1	<1	<1	<1	<1	<1	390	280	255
VOCs												
Cis-1,2-dichloroethene	<u>0.19</u> -	0.14	<0.025	<0:025	<0.025	<u>0.11</u> -	<0.025	<0.025	<0.025	780	490* -	0.51
Trichloroethene	9.5	0.24	<0.025	<0.025	<0.025	0.12	<0.025	<0.025	<0.025	58	340	0.097

#### 4.0 GROUNDWATER PATHWAY

#### **4.1 Hydrogeologic Setting** (Reference 43)

#### Stratigraphic Units

A stratigraphic column (Table 3 on page 18) has been tabulated based upon the stratigraphy of nearby wells. The youngest bedrock formations beneath the site are expected to be Ordovician-age sediments assigned to the Canadian Series. The Roubidoux Formation consists of dolomite, sandy dolomite, and sandstone. In the Camdenton area, soluble portions of the Roubidoux have generally been removed by dissolution. Nearby well logs indicate that the Roubidoux Formation may have been completely removed by erosion in the vicinity of the site.

Underlying the Roubidoux Formation, the Gasconade Dolomite consists of cherty dolomite and is estimated to be approximately 300 feet thick in the vicinity of the site. A basal unit of the Gasconade Dolomite, known as the Gunter Sandstone Member, commonly separates the Ordovician and Cambrian-age strata. The Gunter Sandstone is approximately 25 feet thick in the Camdenton area.

Cambrian rocks in the Camdenton area were deposited in a complex depositional environment. Camdenton is located near the western margin of a Cambrian-age intrashelf sedimentary basin known as the Central Missouri Basin. To the west lies the north-south trending Lebanon Arch, which consists of carbonate platform rocks, that in some areas, thin over Precambrian highlands. Dramatically different lithologies and abrupt facies changes are depicted in area well logs. In general, more shaly, basinal rocks to the east pinch-out against the Lebanon Arch.

Because of the tectonic setting, Cambrian beds in the Camdenton area are difficult to categorize, and "layer-cake" stratigraphy should not be assumed. The following descriptions are simplified. The upper-most Cambrian unit in the area is the Eminence Dolomite, which consists of approximately 300-635 feet of dolomite with minor amounts of chert. The Eminence Dolomite is underlain by about 25-230 feet of Potosi Dolomite, which consists of dolomite, chert, and drusy quartz. Beneath the Potosi Dolomite, in descending order, are the Derby-Doerun Dolomite, the shaly Davis Formation, the Bonneterre Formation, and the Lamotte Sandstone. The entire Cambrian section is estimated to be over 1,150 feet thick.

#### <u>Aquifers</u>

The Ozark Aquifer, which includes all bedrock units above the Cambrian-age Derby-Doerun Dolomite, is the shallowest aquifer beneath site. The Ozark Aquifer is considered exposed at the surface at the Former Hulett Lagoon site. The total thickness of the aquifer is approximately 950 feet. Each of the units which comprise the Ozark Aquifer have individual characteristics that control their water-bearing capabilities; however, in general, the Ozark Aquifer produces good-quality water, with production rates generally proportional

to well depth. Extensive pumping of groundwater in the Camdenton area has created a downward vertical gradient, and the site is located in a groundwater recharge zone.

Because detailed hydrogeologic studies have not been conducted at the site, groundwater flow directions within the bedrock can only be approximated. Prior to pumping of the aquifer, groundwater beneath the site probably flowed westward or northward to discharge areas in the Niangua River valley. Pumping rates at the Camdenton municipal wells are high enough to engulf the site within the cones of depression that surround the municipal wells. The radius of influence of nearby production wells should be determined.

Groundwater flow in the saturated zone is controlled by gradient. According to DGLS geologists, assertions made by Modine's consultants that preferential pathways in the Ozark Aquifer substantially influence flow direction in the saturated zone are incorrect. Water flows downhill; fractures or solution-enlarged channels cannot make water flow uphill. Monitoring well nests are needed to accurately determine the magnitude of the downward vertical gradient. The upper Gasconade Dolomite *may* inhibit the downward migration of contamination. However, fracturing and karst development may have resulted in a local increase in permeability within the otherwise relatively tight upper Gasconade Dolomite.

The Gunter Sandstone is generally highly porous and permeable and is an important source of domestic groundwater supplies in the area. Because the Gunter Sandstone generally yields adequate domestic water supplies, few private wells in the area penetrate the underlying Cambrian Formations. However, municipal wells in the Lake of the Ozarks area are generally cased through the Gunter Sandstone, in order to avoid possible bacterial contamination.

The Eminence and Potosi Dolomites are a major source of municipal drinking water throughout the Ozark area, including the City of Camdenton. The Eminence Dolomite is differentiated from the underlying Potosi Dolomite by the lack of druse. A druse is a rock cavity encrusted with finely crystalline quartz. The druse-rich Potosi Dolomite is the most permeable geologic unit within the Ozark Aquifer and generally has an extensive network of karstic channels.

The shallowest reliable aquitard beneath the site is the St. Francois Confining Unit, approximately 1,200 feet below the surface. The St. Francois Confining Unit separates the Ozark Aquifer from the deeper St. Francois Aquifer. The St. Francois Aquifer includes the Cambrian-age Bonneterre Formation and Lamotte Sandstone. The St. Francois Aquifer is not used as a water source in Camden County. Water losses in the Lamotte Sandstone are common in some parts of the Ozark Region, although the phenomenon is poorly understood. Outside the Cambrian outcrop area, few water wells penetrate the Lamotte Sandstone, since yields may actually be reduced. Groundwater flow directions in the deeper St. Francois Aquifer are generally unknown and may be complicated.

Baseline water-level and pumping rate data needs to be collected before informed decisions about groundwater movement in the Camdenton subsurface can be made. Static water levels should be measured at least monthly at any inactive wells. Detailed records of active wells should include volume of water pumped, length of pumping cycles, and drawdown measurements. The Mulberry City Well (which was shut down on January 26, 1999 because of TCE contamination) produced approximately three times the volume of the other two city wells, suggesting the aquifer is highly heterogeneous. The Mulberry Well probably intercepted more solution-enlarged cavities than the other city wells, although lithologic differences can also explain differences in well yield. Wide variations in aquifer parameters are common in carbonate areas.

The three Camdenton city wells produced a total of 232,458,000 gallons in 1997. An estimate of the cone of depression produced by this pumping can be made by comparing Camdenton to the city of Rolla, which is located in a similar ridge-top geologic setting approximately 50 miles east of Camdenton. In 1960, four Rolla city wells produced approximately 290,250,000 gallons of water from the Ozark Aquifer. The resulting cone of depression was over five miles wide. By 1960, pumping of the Ozark Aquifer in the Rolla area had dropped water levels up to 150 feet compared to the predevelopment potentiometric surface. The relatively deep depth to groundwater in the Camdenton area suggests a similar radius of effect can be expected. Any potential site-related contaminants reaching the water table are expected to move toward the nearest Camdenton City well. Until recently, hydraulic control beneath the Former Hulett Lagoon and Modine sites has been maintained by pumping at the Mulberry well. Now that the Mulberry well has been shut off, TCE contamination is expected to move toward another city well.

Monitoring wells at the Modine site are open to different depth intervals. Therefore, data from these wells cannot be used to create a potentiometric map. The fact that two of the four wells have gone dry in the past suggests that the vertical flow component is significant. Water levels in area wells tend to decrease with depth, supporting the statement that the vertical flow is downward. As previously mentioned, a downward gradient is to be expected in an active municipal well field, particularly if it is located on a ridge top. Static water levels measured during the construction of the newest Camdenton City well (Hickory Street or well # 7) also verify the downward gradient. The Hickory Street well is 1,100 feet deep with 462 feet of casing. The static water level before pressure-grout sealing of the well casing was 222 feet below ground surface. Static water level after sealing was 260 feet below ground surface, indicating a downward vertical gradient. A large upland area that might provide recharge to the Camdenton City wells does not exist. Groundwater monitored by the monitoring wells is essentially moving downward to recharge the pumping wells. Conclusions about lateral flow directions cannot be made based on water levels from the existing monitoring well network.

It has been suggested that contaminants reaching the saturated zone beneath Camdenton will follow "regional groundwater flow" and discharge at the Lake of the Ozarks. However,

groundwater withdrawals averaging over 500,000 gallons per day will create a large cone of depression and obliterate "regional groundwater flow" in any Ozark ridge top setting. A 2-hour pump test of the new Hickory St. well at 550 gallons per minute (gpm) caused a 176-foot drawdown in water level. There is no evidence to suggest that potential contaminants reaching the water table from either the Former Hulett Lagoon or the Modine site can somehow escape the Camdenton well field.

#### **Aguifer Discontinuities**

Minor folds and faults in the area cannot be considered aquifer discontinuities. However, it should be noted that the Cambrian-age formations that form the most productive portions of the Ozark Aquifer beneath the site are highly variable in lithology. The aquifer cannot be considered isotropic, nor does it possess radial symmetry. Aquifer parameters may be so variable as to render groundwater modeling useless.

#### Wellhead Protection Area

Camdenton is located in Area 1, as designated by the DGLS Wellhead Protection Section. Since September 1987, Area 1 bedrock wells have been required to have 80 feet of casing and penetrate at least 30 feet of bedrock. Wells within ¼ mile of the Lake of the Ozarks are located in Sensitive Area B and subject to additional requirements.

#### **Karst Features**

The Camdenton area is considered karst. Significant karst features are present within a four-mile radius of the site. When MW-5 was drilled at the site, numerous fractures and small voids were encountered. Over 5,000 gallons of water was lost during the drilling of the monitoring well.

#### 4.2 Groundwater Targets

Groundwater use within four miles of the site is extensive. At least 3,420 people are served by public wells in the area and an estimated 409 people are served by private wells. A detailed description of the well use follows.

#### Public Drinking Water Wells

The City of Camdenton currently utilizes three wells to supply drinking water to city residents: the Rodeo Grounds well, the Blair Heights well, and the Hickory well. The city also has a fourth well, the Mulberry well, that was taken off line on February 2, 1999 due to TCE contamination. The Mulberry well is currently used only as a standby well when any of the other three wells are not operating. Since February 2, 1999, the Mulberry well has been on-line twice. Due to electrical problems at the Blair well, Mulberry well was pumped from February 2 to the 9<sup>th</sup>, for a total of about 400,000 gallons. Due to problems with the water controls, Mulberry well was pumped from February 12 - 16<sup>th</sup>, for a total of 1,314 gallons (References 44; 45).

. PREFERE	Table 3	3: Stratigraphi	c Column for Fo	ormer Hulett I	_agoon, Car	nden County (after Harvey	et. al.,1983)	
System	Aquifer Group	Approximate Site - Specific Thickness (ft)	Formation	Hydraulic Conductivity (cm/sec)	Regional Thickness (ft)	Dominant Lithology	Water-bearing Character	
Quaternary		8	Colluvium and residuum		0-90	Regolith of residual clay, sand, chert pebbles and cobbles	May contain small amounts of perched water.	
Ordovician	Ozark Aquifer	0?	Roubidoux Formation	10 <sup>-3</sup>	0-90	Clayey residuum, sandstone and sandy dolomite	Not present in sufficient thickness in the Camdenton area to produce usable quantities of water.	
			300	Gasconade Dolomite	10 <sup>-6</sup>	300-385	Cherty dolomite, minor sandstone, and shale	Yields moderate to large quantities of water to wells. Yields range from 20 to 75 gpm. Less-permeable Upper Gasconade may act as a leaky confining unit.
		25	Gunter Sandstone Member	10 <sup>-4</sup>	10-45	Sandstone	Contributes moderate to large quantities of water. Most wells oper to other formations.	
		500?	Eminence Dolomite	10 <sup>-5</sup>	240-600?	Cherty dolomite	Yields 6-100 gpm, the average being about 20 gpm	
•		150?	Potosi Dolomite	10 <sup>-4</sup>	30-330	Dolomite; contains abundant quartz druse	Yields large quantities of water to wells. Yields range from 100 to 750 gpm.	
Cambrian	St. Francois Confining Unit	180	Derby-Doerun Dolomite	10 <sup>-7</sup>	80?-215	Shaley dolomites and shale	Reliable aquitard.	
	Comming one	80	Davis Formation	10-7	50-380?			
	St. Francois Aquifer	160	Bonneterre Formation	10 <sup>-5</sup>	85-200	Dolomite and limestone	Generally used only in outcrop areas May contribute additional 100-200	
		240	Lamotte Sandstone	10 <sup>-5</sup>	140-300	Sandstone and arkosic conglomerate	gpm to wells open to other formations.	
Precambrian	Basement Confining Unit					Igneous and metamorphic rocks	Does not yield water to wells in this area	

The Rodeo well is located on Rodeo Road, just over one mile southeast of the site. The Rodeo well was drilled in 1961 to a total depth of 940 feet with 450 feet of eight-inch steel casing. The pump is set at 420 feet. The yielding strata is the Potosi Dolomite of the Ozark Aquifer. Records show the well yields 380 gpm (Reference 44).

The Blair Heights well is located on Lakeview Drive, 0.7 of a mile south-southwest of the site. The Blair well was drilled in 1974 to a total depth of 1060 feet with 400 feet of ten-inch diameter steel casing. The pump is set at 450 feet. The yielding strata is the Potosi Dolomite of the Ozark Aquifer. Records show the well yields 100 gpm (Reference 44).

The Hickory well is located at the southwest end of Hickory Street, 0.8 of a mile east of the site. The Hickory well was drilled in 1998 to replace the Mulberry well. The Hickory well was drilled to a total depth of 1100 feet with 450 feet of eight-inch diameter steel casing. The pump is set at 500 feet. The yielding strata is the Potosi Dolomite of the Ozark Aquifer (Reference 44).

The Mulberry well is located south of Mulberry Lane, 0.25 of a mile south of the site. The Mulberry well was drilled in 1986 to a total depth of 900 feet with 400 feet of twelve-inch diameter steel casing. The pump is set at 350 feet. The yielding strata is the Potosi Dolomite of the Ozark Aquifer. Records show the well yields 600 gpm (Reference 44).

When in use, the Mulberry well was blended with the other two wells, with the Mulberry well being the largest producer. The City of Camdenton's Public Works Director reported that the Mulberry well was the lead well until July 1998. Before July 1998 the controls on the wells were set such that Mulberry well was always the first to run; the Blair and Rodeo wells only ran when the Mulberry well was not able to handle the demand. During that time, the Mulberry well supplied about 70% of the water to the system. New controls were installed in July 1998, and the city was able to set the time the wells came on. In response to the TCE contamination showing up in the well, the Mulberry well was set as the third well to come on. With the new controls the Mulberry well was cut back to supply only about 40% of the water to the system (Reference 45). The City of Camdenton's water supplies a total of 3,010 people (Reference 46, p. 14).

The Windsor Estate Nursing Home well is located on Highway 5, approximately 1.4 miles northwest of the site. The well was drilled in 1969 to a total depth of 600 feet with 400 feet of six inch casing (Reference 61). This well serves 70 people (Reference 32, p. 131).

The Linn Creek well is located on Highway 5, approximately 2.9 miles northeast of the site. The well was drilled in 1984 to a total depth of 860 feet with 528 feet of six inch steel casing (Reference 62). This well serves 260 people (Reference 32, p. 33).

The Southway Terrace Mobile Home Park well is located on Highway 5, 2.3 miles northwest of the site. The well was drilled in 1970 to a total depth of 550 feet with 350 feet of six inch steel casing (Reference 63). This well serves 85 people (Reference 32, p. 120).

TABLE 4: PUE	BLIC WELLS WITHIN A 4-MILE RADIU HULETT LAGOON SITE	S OF THE FORMER
Distance from Site	Name of Well '	No. of People Served*
0 - 1/4	City of Camdenton's Mulberry Well	2,107 <sup>†</sup>
1/2 - 1	City of Camdenton's Blair Well	1,003 <sup>‡</sup>
	City of Camdenton's Hickory Well	1,003 <sup>‡</sup>
1-2	City of Camdenton's Rodeo Well	1,003 <sup>‡</sup>
	Windsor Estate Nursing Home	70
2-3	Linn Creek	260
	Southway Terrace MHP	85
TOTAL		3,425

<sup>\*</sup> Reference 46, pp. 14, 33, 120, 131

There are several drinking water wells within a four-mile radius of the site that are classified as transient, non-community water systems. They include mostly resorts and restaurants in the Lake of the Ozarks area. These wells, by definition, serve at least 25 different people at least 60 days out of the year (Reference 47). However, the number of people served by these wells will not be included in a count of potential targets due to the transient nature of the population.

#### Private Drinking Water Wells

Within four miles of the site, there are over 485 wells recorded in the DGLS databases. The LOGMAIN database contains information on older wells. The DGLS Well Wellhead Protection Section's Water Well Information System (W.I.M.S) database contains information on wells drilled since 1987. The vast majority of the wells on record are domestic supply wells. Some wells may no longer be active, and many active wells may not be recorded in DGLS databases. Table 5 illustrates the breakdown of private wells within four miles of the site (Reference 43). The population served by private wells was calculated using the estimated average persons per household in Camden County - 2.41 (Reference 48).

TABLE 5: PRIVATE WELLS REGISTERED WITH DNR WITHIN A 4-MILE RADIUS OF THE FORMER HULETT LAGOON SITE							
Distance From Site	Number of Private Wells	Estimated Population Served					
0 - 1/4	1	2					
1/4 - 1/2	-	-					
1/2 - 1	2	5					
1-2	27	65					
2-3	59	142					
3-4	81	195					
TOTAL	170	409					

<sup>&</sup>lt;sup>†</sup> This represents the number of people apportioned to this well when it was in peak operation during the initial time period when TCE was detected in the well

This represents the current situation in Camdenton without the Mulberry well operating

#### 4.3 Previous Sampling

#### **Monitoring Wells**

Modine Manufacturing Company has performed quarterly sampling of the monitoring wells on their site. The TCE concentrations in the monitoring wells are detailed in the table below (Reference 49).

	- Not detected at			npled due to insi				
Date of Sampling	MW-1	MW-2	MW-3	MW-4	MW-5			
09/02/92	ND	ND	These wells w	ere not drilled				
12/07/94	6.9	5.1	until	1995.				
08/16,22/95	11.8	ND	8	88.9	This well was			
11/16/95	9.4	ND	ND	142	not drilled			
02/15,16/96	ND	ND	6.6	173	until 1998.			
	(duplicate 5.4)				unui 1990.			
05/16/96	ND	ND	ND	10				
08/20/96	ND	NT	ND	NS				
12/12/96	ND	NT	NS	NS				
02/28/96, 03/0397	NT	NT	ND	34				
06/04/97	NT	NT	NT	120				
07/16/98	These wells were	hese wells were not sampled at this time. This was during the installation of MW-5.						

#### Public Drinking Water

Table 7, on the following page, shows the history of TCE detections in the City of Camdenton's public drinking water wells. The first time TCE showed up in the Mulberry well was in March of 1993. The sample was collected by the Missouri Department of Health and analyzed at Continental Analytical Services, Inc. (Reference 50).

The DNR requires public drinking water wells be tested for volatile organic compounds every three years. DNR mails sampling containers to the public water supply office, and then a designee, in the City of Camdenton's case, the Public Works Director, collects the sample and sends it to DNR for analysis. When a contaminant is detected, sampling frequency is then increased to quarterly and sometimes monthly. If the running annual average concentration of the contaminant exceeds the MCL, the public system is in violation of the drinking water standard.

The first sample analyzed by DNR in which TCE was detected at the Mulberry well was in January 1997. During sampling in 1997, there was only one sample that exceeded the MCL (February's sample was 5.2 ppb), but the running annual average for that year was below the MCL. In 1998, the levels of TCE began to increase (Reference 50). At that time, the city began looking at options to replace the Mulberry Well. In May 1998, the city

announced they were in the process of planning for a new well to be drilled on Hickory Street to replace the Mulberry Well (Reference 51). In addition, in July 1998, the City of Camdenton installed new regulating controls on their drinking water wells that allowed them to cut back the usage of the Mulberry Well. It went from supplying about 70% of the water when blended with the other two wells, to supplying about 40%. In February 1999, the new Hickory well went on line and the Mulberry well was shut off (Reference 45).

TABLE 7: TCE F	RESULTS FROM S PUBLIC DRIN Results in parts p	IKING WATER	
Date of Sampling	Mulberry Well		Blair Well
03/16/93	2.1	<0.5	<0.5
04/27/94	<0.5	<0.5	<0.5
01/29/97	3.8	3.9*	<0.5
02/17/97	5.2	<0.5	<0.5
03/12/97	3.8	<0.5	<0.5
06/03/97	4.5	<0.5	<0.5
08/26/97	4.3	<0.5	<0.5
12/01/97	4.4	<0.5	<0.5
02/02/98	6.3	<0.5	<0.5
02/17/98	5.2	<0.5	<0.5
03/25/98	3.6	<0.5	<0.5
04/23/98	4.1	<0.5	<0.5
05/21/98	11.8	<0.5	<0.5
06/08/98	5.1	<0.5	<0.5
08/25/98	4.2	<0.5	<0.5
12/02/98	4.4	<0.5	<0.5
01/13/99	26.2	<0.5	<0.5

<sup>\*</sup> The Rodeo well is over one mile from the Hulett lagoon. It is unknown whether this TCE detection was a valid result, especially since all subsequent samples were non-detect for TCE.

#### Private Wells

On April 23, 1998, DNR collected a groundwater grab from a private well at 178 Sunset Drive. The sample was analyzed for VOCs. Cis-1,2-dichlorethene was detected at 12 ppb and TCE was detected at 210 ppb. At that time, the owner was using the well only for lawn watering; the home was hooked up to the city water line for drinking water (Reference 52).

In July 1992, as part of the SI conducted at the 179 Sunset Drive facility, three samples were collected from private wells located near the Lake of the Ozarks. Two of the wells were located in Normac Estates, 1.8 miles west-southwest of the site. The third well was located 1.3 miles southwest of the site. No VOCs were detected in any samples (Reference 36).

#### 4.4 Sampling Locations

Groundwater samples for the PA/SI were collected on January 6-7, 1999. Five monitoring wells, two public water supply wells, and two private drinking water wells were sampled. Figure 3 shows sample locations for all groundwater samples collected as part of the Hulett Lagoon PA/SI (Reference 38).

#### Monitoring Wells 1 & 2

Layne-Western Company, Inc., was subcontracted by DNR for the installation of Monitoring Wells #1 and #2 on the Modine Manufacturing Company property (then known as Modine Heat Transfer). The wells were installed in July 1992 during the SI performed at the 179 Sunset Drive facility. MW-1 is located on the west side of the facility. MW-2 is located northeast of the facility. Total well depth of MW-1 was 178 feet and MW-2 was 197 feet. The wells were constructed with two-inch diameter, polyvinyl chloride (PVC) inner well casing, with steel outer well casing. Both wells have 40 feet of screen at the bottom of the well (References 36; 53).

On January 7, 1999, sample 991464 was collected from MW-1 and sample 991463 was collected from MW-2. Depth to water recorded at 153.2 feet from the top of the casing in MW-1. Depth to water recorded at 165.7 feet from the top of the casing in MW-2 (Reference 38).

#### Monitoring Wells 3 & 4

Layne-Western Company, Inc. of St. Louis was subcontracted by Dames & Moore, consultant for Modine Manufacturing Company, for the installation of Monitoring Wells #3 and #4. Drilling took place from August 8-14, 1995. MW-3 was installed on August 8, 1995, south of the Modine facility. MW-4 was installed on August 11, 1995, just northwest of the facility. MW-3 is 167 feet deep with 64 feet of five-inch diameter steel surface casing. MW-4 is 158 feet deep with 44 feet of five-inch diameter steel surface casing. Both wells are open hole below their casing (Reference 54, p. 35).

On January 7, 1999, sample 991460 was collected from MW-3 and samples 991461 and 991462 were collected from MW-4. Sample 991461 was collected via a submersible pump and 991462 was collected via dedicated bailer. The two different methods for collection were used for comparison purposes. All other groundwater samples from monitoring wells were collected with a dedicated bailer. Depth to water recorded at 153.1 feet from the top of the casing in MW-3. Depth to water recorded at 158.5 feet from the top of the casing in MW-4 (Reference 38).

#### Monitoring Well 5

Layne-Western Company, Inc. of St. Louis was subcontracted by Dames & Moore, consultant for Modine Manufacturing Company, for the installation of Monitoring Well #5. The well was installed just outside what would have been the southwest edge of berm of the Hulett lagoon. Drilling took place from July 7-10, 1998. The well was installed to

determine the presence or absence of volatile organic compounds, in particular, TCE, in the groundwater underlying the former Hulett lagoon. The well was drilled to a total depth of 118 feet below ground surface (bgs). Permanent surface casing was installed in bedrock to a depth of 37 feet bgs. This was done to case off several void spaces that had been encountered during drilling, most notably a void space from 35.0 to 36.5 feet bgs. The well was constructed with schedule 80, two-inch diameter, PVC casing with 30 feet of a 0.01 inch slotted screen. Water was encountered at a depth of 105 feet bgs (Reference 55).

On January 7, 1999, samples 991465 and 991466 (duplicate) were collected from MW-5. Depth to water recorded at 102.7 feet from the top of the casing in MW-5 (Reference 38).

#### **Public Wells**

Sample #991458 was collected from the City of Camdenton Blair well. The Blair well was considered a background well for PA/SI purposes since previous sampling has shown this well not to be contaminated. However, groundwater flow direction has not been definitively determined; the cones of depression created by the city's wells could significantly affect groundwater flow in the area. Sample #991459 was collected from the City of Camdenton Mulberry well, known to be contaminated with TCE (Reference 38).

#### **Private Wells**

Sample 991452 and 991453 (a duplicate) were collected from a residential well, located at 178 Sunset Drive, approximately 790 feet southwest of the site. This well is currently not used for any purpose. When the well was sampled in April 1998 and found to be contaminated with TCE, the owner discontinued use, which at that time was only for watering his lawn. No information is known about the well (Reference 38).

Sample 991457 was collected from a residence in Normac Estates, located 1.8 miles west-southwest of the site on the lakefront of the Lake of the Ozarks. No information is known about the well (Reference 38).

#### 4.5 Analytical Results (Reference 38)

All groundwater samples for the PA/SI were analyzed for total and/or dissolved metals (arsenic, barium, cadmium, chromium, copper, mercury, nickel, lead, selenium, silver), and VOCs. The analytical results for all groundwater samples are detailed in the tables on the following page.

**Monitoring Wells** 

TABLE				R RESULTS		VSI SAMP	LING		
All results in parts per bi * 991461 was collected Bolded results are those	via submer	sible pump		as collected	via dedica	ted bailer			
CHEMICAL MW-1 MW-2 MW-3 MW-4 MW-5 E									
	991464	991463	991460	991461*	991462*	991465	991466	MCL	
METALS									
Arsenic, total	<1.2	<1.2	6	<1.2	NA	<1.2	<1.2	50	
Barium, dissolved	49.7	91	69.6	81.6	NA	55.7	51.6	2000	
Barium, total	58.2	112	151	88.3	NA	67.9	71.3	2000	
Cadmium, total	<1.0	<1.0	2.26	<1.0	NA	1.25	1.97	5	
Chromium, total	3.84	14.3	45.7	5.52	NA	9.39	13.3	100	
Copper, total	6.94	7.85	51.2	<5.0	NA	7.52	8.97	1300	
Nickel, total	<3.0	8.45	29.7	7.61	NA	5.16	4.26	100	
Lead, total	14.1	37.2	97.6	38.7	NA	12.7	15.3	15	
VOCs									
Cis-1,2-dichloroethene	<0.5	<0.5	<0.5	2.1 ,	2.3	35	23	70	
Trichloroethene	10.1	2.5	<0.5	64.1	76.5	1400	1500	5	

For purposes of the PA/SI and according to HRS guidelines, any of MW's 1 through 4 could be considered background for the MW-5. Although previous and current sampling has shown that MW's 1 through 4 have been, or presently are, within the boundaries of the TCE plume, the TCE contamination in MW-5 exceeds three times the TCE concentration in any of the other monitoring wells. Additionally, however, all five monitoring wells are not entirely similar in construction. MW's 3 and 4 are open hole borings below their casing, while MW's 1, 2 are screened for 40 feet; MW-5 is screened for 30 feet. MW-1 is 60 feet deeper than MW-5; and MW-2 is 79 feet deeper than MW-5. Although the intervals from which water is drawn in the monitoring wells is not entirely similar, all five wells draw water from the Gasconade Dolomite formation of the Ozark Aquifer.

Public and Private Drinking Water Wells

TABLE 9: SELECTE	D GROUNDWATE	R RESULTS FROUNDWATE		AMPLING A	T PUBLIC AND PI	RIVATE
All results in parts per bil	lion					
CHEMICAL	Camdenton Blair Well (Background)	Camdenton Mulberry Well		t Drive e Well	Normac Estates Private Well	EPA MCL
	991458	991459	991452	991453	991457	
METALS						
Barium, total	45.3	45.3	67.5	66.6	62.8	2000
Copper, total	21.7	31.7	27.5	16.3	44.7	1300
Nickel, total	<3.0	<3.0	11.2	60.4	<3.0	100
Lead, total	4.4	15.7	<2.5	<2.5	<2.5	15
VOCs						
Cis-1,2-dichloroethene	<0.5	<0.5	13	13	<0.5	. 70
Trichloroethene	<0.5	5.3	240	230	<0.5	5

For purposes of the PA/SI, the Camdenton Blair well was chosen as a background well for the contaminated Mulberry well. The two wells are similar in total depth and both draw from the Potosi Dolomite formation of the Ozark Aquifer. The Mulberry well could in fact serve as its own background since the well was regularly monitored as a public well under Missouri regulations, and was non-detect for TCE until 1997 (except for one sample in 1993 collected by the Missouri Department of Health).

#### 4.6 Conclusions

PA/SI sampling has documented an observed release of TCE to the Ozark Aquifer in the area of the Former Hulett Lagoon site. MW-5, located immediately near the lagoon, contained TCE at 1,400 ppb. The City of Camdenton's Mulberry well, located less than 0.25 of a mile south of the lagoon showed 5.3 ppb TCE during PA/SI sampling on January 6, 1999.

The City of Camdenton officially took the Mulberry Well off line on February 2, 1999 due to the TCE contamination. When in use during the initial time period when TCE was detected, the Mulberry Well was the highest producing well of Camdenton's system, supplying an apportioned 2,107 people. The well is now a reserve well, to be used only when power is down at any other Camdenton Wells. There are three wells currently serving the city within two miles of the site. The City of Camdenton's drinking water wells supply an estimated 3,010 people.

There are two sources of TCE that could be attributed to the contamination present in the City of Camdenton's Mulberry Well. PA/SI sampling has shown the former Hulett lagoon contains TCE contaminated soil, as well as groundwater, at the lagoon site. The lagoon is located approximately 1100 feet north of the Mulberry well. The manufacturing facility at 179 Sunset Drive has also been shown to contain TCE contaminated soil as well as TCE contaminated groundwater. The facility is located approximately 500 feet northwest of the Mulberry Well. It is unknown at this time whether the Mulberry Well contamination is due in whole or in part to the lagoon contamination. Information on groundwater flow direction is inconclusive. DNR's DGLS geologists suggest that the cone of depression created by the Mulberry well, when in operation, influenced groundwater flow in that direction. Now that the Mulberry well has been shut off, groundwater flow is expected to move toward another city well, most likely the Blair well.

#### 5.0 SURFACE WATER PATHWAY

#### 5.1 Hydrologic Setting

The site is situated within the Salem Plateau region of the Ozark Plateau physiographic province. The topography of the Salem Plateau is characterized by a rolling upland surface with rugged hills dissected by entrenched, narrow stream valleys. Karst features,

such as springs, sinkholes, and losing streams, are characteristic of the Salem Plateau (Reference 43).

The Former Hulett Lagoon site is situated near the headwaters of a small unnamed stream which drains southwest to the Niangua Arm of the Lake of the Ozarks. During operation, the Hulett lagoon's receiving stream was identified as a tributary to Jarvis Hollow. The site of the former lagoon has been leveled, while the surrounding terrain exhibits moderate natural relief (5% to 9% slopes). East of the site lies the City of Camdenton. West of the site, the landscape is more rugged, and forests extend down to the Lake of the Ozarks. The natural landforms and drainage patterns at the site have been obscured by lagoon construction and, later, by soil removal actions (Reference 43).

Below the site, the receiving stream is fairly steep and the bedload consists mostly of cobbles and gravel. In 1992, a DGLS geologist with the Water Resources Program examined area streams as part of oversight for an investigation at the 179 Sunset Drive facility. He reported that the Former Hulett Lagoon site is located on the valley floor of the "northeast branch" of an unnamed tributary to Jarvis Hollow. The "southeast branch" of the tributary drains the facility at 179 Sunset Drive. The northeast and southeast branches join near the western corporate boundary of the City of Camdenton, approximately 0.6 miles downstream of the Former Hulett Lagoon site. The lagoon was constructed near the headwaters of the northeast branch, just west of the ridge top where most of Camdenton is located. Water runs onto the site from the upper section of the northeast branch. This channel has been diverted around the northern edge of the former lagoon (Reference 43).

Run-off from the site, entering the northeast branch, flows toward the west for ¼ mile. Runoff then flows southwest approximately 1.6 miles and enters Jarvis Hollow in the NE ¼, NE ¼, SE1/4 of Section 34, Township 38 North, Range 17 West. According to the 7.5 minute HaHaTonka topographic map, the 0.15-mile-long stream segment below this confluence appears to be perennial. Thus, the confluence of the unnamed tributary and the stream in Jarvis Hollow is considered the probable point of entry (PPE) to surface water. Runoff from the Former Hulett Lagoon reaches the Lake of the Ozarks 1.97 miles downstream of the site (Reference 43).

The DGLS geologist noted that the unnamed tributary lost flow in some locations, especially when encountering the Gunter Sandstone. However, it was anticipated that any flow lost in the streambed would stay in the valley. Very little rainfall is necessary to generate surface flow throughout the reach of the stream. The receiving stream for the Former Hulett Lagoon Site has not been officially classified by DGLS, but based on available reports, the stream should be considered losing. The Gasconade Dolomite that forms much of the streambed is not particularly karst. Many nearby streams have been classified as losing (Reference 43).

The 15-mile downstream limit ends near Shepard Cove on the Osage River Arm of the Lake of the Ozarks, approximately 29.5 miles above Bagnell Dam. This point is located

on the Camdenton, MO 7.5-minute quadrangle; SE ¼, Section 24, T. 39 N., R. 17 W. The Osage River flows in a northeasterly direction, toward the Missouri River (References 43; 3).

The site is most likely not located in a flood plain, as it is located at an elevation of approximately 285 meters above mean sea level, while Lake of the Ozarks is at 198 meters above sea level (Reference 3).

#### 5.2 Surface Water Targets

The Lake of the Ozarks is a 59,520 acre lake classified as a major reservoir. The lake is designated for use as livestock and wildlife watering, protection of warm water aquatic life and human health/fish consumption, whole body contact recreation, and boating and canoeing (Reference 56, pp. 11, 35). There are no drinking water intakes on the Lake of the Ozarks (Reference 46, p. 200).

The federally-listed Endangered gray bat is known to occur on the Lake of the Ozarks in Section 2 of T 38 N, R 18 W. The bats forage over streams, rivers, and reservoirs in this part of Missouri (Reference 57).

The federally-listed threatened Bald Eagle winters at the Lake of the Ozarks. Bald eagles generally forage on fish, dead and dying waterfowl, and carrion. Eagles can be adversely affected by heavy metals, bacteria, and other contaminants. Due to the scavenger behaviors of the eagle, they often feed on dead or dying prey that may have been poisoned in some way or may have elevated bacterial levels. In such cases, eagles can be affected through a secondary pathway in the food chain which could harm or kill individuals (Reference 58).

According to National Wetlands Inventory maps prepared by the U.S. Department of the Interior/Fish and Wildlife Service (aerial photography from 1984), the first 0.6 of a mile of the creek bordering the lagoon is a wetland. The remaining portion of the creek leading to the Lake of the Ozarks may be considered a wetland if emergent hydrophytes are present. There are numerous wetlands in and bordering the Lake of the Ozarks (Reference 59).

#### 5.3 Surface Water Conclusions

All surface runoff from the lagoon area enters the tributary to Jarvis Hollow stream that borders the west side of the lagoon. This stream received overflow from the lagoon during operation; thus TCE was historically released to the creek. However, the stream bed near the site is gravel, making sampling impractical. It has been ten years since the lagoon was closed; it is unlikely any TCE would be left in any surface material, soil or sediment, present in other parts of the stream. Since TCE is a DNAPL, the majority of what entered the stream would have infiltrated into the subsurface by now. Current site conditions

indicate the risk from any site surface runoff would be low since the TCE found in the soil at the lagoon was from the four to seven foot depth.

#### 6.0 SOIL EXPOSURE AND AIR PATHWAYS

#### 6.1 Physical Conditions

The native soil in the vicinity of the Former Hulett Lagoon site was the Clarksville-Gepp very cherty silt loam. The Clarksville-Gepp soils are deep, well-drained soils typical of sloping uplands. Permeability is moderate. The content of organic material is moderately low. The shrink-swell potential is moderate. Grass at the site limits wind erosion (Reference 43).

The one acre former lagoon area is an open field area with grassy vegetation. The only structure on-site is Monitoring Well #5, located on the southwest corner of the lagoon's former berm. The lagoon area is relatively flat. During closure, the majority of the sludge was removed and the berms were turned into the middle. Apparently, some of the material from the hill bordering the southeast and east side of the lagoon was scraped in toward the lagoon during closure, but no fill was brought in (Reference 5).

Access is not restricted to the site; there is no fencing. The gravel access road from West Mulberry is not maintained; there are several severe ruts caused from washouts. There have been reports that illegal dumping is occurring on Ron Hulett property along the north and south side of the access road. There were a few pieces of trash in the lagoon area (Reference 5).

#### 6.2 Soil and Air Targets

Residential areas are located immediately north and south of the site. North of the site is an apartment complex; south of the site is one apartment building and several homes. At least two of the apartment buildings in the complex north of the site are within 200 feet of the site, as well as the apartment building and one home south of the site (Reference 5).

The City of Camdenton has an estimated population of 2,544 people (Reference 48, p. 144). Table 10, on the following page, illustrates the breakdown of the number of people estimated to be within a four-mile radius of the site (Reference 60).

TABLE 10: ESTIMATED POPULATION WITHIN A 4-MILE RADIUS	
RADIUS	POPULATION
ON-SITE	0
0 - 1/4	180
1/4 - 1/2	696
1/2 - 1	1,267
1 - 2	1,100
2 - 3	1,280
3 - 4	1,405
TOTAL	5,928

The federally-listed Endangered gray bat is known to occur in Section 2 of T37N, R17W, which is between 2 and 3 miles from the site (Reference 57).

#### 6.3 Soil and Air Conclusions

All soil samples collected as part of the PA/SI were waste/source samples. The TCE contamination in the lagoon is documented in the four to seven foot depth zone. There were no surface soil samples collected from the lagoon area because the majority of the sludge in the lagoon was removed and the majority of TCE near the surface would have volatilized or moved down through the soil profile in the ten years since closure of the lagoon. The potential for possible trespasser exposure to any of the TCE contaminated soil on the site is considered minimal. There are no people living on site, although there are three apartment buildings and one home that are within 200 feet of the site. Access to the site is not restricted. The reports of unauthorized dumping in the area near the lagoon indicate site security may be warranted.

#### 7.0 SUMMARY AND CONCLUSIONS

The Former Hulett Lagoon site is located in the City of Camdenton, 500 feet northeast of the intersection of Dawson Road and Sunset Drive. The site is a closed wastewater lagoon owned and operated by the City of Camdenton. The Hulett lagoon, approximately one acre in size, was one of five municipal lagoons that serviced the City of Camdenton. It was the only lagoon that received industrial effluent in addition to domestic sewage. The lagoon was in operation from 1961 until its closure in late 1989.

From 1967 through 1986, Dawson Metal Products (1967 to 1972) and Sundstrand Tubular Products (1972 to 1986) operated a manufacturing facility that released untreated wastewater into the lagoon. The facility is located approximately 1000 feet southeast of the lagoon at 179 Sunset Drive. The untreated wastewater was known to have contained

several hazardous waste streams, most notably TCE. During closure in 1989, over 2,000 pounds of sludge was removed from the lagoon.

Environmental investigations of the manufacturing facility at 179 Sunset Drive started in 1990 when Modine Manufacturing Company was considering buying the property. About that time DNR received a complaint alleging that 4,500 gallons of TCE had been spilled at the facility. Since that time, there have been numerous investigations conducted at the 179 Sunset Drive facility, including a PA and SI conducted by DNR. The current owner, Modine Manufacturing Company, is presently negotiating a Resource Conservation and Recovery Act (RCRA) Corrective Action Abatement Order on Consent (AOC) through the Permits Section of DNR's HWP. The AOC calls for investigation to determine the nature and extent of contamination on the facility property. However, investigation of the Hulett Lagoon could not be included in the AOC due to a RCRA domestic sewage exemption. Thus, the Former Hulett Lagoon site was referred to Superfund to be addressed under CERCLA.

### Waste/Source Sampling

Although over 2,000 cubic yards of sludge were removed from the lagoon during closure in 1989, PA/SI sampling, as well as previous sampling, document that TCE contaminated soil still remains in the lagoon area. Three samples, collected for the PA/SI near the previous location of the outfall pipe, contained TCE at 9.5 ppm, 0.24 ppm and 0.12 ppm. With such high levels of TCE documented in groundwater at the site (1,400 ppb), it is presumed that the majority of TCE, once deposited in the lagoon, has infiltrated into the bedrock. However, the TCE contaminated soil that remains in the lagoon may be a continuing source of contamination.

### Groundwater

PA/SI sampling has documented an observed release of TCE to the Ozark Aquifer in the area of the Former Hulett Lagoon site. MW-5, located immediately near the lagoon, contained TCE at 1,400 ppb. The City of Camdenton's Mulberry well, located less than 0.25 of a mile south of the lagoon showed 5.3 ppb TCE during PA/SI sampling. The Mulberry well was taken off line on February 2, 1999 due to the TCE contamination. When in use during the initial time period when TCE was detected, the Mulberry Well was the highest producing well of Camdenton's system, supplying an apportioned 2,107 people. There are three wells currently serving the city within two miles of the site. It is estimated that the TCE groundwater plume will begin moving toward the city's Blair well now that the Mulberry well has been shut off. The cone of depression created by pumping the Blair well, located 0.7 of a mile south-southwest, may influence the migration of the plume. The City of Camdenton's drinking water wells supply an estimated 3,010 people.

In addition to the Hulett lagoon, there is another source of TCE contamination that could be contributing to the groundwater plume that affected the City of Camdenton's Mulberry well. The manufacturing facility at 179 Sunset Drive has also been shown to contain TCE contaminated soil as well as TCE contaminated groundwater. The facility is located

approximately 500 feet northwest of the Mulberry Well. It is unknown at this time whether the Mulberry Well contamination is due in whole or in part to the lagoon contamination.

### Surface Water

All surface runoff from the lagoon area enters the tributary to Jarvis Hollow stream that borders the west side of the lagoon. This stream received overflow from the lagoon during operation; thus TCE was historically released to the creek. However, the streambed near the site is gravel, making sampling impractical. It has been ten years since the lagoon was closed; it is unlikely any TCE would be left in any surface material, soil or sediment, present in other parts of the stream. Current site conditions indicate the risk from any site surface runoff would be low since the TCE found in the soil at the lagoon was from the four to seven foot depth.

### Soil and Air

The potential for possible trespasser exposure to any of the TCE contaminated soil on the site is considered minimal. There are no people living on site, although there are three apartment buildings and one home that are within 200 feet of the site. Access to the site is not restricted. The reports of unauthorized dumping in the area near the lagoon indicate site security may be warranted.

### 8.0 RECOMMENDATIONS

The TCE groundwater contamination at the Former Hulett Lagoon site warrants remedial action. The contamination has already caused the closure of the one of the city's public drinking water wells, and the remaining wells are now at risk. Hydraulic control will need to be achieved at the source of the plume to prevent the migration of TCE to the other nearby wells, specifically the Blair well. Current investigation and remedial actions are ongoing at the 179 Sunset Drive facility, however, these activities do not include and will not address the Hulett lagoon contamination.

Although the majority of the sludge from the lagoon was removed, TCE contaminated soil remains. This contaminated soil may warrant removal. At a minimum, access to the site should be restricted.

Using the Hazard Ranking System (HRS) to evaluate site conditions, the Former Hulett Lagoon site scores above 28.5 and qualifies for proposal to the National Priorities List (NPL). The closing of a public drinking water supply well due to contamination from the site is a significant factor in this site evaluation.

Prepared by:

Valerie H. Wilder

Environmental Specialist Site Evaluation Unit

Reviewed by:

Juliann Wallen

Julieann Warren

Chief

Site Evaluation Unit

Approved by:

Gary T. Behrns

Chief

**Superfund Section** 

### REFERENCES

- 1. U.S. Environmental Protection Agency Hazard Ranking System, 40 CFR Part 300, Appendix A, 55 FR 51583, December 14, 1990.
- 2. U.S. Environmental Protection Agency, September, 1995, Superfund Chemical Data Matrix.
- 3. U.S. Geological Survey, 7.5-Minute Series. <u>Topographic Maps</u>. Camdenton, MO 1983, Decaturville, MO 1975, Green Bay Terrace 1983, HaHaTonka, 1982.
- 4. Missouri Department of Natural Resources, DEQ, Appendix A. <u>Locational Data Collection Sheet.</u> January 21, 1999. 2 pages.
- 5. Wilder, Valerie H., Environmental Specialist, HWP, DEQ, DNR to Former Hulett Lagoon and Camdenton Sludge Disposal Technical Files. Memo. <u>Site Visits/Sampling Events on December 1, 16, 1998 and January 21-22, 29, 1999</u>. February 1, 1999. 3 pages.
- 6. United States Department of Agriculture. Soil Conservation Service. <u>Soil Survey of Camden County, Missouri.</u> March 1994. 127 pages.
- 7. United States Department of Commerce. National Weather Service Office for State Climatology. Technical Paper No. 40. Rainfall Frequency Atlas of the United States for Durations from 30 Minutes to 24 Hours and Return Periods from 1 to 100 Years. 1961.
- 8. United States Department of Commerce. <u>Climatic Atlas of the United States.</u> June 1968.
- 9. Jacobs Engineering Group, Inc. Final Environmental Priorities

  Initiative/Preliminary Assessment. Modine Heat Transfer, Inc. (Formerly

  Sundstrand Tubular Products) September 1992. 58 pages plus Figures,
  Tables, and Appendices.
- 10. Missouri Department of Natural Resources. <u>Missouri Water Quality Basin Plans</u>. Volume 4. Osage and Gasconade Rivers (Including Lake of the Ozarks, Truman Reservoir, South Grand, Little Osage, Marmaton, Marais des Cygnes, Sac and Pomme de Terre Rivers, Tebo Creek and Big Piney River). 102 pages.

- B. R. Kesler, Regional Administrator, DEQ, JCRO to Trudy Marco, Grants
   Coordinator, Camdenton, MO. <u>Audit Report and Checklist</u>. June 20, 1986. 13
   pages.
- 12. Victoria M. Haines, Environmental, Health & Safety Counsel, Sundstrand to Valerie Wilder, HWP, DEQ, DNR. Letter. February 5, 1999. 7 pages plus Attachments.
- 13. State of Delaware, Office of Secretary of State. <u>Certificate of Incorporation, Dawson Metal Products, Inc.</u> June 12, 1972. 1 page
- 14. State of Missouri, James C. Kirkpatrick, Secretary of State. <u>Certificate of Authority</u>, <u>Dawson Metal Products</u>, Inc. No. F-157085. September 25, 1972. 1 page.
- 15. State of Missouri, Office of Secretary of State. <u>Application for an Amended</u>
  <u>Certificate of Authority for a Foreign Corporation, Sundstrand Tubular Products, Inc., (formerly Dawson Metal)</u> May 25, 1977. 2 pages.
- Missouri Department of Natural Resources. <u>Corrective Action Abatement Order on Consent</u> to Modine Manufacturing Company, 179 Sunset Drive, PO Box 636, Camdenton, MO 65020. 20 pages.
- 17. State of Missouri, Roy D. Blunt, Secretary of State. <u>Certificate of Withdrawal</u>, <u>Sundstrand Tubular Products</u>, Inc. No. F00157085. April 18, 1991. 1 page.
- 18. Law Environmental, Inc. Project No. 53-1543. <u>Environmental Site Assessment, Modine Heat Transfer, Inc.</u> November 1991. 5 pages plus Tables, Figures and Appendices.
- 19. Todd Crawford, Environmental Engineer to the Honorable Ken Mensendiek, Mayor, City of Camdenton. Letter. September 13, 1978. 1 page.
- 20. John W. Whitfield, Geologist and Gary St. Ivany, Lab Technician, applied Engineering & Urban Geology. <u>Engineering Geologic Report on Collapse</u>
  Potential of Camdenton Lagoons. September 14, 1978. 1 page.
- 21. James O. Jackson, P.E. to Frank Dolan, P.E., Environmental Engineer, DNR. Letter. Test Results from Camdenton. June 21, 1984. 7 pages.
- 22. Warren W. Riley, Jr., City Administrator, City of Camdenton to Frank Dolan, DNR. Letter. Second Sample Results. August 20, 1984. 4 pages.
- 23. Donald Roger Elder, City Administrator, City of Camdenton to Leora M. Reising, Environmental Specialist, JCRO, DNR. Letter. May 27, 1986. 1 page.

- 24. Missouri Department of Natural Resources, Missouri Clean Water Commission.

  <u>Construction Permit.</u> Permit Number 2263. 2 pages.
- 25. Missouri Department of Natural Resources, Laboratory Services Program, DEQ. <u>Pretreatment Monitoring Report, Sundstrand Tubular Products, Inc.</u> April 30, 1987. 3 pages.
- 26. Charles Ray, Missouri Engineering Corp. to Dave Friese, Water Pollution Control Program, DNR. Letter. <u>Sludge Analysis Report.</u> April 25, 1988. 1 page.
- 27. David Freise, P.E., Project Engineer to the Honorable Mac Webster, Mayor, City of Camdenton. Letter. <u>IDG 011 Camdenton, MO Lagoon Closure.</u> May 26, 1988. 1 page.
- 28. David Freise, P.E., Project Engineer to the Honorable Mac Webster, Mayor, City of Camdenton. Letter. <u>IDG 011 Hulett Lagoon</u>. November 2, 1989. 1 page.
- 29. Missouri Engineering Corporation. Specifications and Contract Documents
  Removal and Stockpiling of Sludge from the Hulett Lagoon Camdenton,
  Missouri. March 1989. 17 pages.
- 30. Charles Ray, Missouri Engineering Corporation. <u>Sludge Removal Project Hulett Lagoon Camdenton, MO.</u> July 21, 1989. 2 pages.
- 31. Kay Cyrus to Camdenton City Council. Regarding November 1, 1989, letter from Charles Ray, Missouri Engineering Corporation to Dave Welch, Attorney. 3 pages.
- 32. Ron McCormick to Mr. Hixson and Council Members. Letter. Cost Overrun in the Hulett Lagoon Project. October 20, 1989. 1 page.
- 33. Kent L. Hixson, City of Camdenton to Ronnie Testerman, DNR. Letter. <u>Hulett</u> <u>Lagoon Sludge Disposal Work Completion Summary.</u> April 9, 1990. 1 page.
- 34. Kent L. Hixson, City Administrator, City of Camdenton to Paul Kieler, Jacobs Engineering Group. Letter. <u>Hulett Lagoon Closure Process.</u> March 23, 1992. 1 page.
- 35. Department of Natural Resources, HWP. <u>Preliminary Assessment Sundstrand</u> <u>Camden County, Missouri.</u> January 31, 1992. 10 pages.

- 36. Missouri Department of Natural Resources, Environmental Services Program. <u>Site Sampling Report Sundstrand Site Camdenton MO July 20 through July 31, 1992.</u> December 31, 1992. 41 pages.
- 37. Arthur H. Groner, Chief, Permits Section, HWP, DEQ, DNR to Gary Behrns, Chief, Superfund Section, HWP, DEQ, DNR. Former Hulett Lagoon, Camdenton, Missouri September 8, 1998. 4 pages.
- 38. Allen, Brian J., Missouri Department of Natural Resources, Environmental Services Program. Combined Preliminary Assessment/Site Inspection Sampling Report Former Hulett Lagoon Site Camdenton, Missouri, Camden County. Field Activities Conducted January 6-7, 1999, January 21, 1999. 44 pages.
- 39. U.S. Department of Health & Human Services. Public Health Service. Agency for Toxic Substances and Disease Registry. <u>Toxicological Profile for Trichloroethylene</u>. February 20, 1996. 261 Pages.
- 40. Office of Emergency & Remedial Response, U.S. EPA. <u>Estimating Potential for Occurrence of DNAPL at Superfund Sites</u>. January 1992. 9 Pages.
- 41. Miesche M. Francis, Assistant Geologist, and Daniel J. Price, P.G., Senior Geologist, Dames and Moore to Richard Nussbaum, P.E., Groundwater Enforcement Unit Chief, HWP, DEQ, DNR. Letter Report. Subsurface Investigation Former Hulett Lagoon Camdenton Missouri Dames & Moore Job NO. 27397-023-045 November 4, 1996. 22 pages.
- 42. Missouri Department of Natural Resources, Division of Environmental Quality, Hazardous Waste Program. <u>Cleanup Levels for Missouri (CALM)</u>. September 1998. 31 pages plus Appendices, Figures, Tables and Attachments.
- 43. Elfrink, Neil, Geologist, Environmental Geology Section, GSP, DGLS, DNR to Valerie Wilder, Environmental Specialist, Superfund Section, HWP, DEQ, DNR. Memo. <u>Hydrogeologic Report for the Former Hulett Lagoon Site</u>. March 12, 1999. 11 pages.
- 44. CARES, University of Missouri Columbia and Missouri Department of Natural Resources, Public Drinking Water Program. <u>Public Drinking Water Map Camdenton 3010130, 6 Wells, 2 Chemical Sites, 1 Dealership, Camden County.</u> February 24, 1999. 4 pages.
- 45. Vincent Costa, Director of Public Works, to Valerie Wilder, HWP, DEQ, DNR. Letter. February 24, 1999. 3 pages.

- 46. Missouri Department of Natural Resources, Division of Environmental Quality.


  <u>Inventory of Missouri Public Water Systems</u>. 1998. 211 pages.
- 47. CARES, University of Missouri Columbia and Missouri Department of Natural Resources, Public Drinking Water Program. <u>Public Drinking Water Map Camden County, Missouri</u>. January 1996.
- 48. U.S. Department of Commerce, Bureau of the Census. <u>1990 Census of Population and Housing. Summary Population and Housing Characteristics, Missouri.</u> 1990 CPH-1-27. August 1991. 2 pages.
- 49. Thomas S. Sanicola, Environmental Engineer, Modine Manufacturing to Darleen Westcott, Environmental Engineer, HWP, DEQ, DNR. Letter. July 2, 1997. 9 pages.
- 50. Continental Analytical Services, Inc., and DNR Environmental Services Program.

  <u>Sample Results.</u> March 16, 1993. 42 pages.
- 51. Miller, Joyce L. Lake Sun-Leader, Camdenton, MO. Newspaper Article. <u>Plant Under DNR Gun.</u> May 23, 1998. 1 page.
- 52. Department of Natural Resources, Environmental Services Program. RCRA Sampling Investigation Report. Modine Site Burnau Private Well, Camdenton, MO. April 23, 1998. 8 pages.
- 53. Starbuck, Edie. Division of Geology and Land Survey. Monitoring Well Installation for Sundstrand PA/SI. Geologic Drill Log. November 9, 1994. 8 pages.
- 54. Kump, Chris, Environmental Engineer, Groundwater Unit, Hazardous Waste Program, DNR. <u>Comprehensive Groundwater Monitoring Evaluation, Modine Manufacturing Company, Camdenton, Missouri</u>. January 1998. 44 pages plus Appendices.
- 55. Price, Daniel J., R.G., Managing Principal, St. Louis Office, Dames & Moore to Mr. Thomas S. Sanicola, Environmental Engineer, Modine Manufacturing Company. Final Letter Report, Subsurface Investigation, Monitoring Well Installation Former Hulett Lagoon, Camdenton, Missouri, Dames & Moore Project No. 27397-035-045. October 19, 1998. 7 pages plus attachments.
- 56. Code of State Regulations, Rules of Department of Natural Resources, Division 20-Clean Water Commission, Chapter 7-Water Quality. Water Quality Standards, 10 CSR 20-7.031, March 30, 1994. 114 Pages.

- 57. Lyon, Mary, Policy Analyst, Missouri Department of Conservation to Julie Kelsey, Environmental Specialist, DNR. <u>Former Hulett Lagoon</u>. Letter. December 14, 1998. 1 page with enclosure.
- 58. Wilson, Mark R., Field Supervisor, Fish & Wildlife Service, United State Department of the Interior to Julie B. Kelsey, DNR, DEQ. Letter. December 18, 1998. 4 pages.
- 59. United States Department of the Interior, Fish and Wildlife Service. Green Bay Terrace, MO and HaHaTonka, MO Quadrangles. National Wetlands Inventory Maps. Aerial Photography April 1984. Maps Dated 1993.
- 60. Marble/Geocorr Geographic Correspondence Engine. Census Count
  Information. Internet address: http://www.oseda.missouri.edu/plue/geocorr/.
- 61. CARES, University of Missouri Columbia and Missouri Department of Natural Resources, Public Drinking Water Program. <u>Public Drinking Water Map Windsor Estates Nursing Home, 3069006, 1 Well, 0 Contaminant Sites, 0 Dealerships, Camden County.</u> October, 2, 1996. 2 pages.
- 62. CARES, University of Missouri Columbia and Missouri Department of Natural Resources, Public Drinking Water Program. <u>Public Drinking Water Map Linn Creek, 3010471, 1 Well, 0 Contaminant Sites, 0 Dealerships, Camden County.</u> October, 2, 1996. 2 pages.
- 63. CARES, University of Missouri Columbia and Missouri Department of Natural Resources, Public Drinking Water Program. <u>Public Drinking Water Map Southway Terrace MHP, 3048141, 1 Well, 0 Chemical Sites, 0 Dealerships, Camden County.</u> October, 2, 1996. 2 pages.

# APPENDIX A FIGURES

Figure 1: Site Location Map Former Hulett Lagoon Site Camden County, Missouri



Legend:


MIP/Soil boring locations/identifications

Monitoring well location/identification

99XXXX Sample collected at location indicated

Figure 2: lett Lagoon Site Soil Sampling Locations






▲ Hulett 10 991475

300

0

300 Feet



# **PHOTOGRAPHS**



**PHOTO 1** 

Former Hulett Lagoon Site. Camdenton, MO, Camden County. Photo taken on 10/1/74 by Ronnie Testerman, MDNR, JCRO. View looking northeast at the Hulett lagoon during operation. The northern portion of the lagoon shown in the photo was where influent from domestic sewage entered the lagoon. A small amount of the sludge from the Sundstrand influent, which came in on the south portion of the lagoon can be seen in the foreground of the photo near the wooden catwalk.




PHOTO 2

Former Hulett Lagoon Site. Camdenton, MO, Camden County. Photo taken on 10/1/74 by Ronnie Testerman, MDNR, JCRO. View looking east at the Hulett lagoon during operation. The picture was taken to show the sludge settling around the influent pipe area from Sundstrand.



**PHOTO 3** 

Former Hulett Lagoon Site. Camdenton, MO, Camden County. Photo taken sometime in June or July 1989 by Ronnie Testerman, MDNR, JCRO. View looking northeast at the Hulett lagoon during the beginning of the closure process. The dewatering had begun, but no sludge had been removed.



**PHOTO 4** 

Former Hulett Lagoon Site. Camdenton, MO, Camden County. Photo taken on 12/1/98 by Valerie Wilder, MDNR, Superfund. View looking northeast at the former lagoon. Remnants of the road that was around the lagoon on its berm can be seen in the foreground.



**PHOTO 5** 

Former Hulett Lagoon Site. Camdenton, MO, Camden County. Photo taken on 12/1/98 by Valerie Wilder, MDNR, Superfund. Photo taken looking north at the hillside west of the lagoon. The apartment complex buildings north of the lagoon can be seen through the trees.



### **PHOTO 6**

Former Hulett Lagoon Site. Camdenton, MO, Camden County. Photo taken on 12/1/98 by Valerie Wilder, MDNR, Superfund. Photo taken looking south-southeast. The road surrounding the lagoon on the berm is seen in the right-hand side of the photo. The former lagoon was in the area in the left-hand side of the photo.



**PHOTO 7** 

Former Hulett Lagoon Site. Camdenton, MO, Camden County. Photo taken on 1/21/99 by Valerie Wilder, MDNR, Superfund. Photo taken looking northeast at Geoprobe work during PA/SI sampling.



**PHOTO 8** 

Former Hulett Lagoon Site. Camdenton, MO, Camden County. Photo taken on 1/21/99 by Valerie Wilder, MDNR, Superfund. Photo taken looking north-northeast at Geoprobe work during PA/SI sampling. The apartment complex north of the lagoon can be seen through the trees.

# **PRESCORE**

# PREscore 4.1

PAGE:

1

#### NPL Characteristics Data Collection Form

### Record Information **ÍÍÍÍÍÍÍÍÍÍÍÍÍÍ**

- 1. Site Name: Former Hulett Lagoon (as entered in CERCLIS)
- 2. Site CERCLIS Number:
- 3. Site Reviewer: Valerie H. Wilder
- 4. Date: 3/26/99
- 5. Site Location: Camdenton/Camden, MO (City/County, State)
- 6. Congressional District: 4
- 7. Site Coordinates: Single

Latitude: 92ø45'17.0" Longitude: 038ø00'41.1"

> Site Description iiiiiiiiiiiiiiii

- 1. Setting: Urban
- 2. Current Owner: Municipal
- 3. Current Site Status: Inactive
- 4. Years of Operation: Inactive Site, from and to dates: 1961-1989
- 5. How Initially Identified: RCRA Notification
- 6. Entity Responsible for Waste Generation:
  - Manufacturing
  - Fabr. Struc. Metal Prod.
- 7. Site Activities/Waste Deposition:
  - Surface Impoundment
  - Discharge to Sewer/Surface Water

# PREscore 4.1 NPL Characteristics Data Collection Form

PAGE:

2

Waste Description 1111111111111111

- 8. Wastes Deposited or Detected Onsite:
  - Solvents

Response Actions

- 9. Response/Removal Actions:
  - Drinking Water Well Has Been Closed

RCRA Information iiiiiiiiiiiiiiiii

- 10. For All Active Facilities, RCRA Site Status:
  - Not Applicable

- 11. Workers Present Onsite: No
- 12. Distance to Nearest Non-Worker Individual: > 10 Feet 1/4 Mile
- 13. Residential Population Within 1 Mile: 2143.0
- 14. Residential Population Within 4 Miles: 5928.0

- 15. Local Drinking Water Supply Source:
  - Ground Water (within 4 mile distance limit)
- 16. Total Population Served by Local Drinking Water Supply Source: 3010.0
- 17. Drinking Water Supply System Type for Local Drinking Water Supply Sources:

# PREscore 4.1 HRS DOCUMENTATION RECORD

PAGE: 1

 Site Name: Former Hulett Lagoon (as entered in CERCLIS)

2. Site CERCLIS Number:

3. Site Reviewer: Valerie H. Wilder

4. Date: 3/26/99

5. Site Location: Camdenton/Camden, MO (City/County, State)

6. Congressional District: 4

7. Site Coordinates: Single

Latitude: 92ø45'17.0" Longitude: 038ø00'41.1"

Site names, and references to specific parcels or properties, are provided for general identification purposes only. Knowledge regarding the extent of sites will be refined as more information is developed during the RI/FS and even during implementation of the remedy.

- Municipal (Services over 25 People)
- 18. Surface Water Adjacent to/Draining Site:
  - Stream

1. WASTESTREAM QUANTITY SUMMARY TABLE, SOURCE: Lagoon

PAGE: 3

2. SOURCE HAZARDOUS WASTE QUANTITY FACTOR TABLE

ÚÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄ	ÄÄÄÄÄÄÄÄÄÄÄÄÄ	ÄÄÄÄÄÄÄÄ	ÄÄÄÄÄÄÄÄÄ	ÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄ	ÄÄÄ;
³a. Source ID		3 Lago			3
ÃÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄ	ÄÄÄÄÄÄÄÄÄÄÄ	ÄÄÄÄÄÄÄÄ	ÄÄÄÄÄÄÄÄÄÄ	äääääääääääääääääääääääääääääääääääääää	ÄÄÄ´
<sup>3</sup> b. Source Type		3 Surfa	ace Impound	dment	3
ÃÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄ	ÄÄÄÄÄÄÄÄÄÄ	ÄÄÄÄÄÄÄÄ	ÄÄÄÄÄÄÄÄÄÄ	ÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄ	ÄÄÄ´
³c. Secondary Source Type		3 N	.A.		3
ÃÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄ	ÄÄÄÄÄÄÄÄÄÄ	`ÄÄÄÄÄÄÄÄÄ	ÄÄÄÄÄÄÄÄÄÄÄ	ÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄ	ÄÄÄ´
<pre>3d. Source Vol.(yd3/gal) 3 Source</pre>			0.00	<sup>3</sup> 5445.00	3
ÃÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄ	ÄÄÄÄÄÄÄÄÄÄ	ÄÄÄÄÄÄÄÄ	ÄÄÄÄÄÄÄÄÄÄ	ÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄ	ÄÄÄ´
³e. Source Volume/Area Value		<sup>3</sup> 4.19	E+02		3
ÃÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄ	ÄÄÄÄÄÄÄÄÄÄÄ	ÄÄÄÄÄÄÄÄ	ÄÄÄÄÄÄÄÄÄÄ	ÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄ	ÄÄÄ´
3f. Source Hazardous Constituen	t Quantity	<sup>3</sup> 0.00	E+00	•	3
3 (HCQ) Value (sum of 1b)		3			3
ÃÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄ	ÄÄÄÄÄÄÄÄÄÄÄ	ÄÄÄÄÄÄÄÄ	ÄÄÄÄÄÄÄÄÄÄ	ÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄ	ÄÄÄ´
<sup>3</sup> g. Data Complete?		3	NO		3
ÃÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄ	ÄÄÄÄÄÄÄÄÄÄÄ	ĠÄÄÄÄÄÄÄ	ÄÄÄÄÄÄÄÄÄÄ	ÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄ	ÄÄÄ′
3h. Source Hazardous Wastestrea	m Quantity	3 0.00	E+00		3
3 (WSQ) Value (sum of 1f)		3			3
ÃÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄ	ÄÄÄÄÄÄÄÄÄÄ	ÄÄÄÄÄÄÄÄ	ÄÄÄÄÄÄÄÄÄÄ.	ÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄ	ÄÄÄ´
<sup>3</sup> i. Data Complete?		3	NO		3
ÃÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄ	ÄÄÄÄÄÄÄÄÄÄ	<b>\ÄÄÄÄÄÄÄ</b> Ä	ÄÄÄÄÄÄÄÄÄÄÄÄ	<mark>ÄÄÄÄÄÄÄÄÄÄÄ</mark> ÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄ	ÄÄÄ´
3k. Source Hazardous Waste Quan	tity (HWQ)	<sup>3</sup> 4.19	E+02		3
yalue (2e, 2f, or 2h)		3			3
<u>ÀÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄ</u>	ÄÄÄÄÄÄÄÄÄÄ	<b>\ÄÄÄÄÄÄÄ</b> Ä	ÄÄÄÄÄÄÄÄÄ	ÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄ	ÄÄÄÙ
Source	Depth L:	iquid	Concent.	Units	
Hazardous Substances	(feet)				
<b>ĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀ</b> ĀĀ	ÄÄÄÄÄÄÄÄÄÄ	<b>\ÄÄÄÄÄÄÄÄ</b>	ÄÄÄÄÄÄÄÄÄ	<b>ÄÄÄÄÄÄÄÄÄÄÄÄÄ</b> ÄÄ	ÄÄÄ
Trichloroethylene	> 2	YES	1.2E-01	ppm	

### 3. SITE HAZARDOUS WASTE QUANTITY SUMMARY

•			Constituent or	Hazardous
	Migration	Vol. or Area	Wastestream	Waste Qty.
			Value (2f,2h)	Value (2k)
<b>ÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄ</b> ÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄ	ÄÄÄÄÄÄÄÄÄÄÄÄ	<u>ĀĀĀĀĀĀĀĀĀĀĀ</u> Ā	ÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄ	ÄÄÄÄÄÄÄÄÄ
1 Lagoon	GW-SW-SE-A	4.19E+02	0.00E+00	4.19E+02

PAGE:

4. PATHWAY HAZARDOUS WASTE OUANTITY AND WASTE CHARACTERISTICS SUMMARY TABLE

3 Contaminant Values 3 HWOVs\* 3 WCVs\*\*3 <sup>3</sup> Migration Pathway <sup>3</sup>Toxicity/Mobility 1.00E+01 <sup>3</sup> 100 ³ 6 <sup>3</sup> SW: Overland Flow, DW <sup>3</sup>Tox./Persistence 4.00E+00 3 100 <sup>3</sup> 3 <sup>3</sup> SW: Overland Flow, HFC<sup>3</sup>Tox./Persis./Bioacc. 2.00E+02 <sup>3</sup> 100 <sup>3</sup> 10 3 SW: Overland Flow, Env3Etox./Persis./Bioacc. 2.00E+03 100 <sup>3</sup> SW: GW to SW. DW <sup>3</sup>Tox./Persistence 4.00E+00 3 100 <sup>3</sup> 3 <sup>3</sup> SW: GW to SW, HFC <sup>3</sup>Tox./Persis./Bioacc. 2.00E+02 <sup>3</sup> 100 <sup>3</sup> 10 <sup>3</sup> SW: GW to SW, Env <sup>3</sup>Etox./Persis./Bioacc. 2.00E+03 <sup>3</sup> 100 <sup>3</sup> 18 3 Soil Exposure: Resident 3 Toxicity 0.00E+00 3 0 3 0 <sup>3</sup> Soil Exposure: Nearby <sup>3</sup>Toxicity 0.00E+00 3 0 3 0 <sup>3</sup>Toxicity/Mobility 1.00E+01 3 100 з 6 \* Hazardous Waste Quantity Factor Values

\*\* Waste Characteristics Factor Category Values

Note: SW = Surface Water

GW = Ground Water

DW = Drinking Water Threat
HFC = Human Food Chain Threat
Env = Environmental Threat

# PREscore 4.1 HRS DOCUMENTATION RECORD

- Site Name: Former Hulett Lagoon (as entered in CERCLIS)
- 2. Site CERCLIS Number:
- 3. Site Reviewer: Valerie H. Wilder
- 4. Date: 3/26/99
- 5. Site Location: Camdenton/Camden, MO (City/County, State)
- 6. Congressional District: 4
- 7. Site Coordinates: Single

Latitude: 92ø45'17.0" Longitude: 038ø00'41.1"

Site names, and references to specific parcels or properties, are provided for general identification purposes only. Knowledge regarding the extent of sites will be refined as more information is developed during the RI/FS and even during implementation of the remedy.

PAGE:

2

1. WASTESTREAM QUANTITY SUMMARY TABLE, SOURCE: Lagoon

³a. Wastestream ID 3b. Hazardous Constituent Quantity (C) (lbs.) 3 0.00 3c. Data Complete? NO <sup>3</sup>d. Hazardous Wastestream Quantity (W) (lbs.) <sup>3</sup> ³e. Data Complete? 3f. Wastestream Quantity Value (W/5,000) 3 0.00E+00 

# PRESCORE 4.1 . PAGE: 3 WASTE QUANTITY

### 2. SOURCE HAZARDOUS WASTE QUANTITY FACTOR TABLE

¿ÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄ	
3a. Source ID 3 Lagoon 3	
ĨĠĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸ	
3b. Source Type 3 Surface Impoundment 3	
ĨĠĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸ	
3c. Secondary Source Type 3 N.A. 3	
ĨĠĠĠĠĠĠĠĠĠĠĠĠĠĠĠĠĠĠĠĠĠĠĠĠĠĠĠĠĠĠĠĠĠĠĠĠĠ	
3d. Source Vol.(yd3/gal) 3 Source Area (ft2) 3 0.00 3 5445.00 3	
<i></i> ĊĠĠĠĠĠĠĠĠĠĠĠĠĠĠĠĠĠĠĠĠĠĠĠĠĠĠĠĠĠĠĠĠĠĠĠĠ	
³e. Source Volume/Area Value ³ 4.19E+02 ³	
Ĩĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸ	
3f. Source Hazardous Constituent Quantity 3 0.00E+00	
3 (HCQ) Value (sum of 1b)	
Ĩĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸ	
<sup>3</sup> g. Data Complete? <sup>3</sup> NO <sup>3</sup>	
ĨĠĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸ	
3h. Source Hazardous Wastestream Quantity 3 0.00E+00	
3 (WSQ) Value (sum of 1f)	
ĨĠĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸ	
3i. Data Complete? 3 NO 3	
`ÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄ	
3k. Source Hazardous Waste Quantity (HWQ) 3 4.19E+02	
<sup>3</sup> Value (2e, 2f, or 2h) <sup>3</sup>	
ŰĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀ	
Source Depth Liquid Concent. Units	
Hazardous Substances (feet)	
<u>ÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄ</u>	
Trichloroethylene > 2 YES 1.2E-01 ppm	
-	

PAGE: 4 WASTE QUANTITY

3. SITE HAZARDOUS WASTE QUANTITY SUMMARY

Constituent or Hazardous Migration Vol. or Area Wastestream Waste Qty. Pathways Value (2e) Value (2f,2h) Value (2k) Waste Qty. No. Source ID GW-SW-SE-A 4.19E+02 0.00E+00 1 Lagoon 4.19E+02

4. PATHWAY HAZARDOUS WASTE QUANTITY AND WASTE CHARACTERISTICS SUMMARY TABLE

Contaminant Values 3 HWOVs\* 3 WCVs\*\*3 Migration Pathway <sup>3</sup> Ground Water <sup>3</sup> Toxicity/Mobility 1.00E+01 <sup>3</sup> 100 <sup>3</sup> 6 3 SW: Overland Flow, DW 3Tox./Persistence 4.00E+00 3 100 з 3 <sup>3</sup> SW: Overland Flow, HFC<sup>3</sup>Tox./Persis./Bioacc. 2.00E+02 <sup>3</sup> 100 <sup>3</sup> 10 3 SW: Overland Flow, Env3Etox./Persis./Bioacc. 2.00E+03 3 100 <sup>3</sup> 18 4.00E+00 3 100 3 3 3 3 SW: GW to SW, DW 3Tox./Persistence <sup>3</sup> SW: GW to SW, HFC <sup>3</sup>Tox./Persis./Bioacc. 2.00E+02 <sup>3</sup> 100 <sup>3</sup> 10 3 SW: GW to SW. Env 3Etox./Persis./Bioacc. 2.00E+03 3 100 <sup>3</sup> 18 0.00E+00 3 0 3 0 3 Soil Exposure: Resident 3 Toxicity 0.00E+00 3 0 3 0 3 Soil Exposure: Nearby 'Toxicity <sup>3</sup>Toxicity/Mobility 1.00E+01 3 100 3 6 

\* Hazardous Waste Quantity Factor Values

\*\* Waste Characteristics Factor Category Values

Note: SW = Surface Water

GW = Ground Water

DW = Drinking Water Threat
HFC = Human Food Chain Threat
Env = Environmental Threat

 Site Name: Former Hulett Lagoon (as entered in CERCLIS)

2. Site CERCLIS Number:

3. Site Reviewer: Valerie H. Wilder

4. Date: 3/26/99

5. Site Location: Camdenton/Camden, MO (City/County, State)

6. Congressional District: 4

7. Site Coordinates: Single

Latitude: 92ø45'17.0" Longitude: 038ø00'41.1"

Site names, and references to specific parcels or properties, are provided for general identification purposes only. Knowledge regarding the extent of sites will be refined as more information is developed during the RI/FS and even during implementation of the remedy.

PAGE:

1. WASTESTREAM QUANTITY SUMMARY TABLE, SOURCE: Lagoon

3a. Wastestream ID 3b. Hazardous Constituent Quantity (C) (lbs.) 3 0.00 3c. Data Complete? NO 3d. Hazardous Wastestream Quantity (W) (lbs.) 3 0.00 <sup>3</sup>e. Data Complete? 3f. Wastestream Quantity Value (W/5,000) 3 0.00E+00 

PAGE: 3

# 2. SOURCE HAZARDOUS WASTE QUANTITY FACTOR TABLE

ŢŖĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸ	säääääääääääääääääääääääääääääääääääää
3a. Source ID 3 Lagoon	3
ĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸ	ÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄ
3b. Source Type 3 Surface Impound	dment 3
ÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄ	
3c. Secondary Source Type 3 N.A.	3
ÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄ	مُحْمَدُمُحُمِّمُ حُمِّمُ حُمْمُ
3d. Source Vol.(yd3/gal) 3 Source Area (ft2) 3 0.00	<sup>3</sup> 5445.00 <sup>3</sup>
AÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄ	
³e. Source Volume/Area Value ³ 4.19E+02	3
ĬĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀ	ÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄ
3f. Source Hazardous Constituent Quantity 3 0.00E+00	3
3 (HCO) Value (sum of 1b)	3
ÃÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄ	~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~
<sup>3</sup> q. Data Complete? <sup>3</sup> NO	3
ĬĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀ	~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~
h. Source Hazardous Wastestream Quantity 3 0.00E+00	3
3 (WSQ) Value (sum of 1f)	3
	***************************************
3i. Data Complete? 3 NO	3
3k. Source Hazardous Waste Quantity (HWQ) 3 4.19E+02	3
<sup>3</sup> Value (2e, 2f, or 2h)	3
value (2e, 21, 01 2n) àääääääääääääääääääääääääääääääääääää	
иликалалалалалалалалалалалалалалалалалал	UAAAAAAAAAAAA
Source Depth Liquid Concent.	Units
Hazardous Substances (feet)	
• • • • • • • • • • • • • • • • • • • •	*****************
Trichloroethylene > 2 YES 1.2E-01	
111Chiotoechytene > 2 1E5 1.2E-01	ppm

PREscore 4.1

PAGE: 4 WASTE QUANTITY

3. SITE HAZARDOUS WASTE QUANTITY SUMMARY

Constituent or Hazardous Migration Vol. or Area Wastestream Waste Qty.
No. Source ID Pathways Value (2e) Value (2f,2h) Value (2k) 1 Lagoon GW-SW-SE-A 4.19E+02 0.00E+00 4.19E+02

5

PREscore 4.1
WASTE OUANTITY

4. PATHWAY HAZARDOUS WASTE QUANTITY AND WASTE CHARACTERISTICS SUMMARY TABLE

Contaminant Values 3 HWOVs\* 3 WCVs\*\*3 <sup>3</sup> Migration Pathway 1.00E+01 3 100 3 6 3 <sup>3</sup> Ground Water <sup>3</sup>Toxicity/Mobility 3 SW: Overland Flow, DW 3Tox./Persistence 4.00E+00 3 100 <sup>3</sup> 3 3 SW: Overland Flow, HFC3Tox./Persis./Bioacc. 2.00E+02 3 100 <sup>3</sup> 10 3 SW: Overland Flow, Env3Etox./Persis./Bioacc. 2.00E+03 100 <sup>3</sup> 18 <sup>3</sup>Tox./Persistence 4.00E+00 3 100 з 3 3 SW: GW to SW, DW 3 SW: GW to SW, HFC <sup>3</sup>Tox./Persis./Bioacc. 2.00E+02 <sup>3</sup> 100 <sup>3</sup> 10 <sup>3</sup> SW: GW to SW, Env <sup>3</sup>Etox./Persis./Bioacc. 2.00E+03 <sup>3</sup> 100 <sup>3</sup> 18 0.00E+00 3 0 з О 3 Soil Exposure:Resident'sToxicity 0.00E+00 3 0 3 0 <sup>3</sup> Soil Exposure: Nearby <sup>3</sup>Toxicity 1.00E+01 3 100 <sup>3</sup> 6 <sup>3</sup>Toxicity/Mobility 

\* Hazardous Waste Quantity Factor Values

\*\* Waste Characteristics Factor Category Values

Note: SW = Surface Water

GW = Ground Water

DW = Drinking Water Threat
HFC = Human Food Chain Threat
Env = Environmental Threat

## PREscore 4.1 HRS DOCUMENTATION RECORD

- Site Name: Former Hulett Lagoon (as entered in CERCLIS)
- 2. Site CERCLIS Number:
- 3. Site Reviewer: Valerie H. Wilder
- 4. Date: 3/26/99
- 5. Site Location: Camdenton/Camden, MO (City/County, State)
- 6. Congressional District: 4
- 7. Site Coordinates: Single

Latitude: 92ø45'17.0" Longitude: 038ø00'41.1"

Site names, and references to specific parcels or properties, are provided for general identification purposes only. Knowledge regarding the extent of sites will be refined as more information is developed during the RI/FS and even during implementation of the remedy.

PAGE:

2

1. WASTESTREAM QUANTITY SUMMARY TABLE, SOURCE: Lagoon

<sup>3</sup>a. Wastestream ID <sup>3</sup>b. Hazardous Constituent Quantity (C) (lbs.) <sup>3</sup> 0.00 3c. Data Complete? NO 3d. Hazardous Wastestream Quantity (W) (lbs.) 3 0.00 ³e. Data Complete? NO of. Wastestream Quantity Value (W/5,000) 3 0.00E+00 

PAGE: 3

2. SOURCE HAZARDOUS WASTE QUANTITY FACTOR TABLE

<sub>\$</sub> ĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀĀ
3a. Source ID 3 Lagoon 3
Ĩĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸ
3b. Source Type 3 Surface Impoundment 3
^ <u>ឝឝឝឝឝឝឝឝឝឝឝឝឝឝឝឝឝឝឝឝឝឝឝឝឝឝឝឝឝឝឝឝឝឝឝឝ</u>
³c. Secondary Source Type <sup>3</sup> N.A. <sup>3</sup>
Ĩĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸ
3d. Source Vol.(yd3/gal) 3 Source Area (ft2) 3 0.00 3 5445.00 3
ĨÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄ
³e. Source Volume/Area Value ³ 4.19E+02 ³
Ĩĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸ
3f. Source Hazardous Constituent Quantity 3 0.00E+00
3 (HCO) Value (sum of 1b)
ĨÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄ
<sup>3</sup> g. Data Complete? <sup>3</sup> NO <sup>3</sup>
Ĩĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸĸ
3h. Source Hazardous Wastestream Quantity 3 0.00E+00
3 (WSQ) Value (sum of 1f)
ÃÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄ
3i. Data Complete? 3 NO 3
AÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄ
³k. Source Hazardous Waste Quantity (HWQ) ³ 4.19E+02
3 Value (2e, 2f, or 2h) 3
<u>ОДАДАДАДАДАДАДАДАДАДАДАДАДАДАДАДАДАДАДА</u>
Source Depth Liquid Concent. Units
Hazardous Substances (feet)
nazaldous substances ÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄÄ
Trichloroethylene > 2 YES 1.2E-01 ppm

PREscore 4.1
WASTE QUANTITY

PAGE: 4

3. SITE HAZARDOUS WASTE QUANTITY SUMMARY

PAGE:

5

4. PATHWAY HAZARDOUS WASTE QUANTITY AND WASTE CHARACTERISTICS SUMMARY TABLE

Contaminant Values <sup>3</sup> Migration Pathway 3 HWOVs\* 3 WCVs\*\*3 <sup>3</sup> Ground Water <sup>3</sup>Toxicity/Mobility 1.00E+01 <sup>3</sup> 100 з 6 3 SW: Overland Flow, DW 3Tox./Persistence 4.00E+00 3 100 <sup>3</sup> 3 <sup>3</sup> 10 3 SW: Overland Flow, HFC3Tox./Persis./Bioacc. 2.00E+02 3 100 3 SW: Overland Flow, Env3Etox./Persis./Bioacc. 2.00E+03 100 <sup>3</sup> 18 3 SW: GW to SW, DW <sup>3</sup>Tox./Persistence 4.00E+00 3 100 <sup>3</sup> 3 <sup>3</sup>Tox./Persis./Bioacc. 2.00E+02 <sup>3</sup> 100 <sup>3</sup> 10 <sup>3</sup> SW: GW to SW, HFC 3 SW: GW to SW, Env 3Etox./Persis./Bioacc. 2.00E+03 3 100 <sup>3</sup> 18 з 0 3 Soil Exposure: Resident 3 Toxicity 0.00E+00 3 0 <sup>3</sup> Soil Exposure: Nearby <sup>3</sup>Toxicity 0.00E+00 3 0 3 0 1.00E+01 3 100 3 6 Toxicity/Mobility 

\* Hazardous Waste Quantity Factor Values

\*\* Waste Characteristics Factor Category Values

Note: SW = Surface Water

GW = Ground Water

DW = Drinking Water Threat
HFC = Human Food Chain Threat
Env = Environmental Threat

# **DISPOSITION**

**EPA** 

# POTENTIAL HAZARDOUS WASTE SITE TENTATIVE DISPOSITION

REGION VII

SITE NUMBER


File this form in the regional Hazardous Waste Log File and submit a copy to: U.S. Environmental Protection Agency, Site Tracking System; Hazardous Waste Enforcement Task Force (EN-335); 401 M St., SW; Washington, D.C. 20460.

I. SIT	I. SITE IDENTIFICATION									
A. SITE NAME Former Hulett Lagoon					B. STREET  Dawson Road					
c. city Camdenton					D. STATE E. ZIP CODE 65020					
II. TEN	TATIVE DISPOSITION									
Indicate the recommended action(s) and agend	cy(ies) that should be in	volved by markin	ng 'X' in the a	ppropriate t	ooxes.					
RE			-		1					
A. NO ACTION NEEDED - NO HAZARD		Mark 'X'	EPA	STATE	LOCAL	PRIVATE				
B. INVESTIGATIVE ACTION(S) NEEDED (If										
C. REMEDIAL ACTION (If yes, complete Sec		Х								
D. ENFORCEMENT ACTION (If yes, specify in EPA or the State and what type of enforcement	by the			Х						
E. RATIONALE FOR DISPOSITION Using the Hazard Ranking System (HRS) to evaluate site conditions, the Former Hulett Lagoon site scores above 28.5 and qualifies for proposal to the National Priorities List (NPL). The closing of a public drinking water supply well due to contamination from the site is a significant factor in this site evaluation.										
F. INDICATE THE ESTIMATED DATE OF FIN (mo,day,yr) September 1999	NAL DISPOSITION				OPMENT PLA N WHICH THE					
H. PREPARER INFORMATION										
<sup>1. NAME</sup> Valerie Wilder				3. DATE (mo., day, & yr.) March 30, 1999						
III. INVESTIGATIVE ACTIVITY NEEDED										
A. IDENTIFY ADDITIONAL INFORMATION NI The state will attempt to negotiat site will be recommended for list	e an agreement			the PRI	Ps. If neg	otiations	are not	succes	sful, the	
B. PROPOSED INVESTIGATIVE ACTIVITY (I	Detailed Information)									
METHOD FOR OBTAINING NEEDED ADDITIONAL INFO.	2. SCHEDULED DATE OF ACTION (mo,day,& yr)	3. TO BE PEI BY (EPA, Con State, Etc.)		4. ESTIN		5. REMAR	rks			
a. TYPE OF INSPECTION (1) (2)										
b. TYPE OF MONITORING					,					
(1)										
(2)										
c. TYPE OF SAMPLING (1)										
(2)										

continued From Front								
(1)								
(2)								
(1)								
(2)								
C. ELABORATE ON ANY	OF THE INF	ORMATION PR	OVIDED IN PART I	3(on front a	and above	AS NEEDED TO ID	ENTIFY ADDITIONAL INVES	STIGATIVE WORK.
D. ESTIMATE MANHOUR	RS BY ACTIO	N AGENCY						
1. ACTION AGENCY		OTAL ESTIMATESTIGATIVE AC	TED MANHOURS F	OR	1. ACT	ION AGENCY	2. TOTAL ESTIMATE INVESTIGATIVE ACT	
a. EPA					b. STAT	ΓE		
c. EPA CONTRACTOR					d. OTH	ER (specify)		
IV. REMEDIAL ACT	rions						指有品质和特殊	
A. SHORT TERM/EMERO alternate water supply, etc.							under immediate control, e.g.	, restrict access, provide
1. ACTION		2. EST. START DATE mo, day, yr	3. EST. END DATE mo, day, yr	4. ACT AGENC EPA, St Private	Y ate,	5. ESTIMATED COST	6. SPECIFY 311 OR OTH THE MAGNITUDE OF TH	
Excavation of TCE contam	inated soil					\$	41	
						\$		
						\$		
						\$		
						\$		
						\$		
B. LONG TERM STRATE Key Words for each of the	GY (On Site a actions to be	and Off-Site): L used in the spa	ist all long term solu ces below.	tions, e.g.,	excavatio	n, removal, ground	water monitoring wells, etc. S	ee instructions for a list of
1. ACTION		2. EST. START DATE mo, day, yr	3. EST. END DATE mo, day, yr	4. ACT AGENO EPA, St Private	Y ate,	5. ESTIMATED COST	6.SPECIFY 311 OR OTHE THE MAGNITUDE OF TH	
Groundwater cleanup of To	CE plume				767	\$		
						\$		
						\$		
						\$		
						\$		
						\$		
C. ESTIMATED MANHOL	JRS AND CO	ST BY ACTION	AGENCY					
1. ACTION AGENCY		EST. MAN- OR REMEDIAL ES	3. TOTAL EST FOR REMEDIA ACTIVITIES		1. ACT	ION AGENCY	2. TOTAL EST. MAN- HOURS FOR REMEDIAL ACTIVITIES	3. TOTAL EST. COST FOR REMEDIAL ACTIVITIES
a. EPA					b. STATE			
c. PRIVATE PARTIES					d. OTHER (	specify)		

# Former Hulett Lagoon Site U.S.G.S. Topographic Maps Reference 3





Former Hulett Lagoon Site Combined PA/SI Reference 4

# Appendix A Department of Natural Resources Division of Environmental Quality

### **Locational Data Collection Sheet**

This sheet is used to record required locational data. Attach the *Optional Locational Data Collection Sheet* if you need to record additional information.

1. Facility or Site (Name and Address)	rmer	Hulett	Lappon Site -	- O.l mile	NE of	
1. Facility or Site (Name and Address) For intersection of Dawson Rd	3 Sun	iset Dri	ve Camder	nton MO	65020	
			50.8 T	,		
2. Facility ID, Permit Number or Other Ide	ntifier					
3. Data Owner (1) DEQ/ADM (2	) APCP	(3) ESP	(4) HWP (5) LRF	(6) PDWP	(7) SW	<b>VCP</b>
(8) SWMP (9) TAP (10) WPCP	Other	:				
4. Locational Data (Leave blank for area features	s, such as r	oads; streams o	r site boundaries.)	Latitude	Longitud	le 👢
5. Unit of Measurement (1) Degrees, Min	utes, Seco	onds or (2)	Decimal Degrees	38.01143	92.754	171
6. Method of Determining Location (Indicate	e the metho	od used to deter	mine the latitude and longitu	de coordinates.)		
Address Matching (Geocoding)	Code	The Charles	Differential Post Pro	cessing	Carrie of Contract Co	G3
Block/Group	A2	14.00	Precise Positioning	Service		G4
Digitization	A6	4	Signal Averaging			G5
Nearest Street Intersection	A4		Real Time Differenti	al Processing		Ġ6
Other Address Matching	AO		Interpolation		8	的技術
Primary Street Name	A5		Aerial Photograph			12
Street Centerline	А3		Map			11
Zip Code Centroid (Center)	Z1		Satellite Imagery			13
Census - 1990	1		Other Interpolation			10
Block Centroid (Center)	C1	100	Other		*	回婚的
Block/Group Centroid	C2	44.74	Classic Survey			S1
Block/Track Centroid	C3		Land Survey			P1
Other Centroid	СО		Loran C Code			L1
Global Positioning System	為感觉		Quarter Section Des	scription		S2
Static Mode	G1		Unknown			UN
Kinematic Mode (Dynamic)	G2	1000	The state of the s			
7. Locational Data Accuracy (+/- meters)	:	38.1 FF		The second secon		
8. Type of Locational Data Represented	(P) Si	ngle Point	(L) Line	(A) Area	1 1606	
9. Horizontal Datum (Indicate the horizontal dat	um used to	locate the colle	ction site feature.)	P		
(1) NAD27) (2) NAD83, (3) WGS84,	(U) L	Jnknown	Other:			

# Appendix A Department of Natural Resources Division of Environmental Quality

## **Locational Data Collection Sheet**

Continued

ollection Site Featu	ıre		Code	Nor	theast Comer of the Fa	cility or Site		١		
Bridge			.BR	Non	Northwest Corner of the Facility or Site					
Building			BL	Pile	(					
Center of Facility or	r of Facility or Site		enter of Facility or Site	te		Pipe	e (Outfall, Intake, Point	of Connection	on, Break, etc.)	(
Described by Descriptive Comment Field			DC	Rail	Rail Road					
Described by Site Na	ame		DS	Roa	nd					
Equipment Point of Use			EU	Sou	theast Corner of the Fa	acility or Site		1		
Intersection (Road, Pipe, Street, etc.)			IN	Sou	thwest Corner of the F	acility or Site	)	1		
Lagoon or Pond			LS	Sta	ck					
Loading Facility or Dock			LD	Tan	k, Standpipe, Tower					
Main Access Point (Entrance, Gate, etc.)			MG	Ven	nt					
Main Office			MA	Wel	II			1		
Missouri Land Surve	y Monume	ent	MM	Unk	nown					
Monitoring Station			AM	Other (use Collection Site Descriptive Comments below )						
east end of pipe 12; or s	tarted at the	NW corner, w	ent clockwise	around the	eature represented by the site, recorded 27 points a	and ended bac	te Feature. For example, an ou k at the starting point.)			
east end of pipe 12; or s	colle Che	a NW comer, w	ent clockwise	around the	site, recorded 27 points a	and ended bac	te Feature: For example, an out the starting point.)			
east end of pipe 12; or s  Reading was  Source of Locati	colle Ca	a NW comer, w	ent clockwise	around the	site, recorded 27 points a	and ended bac	k at the starting point.)	ilfə		
east end of pipe 12; or s  Reading www  Source of Locati  Description	colle Cac	a SWRO	ent clockwise	around the	site, recorded 27 points a the forwar (	MOON N1	ex at the starting point.)  EPA Headquarters	ilfə'		
east end of pipe 12; or s  Reading www  Source of Locati  Description  Citizen	colle CT	a SWRO	ent clockwise	D3 D4	LRP PDWP	N1 N2	EPA Headquarters Private Sector	itte		
east end of pipe 12; or s  Cading wwo  Source of Locati  Description  Citizen  Contractor	colle Cde Conal Dat Code CT CR	a SWRO KCRO NERO	ent clockwise	D3 D4 D5	LRP PDWP SWCP	N1 N2 N3	EPA Headquarters Private Sector Regulated Entity	atta*		
east end of pipe 12; or s  Cading www  Source of Locati  Description  Citizen  Contractor  Dun & Bradstreet	colle Code CT CR DB	a SWRO KCRO NERO SLRO	ent clockwise	D3 D4 D5 D6	LRP PDWP SWCP SWMP	N1 N2 N3 N4	EPA Headquarters Private Sector Regulated Entity Tribe			
east end of pipe 12; or s  Cadency was  Source of Locati  Description  Citizen  Contractor  Dun & Bradstreet  EPA, Region 7	colle C-e	a SWRO KCRO NERO SLRO APCP	ent clockwise	D3 D4 D5 D6 D7	LRP PDWP SWCP SWMP TAP	N1 N2 N3 N4 N5	EPA Headquarters Private Sector Regulated Entity	atta*		
east end of pipe 12; or s  Cading was  Source of Locati  Description  Citizen  Contractor  Dun & Bradstreet  EPA, Region 7  JCRO	colle Code CT CR DB R7 D1	a SWRO KCRO NERO SLRO APCP ESP	ent clockwise	D3 D4 D5 D6 D7 D8	LRP PDWP SWCP SWMP TAP WPCP	N1 N2 N3 N4 N5 N6	EPA Headquarters Private Sector Regulated Entity Tribe Unknown	atta*		
east end of pipe 12; or s  Cadency was  Source of Locati  Description Citizen Contractor Dun & Bradstreet EPA, Region 7 JCRO SERO	colle C-e	a SWRO KCRO NERO SLRO APCP	ent clockwise	D3 D4 D5 D6 D7	LRP PDWP SWCP SWMP TAP	N1 N2 N3 N4 N5	EPA Headquarters Private Sector Regulated Entity Tribe Unknown	atta*		
east end of pipe 12; or s  Cading was  Source of Locati  Description  Citizen  Contractor  Dun & Bradstreet  EPA, Region 7  JCRO	colle	a SWRO KCRO NERO SLRO APCP ESP HWP	ent clockwise	D3 D4 D5 D6 D7 D8 D9	LRP PDWP SWCP SWMP TAP WPCP DEQ/Adm	N1 N2 N3 N4 N5 N6	EPA Headquarters Private Sector Regulated Entity Tribe Unknown Other	ntta'		
east end of pipe 12; or s  Cading wwo  Source of Locati  Description Citizen Contractor Dun & Bradstreet EPA, Region 7 JCRO SERO	colle	a SWRO KCRO NERO SLRO APCP ESP HWP	ent clockwise	D3 D4 D5 D6 D7 D8 D9	LRP PDWP SWCP SWMP TAP WPCP DEQ/Adm	N1 N2 N3 N4 N5 N6	EPA Headquarters Private Sector Regulated Entity Tribe Unknown Other	atta*		



Mel Carnahan, Governor • Stephen M. Mahfood, Director

### NT OF NATURAL RESOURCES

DIVISION OF ENVIRONMENTAL QUALITY P.O. Box 176 Jefferson City, MO 65102-0176

### **MEMORANDUM**

DATE:

February 1, 1999

TO:

Former Hulett Lagoon and Camdenton Sludge Disposal Technical Files

FROM:

Valerie H. Wilder, Environmental Specialist  $\mathcal{N}^{\mathcal{U}}$ 

Site Evaluation Unit, Superfund Section

Hazardous Waste Program

SUBJECT:

Site Visits/Sampling Events on

December 1, 16, 1998 and January 21-22, 29, 1999

### December 1, 1998, Site Visits

On December 1, 1998, I traveled to Camdenton, Missouri, to review city files on the former Hulett Lagoon. I went to City Hall and spoke with the mayor, Mr. Elmer Meyer. I made copies of the pertinent information on the operation and closure of the Hulett Lagoon. Mr. Tom Emry, Camdenton's Sewer Treatment Plant Manager, stopped by the city hall to answer some of my questions and help interpret maps. After reviewing the files, Mr. Vince Costa, Public Works Director, drove me around and showed me the former Hulett Lagoon, the sludge disposal area out near the airport, and all of the city's drinking water wells.

Directions to the Former Hulett Lagoon site: from the intersection of U.S. Highway 54 and State Route 5 in Camdenton, take State Route 5 northwest for 0.3 of a mile to East Mulberry; take a left onto East Mulberry and the first right onto West Mulberry. When the paved portion of West Mulberry curves to the left, continue straight onto a gravel driveway that leads behind the Ron Hulett Chevrolet-Olds-Buick Jeep/Eagle automobile dealership. Stay to the left on a gravel road that leads down to the lagoon. This road is not regularly maintained; there are several severe ruts caused from washouts.

The lagoon was named and most commonly referred to as the Hulett Lagoon, apparently due to its proximity to the Ron Hulett automobile dealership that is located at 249 N. Highway 5. The former Hulett Lagoon is currently an open field area with grassy vegetation. Remnants of the former berm and the road that surrounded the lagoon are still visible. The lagoon area is generally flat, with surface runoff flowing to the northwest and entering an intermittent drainage that travels to the west. There is a

Former Hulett Lagoon and Camdenton Sludge Disposal Technical Files February 1, 1999
Page Two

monitoring well, installed by Modine Manufacturing's consultant, located just outside what would have been the southwest edge of the berm of the lagoon. This is known as MW-5. During the closure of the lagoon, apparently, no soil was brought in for the mixing. Some soil from the hillside southeast of the lagoon was scraped in to fill the void.

The lagoon is located in a mixed residential/commercial area of Camdenton. It is bordered on the north by an apartment complex; on the west by a strip of woods about 500 feet wide with Dawson Road on the other side; on the east by woods; and on the south by a strip of woods and then residences. At least two of the apartment buildings in the complex north of the site are within 200 feet of the site, as well as the apartment building and one home south of the site. Access to the lagoon area is not restricted. There is no fencing or gates.

Directions to the Camdenton Sludge Disposal Area site: from the intersection of U.S. Highway 54 and State Route 5 in Camdenton, take State Route 5 southeast for 4.4 miles to County Road 5-120; take a left onto CR 5-120, a gravel road, and travel east. The disposal area is 0.3 of a mile down the road on the north side.

The outline of the stockpiling area is faintly discernable today. The spreader used during the sludge disposal operation was left on-site and is situated approximately 100 yards northwest of the stockpiling area. There are no other structures in the area. Most drainage for the site flows into a low ditch that runs west to east across the southern portion of the site.

The sludge disposal area is bordered on the south by County Road 5-120; on the north by the Camdenton Memorial Airport; on the west by a residence; and on the east by a wooded area. The residence at 3499 RR3 is within 400 feet of the western edge of the site. Access to the site is not restricted. There is no fencing or gates

### December 16, 1998, Site Visits

On December 16, 1998, Brian Allen, of the Environmental Services Program, and I traveled to Camdenton to visit the two sites and begin planning for the Combined PA/SI sampling events that were scheduled for January 1999. We met Mr. Larry Coleman, a city employee at the Sewer Treatment Plant, at the sludge disposal site near the airport. Mr. Coleman lives just down County Road 5-120 from the sludge disposal site. Mr. Coleman told us about the sludge disposal operations that occurred during the closure of the Hulett Lagoon in 1989 and 1990. Since Mr. Coleman lived just down the road, he saw activity at the sludge disposal area almost daily. He said that the sludge was more difficult to spread evenly than the contractors originally anticipated. It didn't

Former Hulett Lagoon and Camdenton Sludge Disposal Technical Files February 1, 1999
Page Two

dry out completely and would stick together in clumps. Near the end of the process, he said the contractor took the last several piles of sludge material and simply dumped them into the ditch located about 50 feet north of the circular storage area. It was not spread, mixed or disced.

The following information regarding the sampling events are details that are not documented in the Environmental Services Program Sampling Reports.

### January 21, 1999, Sampling Event

Sampling at the Hulett Lagoon commenced on January 21, 1999. That day, Ron Hulett car dealership personnel reported that people often dump trash and junk in the wooded area behind their facility that borders the road leading down to the lagoon. There were also a few pieces of trash in the lagoon area.


### January 22, 1999, Sampling Event

Sampling at the Camdenton Sludge Disposal Area site commenced on January 22, 1999. Green sludge material was encountered in borings Hulett 12 and Hulett 19, from the ditch area.

### January 29, 1999, Sampling Event

Camden County PWSD #2 personnel reported that Well #2 is the primary well that supplies 99 percent of the water for the district.

VHW:In



# **Contents**

Indeed a second and the		
Index to map unitsiv	Clarksville series	
Summary of tables v	Doniphan series	
Foreword vii	Gasconade series	
General nature of the county 2	Gatewood series	
How this survey was made 3	Gepp series	
Map unit composition 4	Gunlock series	59
General soil map units 5	Hartville series	60
Soil descriptions 5	Huntington series	61
Detailed soil map units	Kaintuck series	61
Soil descriptions 13	Knobby series	62
Prime farmland	Lebanon series	62
Use and management of the soils	Moniteau series	62
Crops and pasture	Niangua series	63
Woodland management and productivity 39	Nolin series	64
Windbreaks and environmental plantings 41	Peridge series	64
Recreation 42	Plato series	64
Wildlife habitat	Poynor series	65
Engineering 44	Razort series	
Soil properties 51	Viraton series	66
Engineering index properties 51	Formation of the soils	69
Physical and chemical properties 52	Factors of soil formation	69
Soil and water features 53	Geology, physiography, and hydrology	71
Classification of the soils	References	
Soil series and their morphology 55	Glossary	
Bardley series	Tables	
Onderman and a		

Issued March 1994

### General Nature of the County

This section provides general information about Camden County. It describes climate and history and development.

### Climate

Table 1 gives data on temperature and precipitation for the survey area as recorded at Camdenton in the period 1951 to 1987. Table 2 shows probable dates of the first freeze in fall and the last freeze in spring. Table 3 provides data on length of the growing season.

In winter, the average temperature is 35 degrees F and the average daily minimum temperature is 24 degrees. The lowest temperature on record, which occurred at Camdenton on December 25, 1983, is -20 degrees. In summer, the average temperature is 77 degrees and the average daily maximum temperature is 89 degrees. The highest recorded temperature, which occurred on July 14, 1954, is 115 degrees.

Growing degree days are shown in table 1. They are equivalent to "heat units." During the month, growing degree days accumulate by the amount that the average temperature each day exceeds a base temperature (50 degrees F). The normal monthly accumulation is used to schedule single or successive plantings of a crop between the last freeze in spring and the first freeze in fall.

The total annual precipitation is 42.32 inches. Of this, 25 inches, or about 59 percent, usually falls in April through September. The growing season for most crops falls within this period. In 2 years out of 10, the rainfall in April through September is less than 20 inches. The heaviest 1-day rainfall during the period of record was 4.67 inches at Camdenton on October 13, 1968. Thunderstorms occur on about 53 days each year.

The average seasonal snowfall is about 19 inches. The greatest snow depth at any one time during the period of record was 16 inches. On the average, 12 days of the year have at least 1 inch of snow on the ground. The number of such days varies greatly from year to year.

The average relative humidity in midafternoon is about 60 percent. Humidity is higher at night, and the average at dawn is about 80 percent. The sun shines 65 percent of the time possible in summer and 50 percent in winter. The prevailing wind is from the south-southwest. Average windspeed is highest, 12 miles per hour, in spring.

Tornadoes and severe thunderstorms occur occasionally, but they are local in extent and of short duration. They may cause damage in scattered areas. The amount of damage varies. Hailstorms sometimes

occur in scattered small areas during the warmer part of the year.

### **History and Development**

Osage and Delaware Indians once inhabited the territory now known as Camden County. They built their villages on the terraces along major streams, where they hunted, fished, and raised corn, beans, and pumpkins. In 1827, white settlers began moving into the area after the Indians signed a treaty ceding the land to the U.S. Government (3). For many years after the treaty was signed, the Indians continued to hunt in the area. They camped at various places and hunted deer, bears, turkeys, and raccoons and other small game. They preserved the meat by drying it on scaffolds over fires. After 1846, they no longer returned to the area as a group (3).

Ruben Berry and William Pogue were among the earliest permanent white settlers in the survey area. When they arrived in 1827, they discovered the hull of a keelboat submerged in the Osage River (3). Also, a wooden fur press was found at the mouth of Linn Creek. These artifacts were evidence that French or Spanish explorers, hunters, and trappers had also been in the area. Other settlers later came to the area from Kentucky, Tennessee, and Virginia (8).

Kinderhook County, which is now known as Camden County, was organized in accordance with an act of the Legislature and approved by Governor Thomas Reynolds on January 20, 1841 (3). A site was selected for the county seat on April 12, 1841, in the town of Oregon. The county name was changed to Camden County by an act of the General Assembly of Missouri on February 23, 1843, and the name of the county seat was changed from Oregon to Erie. In 1850, the county seat was moved from Erie to Linn Creek (3). When Linn Creek was inundated by the creation of the Lake of the Ozarks, the county seat was moved to its present location at Camdenton.

Because of the cherty soils, limited transportation facilities, distant markets, and hilly, forested topography, the agricultural enterprises of the area were generally limited to part-time livestock farming. Timber was harvested mostly for railroad ties, fuel, and building material. Other occupations centered around hunting and fishing and the handcrafting of necessities for subsistence. Some row crops were grown in small areas on the stream terraces and flood plains and were used as livestock feed. After World War II, the livestock economy was based on the production of unfinished feeder cattle (5). Higher cattle prices in the 1960's and 1970's made the conversion of timberland to pasture profitable.

Former Hulett Lagoon Site Combined PA/SI P. O. Box 941 Columbia Missouri 6520

RECEIVED

93 MAY 5: AM 11:00

HAZAROGIS WASTE PROGRAM MISSOURI DEPARTMENT OF MATURAL RESOURCES Property of

Please Telumto >

National Weather Service Office for State Climatology P. O. Box 941 Columbia Missouri 65201

TECHNICAL PAPER NO. 40

# RAINFALL FREQUENCY ATLAS OF THE UNITED STAT

for Durations from 30 Minutes to 24 Hours and Return Periods from 1 to 100 Years

National Weather Service Official for State Climatology P. O. Box 941 Columbia, Missouri 65201



1961

Motional Web

Former Hulett Lagoon Site Combined PA/SI Reference 8



# U.S. DEPARTMENT OF COMMERCE C. R. Smith, Secretary


ENVIRONMENTAL SCIENCE SERVICES ADMINISTRATION Robert M. White, Administrator

ENVIRONMENTAL DATA SERVICE Woodrow C. Jacobs, Director

**JUNE 1968** 

REPRINTED BY THE
NATIONAL OCEANIC AND ATMOSPHERIC ADMINISTRATION
1983

# MEAN SPEED (m.p.h.), AND FASTEST MILE OF WIND, MONTHLY AND ANNUAL - Contin



Former Hulett Lagoon Site Combined PA/SI Reference 9

### U.S. ENVIRONMENTAL PROTECTION AGENCA

### ALTERNATIVE REMEDIAL CONTRACTING STRATEGY

**REGIONS VI, VII, VIII** 


### **VOLUME I**

FINAL
ENVIRONMENTAL PRIORITIES INITIATIVE/
PRELIMINARY ASSESSMENT
MODINE HEAT TRANSFER, INC.
(FORMERLY SUNDSTRAND TUBULAR PRODUCTS)
BOX 636 SUNSET DRIVE
CAMDENTON, CAMDEN COUNTY, MISSOURI
EPA ID NO. MOD062439351

U.S. EPA CONTRACT NO. 68-W8-0122 U.S. EPA WORK ASSIGNMENT NO. 47-7JZZ U.S. EPA REGION VII

### PREPARED BY

JACOBS ENGINEERING GROUP, INC. 10901 WEST 84TH TERRACE, SUITE 210 LENEXA, KANSAS 66214 (913) 492-9218 JACOBS PROJECT NUMBER 12-D247-22



SEPTEMBER 1992

### TABLE OF CONTENTS

SECT	<u>ION</u>		<u>PAGE</u>
EXEC	UTIVE S	SUMMARY	ES-1
1.0	INTR	ODUCTION	1
1.0	1.1	Objective	1
	1.2	Scope of Work	1
2.0	SITE	DESCRIPTION	1
	2.1	Site Location	1
	2.2	Site Features	2
	2.3	Ownership History	2
	2.4	Nature of Operations	2
	2.5	Permit and Regulatory History	5
3.0	ENVI	RONMENTAL SETTING	6
	3.1	Area Water Supply	6
	3.2	Potential Surface Water Receptors	6
	3 <b>.3</b>	Regional Geology/Hydrogeology	8
	3.4	Site Geology and Hydrogeology	9
	3.5	Area Climatology and Meteorology	10
	3.6	Critical Habitats and Endangered Species	10
	3.7	Population/Census Information	
4.0	VISU	AL SITE INSPECTION	10
	4.1	Visual Site Inspection Participants	10
	4.2	Solid Waste Management Units (SWMUs) and	
		Other Areas of Concern (AOCs)	11
REFE	RENCE	s	57
		FIGURES	
Figur	e 1	Site Location Map	
Figur	e 2	Surface Water Runoff Map	
Figur	e 3	Historical Building Additions	
Figur	e 4	Past and Present SWMU Location Map	
Figur	e 5	Four-Mile Radius Map	
Figur	e 6	15-Mile Surface Water Migration Pathway	
Figur	e 7	Present TCA Wastestream	
Figur	e 8	Historical Vapor Degreaser and Still Location Map	

i




Table 1

### **TABLES**

Table 1 SWMU/AOC Identification Summary
Table 2 LAW Environmental Site Assessment Analytical Results Summary

Table 3 Wells Within 4-Mile Radius of Modine Heat Transfer, Inc.

### **APPENDICES**

Appendix A	1980 Part A Application, 1983 Revised Part A Application and RCRA Technical Review
Appendix B	1990 Part A Application
Appendix C	Closure Plans
Appendix D	Wastewater Discharge Permit City of Camdenton, Missouri
Appendix E	Environmental Site Assessment by LAW Environmental, November 1991
Appendix F	Well Logs
Appendix G	Photodocumentation
Appendix H	Analytical Results of Hulett Lagoon Sludge
Appendix I	Correspondence from the MDNR to Mayor Webster Regarding Hulett Lagoon Closure Options
Appendix <b>J</b>	Closure Plan Analytical Results
Appendix K	Present Waste Disposal Method

#### **EXECUTIVE SUMMARY**

A Visual Site Inspection (VSI) and a Preliminary Assessment (PA) were conducted by Jacobs Engineering Group Inc. (Jacobs), on behalf of the U.S. Environmental Protection Agency (EPA) Region VII, at Modine Heat Transfer, Inc. (MHT) on March 4, 1992. The Modine facility is on Sunset Drive in Camdenton, Missouri, in Camden County. MHT is a manufacturing facility that produces air conditioning coils and feeder parts from aluminum and copper tubing. The manufacturing process consists of aluminum and copper cutting and brazing, aluminum etching, and, previously, a limited amount of chromium electroplating.

The facility began production in 1967. During the history of the facility, the ownership has changed three times. Previous owners include Dawson Metal Products, Inc. (1967 to 1974) and Sundstrand Tubular Products (1974 to 1990). MHT is the current owner/operator. Various types of hazardous waste are generated during the manufacturing process including: 1,1,1-trichloroethane (TCA); paint waste; wastewater pretreatment sludge; solvents; and waste oil. Non-hazardous wastes generated by the facility include: paper; cardboard; scrap metal; and general refuse. All wastes are either drummed in 55-gallon barrels, stored in high-capacity storage tanks, shipped to recycling centers, processed by the pretreatment wastewater unit, and released to the city publically-owned treatment works (POTW), or stored for reclamation or disposal by contracted services. From 1967 until 1986, wastes were disposed through mudpits to the Hulett Lagoon, which was owned by the city of Camdenton. In 1986, a pretreatment wastewater system was placed on-line, which remains in service.

Thirty-four Solid Waste Management Units (SWMUs) and four Areas of Concern (AOCs) have been identified at this facility. The SWMUs and AOCs identified are:

SWMU Number 1	Hulett Lagoon
SWMU Number 2	Mudpits
SWMU Number 3	Pretreatment Wastewater System/Filter Press
SWMU Number 4	Tank and Drum Storage Area Number 1
SWMU Number 5	Drum Storage Area Number 2
SWMU Number 6	Waste FIN Oil Storage Tank Number 1
SWMU Number 7	TCA Waste Storage Tank Number 6
SWMU Number 8	Copper Cleaning Line
SWMU Number 9	Copper Cleaning Line Scrubber
SWMU Number 10	Aluminum Cleaning Line
SWMU Number 11	Large Aluminum Brazing Furnace
SWMU Number 12	Large Aluminum Brazing Furnace Scrubber
SWMU Number 13	Small Aluminum Brazing Furnace
SWMU Number 14	Small Aluminum Brazing Furnace Scrubber

	SWMU	Number 15	Chrome Cleaning Line
100	MMU	Number 16	Chrome Cleaning Line Scrubber
15	SWMU	Number 17	Aqueous Cleaning Bath
7	SWMU	Number 18	Vapor Degreaser and Still M184
	SWMU	Number 19	Vapor Degreaser and Still M185 (Former)
Transfer of	SWMU	Number 20	Vapor Degreaser and Still M185 (New-Location 1)
	SWMU	Number 21	Vapor Degreaser and Still M185 (New-Location 2)
	SWMU	Number 22	Vapor Degreaser and Still M487 (Former)
	SWMU	Number 23	Vapor Degreaser and Still M487 (New)
	SWMU	Number 24	Vapor Degreaser and Still M460 (Former-Location 1)
推译的	SWMU	Number 25	Vapor Degreaser and Still M460 (Former-Location 2)
	<b>SWM</b> U	Number 26	Vapor Degreaser and Still M567
	<b>SWM</b> U	Number 27	Vapor Degreaser and Still M394 (Former-Location 1)
	<b>SWM</b> U	Number 28	Vapor Degreaser and Still M394 (Former-Location 2)
	<b>SWM</b> U	Number 29	Vapor Degreaser and Still M394 (Former-Location 3)
	<b>SWM</b> U	Number 30	Two 2,000-Gailon Storage Tanks
	<b>SWM</b> U	Number 31	Drum Storage Area Number 3
, ,	SWMU	Number 32	Pretreatment/Drum Storage Area
) 5	SWMU	Number 33	Non-Hazardous Waste Receptacle
;	SWMU	Number 34	Scrap Metal Storage Bins
	SWMU	Number 35	Fire Training Area
4	AOC A		Raw Materials Storage Area
	AOC B		Pallet Storage Area
4	AOC C		Tool Crib/Maintenance Area
4	AOC D		Paintline

The above-listed SWMUs remain active with the exception of SWMU Numbers 1, 2, 4, 5, 11, 12, 13, 15, 16, 19, 20, 22, 24, 25, 27, 28, 29, and 31. These SWMUs are no longer in operation and, except for a portion of SWMU Number 2, have been dismantled or removed from the site.

Two potential release areas were identified in 1991 by LAW Environmental during an Environmental Site Assessment conducted on behalf of the MHT facility. The areas investigated include two former drum storage areas (SWMU Numbers 4 and 31) where soil borings revealed elevated levels of hazardous substances. LAW recommended further investigation to determine the nature and extent of the contamination.

The facility holds interim status as a treatment, storage, and disposal (TSD) facility. In March 1992, MHT submitted a Revised Closure Plan to the Missouri Department of Natural Resources (MDNR) in order to terminate its interim status.

The gray bat (<u>myotis griesecens</u>) is the only federal and state-threatened species known to exist within a 15-mile downstream distance from the facility. No critical habitats or sensitive environments exist at the facility or are within one-half mile. No aquatic critical habitats or sensitive environments exist within 15-miles downstream from the facility.

### SWMU NUMBER: 1

SWMU NAME: Hulett Lagoon

SWMU DESCRIPTION: The Hulett Lagoon is 1/4 mile northeast of the Modine facility on the east side of bDawson Road. The lagoon is owned by the City of Camdenton, Missouri. The lagoon was constructed in 1961 under the State of Missouri Grants Program and is approximately one acre in size. The lagoon was constructed of clay, and its berms were approximately 25 feet wide and 15 feet high. The location of the Hulett Lagoon is depicted on Figure 1 as SWMU Number 1 (Reference 15).

Modine began utilizing the lagoon in 1967. The facility would release its untreated wastewater and stormwater into the lagoon through a series of "mudpits" (SWMU Number 2) via a storm sewer.

DATES OF OPERATION: The Hulett lagoon was in operation from 1961 until its closure in late 1989. The Modine facility utilized the lagoon for its waste disposal system from 1967 through 1986, when the facility installed its pretreatment wastewater system.

In 1988, the City of Camdenton began RCRA closure of the Hulett Lagoon. The sludge was sampled for metals, and analytical results are presented in Appendix H. High levels of chromium, lead, and nickel were detected. City officials were given several options by MDNR to consider in completing the abandonment and closure of the Lagoon within the MDNR Water Resources Program (Appendix I). The option chosen and implemented by the city was the subsurface application of sludge from the lagoon by spreading it in place and discing and plowing it into the subsurface soils. The berms were then turned in and mixed to a 1:1 ratio with surrounding soils. The sludge was then taken by truck to the municipal airport and land-applied at a field near the runway in accordance with the terms of the MDNR correspondence contained in Appendix I. No confirmation samples were collected following removal of the sludge. The city is in the process of leveling the site of the former lagoon and opening it up for a neighborhood park (Reference 15). It should be mentioned that using this area for purposes other than sewage sludge disposal is contrary to the terms agreed upon between MDNR and the City of Camdenton.

WASTES MANAGED: Wastes managed by the Hulett Lagoon included all wastewater, stormwater, and aluminum and copper cleaning line wastes from the MHT facility. Information regarding the type and quantity of waste distributed and accumulated at the Hulett Lagoon is not available. Potential wastes handled include: F001, F006, D001, and D098.

RELEASE CONTROLS: Release controls at the Hulett Lagoon include clay lining and berms.

RELEASE HISTORY: The Hulett Lagoon was the site for release of all untreated process wastes from the MHT facility. As stated previously, elevated levels of chromium, lead, and nickel were detected in the sludge analysis recorded during closure of the lagoon.

MIGRATION PATHWAYS: The primary migration pathways for contaminants in order of decreasing likelihood would be soil, surface water, and groundwater.

PHOTOGRAPH NO.: 1 and 2

## NUMBER: 2

NAME: Mudpits

The mudpits were approximately 15 feet apart, running from the scrap-metal bins to the reatment/drum storage area (SWMU Number 32). Each mudpit consisted of a 4-foot by 4-foot cement approximately 4 feet in depth. Two of the four mudpits no longer exist and are beneath the reatment/drum storage area. The location of the mudpits is depicted on Figure 3 as SWMU Number 2.

mudpits were connected by a 6-inch steel line that delivered stormwater, boiler water, chrome, copper, and imminum cleaning line waste from the manufacturing process. Each sump received the previous sump's wastes intil wastewater was discharged into the sewer. The southern-most mudpit was an open pit which collected piler water and stormwater. The second mudpit directly collected aluminum cleaning line waste and stormwater rom the first. The third and fourth mudpits collected copper cleaning line waste in addition to the aluminum cleaning line waste and the stormwater runoff. These four mudpits collectively discharged wastewater into a storm sewer line which led directly to the Hulett Lagoon (SWMU Number 1)(Reference 12).

**DATES OF OPERATION:** The mudpits were in operation from 1967 to 1986. Two of the four mudpits were removed to construct the pretreatment/drum storage area. The two remaining mudpits, which are no longer in service, are covered by plywood sheets.

wastes managed by the mudpits included wastewater, stormwater, and aluminum and copper cleaning line wastes. Information on the type and quantity of waste accumulated and distributed through the mudpits is unavailable. Potential wastes handled by these units include: F001, F006, D001, and D098.

RELEASE CONTROLS: Release controls for the mudpits included the 4-foot by 4-foot concrete sump walls which were 6 inches in width. The sumps were covered on the surface by a wooden ply-board which prevented precipitation from entering the sumps. The southern-most sump was not covered, however, and did receive run-on from the manufacturing building. No other release controls or secondary containment were utilized at this SWMU.

**RELEASE HISTORY:** There is no record or documentation of any release of materials associated with the mudpits during the operation lifetime.

MIGRATION PATHWAYS: If a release were to occur from the mudpits, the primary migration pathways would be soil, surface water, groundwater, and air, in decreasing order of likelihood.

PHOTOGRAPH NO.: 3

# **MISSOURI WATER QUALITY 3ASIN PLANS**

### **JOLUME 4**

Osage and Gasconade Rivers (Including ake of the Ozarks, Truman Reservoir, South irand, Little Osage, Marmaton, Marais des ygnes, Sac and Pomme de Terre Rivers, ebo Creek and Big Piney River).

ABLE OF CONTENTS Page
.ntroduction
BASIN 30 Lower Osage River 3
BASIN 31. Lake of the Ozarks 10
BASIN 32. Dry Auglaize and Wet Glaize Creeks
BASIN 33. Niangua River 26
BASIN 34. Truman Reservoir
BASIN 35 Northwest Tributaries to Truman Reservoir (South Grand River, Big Creek) 38
BASIN 36. Tebo Creek
BASIN 37. Western Tributaries to Truman Reservoir (Marais des Cygnes, Marmaton, Little Osage Rivers)
BASIN 38 Sac River Below Stockton Dam 61
BASIN 39 Stockton Reservoir 66
BASIN 40. Little Sac River 70
BASIN 41. Sac River Above Stockton Reservoir
BASIN 42. Pomme de Terre River below Dam 81
BASIN 43. Pomme de Terre Reservoir 83
BASIN 44. Pomme de Terre River Above Reservoir
BASIN 45 Gasconade River Except Big Piney River
BASIN 46 Big Piney River 98
BIBLIOGRAPHY 102

#### INTRODUCTION

Missouri's Water Quality Basin Plans are a guide to managing the quality of the aquatic resources of the state. In their simplest form they are a set of water quality problems and a corresponding set of actions which will correct these problems.

There are only a few basic kinds of water quality problems such as organic enrichment from domestic and industrial discharges and from livestock, discharges of toxic materials which come from domestic and industrial sources, acid runoff or seepage from coal mined lands, highly mineralized water (a naturally occurring problem in certain groundwaters), and lastly, sediment from erosion of soil or mine tailings

At any given location, the apparent simplicity of our water problems is complicated by such specifics as the volume of the pollutant discharge and its variability, the concentration of specific pollutants and their variability, and the volume of the receiving stream and its variability. The proximity of other pollutant sources or areas of water use (water based recreation areas, drinking water withdrawal points) tends to make a problem in a particular location, if not unique, at least discernably more or less severe than a similar problem in another location. These plans should note which problems are of the highest priority.

In recognizing the need to write management plans for specific problem areas, this document divides the state into eight major drainages (corresponding to the eight volumes of this document). It then divides the eight drainages into 77 basins and presents a specific list of water quality problem areas and recommended solutions for each basin

The first part of each basin plan is a description of the basin in terms of geography, geology, hydrology, and aquatic use potential. This description is followed by a detailed inventory of all known actual or potential sources of water pollutants. The final part of the basin plan is a discussion of water quality problems and how they affect our water quality goals for the basin, and the basin plan itself in the form of tables listing specific water quality problems, their sources, and recommended solutions.

Each basin plan consists of the following sections

**BASIN NUMBER** 

**BASIN NAME** 

DRAINAGE AREA

COUNTIES: (Included partially or wholly within the basin)

BASIN DESCRIPTION: Geographic limits of the basin and major streams within the basin

**LAND USE:** Percentage of basin in forest, pasture or cropland, urban lands, or mined lands

CLASSIFIED STREAMS: Missouri's water quality standards (CSR 1981) recognize three kinds of surface waters

- P1 Reservoirs, Lakes, Sloughs, Backwaters, and other impounded waters
  - P Permanently flowing streams
- C Streams which may cease flow during prolonged dry weather but maintain permanent pools which act as refuges for aquatic life and provide drinking water for livestock and wildlife

HYDROGEOLOGY: A description of the surficial and underlying geologic strata and how they influence water movement within the basin

GEOLOGIC CROSS SECTION DIAGRAM: This diagram shows the geologic strata from the surface to a depth of at least 500 feet, indicates how deeply stream valleys incise these strata, and indicates how much water is discharged by known springs from each of these strata

STREAM FLOW: Stream flow data are taken from USGS records
There are several flow statistics or descriptions used in water management. Those included in the stream flow table which may require explanation are.

Mean flow The arithmetic average flow That is, the sum of all flows divided by the number of flow measurements.

Median flow. The flow which is exceeded exactly 50% of the time.

- 7 day-Q10 flow The lowest average flow for a seven consecutive day period with a recurrence interval of ten years.
- 7 day-Q2 flow. The lowest average flow for a seven consecutive day period with a recurrence interval of two years

STREAM USES (CSR, 1981): Missouri recognizes nine beneficial uses of the state's waters. Based on numerous public meetings, user surveys and other studies, each classified stream in the state (Class P1 P. or C), or segment thereof, has a list of uses appropriate to that stream The Mississippi and Missouri Rivers and Shoal Creek (Jasper and Newton Counties) have the most recognized uses (seven), a few streams which are badly polluted, like Turkey Creek (Jasper County), have none.

The nine beneficial uses are: (1) Irrigation of croplands. (2) Livestock and wildlife watering. (3) Protection of aquatic life and fishing. (4) Coldwater sport fishery (trout fishing). (5) Whole body contact recreation (swimming, water skiing, skin diving). (6) Drinking water supply. (7) Industrial process and cooling water; (8) Commercial fishing. (9) Limited water contact recreation (canoeing, boating)

LAKE USES (CSR, 1981): All classified lakes and reservoirs (P1) are identified and their beneficial uses listed. A list of all lakes and reservoirs (including unclassified ones) greater than 50 acres is given, showing location, size, and major use(s).

This section also gives the total number of lakes and reservoirs inventoried by the dam safety program (generally those reservoirs greater than 2 acres in area), the range in size, and the mean and median lake area

Volume 4, Introduction, Page 1

WITHDRAWALS: This section indicates whether or not there are public drinking water withdrawals from surface waters in this basin and which streams or reservoirs these withdrawals are taken from

**POPULATION:** 1980 population data are given as is the population change from 1970 to 1980. This section also makes projections of future population trends.

WATER QUALITY DATA: Important sources of water quality information for the basin are listed. Other information referenced within the basin plans but not listed here appear in a bibliography at the end of each of the eight volumes.

**ENDANGERED SPECIES:** Any animal species which should be noted by an Environmental Impact Statement (EIS) or a Finding of No Significant Impact (FONSI) are included. Either an EIS or a FONSI is required for any construction activity that uses federal funds.

BASIN MAPS: There are two basin maps. The first shows the classified stream network, those unclassified streams having an NPDES or Non-NPDES facility, and the unclassified headwaters of classified streams. It also shows stream names, county lines, the location and sizes of all NPDES discharges and other potentially significant sources of water pollution. Solid stream lines are classified "P", dashed stream lines are classified "C", and dot-dashed stream lines are unclassified. The letter-number code is explained in Table 1.

The second map shows the drainage network and the location of towns, petroleum and ammonia pipelines, and active railroads. It also shows losing stream segments as heavy dotted lines. (Where there is contradictory information on stream names, the names appearing on USGS 7.5- or 15-minute topographic maps are used.)

OTHER MAPS: A few basins have additional maps which give more detailed information on location, size, and condition of lead-zinc and bante tailings areas.

LOW FLOW DIAGRAM: This diagram is a schematic map of the basin which shows all classified streams and all potentially significant discharges

All streams are shown as vertical lines and are drawn to scale for actual stream length. Solid lines are Class P streams, dashed lines are Class C streams, and alternating dots and dashes are unclassified streams. The width of the vertical lines of Class P streams are drawn to scale for volume of flow at the 7 day-Q10.

Horizontal lines are not stream segments, but they mark the location of inflow of discharges or tributaries to a stream. Volume of tributary, inflows or discharges are also estimated flows for the 7 day-Q10, and these numbers follow the name of the tributary or the discharge on the horizontal line. Numbers appearing on the vertical stream lines are calculated 7 day-Q10 values.

Stream segments known or believed to be affected by discharges are indicated

Lakes and reservoirs are drawn to their approximate shape. The length of the impoundment can be found by scaling the distance along the center line of the impoundment. The outlines of reservoirs have two lines. The inner line indicates the boundaries of the normal use pool and the outer line the flood pool.

INVENTORY TABLE: This table lists all NPDES permitted discharges in the basin, other potential waste or wastewater sources, and surface withdrawals for public drinking water supplies "S" "T" 'R" refers to "Section", "Township", and "Range" If there is no direction after the range, it is assumed to be "West".

WATER QUALITY PROBLEMS, POINT SOURCE: Point source problems have been identified through physical and chemical water quality monitoring by the Department of Natural Resources and several other organizations, and by visual surveys and surveys of the benthic plant and animal communities of streams. These latter surveys are conducted primarily by the Departments of Conservation and Natural Resources.

WATER QUALITY PROBLEMS, NON-POINT-SOURCE: Non-point source water quality problems have been quantified, where possible, by Section 208 planning activities which took place between 1978 and 1982 Soil erosion and sediment delivery studies were made by SCS and USGS. Lead-zinc mining related impacts were studied by USGS, the Departments of Conservation and Natural Resources, and the University of Missouri, Rolla. Inventories of lead-zinc, coal, and barite mining areas and their reclamation states were made by the Department of Natural Resources.

BENEFICIAL USE ATTAINMENT: This section evaluates existing in-stream water quality and whether or not it meets the standards required for the beneficial uses identified in that basin

SUMMARY TABLE OF POINT SOURCE PROBLEMS AND MANAGEMENT NEEDS: All municipal facilities are listed as are any non-municipal NPDES permitted discharges that are, or are suspected of causing water quality problems in receiving streams. Length of affected segment, classification of affected segment (permanent flow (P), permanent pools and intermittant flow (C), and completely dry stream bed during dry periods (U)), a recent permit compliance record and recommended DNR action to alleviate the problem are all included in this table. The severity of impacts were described as affected (aff) or polluted (poil). A polluted length had a partially or totally impaired use. An affected length had a noticeable affect but uses were not impaired.

SUMMARY TABLE OF OTHER PROBLEMS AND MANAGEMENT NEEDS: This table lists all known or suspected water quality problems arising from sources that do not hold NPDES permits. Soil erosion, stream channelization, drainage from abandoned mined lands or animal confinement areas are common non-NPDES source problems. The

problem, the stream segment affected, cause, and the recommended DNR action to alleviate the problem are included in the table

Volume 4 contains Basins 30-46 which include all streams in the Osage and Gasconade River System

The streams of the western part of the Osage River basin rise in Kansas or extreme western Missouri and flow through a flat prairie land of row crops and pastures. Although most of the area has not been glaciated, it is underlain by Pennsylvanian rock which retards downward movement of water to the groundwater. Thus most rainfall runs off high stream flow during and immediately after rains, and streams have low or no flow during dry periods. Groundwaters are recharged very slowly, groundwater movement is slow, and wells generally yield small amounts of water which are usually very mineralized.

The streams further east are in unglaciated terrain underlain by older limestones and dolomites. There is more movement of water to the subsurface, thus baseflows of streams are greater and wells usually have good yields of potable water.

The Osage system contains four large reservoirs which are a major focal point for fishing, camping, boating, and swimming in the state. The Gasconade River is totally unimpounded and is an excellent river for canoeing and float fishing for smallmouth bass. The four large reservoirs have reduced stream habitat in the basin but have replaced it with lake habitat. Thus the potential fishery has been increased but the presence and operation of the reservoirs, particularly Truman Reservoir, threatens to reduce this fishery.

Except in western Missouri where soil erosion causes instream turbidity and some loss of aquatic habitat, nonpoint pollution sources are not significant factors in aquatic habitat degradation

### TABLE 31-1—LAKE OF THE OZARKS

### **NPDES Inventory**

	FACILITY	Location S T R	Receiving Stream	County	Facility Type or Waste Char.	Design P.E.	Flow (MGD)	NPDES Permit No
Munic	cipal Discharges			,			<u> </u>	<del> </del>
	Camdenton Lgn #1  CP White	NW SE 35,38.17	Racetrack Hollow	Camden	2-c lagoon	1,765	176	004856
W2	Camdenton Lgn #2 Cedar Str	NW SE 25,38,17	Trib to Lake of the Ozarks	Camden	2-c lagoon	742	074	004858
W3	Camdenton Lgn #3 Factory Rd	SW SW 24,38,17	Trib to Jarvis Hollow	Camden	1-c lagoon	265	027	004857
W4	Camdenton Lgn #5 Clint Ave/Wilkerson Ave	Ctr E W 24,38,17	Possum Hollow Ck	Camden	2-c lagoon	716	071	004860
W5	Camdenton Lgn. #6 Parish Subd	Ctr. N S 19,38,16	Trib. to S. Fk Linn Ck	Camden	1-c lagoon	850	085	004859
W6	Cole Camp STP	NE SE 34,43,21	Cole Camp Creek	Benton	Oxidation Ditch	2.225	222	005662
W7	Lincoln Lgn (E)	NE NW 26,42,22	Trib to Cole Camp	Benton	1-c lagoon	870	087	004419
W8	Linn Creek STP	SE SW 8,38,16	Linn Creek	Camden	1-c lagoon	45	004	005471
W9	Warsaw STP	NE SE 16,40.22	Lake of the Ozarks	Benton	3-c lagoon	2,200	220	004923
Non-F	Municipal Discharges							
W17	Skyline Motel	NW 6,39,15	Lake of the Ozarks	Camden	1-c iagoon	35	001	008347
W18	Shoreline Motel	SW 19,40,15	Lake of the Ozarks	Miller	Septic tank/s f	35	001	008348
W19	Alhonna Resort	SE NE 25,40,17	Lake of the Ozarks	Camden	septic tank/s.f	35	002	008339
W20	Gold Nugget Junction	NE 28,39,16	Trib to Lake Ozarks	Camden	1-c lagoon	32	002	008331
W21	Camdenton Med Center	SW 14,38,17	Possum Hollow	Camden	1-c lagoon (Hg, Ba, Ag limits)	73	005	008330
W22								
W23	Point Breeze Resort	NE 11,39,16	Lake of the Ozarks	Camden	septic tank/s f	57	003	008326
W24	Osage Beach Elem School	S 6,39,15	Trib to Lake of the Ozarks	Camden	septic tank/s f	165	002	008298
W25	-			1		ļ		1
W26	Lodge of the Four Seasons	SW SW 27,40,16	Lake of the Ozarks	Camden	activ sludge	3,268	376	008217
W27	Tan-Tar-A Resort	SE SE 7,39.16	Lake of the Ozarks	Camden	Rotating Bio-Media	1.700	170	008193
W28	Tan-Tar-A Estates	SW SE 7,39,16	Lake of the Ozarks	Camden	extended aeration	500	050	008196
W29	Lake Osage Apartments	SW SW 1,39,16	Lake of the Ozarks	Camden	extended aeration	90	009	008193
W30	Camp Sabra	NE SW 7,40,16	Lake of the Ozarks	Morgan	1-cell lagoon	50	005	005632
				1.	septic tank/s f	30	003	1
W31	Waters Edge Condo	NW NW 34,40,16	Lake of the Ozarks	Camden	extended aeration	1,272	084	005434
W32	Fawn Valley Commun	NE NE 5,39,18	Lake of the Ozarks	Camden	extended aeration	500	050	005407
W33	Kirkwood Lodge	S 6,39,15	Trib to Lake of the Ozarks	Camden	septic tank/s f	60	006	004476
W34	Hawk Nest Lodge	NW SE 11,39,16	Lake of the Ozarks	Camden	extended aeration	436	044	010116
W35	Headwaters Motel	SW 22,40,22	Trib to Lake of the Ozarks	Benton	1-c lagoon	36	003	004398
W36	Harbor Houses Condo	SE NE 33,41,17	Soap Ck	Morgan	1-c lagoon	74	007	003415
W37	Mariner's Cove Subd	SW 11,39,16	Lake of the Ozarks	Camden	extended aeration	321	032	003400
W38	Ft Leonard Wood Rec Area (S)	NW NW 32,39,15	Lake of the Ozarks	Camden	2-c lagoon	50	002	002977
W39	Ft Leonard Wood Rec Area (N)	NE NE 30,39,15	Lake of the Ozarks	Camden	3-c lagoon	161	011	002976
W40	Windjammer Condo	NE NE 21,40,16	Lake of the Ozarks	Camden	extended aeration	130	013	010047
W41	Town and Country Motel	SE SE 10,39,16	Trib to Lake of the Ozarks	Camden	extended aeration	113	004	010088
W42	Osage Beach Skelly	SW SE 16.39,16	Lake of the Ozarks	Camden	extended aeration	13	002	010144
	Fifty-eight Facets	SW SE 19,40,16	Lake of the Ozarks	Camden	extended aeration	183	019	009998
	Spa Resort	317 32 13,40,10	Land Of the Ozding	Camberr		163	013	003990
	Eagle Point Condo	28.40.16	Lake of the Ozarks	Camden	extended aeration	30	003	009980

### TABLE 31-2—SUMMARY OF POINT SOURCE IMPACTS AND MANAGEMENT NEEDS

Waste Trt. Mgnt. Area	Type Sewerage Facility	Receiving Water Impacts					From No-	Managamant	Expected	Future DNR	
		Estimated		Observed			Freq. Non- Com-	Management Needs/	Expected Beneficial	Monitoring	Recommended
		Impact	Miles	Impact	Miles	Severity	pliance	Priority	Use Improvement	Needs	Action
Camdenton	2-c lagoon #1 (C P White)			No impact 82				Eliminate, regional facility/Low	Public health benefit	Low-flow survey after upgrade	Refer to Grants Admin Sect.
	2-c lagoon #2 (Cedar St.)			No impact 82				Eliminate, regional facility/Low	Public health benefit	Low-flow survey after upgrade	Refer to Grants Admin. Sect.
	1-c lagoon #3 (Factory Rd.)			No impact 82				Eliminate, regional facility		Effluent analyses for toxic metals and organics	Refer to Grants Admin. Sect.
	1-c lagoon #4 (Wilkerson Ave )			No impact 82				Eliminate regional facility/Low	Public health benefit	Low-flow survery after upgrade	Refer to Grants Admin Sect
	1-c lagoon #5 (Clint Ave.)			No impact 82				Eliminate, regional facility/Low	Public health benefit	Low-flow survey after upgrade	Refer to Grants Admin. Sect.
	1-c lagoon #6 (Parish Subd.)			No impact 82				Eliminate, regional facility/Low	Public health benefit	Low-flow survey after upgrade	Refer to Grants Admin. Sect.
Cole Camp	Oxidation ditch			Reduced benthos, discoloration 83	2.0 C	Aff		Proper O&M/Low	Minor aesihetic improvement, improved aq habitat	Low-flow survey 84	Continued observation by R.O.
Lincoln (E) (1-c lagoon in Basin 34)	1-c lagoon			Aesthetic problems 82, 83	0-1 0 U 0 5- 1 0 U	Poli Aff	X/12	Eliminate and replace with 3-c lagoon/Low	Minor aesthetic improvement	Low-flow survey after upgrade	Refer to Compliance and Grants Admin. Sects.
Linn Ck	1-c lagoon			Unknown due to gravel dredging operation			X/12	Upgrade or replace/Low	None	Low-flow survey after upgrade	Refer to Compliance Sect.
Warsaw	3-c lagoon			Green water, reduced benthos 83	0 1 P	Aff				Low-flow survery after upgrade	Continued observation by R O



### Former Hulett Lagoon Site Combined PA/SI Reference 11

DIVISION OF Environmental Quality Division of Geology and Land Survey Division of Management Services Division of Parks and Historic Preservation

#### JOHN ASHCROFT Governor

### FREDERICK A. BRUNNER

Director

#### STATE OF MISSOURI DEPARTMENT OF NATURAL RESOURCES

### DIVISION OF ENVIRONMENTAL QUALITY

Jefferson City Regional Office 1001A Southwest Boulevard P.O. Box 176 Jefferson City, MO 65102 314-751-2729

June 20, 1986

1.720 Camdenton

Ms. Trudy Marco Grants Coordinator City Hall P.O. Box 399 Camdenton, MO 65020

Dear Ms. Marco:

Enclosed is the report and checklist from the audit of your approved Pretreatment Program implementation, as conducted by Leona M. Reising of my staff. If you have any questions concerning this report please call Leora M. Reising or Jerry Croy at (314) 751-2729.

Sincerely,

JEFFERSON CITY REGIONAL OFFICE

B.R. Kesler

Regional Administrator

BRK/LR/ko

Enclosure

cc: Water Pollution Control Program, Attn: Rich Kuntz

Pretreatment Compliance Audit
City of Camdenton
NPDES Permit Numbers
C.P. White - MO-0048569
Dump - MO-0048585
Hulett - MO-0048577
Wilkerson-Clint - MO-0048607
Parish - MO-0048593

June 20, 1986 ·

On April 15. 1986 an audit was conducted of the Industrial Pretreatment Program as implemented by the City of Camdenton, Ms. Trudy Marco and Mr. D. Roger Elder represented the city and Ms. Leora M. Reising represented the Missouri Department of Natural Resources.

The City of Camdenton received approval to implement the Industrial Pretreatment Program on September 26, 1983 by the Missouri Department of Natural Resources. The City of Camdenton operates five lagoons. However, only one lagoon is of interest to the Industrial Pretreatment Program, that is the Hulett (a.k.a. Factory) lagoon.

#### FINDINGS:

The City of Camdenton has jurisdiction over their entire collection and treatment system. They operate five lagoons, only one receives an industrial waste. The Hulett lagoon receives the waste from Sunstrand Tubular Products, Inc.

Sunstrand Tubular Products, Inc. is a manufacturer of aluminum and copper components and heat transfer coils for air conditioners, used in homes, automobiles, and various industries. The manufacturing process consists of aluminum and copper cutting and brazing, aluminum etching, and a small amount of chromium electroplating. They have installed a pretreatment system to remove heavy metal components from their wastewater primarily from the aluminum etching process. The system was finished prior to the pretreatment audit but the reagent tanks were still being filled so it was not in operation.

The City of Camdenton has not developed their sampling, inspection, and permitting procedures. They need to address a variety of topics in their pretreatment program. An increase in personnel familiar with pretreatment and/or sampling and tracking procedures would be helpful. Parts of the program could be contracted to consultants.

The city personnel involved have been very conscientious but they are working with a handicap of not enough time and resources.

#### **RECOMMENDATIONS:**

- 1. Establish, document, and implement formal sampling procedures.
- 2. Pursue enforcement actions as specified by the federal pretreatment regulations.

Pretreatment Compliance Audit City of Camdenton June 20, 1986 Page two

- 3. Establish local limits with regards to production rates, method of waste treatment, method of sludge disposal, and NPDES discharge limits.
- 4. Have adequate personnel available or on contract for sampling, analyzing, monitoring, tracking, and enforcing the pretreatment program.
- 5. Up-date city ordinances and policies with any changes in the federal pretreatment program.
- 6. Submit all changes of your sewer use ordinance and pretreatment program to the Department of Natural Resources for approval.

Should you have any questions please call the Jefferson City Regional Office at (314) 751-2729.

Submitted By:

Leora M. Reising

Environmental Specialist

Approved By:

B.R. Kesler

Regional Administrator

LR/ko

Enclosure

### INSPECTED BY Leave M. Reising DATE OF AUDIT 9/16/86

### POTV PRETREATMENT PROGRAM AUDIT

1.	Gener	ral Information
	(A)	NAME OF PERMITTEE: CITY OF CAMBENTON (B) NPDES # MO-0048577
	(C)	MAILING ADDRESS: CITY HALL . HULETT (AKA. FACTORY)
		P.O. BOX 399
		CAMPINTON MO 65020
	(D)	POTW ADDRESS: NONE
		•
	(E)	POTH REPRESENTATIVE: D. ROGER ELDER
	(F)	TITLE: CITY ADMINISTRATOR
	(G)	TELEPHONE NO: (314). 346-3600
		PRETREATMENT PROCRAM APPROVAL DATE: 9 / 26/83
		PREVIOUS PRETREATMENT AUDIT:/ NONE
2.	POTW	<u>Information</u> .
		DESIGN DRY WEATHER FLOW 26,500 GD togeth
		AVERACE ANNUAL FLOW(mgd)
	(C)	PERCENT INDUSTRIAL FLOW UNKNOWN 7
		SEWER SYSTEM: SEPARATE X COMBINED
		LEVEL OF TREATMENT: Primary TYPE:
		SecondaryX LAGOON
		Advanced Secondary
		Tertiary
	(F)	METHOD OF SLUDGE DISPOSAL: NOT APPL.
		Eliza di dadati bidi della Tra di Ali I a
3.	Summ	ary of Program Evaluation (S) (U) (R) N/A
	(A)	Legal AuthorityX
	(B)	Local Limits 🗶
	(C)	Inspection and Monitoring ProceduresX
	(D)	Control Mechanism and Enforcement X
	(E)	POTW Records and Public Participation.
		Program Resources
(S)	- Sa	tisfactory (U) - Unsatisfactory
,		

(R) - Revisions to Program Needed

		LEGAL AUTHORITY		<u> </u>	10
1.	POTW (A)	Jurisdiction Are all industrial contributions within the POTV's jurisdiction	<u>Yes</u>	No.	N/A
	(B)	Is this jurisdictional situation as documented in the approved pretreatment program	X		
		If not, have legal agreements/contacts been entered into with new jurisdictions			<u>×</u>
	(C)	Are exiting pretreatment agreements with contributing jurisdictions proving to be effective for regulating IUs in those jurisdictions		<u> </u>	X
	COMM	ENTS:			
2.	Seve (A)	Is the current SUO identical to that in the approved pretreatment program  If not, were revisions approved by the State  If not, did unapproved changes occur to section  o General Prohibitions  o Specific Prohibitions  o Local Limits  o Categorical Standards  o Control Mechanisms  o Inspection, Surveillance & Monitoring  o Compliance & Enforcement  o Confidentiality Requirements  o Special Agreements/Waivers	<u>-</u>	<del></del>	
	COMM				
3.	Summ	ary Evaluation of Legal Authority	(S)	ເບາ	(R)
	COMM	ENTS:	<u>X</u>		

### LOCAL LIMITS

•	Stat	<u>us</u> Yes No
	(A)	Does the POTW have local limits
		If yes, are local limits technically based X
	(B)	Do local limits exist for:  BOD.
	(C)	Are removal credits employed
	(D)	If there is more than one POTW treatment plant, are the local limits established specifically for each plant
2.	Cate	gorical Industries
	(A)	Number of industries affected by Categorical Standards
	(B)	Number of industries using the combined waste stream formula
	(C)	Number of industries with production based limits
	(D)	system for which the categorical standard is more stringent than the locally established limits
		If yes: Is the more stringent limit in the

з.	Effectiveness of Local Limits		
	(A)	Is POTW consistently meeting NPDES limits X	
	(B)	Has the POTV been free from industrial inhibition/upsets	
	(C)	Are water quality standards being met unknown	
	(ם)	Has the POTV been free of sludge contamination problems	
	(E)	Has toxicant sampling of POTW influent, effluent and sludge been conducted during the last year	
	(F)	Does the POTV conduct biomonitoring analyses of the effluent	
	COMM	ENTS:	
4.	Summ	ary Evaluations of Local Limits (S) (U) (R)	
	COMM	ENTS: (5) (7)	
		Sunatrond installed its pretreatment	
		Sunatrond installed its pretreatment silt printings with printing (prom & 1: -9A) porriga	
		April & May)	

### INSPECTION AND MONITORING PROCEDURES

1.	Cene	<u>ral</u>
	(A)	How many facilities were inspected in the last year
	(B)	How many facilities were sampled in the last year O O 7
	(C)	What percentage of inspections were announced
	(ם)	What percentage of sampling visits were announced
	COMM	ENTS:
2.	Proc	<u>edures</u>
	(A)	Yes No Are formal sampling and inspection procedures established
	(B)	Are inspectors provided with safety equipment X
	(C)	Are samples split with industry personnel NA
	(D)	Are all samples properly preserved MA
	(E)	Are chain-of-custody procedures employed PA
	(F)	Do all analyses conform to EPA methodologies. ~/A
	(G)	Is there a QA/QC program for sample analyses. NA
	COMM	ENTS: The city has not take samples at Sunstrand.
з.	Summ	ary Inspection and Monitoring Evaluation
	COMM	ENTS: (S) (U) (R)

### CONTROL MECHANISM AND ENFORCEMENT

Indicate		the type(s) of control mechanism employed:
		Permit System
1.	Conti	rol Mechanism Yes No N/A
	(A)	Yes No N/A  Is the control mechanism as described in the approved program
	(B)	Are all significant industrial users regulated through the control mechanism
	(C)	Are permits/contracts:  o For a limited duration
	(ם)	Do permits/contracts:  o Contain local limits
	COMMI	ENTS:
2.	Nonco	ompliance and Enforcement
	(A)	How many categorical industrial users (CIUs) were found to be out of compliance with local or categorical discharge limits (whichever is more stringent) during the past year
		How many of these CIUs regained compliance during the same period of time
	(B)	How many significant industrial users (SIUs) were found to be out of compliance with local discharge limits during the past year
		How many of these SIUs regained compliance during the same period of time

	(C)	Fist enforcement actions taken to pring Alorators into combinance.				
		Administrative	Yes No	How many times		
		o Verbal warning o Written warning o Notice of violation letter o Compliance schedule	$\frac{X}{X} - \frac{X}{X}$			
		o Revoke permit o Termination of service o Other (specify)	<u>X</u> <u>X</u> X X X			
		<u>Legal</u>				
		o Consent decree o Civil penalties o Criminal penalties o Injunctive relief o Other (specify)	<u>X</u>	<u> </u>		
	(D)	How many IUs are currently operational a compliance sheedule to correct diviolations	ing under Hischarge			
	(E)	What percentage of all IUs regulat the POTW pretreatment program are with pretreatment standards at the	in complian			
	COMM	ENTS:				
з.	Summ	ary Control Mechanism & Enforcement	Evaluation	(S) (U) (R)		
	COMM	ENTS:		<u> </u>		

### POTW RECORDS AND PUBLIC PARTICIPATION

1.	Indu	strial Waste Survey (IWS) Yes	No
	(A)	Is the IWS periodically updated	<u> </u>
	(B)	Have all new industrial discharges been adequately characterized	
	(C)	Have any industries been removed from the list of significant dischargers	_X_
	COMP	MENTS:	
2.	Repo	ort Review & Analysis	
	(A)	Are inspection and sampling records well organized and readily retrievable	
	(B)	Are sampling results checked against discharge standards	
	(C)	Are appropriate actions taken in response to problem monitoring reports	
	(0)	Are all records maintained for 3 years	<del></del>
	COM!	ENTS: No sampling has been done	
з.	<u>Indu</u>	estrial Reporting	
	(A)	Has the POTW required self-monitoring reports from industrial users in accordance with categorical standards	
	(B)	Has the POTV required submission of baseline monitoring reports	
	(C)	Are self-monitoring reports and BMR verified by field inspectionsX	
	COMM	ENTS:	

4.	Publ.	ublic Participation Yes		No		
	(A)	Did the POTW publish an annual notice of violators in local newspapers		<u> </u>		
	(B)	Are all program records available to the public	_X_			
	(C)	Has public comment been solicited during . revisions to the SUO and or local limits	X		N/A	_
	COMM	ENTS:				
5.	Summ	ary POTW Records and Public Participation Evaluati	on			
	COMM	ENTS:	(S)	(U)	(R) X	

9 or 120

### PROCRAM RESOURCES

1.	Mane	oover.	Yes	No
	(A)	Are adequate personnel provided in the following areas:	163	
		o Sampling o Sample analyses o Inspection o Administration o Legal o Technical Review	• NA • X • X	
	(B)	Do available personnel have appropriate training	•	_X_
	(C)	Is a commercial lab used		
		If yes, for what analyses:		
	COMM	MENTS:		
2.	Equi	<u>lpment</u>		
	(A) (B) (C) (D)	Is adequate sampling equipment available	•	
	COMM	MENTS:		
з.	Fund	ding		
	(A)	Is the program adequately funded	·	
	(B)	Is funding expected to continue at an adequate level	•	
	COMP	MENTS:		
	_			
4.		mary Evaluation of Resources (S) (U	) (R)	
	COMP	MENTS:	X	_



Former Hulett Lagoon Site Combined PA/SI Reference 12

Victoria M. Haines Environmental, Health & Safety Counsel Direct Dial: 815-226-6136 Law Dept. Fax: 815-226-3202 e-mail: ccglath@snds.com

February 5, 1999

RECEIVED

FEB 8 1999

HAZARDOUS WASTE PROGRAM MISSOURI DEPARTMENT OF NATURAL RESOURCES

Valerie Wilder
Environmental Specialist
Hazardous Waste Program
Department of Natural Resources
P.O. Box 176
Jefferson City, MO 65102-0176

RE: Missouri Department of Natural Resources' December 18, 1998 Letter Preliminary Assessment/Site Inspection - Former Hulett Lagoon

Dear Ms. Wilder:

This letter and attachments are voluntarily submitted on behalf of Sundstrand Corporation ("Sundstrand") in response to the Missouri Department of Natural Resources' ("MDNR") December 18, 1998 letter to Sundstrand requesting written responses to specific questions set forth in the letter. It is Sundstrand's understanding that this is not a "notification and request for information" pursuant to 104(e) of the Comprehensive, Environmental Response, Compensation & Liability Act of 1980, as amended, ("CERCLA"), given the MDNR does not have the authority to issue such a request. Rather this request is made as part of MDNR's Preliminary Assessment /Site Inspection under CERCLA at the former Hulett Lagoon, a closed lagoon which was part of the City of Camdenton's publicly owned wastewater treatment facility ("POTW") permitted under the Clean Water Act. Nevertheless, Sundstrand is voluntarily providing responses and documents to this request as well as identifying appropriate references to the Modine Manufacturing Company ("Modine") and MDNR files.

By cooperating with the MDNR, Sundstrand does not waive any rights or defenses that it may have to this or subsequent requests or actions. The responses to any of the questions in the attachment should not be construed as an admission of any liability on the part of Sundstrand. Further, none of the material or responses supplied

Valerie Wilder February 5, 1999 Page Two

herein should be construed as an admission of wrong-doing or evidence of any violation of federal, state, or local statutes or ordinances.

In summary, Sundstrand's understanding is that the former Sundstrand Tubular Products facility ("Facility"), located in Camdenton, Missouri, and operated from 1972 to 1990, did discharge wastewater into the City of Camdenton's sewer system as authorized by the Missouri Clean Water Act and pursuant to a pretreatment permit. Sundstrand is currently unaware of any waste containing TCE which was disposed of by Sundstrand at or near the Hulett Lagoon other than through the sewer system. It is our understanding that Modine, the current owner of the Facility is undergoing RCRA closure and is testing and remediating the soils and groundwater pursuant to RCRA regulations. Historical documents regarding the use and disposal of hazardous substances were left at the site when the Facility was sold to Modine. Any spills or other releases at the Facility may be documented in Modine's records.

Attached is the information requested in the letter and the documents which support the responses. Although a number of the questions were unclear in certain areas, Sundstrand has provided the information it interpreted the questions to be requesting, instead of objecting to the questions. This was done to facilitate MDNR's inspection time frame. If the MDNR believes that the question was not interpreted properly, Sundstrand will try to be responsive once notified of the discrepancy.

Finally, when Sundstrand sold Sundstrand Tubular Products, Inc. to Modine, a viable corporation continued to exist and operate out of the facility. It therefore seems more efficient, productive and appropriate for the MDNR to seek further information or any remedial actions from the current owner/operator of the Facility, Modine, rather that Sundstrand.

If you have any questions concerning this response, please do not hesitate to call me at 815-226-6136.

Very truly yours,

SUNDSTRAND CORPORATION

Victoria M. Haines

Victor H

VMH:cmm

### Sundstrand Corporation's Response to the MDNR's December 18, 1998 Letter Former Hulett Lagoon, Camdenton, Missouri Combined Preliminary Assessment/Site Inspection

1. State when Sundstrand Corporation or Sundstrand Tubular Products acquired any interest in or ownership in the site located at 179 Sunset Drive, Camdenton, Missouri, or portion thereof. Provide copies of all documents evidencing or relating to such ownership or interest, including, but not limited to purchase agreements, deeds, or leases, etc.

In 1972 Sundstrand Corporation incorporated Dawson Metal Products, Inc. ("Products"), a Delaware Corporation, as a wholly owned subsidiary of Sundstrand Corporation ("Sundstrand"). On June 29, 1972, Products acquired the business and assets of Dawson Metal Products, Inc. ("Dawson"), a Kansas Corporation. In connection with the acquisition Products, the Delaware corporation, by way of assignment, acquired a leasehold interest in the Sunset Drive property. See Attachment 1. After the acquisition was complete, Dawson, the Kansas corporation, continued in existence.

Sundstrand believes the Sunset Drive property was held by Dawson, the Kansas corporation, pursuant to a lease dated November 28, 1966 between Dawson and the Camdenton Industrial Development Corporation. See Attachment 2. The lease had a term of ten years (which is believed to have commenced July 1, 1967) with an option to Dawson to purchase.

Products, the Delaware corporation, changed its name to Sundstrand Tubular Products, Inc. ("Sundstrand Tubular") on May 25, 1977.

By agreement dated August 24, 1990 Sundstrand agreed to sell the business and assets of Sundstrand Tubular to Modine Manufacturing Company ("Modine"). This transaction was closed on October 18, 1990 and the Sunset Drive property of Products was transferred to Modine by deed dated around October 18, 1990.

On November 27, 1990, Products changed its name to Sundstrand Camdenton, Inc. and on March 15, 1994 Sundstrand Camdenton, Inc. was liquidated.

2. State how long Sundstrand Corporation or Sundstrand Tubular Products held interest or ownership in the site at 179 Sunset Drive, Camdenton, Missouri. State the current status of the Sundstrand Tubular Products Corporation. Provide copies of all documents evidencing or relating to the sale, dissolution, or termination of Sundstrand Tubular Products.

See Response #1.

- 3. Identify the physical characteristics of the facility during Sundstrand's operations. Provide a facility map showing the location of surface and subsurface features. Include the following in your description:
- a. Surface structures (e.g., buildings, tanks, etc.);
- b. Underground tanks, pits, and/or vats;
- c. Subsurface pipelines, utility lines, sewage and drainage systems; and
- d. All construction, alterations, renovations, and/or demolition of the items in 4.a. through 4.c. above.

The Sundstrand Tubular facility ("Facility") was a metal-sided manufacturing facility of approximately 100,000 sq. ft. It was originally constructed by Dawson in 1968 with additions in 1971, 1973, 1977 and 1983. There were no underground storage tanks located at the Facility. The Facility had four small concrete mud pits used to settle solids along the west exterior wall. See Attachment 3. See also MDNR's RCRA files.

4. Describe all processes performed at the facility.

Sundstrand Tubular manufactured heat transfer components for commercial and automotive industries at the Facility. The manufacturing process flowed as follows:

- a. Copper and aluminum tubing were fed from rolls to benders to form U shapes and then cut off;
- b. Parts were then immersed in alkaline cleaning lines to remove oil and chips;

а

- c. Parts were degreased to remove any remaining oil;
- d. Clean parts were assembled and small U shaped copper tubing and aluminum tubing ends were brazed to assembled cores using manual and automatic brazing systems;
- e. The assembled heat transfer components were degreased and/or alkaline cleaned and then tightness tested using refrigerant; and
- f. Finally, the components were then painted if required by the customer and packaged for shipment. See Attachment 4.

- 5. Did Sundstrand ever transport to the facility or use, purchase, generate, store, treat, dispose or otherwise handle any hazardous materials at the facility? If the answer to this question is anything but an unqualified a "no," identify:
- a. The chemical composition, characteristics, physical state (e.g., solid, liquid) of each hazardous materials transported, used, purchased, generated, stored, treated, disposed or otherwise handled;
- b. For each such hazardous material used, state how, when, where and in what quantities the hazardous material was purchased, used, generated, stored, treated, transported, disposed or otherwise handled;
- c. Any analyses conducted of the hazardous material so transported, used, purchased, generated, stored, treated, disposed, or otherwise handled, and provide copies of such analyses.

Sundstrand is interpreting the term facility used in this question to mean the manufacturing facility and not the Hulett Lagoon. Purchase and consumption records of materials were maintained solely by Sundstrand Tubular during its operation of the business at the time of Sundstrand Tubular's sale to Modine. Sundstrand believes that Sundstrand Tubular submitted a SARA Tier 2 submittal to the USEPA and State of Missouri in 1989. If the documents still exist, they would be on site and maintained by Modine. (Sundstrand did not take possession of these documents at the time of Sundstrand Tubular's sale to Modine.) See also the MDNR's RCRA files.

- 6. Did Sundstrand arrange for transportation, disposal or treatment of waste materials, including hazardous substances to the facility? If the answer to this question is anything but an unqualified "no," identify:
- a. The persons with whom you made such arrangements;
- b. The type of arrangements made;
- c. Every date on which such arrangements or shipments took place;
- d. The total quantity of waste materials or hazardous substances transported to the site:
- e. The amount paid or collected in connection with each transaction, the method of payment, and the identity of the person from whom payment was given or received;
- f. The names and addresses of any persons who transported waste materials or

hazardous substances to the site;

g. All documents containing information responsive to subparts a. through f. of this question.

No. Sundstrand Tubular was not a commercial transport, storage and disposal facility and did not bring hazardous wastes onto the Facility for any purpose.

- 7. Identify to the best of your ability whether any leaks, spills, releases or threats of releases of any kind into the environment of any hazardous materials have or may have occurred at the Sundstrand facility. If yes, please provide the following:
- a. When such releases occurred,
- b. How the releases occurred,
- c. What hazardous substances were released,
- d. What amount of each such hazardous substance was so released,
- e. Where such releases occurred,
- f. Any and all activities undertaken in response to each such release; and

Sundstrand is aware of two potential releases at the Facility. Pursuant to former Dawson employees, a fire broke out at the Facility in the 1960's. In fighting the fire, a washdown occurred in an area where trichloroethylene ("TCE") was utilized. A second alleged release of 4500 gallons of TCE was anonymously reported to the MDNR August 9, 1990. Sundstrand has investigated both situations and concluded that neither release had occurred. Subsequent investigations by Modine in November 1991 and by MDNR in March 1993 also could not confirm that the releases had occurred. See Attachment 5. See also MDNR's RCRA files.

8. State whether, at the time Sundstrand acquired the facility, there was any reason to know or suspect that any hazardous substances were disposed or spilled on, in or at the site.

No.

9. Please submit information on all persons and how they may be contacted (include current work and home addresses and phone numbers) with information relating to any of the above questions.

Mark Chiado, Sundstrand Corporation, Manager, Environmental Planning & Auditing, 815-226-6351

Victoria Haines, Sundstrand Corporation, Environmental, Health & Safety Counsel, 815-226-6136

William R. Coole, Sundstrand Corporation, Associate General Counsel, 815-226-6303

Tom Misiak, The Falk Corporation, President, 414-937-4777

Robert Miller, Sundstrand Corporation, Director, Environmental, Health & Safety, 815-226-2755

William Johnson, Sundstrand Corporation, Risk Manager, 815-226-7820

10. Please indicate whether any of the following individuals are currently employed with Sundstrand Corporation or any subsidiary thereof (include current position/title, work and home addresses and phone numbers):


William R. Coole\*
Paul Donovan\*
James W. Ethington
Kenelm Groff
Lloyd E. Larson
LeMoyne G. Loseke
Charles E. Martin
Frank G. Malewitz
Thomas F. Otto
Philip W. Polgreen
Ted L. Ross
Richard M. Schilling
Neil D. Traubenberg\*
Berger G. ("Bud") Wallin
Donald M. Wills

individuals still employed.

Venevieve maroske

My Commission expires: May 31, 1974 Former Hulett Lagoon Site

Combined PA/SI Reference 13



### Office of Secretary of State


### I, Walton H. Simpson, Secretary of State of the State of Delaware,

on hereby certify that the Certificate of Incorporation of the "DAWSON METAL PRODUCTS, INC.", was received and filed in this office the twelfth day of June, A.D. 1972, at 10 o'clock A.M.;

And I do hereby further certify that the aforesaid Corporation is duly incorporated under the laws of the State of Delaware and is in good standing and has a legal corporate existence so far as the records of this office show and is duly authorized to transact business.

In Testimony Whereof, Thave hereunto set my hand

and official seal at Dover this thirteenth day of June in the year of our Lord one thousand nine hundred and seventy-two.



Secretary of State

Walter H Simpson

No. ... Fr157.085.....



Former Hulett Lagoon Site Combined PA/SI Reference 14

### STATE

JAMES C. KIRKPATRICK, Secretary of State
CORPORATION DIVISION

### Certificate of Authority

WHEREAS,

DAWSON METAL PRODUCTS, INC.

(using in Missouri the name

DAWSON METAL PRODUCTS, INC.

incorporated under the Laws of the State of

DELAWARE

for a term

of perpetual years and now in existence and in good standing in said State has filed in the office of the Secretary of State, duly authenticated evidence of its incorporation, as provided by law, and has, in all respects, complied with the requirements of General and Business Corporation Law governing Foreign Corporations;

NOW, THEREFORE, I, JAMES C. KIRKPATRICK, Secretary of State of the State of Missouri, by virtue of the authority vested in me, do hereby certify that said corporation is from the date hereof duly authorized to carry on the business of

### Sale and distribution of air conditioning equipment and related parts.

in the State of Missouri,


and is entitled to all rights and privileges granted to Foreign Corporations under The General and Business Corporation Law; that the entire amount of its stated capital and surplus is

\$654,558.00. and \$1,000.00. of the amount of stated capital of said corporation is

represented by

1,000 shares of common 2 \$1.00

that the proportion of stated capital and surplus represented in Missouri is \$ 647,715.00 and that its registered office in Missouri is located at 314 North Broadway, St. Louis



IN TESTIMONY WHEREOF, I have hereunto set my hand and affixed the GREAT SEAL of the State of Missouri, at the City of Jefferson, this \_25th\_day of \_\_\_\_\_\_\_\_, 19.72.

James ettick alicel Socretary of State

RECEIVED OF: DAWSON METAL PRODUCTS, INC.
Seven hundred sixty-eight end no/00 Dollars, \$ 768.00
En Codit of Consel Bosses Find on Asses of Language Translation

For Credit of General Revenue Fund, on Account of Incorporation Tax and Fee.

No.....F-157085

Dorochymae Miller Deputy Collector of Revenue



### State of Missouri · · · Office c

Former Hulett Lagoon Site Combined PA/SI Reference 15

### APPLICATION FOR AN AMENDED CELEBOOK FOR A FOREIGN COK.

(To be submitted in duplicate by an attorney)

HONORABLE JAMES C. KIRKPATRICK SECRETARY OF STATE STATE OF MISSOURI JEFFERSON CITY, MO. 65102 Products, Inc. SUNDSTRAND TUBULAR PRODUCTS, INC., formerly Dawson Metal / a corporation. pursuant to the provisions of "The General and Business Corporation Law of Missouri" relating to amended certificate of authority of Foreign Corporation, does hereby state, (1) Its name is Sundstrand Tubular Products, Inc. it was incorporated in the State of Delaware ; and it was qualified in the State of Missouri on September 25, 1972 (2) The name it will use in Missouri is \_\_\_\_\_Sundstrand\_Tubular\_Products.\_Inc. The address of its principal office in the state or country of organization is Sunset Drive, Camdenton, Missouri 65020 (Include street and number, if any.) (4) The address of its registered agent in Missouri is ...... 314 North Broadway, St. Louis, Missouri 63102 (Include street and number, if any.) and the name of registered agent in Missouri at such address is ..... C T Corporation System (5) The corporation is qualified under the following states and countries other than Missouri: NONE FILED AND AMENDED CERTIFICATE OF **AUTHORITY ISSUED** AUG 29 1977 (6) By appropriate corporate action on May 25 ( 1. Changed its corporate name to Sundstrand Tubular Products, Inc.

PLACE NOTARY SEAL HERE

My Commission expires: September 29, 1980 AND AMENDED CERTIFICATE OF

FILED AUTHORITY ISSUED

AUG 29 1977

Corporation Dept. SECRETARY OF STATE

No. F00157085



### STATE OF MISSOURI

ROY D. BLUNT, Secretary of State

CORPORATION DIVISION

### Certificate of Withdrawal

WHEREAS, an Application for Withdrawa	lof
	SUNDSTRAND TUBULAR PRODUCTS, INC.
aDELAWARE	corporation, has been received, found to conform to law, and filed
NOW, THEREFORE, I, ROY D. BLUNT,	Secretary of State of the State of Missouri, issue this Certificate of
Withdrawal, certifying that the afornamed of	corporation is withdrawn from this state.
	IN TESTIMONY WHEREOF, I hereunto set my hand and affi
	the GREAT SEAL of the State of Missouri. Done at the City of
	Jefferson, this18th day ofAPRIL
	19 <u>91</u> .
	Loy Secretary of State

Corp. #27 (1-85)



#### **ENVIRONMENTAL SITE ASSESSMENT**

## MODINE HEAT TRANSFER, INC. POST OFFICE BOX 636 SUNSET DRIVE CAMDENTON, MISSOURI

#### PREPARED FOR:

MODINE MANUFACTURING COMPANY 1500 DEKOVEN AVENUE RACINE, WISCONSIN

PREPARED BY:

RECEIVE D

HAZARDOUN WASTE PROGRAM MISSOURI DEPARTMENT OF NATURAL RESOURCES

LAW ENVIRONMENTAL, INC.
911 WASHINGTON AVENUE, SUITE 160
ST. LOUIS, MISSOURI

LAW ENVIRONMENTAL PROJECT NO. 53-1543

**NOVEMBER 1991** 



### TABLE OF CONTENTS

			Page Number		
1.0	BACKGROUND INFORMATION				
2.0	PURPOSE				
3.0	WORK COMPLETED				
4.0	SUMMARY	SUMMARY OF SITE CONDITIONS			
	4.2 Site C	Description	3		
5.0	RESULTS O	OF LABORATORY ANALYSES	4		
6.0	CONCLUSIONS				
7.0	RECOMMENDATIONS				
TABL	ES				
	Table 1 Table 2	Summary of Field Organic Vapor Analyses of Soil Samples Summary of Soil Laboratory Analyses			
FIGURES					
	Figure 1 Figure 2 Figure 3	<ul> <li>Generalized Site Plan Showing Manufacturing Plant Premises</li> <li>Area #1 Detail Map with Hand Auger Boring Locations and Analytical</li> </ul>			
	Figure 4	Results of Soil Samples Area #2 Detail Map with Soil Boring Locations and Analytica of Soil Samples	al Results		
APPENDICES					
	4 4	Soil Boring Logs Laboratory Data Sheets			



#### 1.0 BACKGROUND INFORMATION

The project site is a manufacturing plant located in Camdenton, Missouri (Figure 1). The plant formerly operated as the Sundstrand Tubular Product, Inc. facility, a subsidiary of the Sundstrand Corporation, prior to the October 19, 1990 acquisition by Modine Heat Transfer, Inc., a subsidiary of the Modine Manufacturing Company. The plant is currently operating as the Modine Heat Transfer, Inc. facility producing heat transfer products, and is a RCRA generator. It is our understanding that the facility has submitted a Part B operating permit application and is currently operating under interim status.

The plant has used 1,1,1-trichloroethane (TCA) for degreasing operations since December, 1990. The plant generated trichloroethylene (TCE) waste during degreasing operations from the early 1970's to December 1990. According to information obtained from Modine Manufacturing Company, the TCE waste was containerized in 55 gallon drums and stored outside the plant in two separate locations from the early 1970's to 1983. One area of storage was located along the south outer wall of the plant where the drums were placed on a concrete pad (Area 1). The Missouri Department of Natural Resources suggested to Modine that an alleged 4,500 gallon release of spent solvent occurred at the plant. It is our understanding that a building addition was erected over the spill area in 1983. Another storage area was located along the outer west wall of the plant building (Area 2). Information pertaining to the exact location and leak history of this storage area is not readily available to Law Environmental at this time. Figure 2 is a generalized site plan showing locations of Areas 1 and 2.

#### 2.0 PURPOSE

The purpose of this project was to assess site soil in Areas 1 and 2 for the presence of TCE. The tasks performed include drilling soil borings for the purpose of collecting soil samples for laboratory analyses and preparation of this summary report.

#### 3.0 WORK COMPLETED

Five soil borings were drilled in an area where Don Mans of Modine believed the leakage of the TCE from the fifteen 55-gallon drums occurred (Area 1). Three of these borings (HA-1, HA-2, and HA-3) were drilled from the plant floor surface and two of these borings (HA-4 and HA-5) were drilled from the floor of the degreasing machine pit. The floor of the degreasing machine pit is approximately 5.5 feet below the plant floor surface. See Figure 2 for location of Area 1 and Figure 3 for a detail map of Area 1 showing boring locations. The concrete floor of the plant was cored by the use of an electric core drill. Borings were drilled and soil samples collected by the use of a hand auger. Soil samples were collected at two foot intervals to a depth at which the hand auger refused to advance.

Former Hulett Lagoon Site Combined PA/SI Reference 19

100

1.200 Camdenton

MO-0048577; MO-0048593 MO-0048569; MO-0048585

MO-0048607

September 13, 1978

Honorable Ken Mensendiek, Mayor City of Camdenton 112 Court Circle Camdenton, Missouri 65020 marked to

Dear Mayor Mensendiek:

An inspection was conducted of the operation and condition of the wastewater treatment facilities serving the City of Camdenton, Missouri on September 7, 1978. The following unsatisfactory features were observed and recommendations are hereby made for their correction.

#### UNSATISPACTORY FEATURES:

- 1. The Hulett Lagoon (#3) is short circuiting the industrial waste.
- 2. The industrial waste entering the Hulett lagoon appears to kill off the south end of lagoon reducing the facility's effective size.
- 3. The Clint Lagoon needs its own NPDES permit.

#### COMMENTS:

The sewage lagoons serving Camdenton seemed for the most part to be well maintained. The Hulett Lagoon, however has a large problem with its industrial influent. The sewage from Sunstrand enters the lagoon at the south end, which is the same end that the discharge pipe is on. The detention time for the industrial waste could not be more than a few hours, far too short a period to trust the waste.

To correct the short circuiting problem, the location of the influent pipe from Sunstrand should be moved to the north end of the lagoon, or the sewage line could be tied in to the other influent line already at the north end.

Mayor Kan Mensendiek Paga 2 September 13, 1978

The strength of the industrial sewage entering Hulett Lagoon is apparently too great for the facility to handle. The City should enforce its sewar use ordinance, if it has one, to prevent misuse of the sewers and sewage treatment facilities.

Our records show no response by the City toward obtaining a permit for the discharge from the Clint Lagoon. It currently is listed in the NPDES Permit \$M0-0048607 as the first cell of a two cell lagoon. It has, however, its own discharge point and therefore needs its own permit. Either the affluent pipe in Clint Lagoon shall be capped or a permit shall be applied for from this department. The appropriate forms are enclosed.

#### RECOMMENDATIONS:

- 1. Correct the short circuiting in Hulett Lagoon.
- 2. Enforce or create sever use ordinances.
- 3. Apply for discharge permits for Clint and Wilkerson Lagoons.

Sincerely,

Todd Crawford Environmental Engineer

TC/bc

Enclosures

CC: Jeff Hancock, City Administrator

NOV-20-1998 14:32

Former Hulett Lagoon Site Combined PA/SI

ENGINEERING GEOLOGIC REPORT ON COLLAPSE POTENTIAL OF CA Reference 20

#### CAMDEN COUNTY, MISSOURI

LOCATION: White Lagoons, SW4, SW4, NE4, Sec. 35, T. 38 N., R. 17 W., Macks Creek Quad. Hulett Lagoon, SW4, SW4, SW4, Sec. 24, T. 38 N., R. 17 W., Macks Creek Quad. Clint Lagoons, NE's, NE's, SW's, Sec. 24, T. 38 N., R. 17 W., Camdenton Quad. Parish Lagoon, SEt, SWt, NEt, Sec. 19, T. 38 N., R. 16 W., Camdenton Quad. Dump Lagoons, NWt, SWt, SEt, Sec. 25, T. 38 N., R. 17 W., Stoutland Quad.

#### RESULTS:

Investigation of lagoons for the City of Camdenton occurred on September 12, 1978 by Gary St. Ivany and John W. Whitfield. The Camdenton area is underlain by the Gasconade dolowite formation. Layers of chart (one exposed bed was 12 feet thick) and Gunter sandstone were present in the stream beds. Streams were intermittent, with isolated pools and discharge effluent composing most of the flow. Possibilities exist for localized groundwater pollution effecting shallow and poorly cased wells to some extent. Streams in the area drain into Lake of the Ozarks.

The Camdenton lagoons should not be considered in danger of failure by catastrophic collapse, but localized groundwater pollution is possible. For these reasons, the lagoons are designated as Category 2.

Problems exist at the Hulett lagoon site which appear to be design related and not geologic. Effluent was observed bubbling up approximately 40 feet from the discharge pipe. This area appeared to be solid effluent to within 6 inches of the surface. An open channel existed directly from the inlet pipe to the discharge pipe. thus, causing a short circuit. On closer examination, the thick effluent was not solid but floating. It was possible to extend a rod through the effluent to the bottom of the lagoon. Discharge from the lagoon was dark green in color with a thick white foam floating on the surface. If a short circuit does exist in the Hulett lagoon, corrective measures are needed. A possible solution is the location of the inlet pipe at the opposite and of the lagoon to where the discharge pipe is stationeđ.

This situation may be a result of effluent from the metal fabricating plant that

discharges into this lagoon.

A CONTRACTOR OF THE PROPERTY O

ু কর<u>ে স্থার একে এইক্রমন্থ্</u>য করে প্রভ<u>েষ্ট্রের করে । এক্রম্</u>রের করে বছরুছে এবং এবং এক্রিক করে সুক্র করে। এই এক এই বছরুছ

John W. Whitfield, Geologist

Applied Engineering & Urban Geology

Geology & Land Survey

Artmin whiteell

September 14, 1978

They St. I vans Gary st. Ivany, Lab Technician

Applied Engineering & Wrban Geology

Geology & Land Survey September 14, 1978

orig: Jim Odendahl

July 24. Sair Former Hulett Lagoon Site Combined PA/SI Reference 21 in languages

June 21, 1984

JUN 25 1984

Mr. Frank Dolan, P.E. Environmental Engineer Ho. Department of Natural Resources P.O. Box 1368 Jerrerson City, Missouri 65102

RE: Test results from Camdenton

Dear Hr. Dolan:

Attached is a copy of the test results for Camdenton's Factory Lagoon. The City will be performing another series of tests but, because of the expense we would appreciate your input concerning the actual items requiring retesting. The City will meet with you now or after the second test results are available. Please contact me or Mr. Ruc Filey concerning the tests needed and if we need to schedule a resting at this time.

If you ahve any questions please feel free to contact me or hr. kiley.

Sincerely,

James C. Jackson, P.N.

J(N) i sw

cc: Hr. Curtis Ogg

City of Candenton



114 East Elm, Suite 3 O'Fallon, MO 63366 314/281-2858

Client: Camdenton, City of

PD Box 399

Customer P. O. Number: 20502

Camdenton

Attention: Bud Riley

MO 65020

Date Reported: 06/15/--

Date Sampled: 05/22/84
Date Received: 05/23/84

MMTL Report No: 17509

MMTL Account No: 10238

#### REPORT OF ANALYSIS

Sample No.	Units	Results
ravenua	=====	222224
SAMPLE #1		
Residue, Total Suspend	ded MG/L	2
→ Total Chrom: υπ	MG/L	( .0C
y 👽 - Shromium, Hexavalent -	mG/L	ି ( .ଉ≳
🔎 lotal Copper	MG/L	େ ଅଷ୍ଟେ
Total Zinc	MG/L	. 04
SHAPEC #C	•	
🔭 🔭 Residue, fotal Saspend	ded MG/L	37
Total Consumbus	mG/L	. 28
Dr. Sheddiam, Hoddyddent	r/G/L	( .છેટ
🎇 , Motsi Copper	2 <b>57</b> 1.	2.3
N° ∕ Stotal Zinc	*6/L	. 1 <i>ë</i>
West minuteers		•
Toluene	u6/E	< 1Ø
Trichloroethylene	13137L	28
Grease & Oil, gravime	tric MG/L	41
SOMPLE #3		
🔥 🖍 Nesidue, Total buspen	oed MG/L	£
pr de lotal Copper	. MG/L	. 11.
Total Zinc	MG/L	, এক
$\mathcal{K}^{\!$	tric MG/L	⟨ 5
SAMPLE #5		
Total Chromium	mGZL.	18
Total Copper حرر	MG/L	1 400
S/ Total Zinc	MG/L	100
Y Per Cent Dry Solids	%	` 3. Ø

or a usua pollacepadu. Ana l'espacarangapada suapuda espacana a quara espacaus

Comments:

\*See attached table.

Approved by: \_ Din Tanpa

Page No.

### Sample #2

Name	Sample Concentration ug/L
Bis(2-chloroisopropyl) ether bis(2-chloroethyl) ether	<1
Bis(2-chloroethyl) ether Bis(2-chloroethoxy) methane	10 <1
4-Chlorophenyl phenyl ether	10
4-Bromophenyl phenyl ether	<b>75</b>

314/874 8080

114 East Elm Suite 3 O'Fallon, MO 63366 314/281-2858

Client: Sunstrand Tubular Products, Inc.

PO Box 636, Sunset Drive

Camdenton

MD 65020

Date Reported: 06/15/.

Date Sampled: 05/28/84

Date Received: 05/23/84

Attention: Don Mans

MMTL Report No:

17510

Customer P. D. Number: 1518

MMTL Account No: 10109

#### REPORT OF ANALYSIS

Samp	le No.	Units	Results
		*****	222222
SAMPI	LE #4		
	Residue: Total Suspended	MG/L	16
	Total Chromium	MG/L	( .0≘
•	Chromium, Hexavalent	MG/L	(.02
. 12	Total Copper	MG/L	. 51
, <b>Ž</b>	Total Zinc	MG/L	. 30
. 1	Haloethers		*
2,4	Toluene	UG/L	15
	Trichlorosthylene	UG/L	41
	Grease & Oil, gravimetric	MG/L	18

Commerits:

\*See attached table

Page No. 1

# Sample #4

Neze	Sample Concentratio
Bis(2-chloroisopropyl) ether	<1
Bis(2-chloroethyl) ether	140
Bis(2-chloroethoxy) methane	<1
4-Chlorophenyl phenyl ether	5
4-Bromophenyl phenyl ether	<5

## Report Number 17693-1

Name	Sample Concentration ug/L
Bis(2-chloroispropyl) ether	1500
Bis(2-chloroethyl) ether	190
Bis(2-chloroethoxy) methane	34
4-Chlorophenyl phenyl ether	<5
4-Bromophenyl phenyl ether	<5

sample from layour

<u>Name</u>	Sample Concentration ug/L				
	•				
Bis(2-chloroispropyl) ether	29				
Bis(2-chloroethy1) ether	250				
Bis(2-chloroethoxy) methane	320				
4-Chlorophenyl phenyl ether	<5				
4-Bromophenyl phenyl ether	<5				

Former Hulett Lag Combined PA/SI Reference 22

112 Court Circle P.O. Box 3 Camdenton, Mo. 65020 314 346 3600

August 20, 1984

Former Hulett Lagoon Site

Mr. Frank Dolan Department of Natural Resources P.O. Box 1368 Jefferson City, Missouri 65102

Dear Mr. Dolan:

This is to confirm our meeting for Monday, August 27, 1984 at 10:00 AM, at City Hall on the pre-treatment program.

Enclosed you will find the second sample results.

Sincerely,

Warren W. Rile City Administr

WWR/kb

Mayor Kelsey

Mr. Jim Jackson, Jackson Engineering

Mr. Tom Misiak, Sundstrand Tublar Products

Mr. Curtis Ogg, Jefferson City Regional Office



Columbia, MO ₹52,91 ... 314/874-8080

114 East Elm, Suite 3 O'Fallon, MO 63366 314/281-2858

AUC 221984

Client: Camdenton, City of

PO Box 399

Camdenton

MO 65020

Date Reported: 08/14/84
Date Sampled: 07/19/84

Date Received: 07/20/84

Attention: Bud Riley

MMTL Report No:

17692

Customer P. O. Number:

MMTL Account No:

10238

# REPORT OF ANALYSIS

Sample No.	Units ====	Results
#2		
Residue, Total Suspended	MG/L	95
Total Chromium	MG/L	.5
Chromium, Hexavalent	MG/L	. 20
Total Copper	MG/L	4. 1
Total Zinc	MG/L	.23
Haloethers		*
Toluene	UG/L	( 10
many the property of the formal section	UG/L	508
Grease & Oil, gravimetric	MU/L	<b>E</b> ,

Comments: \*See Attached Table

Approved by: IDM Hopp

Page No.

1

sample from layour

<u>Name</u>	Sample Concentration ug/L
Bis(2-chloroispropyl) ether	29
Bis(2-chloroethyl) ether	250
Bis(2-chloroethoxy) methane	320
4-Chlorophenyl phenyl ether	<5
4-Bromophenyl phenyl ether	<5



10: Senstand effluent

Columbia, MO 35203 -. 314/874-8080

114 East Elm, Suite 3 O'Faill n. MO 63366 314/381-2858

Client: Sunstrand Tubular Products, Inc.

PO Box 636, Sunset Drive

Canderton

MD 65000

Date Reported: 00/14/84

Date Sampled: 07/19/84

Date Received: 07/20784

Attentions Don Mans

MARINE MARINE E TOUR

. 4.33

. Contomer P. O. Nombert

Most in the social for the 10:37

REPORT OF AMALY US

Sample 180.	Units	Rosults.
With the total	art to like	acume of the
#4		
Residue, Total Suspended	aG, t.	320
local Chromium	MUZL	7.6
Chromium, Hexavalent	MG/L	( .ଶଙ
Total Copper	MG7L	29
Total Zinc	MG7L.	1.4
Halmethers		<b>16</b> .
loludne	Uli/L	ረ 1ውስላ
Trichlorosthylene	1367L	4900
Grease & Oil, gravimetric	MG/L	1 4 হাউ

Comments: \*See Attached Table

1,100 - Condento

Former Hulett Lagoon Site Combined PA/SI Reference 23

# City of Camdent...

112 Court Circle P.O. Box 399 Camdenton, Mo. 65020 314 - 346 - 3600

May 27, 1986

Ms. Leora M. Reising
Environmental Specialist
Department of Natural Resources
Jefferson City Regional Office
1001A Southwest Boulevard
P.O. Box 176
Jefferson City, Missouri 65102

Dear Ms. Reising:

As you are aware, the City of Camdenton has one (1) industry and it is the only industry involved in pretreatment.

With joint efforts between Sundstrand and the City of Camdenton, a CDBG Grant was obtained from the state to construct the retreatment plant for Sundstrand.

The plant has been completed and has been on the line since April 14, 1986. With the exception of some minor start-up problems, the plant appears to be functioning properly. Sundstrand will furnish the City data as it pertains to their testing which will be forwarded to you and your department.

If you have any questions, please feel free to contact me or Trudy Marco.

Sincerely,

City Administrator

DRE/bc

cc: Mayor Kelsey

Trudy Marco, Grant Coordinator

TDG-011 - Camdenton

# STATE OF MISSOURI DEPARTMENT OF NATURAL RESO

Former Hulett Lagoon Site Combined PA/SI Reference 24

MISSOURI CLEAN WATER COMMISSION

1.110 Candilone



# **CONSTRUCTION PERMIT**

The Missouri Department of Natural Resources hereby issues a permit to: City of Camdenton 112 Court Circle P.O. Box 399

Camdenton, MO 65020

for the construction of (describe facilities):

SEE ATTACHED SHEET

Permit Conditions:

Construction of such proposed facilities shall be in accordance with the provisions of the Missouri Clean Water Law, Chapter 204, RSMo, and regulations promulgated thereunder, or this permit may be revoked by the Department of Natural Resources.

As the Department of Natural Resources does not examine structural features of design or the efficiency of mechanical equipment, the issuance of this permit does not include approval of these features.

A representative of the Department may inspect the work covered by this permit periodically during construction. Issuance of an operating permit by the Department will be contingent on the work substantially adhering to the approved plans and specifications.

This permit applies only to the construction of wastewater treatment facilities; it does not apply to other environmentally regulated areas.

September 23, 1986

Effective Date

Frederick A. Brunner, Ph.D.

Director, Department of Natural Resources

March 23, 1988

Termination Date

Filing Fee Paid

Director of Staff, Clean Water Commission

#### CONSTRUCTION PERMIT

SEWERS AND FORCE MAINS: 4,625 lineal feet of 8 inch diameter sewer pipe and 2,367 lineal feet of 6 inch diameter force main as shown on the approved plans.

LIFT STATIONS: A packaged dry well lift station with two pairs of pumps. Each pair of pumps will be capable of discharging at a rate of 175 gpm at a total dynamic head of 185 feet.

These facilities are designed to eliminate the existing factory lagoon, NPDES #MO-0048577, and transport the wastes from the new Sunstrand Expansion to the C.P. White sewage collection system.

Discharge is to be into the C.P. White Lagoon, NPDES # MO-0048569.

Former Hulett Lagoon Site Combined PA/SI Reference 25

# MISSOURI DEPARTMENT OF NATURAL RESOURD DIVISION OF ENVIRONMENTAL QUALITY LABORATORY SERVICES PROGRAM

DEC 15 1987

Pretreatment Monitoring Report Sundstrand Tubular Products, Inc. Camden County, Missouri April 30, 1987

#### INTRODUCTION

At the request of the Water Pollution Control Program a pretreatment monitoring survey was conducted of the industrial wastewater discharge of the Sundstrand Tubular Products factory in Camden County, Missouri. Sampling was conducted from 1500 through 1530 on April 30, 1987 by Lon O'Bannon, III of the Laboratory Services Program, Division of Environmental Quality.

#### **METHODS**

A grab sample (87-1111) was collected of the effluent from the treatment system discharge weir.

All analyses were performed by the Division's Laboratory in Jefferson City. All analyses were conducted in accordance with methods outlined in the Missouri Clean Water Commission Effluent Regulation (10 CSR 20-7.015).

#### **OBSERVATIONS**

The sample was light yellow-green and nearly clear.

**RESULTS** 

See the attached analytical results.

Submitted by

Lon O'Bannon, III

Water Quality Specialist

Field Services Section

Laboratory Services Program

Date

ecamber 7, 1987

Approved by

dames H. Long

Director

Laboratory Services Program

cc: Richard Kuntz, Permits Section, Water Pollution Control Program
Bill Kesler, Regional Administrator, Jefferson City Regional Office

#### LABORATORY SERVICES PROGRAM RESULT OF SAMPLE ANALYSIS

Sample No. 87-1111

Date: 04/30/87

Date: 12/01/87 Project Code: 3211/3222 Reported to: LON O'BANNON III Affiliation: WQM

Sample Description:

SUNDSTRAND TUBULAR PRODUCTS, INC. - CAMDEN CO.

PRETREATMENT MONITORING.

GRAB FROM TREATMENT SYSTEM DISCHARGE WEIR TANK

Collected by: LON O'BANNON III

Affiliation: WQM

PARAMETERS	RESULTS				
CYANIDE	<0.05 mg/L				
TOTAL SILVER	<l l<="" td="" ug=""></l>				
TOTAL CADMIUM	<2 ug/L				
TOTAL CHROMIUM	2,700 ug/L				
TOTAL COPPER	890 ug/L				
TOTAL HEX. CHROMIUM	180 ug/L				

Page 2 Sample no. 87-1111 Date 12/01/87

PARAMETERS

RESULTS

TOTAL NICKEL

50 ug/L

TOTAL LEAD

<5 ug/L

TOTAL ZINC

110 ug/L

VOA RESULT : NO RESULT

COMMENTS: ANALYTICAL ERROR

Missouri Engineering Corporation
ENGINEERING CONSULTANTS

P.O. BOX 13 ROLLA, MISSOURI 65401 • PHONE: 314-364-4003

April 25, 1988

Dave Friese
Department of Natural Resources
Water Pollution Control Program
P. O. Box 176
Jefferson City, MD 65102

Dear Dave:

You will find enclosed a copy of the sludge analysis report on the sludge from the abandoned Hulett Lagoon in Camdenton, Missouri. I have calculated the amount of dry sludge, based on an average of 9" thickness, at approximately 1250 cubic yards. 9375 gallers

The soil available in the berms to be mixed with the sludge if left on site would be approximately 2000 cubic yards.

I am also sending a copy of this letter to Ken Arnold. Would you both please review the data and let me know what the next step can be?

Sincerely,

MISSOURI ENGINEERING CORP.

Charles Ray

CR/1c

Enc.

cc: Mayor Webster, Camdenton

Ken Arnold

Charles K

Wike Romando



1915) Lackland Road St. Louis, Misso 16 63146 (314) 434-6960

REPORT OF ANALYSIS

CLIENT: Valda Mahoney

Missouri Engineering Post Office Box 13 Rolla, MO 65401

REPORT DATE:

April 19, 1988

SAMPLE ANALYZED: Ten sludge samples for

metals analysis.

DATE RECEIVED:

March 7,1986

PROJ. #: 3222-00353

P.O. 8:

Parameter	# 1	<b>\$</b> 2	‡ J	• 4 ========	<b>+</b> 5	<b>‡</b> 6	<b>1</b> 7
Aluminum (MG/L)	55700	67400	77000	89300	79200	47100	52000
Chromium (MG/L)	12400	24300	28900	19000	24300	12300	15600
Cadeius (M6/L)	₹ 26.0	₹ 25.4	₹ 35.7	(13.3	< 26.0	< 23.2	< 27.8
Copper (M6/L)	28800	24300	15100	52400	22600	34900	18700
Lead (MG/Lit	(101	< 99.1	<139	150	< 101	146	153
Nickel (M6/L)	91.0	119	179	215	110	85.9	89.0
Zinc (MG/L)	4910	4170	4330	5760	3810	4910	3710
	7.02	9.04	5.92	15.78	8.32	9.81	7.83
•							
Parameter	# 8	<b>#</b> 9	# 10				٠.
2222222	77222222	2222222	:=======	•			
Aluminum (M6/L)	53200	55100	51200				•
Chromium (M6/L)	11400	6430	15900				
Cadaius (M6/L)	( 9.90	< 22.8	(18.2				

30100

Lead (MG/L) 113 155 125 Nickel (M6/L) 48.5 77.4 111 Zinc (M6/L) 3470 2920 3620 8.88 25.09

4540

13200

Copper (M6/L)

All results have been corrected for percent solids. #All concentrations have been corrected for Aluminum interference. See reverse side for "STANDARD CLAUSES".

/disk 25

JOHN ASHCROFT
Governor

## Former Hulett Lagoon Site Combined PA/SI Reference 27

Division of Energy Division of Englanders

Division of Geology and Land Survey
Division of Management Services
Division of Parks, Recreation,
and Historic Preservation

## FREDERICK A. BRUNNER Director

# STATE OF MISSOURI DEPARTMENT OF NATURAL RESOURCES

DIVISION OF ENVIRONMENTAL QUALITY
P.O. Box 176
Jefferson City, MO 65102

May 26, 1988

The Honorable Mac Webster
Mayor of Camdenton
112 Court Circle, P.O. Box 1048
Camdenton, MO 65020

Re: IDG - 011 Camdenton, MO Lagoon Closure

Dear Mayor Webster:

This letter is to explain what options are available for the City to pursue in order to completely abandon and close the Huelett or Factory Lagoon. We have reviewed the sludge sample analysis which your engineer sent to us on April 25, 1988 and May 20, 1988. The first step before you assess each option is to determine the percent moisture and the sludge depth at each sample site and to use the information to calculate the total weight of each of the various metals.

There are several options available to the City which are briefly explained below.

#### Option 1

Dispose of the sludge on site, at the lagoon. This option will require the preparation of a solid waste disposal area permit application complete with plans and specifications. The Waste Management Program would then review the application to determine if it could issue the permit. A point of contact for additional information and the time requirements of this-option would be Mr. Tom Gredell at 751-3176.

#### Option 2

Haul sludge to a permitted, sanitary landfill. This would require a Special Waste Disposal Request. The sludge must also have no "free liquid" in order to be properly handled. A copy of the special waste disposal request form is enclosed. Tom Gredell would be your contact person as in option #1.

#### Option 3

Surface application in accordance with the Missouri Sludge Guide, "Agricultural Use of Municipal Wastewater Sludge" (Table 4).

The Honorable Mac Webster May 26, 1988 Page 2

This would require the preparation and approval of a sludge management plan. The plan would limit the rate at which sludge could by applied. The rate would be based upon limiting the weight of metals to be applied to allow the unrestricted use of the land in the future. You should contact Ken Arnold at 751-6624 for additional information.

#### Option 4

Sub-surface application at the maximum one time rate. This would require either injecting the liquid sludge with chisel plows under the soil surface, or spreading the sludge, discing and then plowing the field. The rate of application would be higher than in option #3, but could not exceed the maximum cumulative site loadings per the Sludge Guide. This option would require the site to be City owned and the site would be restricted for use as a sludge disposal site in the future. Ken Arnold would be your contact person as in option #3.

Please note that what ever option is used, the lagoon must not discharge to the creek unless the City receives a new operating permit. The lagoon currently doesn't have a discharge permit. Preferably, any discharge would be to the City's sewer and be tested for compliance with the City's pretreatment ordinances before being introduced to the sewer.

We suggest you work closely with your engineer to quickly resolve the fate of the sludge disposal and lagoon abandonment. Please note the grant cannot be closed and final reimbursement made until this work is complete. If you should have any questions, please do not hesitate to call me at 751-6619.

Sincerely,

WATER POLLUTION CONTROL PROGRAM

David Freise, P.E. Project Engineer

DF/pa

cc: Jefferson City Regional Office
Missouri Engineering Corporation



### Former Hulett Lagoon Site Combined PA/SI Reference 28

Division of Geology and Land Survey
Division of Management Services
Division of Parks, Recreation,
and Historic Preservation

#### JOHN ASHCROFT Governor

G. TRACY MEHAN III

# STATE OF MISSOURI DEPARTMENT OF NATURAL RESOURCES

DIVISION OF ENVIRONMENTAL QUALITY
P.O. Box 176
Jefferson City, MO 65102

November 2, 1989

The Honorable Mac Webster Mayor of Camdenton 112 Court Circle, P.O. Box 1048 Camdenton, MO 65020

Re: IDG-011 Huelett Lagoon

Dear Mayor Webster:

I recently visited the above referenced lagoon site and the temporary sludge storage site at the city airport. During my visit, I noted a berm was not yet in place around the temporary storage to prevent solids run off. This is a condition of the approval issued February 22, 1989. The city administrator, Kent Hixson, stated the berm would be in place as soon as possible.

I would also like to remind you the approval is valid for only one year. Therefore, the sludge spreading must be completed in accordance with the plan and approval letter by February 22, 1990.

Thank you for your consideration in these matters and please thank Kent Hixson for me for the time he spent with me that day.

Sincerely,

WATER POLLUTION CONTROL PROGRAM

David Freise, P.E. Project Engineer

DF:mle

cc: Jefferson City Regional Office City Administrator, Kent Hixson Missouri Engineering Corporation

Former Hulett Lagoon Site Combined PA/SI Reference 29

SPECIFICATIONS

AND

CONTRACT DOCUMENTS

REMOVAL AND STOCKPILING OF

SLUDGE FROM THE HULETT LAGOON

CAMDENTON, MISSOURI



March, 1989

MISSOURI ENGINEERING CORPORATION 211 HWY. 63 SOUTH ROLLA, MISSOURI

#### TABLE OF CONTENTS

Advertisement for Bids

Information for Bidders IB-1 - IB-3

Proposal Form PF-1 - PF-4

Bid Bond BB-1 - BB-2.

Bidders Qualifications & Subcontracting BQ-1

Certificate of Owners's Attorney

Agreement A-1 - A-4

Performance Bond PB-1 - PB-2

Payment Bond PAB-1 - PAB-2

General Conditions GC-1 - GC-21

Supplemental General Conditions SGC-1 - SGC-21

Technical Specifications 1 - 4

Location Map Appendix I

Sludge Disposal Sites Appendix II

Access Road & Storage Facility Appendix III

Hulett Lagoon Location Appendix IV

Airport Location Appendix V

Sludge Analysis Report Appendix VI

## Missouri Engineering Corporation **ENGINEERING CONSULTANTS**

P O BOX 13 ROLLA, MISSOURI 65401 • PHONE 314-364-4003

April 18, 1989

REMOVAL AND STOCKPILING OF SLUDGE FROM THE HULETT LAGOON CAMDENTON, MISSOURI

ADDENDUM NO. 1

This project to be bid May 2, 1989, at 1:30 p.m.

Item No. 1. Bidders are hereby notified of a pre-bid conference at City Hall, Camdenton, Missouri, at 1:00 p.m., April 26, 1989.

MISSOURI ENGINEERING CORPORATION

Parles

Monald d Trelomiel

Received By:

#### INFORMATION FOR BIDDERS

BIDS will be received byCity of Camdenton, Missouri
(herein called the "OWNER"), at City Hall, Camdenton, Missouri
until 1:30 PM, May 2, , 19 89 , and then at said office
publicly opened and read aloud.
Each BID must be submitted in a sealed envelope, addressed to
Clerk, City Hall, at <u>Camdenton</u> , MO 65020
Each sealed envelope containing a BID must be plainly marked on the outside as BID for Removal and Stockpiling of Sludge from the Hulett Lagoonand the
envelope should bear on the outside the BIDDER's name, address and license number if applicable, and the name of the project for which the BID is submitted. If forwarded by mail, the sealed envelope containing the BID must be enclosed in another envelope addressed to the OWNER at
City Hall, Camdenton, Missouri .

All BIDS must be made on the required BID form. All blank spaces for BID prices must be filled in, in ink or type written, and the BID form must be fully completed and executed when submitted. Only one copy of the BID form is required. Tied bids will not be considered by the OWNER.

The OWNER may waive any informalities or minor defects or reject any and all BIDS. Any BID may be withdrawn prior to the above scheduled time for the opening of BIDS or authorized postponement thereof. Any BID received after the time and date specified shall not be considered. No BIDDER may withdraw a BID within 90 days after the actual date of the opening thereof. Should there be reasons why the contract cannot be awarded within the specified period, the time may be extended by mutual agreement between the OWNER and the BIDDER.

BIDDERS must satisfy themselves of the accuracy of the estimated quantities in the BID schedule by examination of the site and a review of the drawings and specifications including ADDENDA. After BIDS have been submitted, the BIDDER shall not assert that there was a misunderstanding concerning the quantities of WORK or of the nature of the WORK to be done.

The OWNER shall provide to BIDDERS prior to BIDDING, all information which is pertinent to, and delineates and describes, the land owned and rights-of-way acquired or to be acquired.

### ADVERTISEMENT FOR BIDS

CITY OF CAMDENTON, MISSOURI (Owner)	
Separate sealed bids for Camdenton Sludge for	
Removal and Stockpiling of Sludge from the Hulett Lagoon	
will be received by Brenda Colter, City Clerk	•
at the office of City Hall, Camdenton, Missouri 65020	•
until 1:30 o'clock (XXM P.M.,S.TX D.S.T.) May 2	
1989, and then at said office publicly opened and read aloud.	.,
The Information for Bidders, Form of Bid, Form of Contract, Plans, Specifications, and Forms of Bid Bond, Performance and Payment Bond, and other contract documents may be examined at the following:	
City Hall, Camdenton, Missouri 65020	-
Missouri Engineering Corporation	
211 Hwy. 63 South, Rolla, MO 65401	-
Copies may be obtained at the office ofMissouri Engineering Corporat	ion
located at 211 Hwy. 63 South, Rolla, MO 65401 upon payment of	_
\$ 10.00 for each set. Any plan holder, upon returning such set	
promptly and in good condition, will be refunded \$ -0-	
The owner reserves the right to waive any informalities or to reject any or all bids.	
Each bidder must deposit with his bid, security in the amount, form and subject to the conditions provided in the Information for Bidders.	
Attention of bidders is particularly called to the requirements as to conditions of employment to be observed and and minimum wage rates to be paid under the contract, Section 3, Segregated Facility, Section 109 and E.O. 11246.	
No bidder may withdraw his bid within 30 days after the actual date of the opening thereof.	

Date

The CONTRACT DOCUMENTS contain the provisions required for the construction of the PROJECT. Information obtained from an officer, agent, or employee of the OWNER or any other person shall not affect the risks or obligations assumed by the CONTRACTOR or relieve the contractor from fulfilling any of the conditions of the contract.

Each BID must be accompanied by a BID bond payable to the OWNER for five percent of the total amount of the BID. As soon as the BID prices have been compared, the OWNER will return the BONDS of all except the three lowest responsible BIDDERS. When the Agreement is executed the bonds of the two remaining unsuccessful BIDDERS will be returned. The BID BOND of the successful BIDDER will be retained until the payment BOND and performance BOND have been executed and approved, after which it will be returned. A certified check may be used in lieu of a BID BOND.

A performance BOND and a payment BOND each in the amount of 100 percent of the CONTRACT PRICE, with a corporate surety approved by the OWNER, will be required for the faithful performance of the contract.

Attorneys-in-fact who sign BID BONDS or payment BONDS and performance BONDS must file with each BOND a certified and effective dated copy of their power of attorney.

The party to whom the contract is awarded will be required to execute the Agreement and obtain the performance BOND and payment BOND within fifteen (15) calendar days from the date when NOTICE OF AWARD is delivered to the BIDDER. The NOTICE OF AWARD shall be accompanied by the necessary Agreement and BOND forms. In case of failure of the BIDDER to execute the Agreement, the OWNER may consider the BIDDER in default, in which case the BID BOND accompanying the proposal shall become the property of the OWNER. Upon default by the first low BIDDER the AWARD may then be made to the next lowest responsible BIDDER, or the WORK may be readvertised for a construction CONTRACT or otherwise, as the OWNER may decide.

The OWNER upon receipt of an acceptable performance BOND, payment BOND, Certificate of Insurance, and AGREEMENT signed by the party to whom the AGREEMENT was awarded, shall within a reasonable period of time sign the AGREEMENT and return to such party an executed duplicate of the AGREEMENT. The OWNER upon signing the AGREEMENT and within a reasonable period of time shall issue the NOTICE TO PROCEED.

The OWNER may make such investigations as deemed necessary to determine the ability of the BIDDER to perform the WORK, and the BIDDER shall furnish to the OWNER all such information and data for this purpose as the OWNER may request. The OWNER reserves the right to reject any-BID

if the evidence submitted by, or investigation of, such BIDDER fails to satisfy the OWNER that such BIDDER is properly qualified to carry out the obligations of the Agreement and to complete the WORK contemplated therein.

100

A conditional or qualified BID will not be accepted.

Award will be made to the lowest responsive, responsible BIDDER, based on the total base bid for the work described in the proposal form.

All applicable laws, ordinances, and the rules and regulations of all authorities having jurisdiction over construction of the PROJECT shall apply to the contract throughout.

Each BIDDER is responsible for inspecting the site and for reading and being thoroughly familiar with the CONTRACT DOCUMENTS. The failure of omission of any BIDDER to do any of the foregoing shall in no way relieve any BIDDER from any obligation in respect to its BID.

Further, the BIDDER agrees to abide by the requirements under Executive Order No. 11246, as amended, including specifically the provisions of the equal opportunity clause set forth in the SUPPLEMENTAL GENERAL CONDITIONS.

The low BIDDER shall supply the names and addresses of major material SUPPLIERS and SUBCONTRACTORS when required to do so by the OWNER.

The A/E	is	Missouri Engineering Corporation	<u> </u>	The A/E's
		ì		
address	is	211 South Highway 63 South, Rolla, Miss	souri	i 65401

The Bidder agrees by the submission of his bid that he will not discriminate against any employee or applicant for employment because of race, creed, color, national origin, or sex in connection with the performance of work under this bid and/or contract.

#### PROPOSAL FORM

TO: City Council Camdenton, Missouri

The UNDERSIGNED BIDDER, having examined the plans, specifications, general and special conditions and other proposed contract documents attached hereto and referred to herein, and any and all addenda thereto; the location, arrangement, and construction of existing railways, streets, roads, structures and facilities which affect or may be affected by the proposed work, the topography and condition of the site of the work, and having acquainted with and fully understanding (a) the extent and character of the work covered by this Proposal; (b) the location, arrangement and specified requirements of and for the proposed new structures and miscellaneous items or work appurtenant thereto; (c) the nature and extent of the excavations to be made and the type, character, and general condition of the materials to be excavated; (d) the necessary handling and rehandling of excavated materials; (e) all existing and local conditions relative to construction difficulties and hazards, labor, transportation, hauling, trucking, and rail delivery facilities; and (f) all other factors and conditions affecting or which may be affected by the specified work.

HEREBY PROPOSES to furnish all required materials, supplies, equipment, tools, and plant; to perform all necessary labor; and to construct, install, erect, and complete all work stipulated in, required by, and in accordance with, the proposed contract documents hereto attached and the plans and other documents referred to therein (as altered, amended, or modified by and all addenda thereto) at the prices stated below.

Bidder hereby agrees to commence work under this contract on or before date to be specified in written 'Notice to Proceed" of the Owner and to fully complete the project within:

60 Consecutive Calendar Days

Removal and Stockpiling of Sludge from the Hulett Lagoon

Bidder further agrees to pay as liquidated damages the sum of \$100.00 for each consecutive calendar day thereafter as hereinafter provided in the General Conditions.

Bidder agrees to perfrom all the work as described in the specifications and as shown on the plans for the following prices.

#### REMOVAL AND STOCKPILING FROM THE HULETT LAGOON

Item No.	Description	Estimated Quantity	Unit Price	Extension	
1.	Lagoon Dewatering by Pumping	50 Hrs.	ş 36.50	\$ 1,825.00	
2	Lime added to Sludge, Complete	100 Tons	ş 14.60	\$ 1,460.00	
3.	Discing of Sludge	40 Hrs.	\$ 43.25	ş 1,730.00	
4.	Sludge Removal from Lagoon and Stockpiling, Complete	1500 Cu Yds	\$ <u>7.73</u>	\$ 11,595.00	
5.	Site Work at Stockpile Site	L.S.	\$	2,920.00	
	,	TOTAL	\$	19,530.00	

Listed above is the revised proposal form including unit prices and then extensions. This proposal form was revised due to excluding unit prices in the original bid; however the total remains the same. I agree to the above unit prices, extensions and total and agree to perform the work described above for these prices.

Ronald A. McCormick, Owner

McCormick Gravel & Excavating

Date'

It is mutually understood and agreed by and between the parties of this contract, in signing the agreement thereof, that time is of the essence in this contract. In the event that the Contractor shall fail in the performance of the work specified and required to be performed within the period of time stipulated therefor in the Contract Agreement binding said parties after due allowance for any extension of time which may be granted under provisions of the preceding paragraph, the Contractor shall pay unto the Owner, as stipulated liquidated damages and not as a penalty the sum stipulated therefor in the Proposal, for each and every calendar day that the Contractor shall be in default.

Liquidated damages will be waived for any period of time covered by a time extension granted by the Owner.

In the case of joint responsibility for any delay in the final completion of the work covered by this contract, where two or more separate contracts are in force at the same time and cover work on the same project and at the same site, the total amount of liquidated damages assessed against all contractors under such contracts, for any one day of delay in the final completion of the work, will not be greater than the approximate total of the damages sustained by the Owner by reason of such delay in completion of the work, and the amount assessed against any Contractor for such one day of delay will be based upon the individual responsibility of such Contractor for the aforesaid delay as determined by and in judgment of the Owner.

The Owner shall have the right to deduct said liquidated damages from any moneys in its hand, otherwise due, or to become due, to said Contractor, or to sue for and recover compensation for damages for non-performance of this contract at the time stipulated herein and provided for.

The undersigned hereby agrees to enter into contract on the attached contract forms and furnish the necessary bond and evidence that insurance of the kind and minimum limits specified is in force within ten days from the date of your acceptance of this proposal, to begin assembly of materials and equipment within ten days from receipt of executed copies of the contract and to complete said work within the indicated number of consecutive calendar days from and after the date of receipt from the Owner of a written work order.

If this proposal is accepted, and should (I) (We) for any reason fail to sign the contract within ten days, as above stipulated, the deposit which has been this day made with the Owner shall at the option of the Owner be retained by the Owner as liquidated damage for the delay and expense caused the owner but otherwise it shall be returned to the undersigned in accordance with the provisions set forth in Information for Bidders.

I	have	, have	not	: <u> </u>	parti	lci	pated	in a	previo	ous con	trac	ct, subject
to	the	provisions	οf	Section	301	of	Execu	itive	Order	11246,	as	amended.
			-				~					-

I have \_\_\_\_, have not \_\_\_\_\_, submitted required compliance reports under such previous contracts.

DATED AT	<del></del>			<del></del>	this	day
of May		, 19 <u>P</u>	<u> </u>			
SIGNATURE:						
If an individual	: Romald A	McCo	em, c	<u>K</u>	_ doing bus	iness as
	McCorn	cta	eave/	+ EX	cavati	19
If a Partnership						<i>)</i>
	Ву				Member of	the Firm
If a Corporation						***************************************
	Ву					
	Title					
ATTEST:	Secre	tary			•	,
(CORPORATE SEAL	) ,	,	,			
Business Addres	s of Bidder_	RR	ے_	Box	193 E	
	•	Ver:	sa: 11	/ es,	Mo	65084
If Bidder is a	corporation,	supply	the fo	llowing :	information	:
State in which	incorporated	<u> </u>	, -	. <u></u>		
Name and Addres	s of its:	-				
President_						
•					-	V
Secretary_	-					,
	• •	5 45 H		,	m e e e	

### BIDDERS QUALIFICATIONS & SUBCONTRACTING

To evaluate the bidders' qualifications for acceptance on this project, the Owner requests the following:

a. Previous Experience (Projects of similar construction detail)

		=			
	Location	Year	Type	Mat'l Type & Size	Approx. Bid
Lake of	the Uzaxk	1989	predgine	mud + grave/ 6" + unde	+6500
1. 1. 1. 1.	4.4.6	1989	Deadsin	1500 yd	*250°C
	he Ozanke		Dredging	mud +grave / 6 + under	*
Lake oft	he ocarks	1989	Ore 19 mg	mud -gKAVE 1 6" + under	2500
Laurie.	Mu	1989	pond	diet Kick	15000
	b. List o	f Equipme	ent avail	able for this job:	
	_		_	B Excavator	
	Coter	pillar	955	H DozeR/Loader	·
2	Dump	Trucks	Cland	cm) John Deen	e traetor
				the sump, 2'pu	
	you gas u	raus wa	go we	ya kuong, - pi	unp-pix
					····
	c. List o	of subcon	tractors	contemplated for this	job:
		(Name)		(Type of	Work)
	Carl	1117/2	مسده	()um 2	truck .
			<del></del>		
-					
ı	-	_			
			-		
This	report is	an integ	ral part	of the proposal.	_
	Date	·	ì	5/2, 19 89.	<del>.</del>
	By lon	ald q	Trul	Franch	
	Title ()	1			# - St - T - T - T - T - T - T - T - T - T -

## CERTIFICATE OF OWNER'S ATTORNEY

I, the undersigned,		_, the duly
,	(Print)	_
authorized and acting legal re	presentative of	<del></del>
	, do hereby certify as follo	ws:
	en e	
I have examined the foregoing	•	ı
	and surety bonds and the	manner of
execution thereof, and I am of agreements have been duly execution their duly authorized have full power and authority the respective parties named to constitute valid and legally the same in accordance with the addition, I have examined the coverages per the requirements General Conditions of the continsurance is in full force and	cuted by the proper parties to representatives; that said representatives; that said represents of the execute said agreements of thereon; and that the foregoing obligations upon the erms, conditions and provision Certificate of Insurance for sof the General Conditions/Stract documents and find that	hereto acting epresentatives n behalf of ng agreements parties executing as thereof. In amounts and supplemental
, ,	Description Project Attorn	ney
6/1/89 Date		-
	Address:	

#### **AGREEMENT**

THIS AGREEMENT, made this 6 <sup>TH</sup> day of June, 1989,
by and between City of Camdenton, Missouri, hereinafter called (name of Owner), (xxxindixidux)
and McCormick Gravel & Excavating doing business as (an individual),
or (axpareners), or (axeorporetion) hereinafter called "CONTRACTOR".
WITNESSETH: That for and in consideration of the payments and agreements
herein after mentioned:
1. The CONTRACTOR will commence and complete the construction of
REMOVAL & STOCKPILING FROM THE HULETT LAGOON .
2. The CONTRACTOR will furnish all of the materials, supplies, tools,
equipment, labor, and other services necessary for the construction and
completion of the PROJECT described herein.
3. The CONTRACTOR will commence the work required by the CONTRACT
DOCUMENTS within 3 calendar days after the date of the NOTICE TO
PROCEED and will complete the same within 60 calendar days unless
the period for completion is extended otherwise by the CONTRACT DOCUMENTS.
4. The CONTRACTOR agrees to perform all of the WORK described in
the CONTRACT DOCUMENTS and comply with the terms therein for the sum of
Nineteen thousand five hundred thirty and 00/100 ollars \$ 19,530.00
5. The term "CONTRACT DOCUMENTS" Means and includes the following:

(A)	Advertisement for BIDS				
(B)	Information for BIDDERS				
(C)	BID				
(D)	BID BOND				
(E)	Agreement				
(F)	General Conditions				
(G)	SUPPLEMENTAL GENERAL CONDITIONS				
(H)	Payment BOND				
(I)	Performance BOND				
(J)	NOTICE OF AWARD				
(K)	NOTICE TO PROCEED				
(L)	CHANGE ORDER				
(M)	DRAWINGS prepared by				
	numbered through, and dated,				
(N)	SPECIFICATIONS prepared or issued by				
	Missouri Engineering Corporation				
	dated, 19				
(0)	ADDENDA:				
	No. 1 , dated <u>April 18</u> , 19 89				
	,				
	, 19				
-					
	, 19				

- 6. The OWNER will pay to the CONTRACTOR in the manner at such times as set forth in the General Conditions such amounts as required by the CONTRACT DOCUMENTS.
- 7. This Agreement shall be binding upon all parties hereto and their respective heirs, executors, administrators, successors, and assigns.

IN WITNESS WHEREOF, the parties hereto have executed or caused to be executed by their duly authorized officials, this Agreement in  $(\underline{\phantom{a}}4)$  copies each of which shall be deemed an original on the date first above written.

OWNER:

CITY	OF CAMDENTON, MISSOURI	
Ву 2014	abelita	
Name	Mac Webster (Please Type)	
Title	Mayor	-

(SEAL)

ATTEST:

Name Brenda Calter
(Please Type)

Title City Clerk

CONTRACTOR:

McCORM	IICK GRAVEL & EXCAVATING
By Mon	rald a. Trulormich
Name	Ronald A. McCormick
	(Please Type)
Address	R. R. 2, Box 193E
	Versailles, MO 65084
Employer	Identification Number:
- •	
42-1	311948
	·
	15 <u></u> .
The same of the same	

(SEAL)

ATTEST:

## TECHNICAL SPECIFICATIONS

General	Page	1
Lagoon Dewatering	Page	1
Sludge Removal & Stockpiling A. Preparation	Page	2
B. Transportation	Page	3
C. Stockpiling	Page	3
Basis of Payment of Sludge Removal	Page	4

#### GENERAL

The Contractor shall provide the services, equipment and all appurtenances for the removal and stockpiling of the existing wastewater sludge located within the Hulett Lagoon. This lagoon has been eliminated as a part of the city's sewer system with construction of new sewer lines. The lagoon's primary contributor was a metal tubing company and hence, the metals content in the sludge accumulated in the lagoon is of a higher than normal concentration. Test results of samples taken of the sludge are given as an appendix to this report. The locations of the lagoon and the stockpiling area are also given in the appendices. The contractor's responsibility will be to stockpile the sludge at the site provided in accordance with the following specifications.

1. LAGOON DEWATERING: The Contractor shall pump the existing water from the lagoon and discharge it into the existing sewer manhole approximately 100 feet away, see Appendix I. The Contractor shall make all provisions as provided to prevent any solids to be discharged into the sewer system. The lagoon presently has 6" to 12" of water standing in the bottom with the sludge. The contractor shall dewater the sludge to at least a condition where the sludge will cake. The expected solids content is 12 to 15 percent. The contractor will be allowed to construct a sump pit in one of the lower parts of the lagoon. This pit must be of seal tight construction such as metal or fiberglass. This sump can be placed in an area where the sludge has been removed and down to an elevation of approximately 18" depth. The upper portion of the sump shall be provided with screens having mesh wire to prevent

solids easy access to the sump. When the sump has been placed the outer edges shall be backfilled and sealed so as to prevent leakage around the sump box. This will be done by compacting the soil backfill into the excavated areas. The contractor shall be paid for this work at an hourly rate while the pump is in operation. The pump or pumps used shall not exceed a total of 200 GPM into the sewer system. The contractor has sole responsibility for insuring that the dewatering is directly pumped into the sewer line.

#### SLUDGE REMOVAL & STOCKPILING:

#### A. PREPARATION

The Contractor shall remove as much of the concentrated sludge from the cell as possible without excavating into the soils of the floor. This may be accomplished with a high lift or other piece of equipment as selected by the contractor. If the sludge is not suitable for removal using these methods, after dewatering and normal evaporation, the contractor may add lime and/or disc the sludge to assist in the drying. The proposal form provides for unit costs for these items but will not be paid for unless prior approval is obtained from the city.

After the contractor has removed as much of the sludge as possible from the cell bottom, then upon approval of the Engineers, a pit may be excavated to allow for collection of the remaining sludge. This will only be allowed in an area where tests can be performed to insure proper soils conditions will prevent seepage.

#### B. TRANSPORTATION

The Contractor shall load the sludge into a truck capable of a liquid tight performance. A rubber seal, gasket, or sealant material between the tailgate and the bed and a bed cover shall be required to pervent leakage of sludge materials from the truck while in transit to the stockpile location. All trucks shall be inspected prior to leaving the site to insure that seepage is not occurring. The contractor is totally responsible for cleaning up any seepage or spills that occur in any area between the two sites.

The Contractor shall provide a water tank or other means, at the stockpile site, to allow the trucks to be cleaned on the exterior of the bed, should accumulation cause for spillage on the return trips.

#### C. STOCKPILING

The stockpiling site is located approximately 150 linear feet from the county road. The Contractor shall provide his own access to the stockpile area at the location designated. The Contractor shall provide clearing, install culverts, crushed stone, etc. as necessary for his operations.

Before stockpiling begins, the contractor shall plow 2 furrows around the site, except for the area on the higher side, needed for truck access to the area. These furrows shall be sufficient to prevent drainage from the site. The area to be encompassed is approximately 160 feet in diameter.

The sludge shall be stockpiled to a height of no more than 2 feet.

The Contractor shall level the sludge after is is dumped from the trucks as necessary so as to normally maintain this height of less than 2 feet. This could be accomplished once daily.

This access road as provided by the contractor shall remain in place after the contractor's work has been completed.

#### BASIS OF PAYMENT OF SLUDGE REMOVAL

The sludge was checked for the thickness of the layer at varying points in the lagoon. Two piles of up to 18" thickness are located at each of the inlet pipes. The remainder of the cell is covered with sludge ranging basically in thickness from 6" to 12". The amount of sludge to be removed has been shown on the proposal form at 1500 cubic yards. Actual quantities are believed to be less. Final payment will be based on the actual amount of sludge removed and stockpiled having at least a 12% solids content. The size and number of trucks shall be recorded showing the total trips of each. This shall be used to determine the actual quantity removed. If discrepancies are encountered in the size and number of loads, then the stockpile area shall be guided as a cross check. This will all be done with a member of the construction crew present.

#### SECTION 1 CALCULATIONS

- I. Determination of Acreage for Sludge Disposal
  - A. Limitations
    - 1. Maximum cumulative copper limit of 500 bls./acre
    - 2. Camdenton Airport
      - a. Field No. 1 25.0 acres
      - b. Field No. 2 17.4 acres
  - B. Conversion Factors
    - 1. 1 MG/L = 1 ppm
    - 2. Weight of water = 62.4 lbs/cu ft
    - 3. Weight of lagoon sludge = 1.2 x weight of water

$$=$$
 (1.2) (62.4)  $=$  74.88 lbs/cu ft

- C. Information from Test Reports and References
  - 1. Average metal analysis for ten copper samples = 24,464 MG/L
- D. Calculation of Acreage Using DNR Guidelines
  - 1. Total sludge limit of copper in dry tons/acre

a,	, Metal Cu	ppm 24,464	ж	0.002 =	lbs./dry ton 48.928
ь.	(1)	(2	2)		(3)
	Cumulative Metal Limits	Slud Meta	_		Total Sludge Limit dry tons/acre
	lbs./acre 500		dry :	ton	col. 1 → col. 2 10.219
	250	48.9	128		5.1725

2. Weight of Dry Sludge

3. Field No. 1 (25.0 acres) accepts a Cumulative Metal Limit of 500 lbs/acre. Apply 164 tons to Field No. 1. The 164 tons will be dispensed on 16.1 acres.

Field No. 2 (17.4 acres) accepts a Cumulative Metal Limit of 250 lbs/acre. Apply 89 tons to Field No. 2. The 89 tons will be dispensed on 17.4 acres.

#### II. Acidity Warrents Liming of the Disposal Site

#### A. Limitations

- 1. Disposal site should have a pH value of 6.0
- B. Information from Test Reports
  - 1. Field No. 1 & 2 at the Camdenton Airport has a Enm requirement of 4330 and 2195 respectively.
  - 2. To determine the amount of limestone needed in tons/acre divide the ENM requirement by the guarantee of the limestone dealer.
- C. Procedure for obtaining pH of 6.0
  - 1. Apply lime to disposal site before applying the sludge
  - 2. Disc lime into field before applying the sludge
  - 3. Have soil samples taken to verify an acquired pH of 6.0.

#### ,III. Dewatering, Storage and Disposal of Sludge

#### A. Limitations

- 1. The sludge will be transported by a dump truck with the means to protect leakage or spillage of the sludge.
- B. Information from Test Reports
  - 1. On May 16, 1988 the sludge contained an average of 11.5% soild.

#### C. Procedure

- 1. Dewatering of sludge should occur by removal of liquids and Natural evaporation. Discing and Liming sludge maybe used to assist coagulation.
- 2. Transport sludge by dump truck to a designated storage area at the Camdenton Airport.
- 3. Precautions should be taken to contain the sludge while stockpiled. A berm will be necessary around the temporary storage site at the airport to contain any run-off.
- '4. A Dry Sludge Applicator should be used to apply th sludge onto Field No. 1 & 2.

#### Note:

- 1. The sludge must be thoroughly mixed before being land applied due to the variability of the metals concentration throughout the lagoon as shown by the sample report dated April 19, 1988.
- 2. Percent solids concentrations must be run daily on the sludge when it is being applied to ensure the loading rate can be calculated as the application progresses.
- 3. Upon completion of the work, a summary must be submitted to the Department of Natural Resources.

#### SECTION 2 REFERENCES

 Agricultural Use of Municipal Wastewater Sludge - A Planning Guide Missouri Department of Natural Resources Division of Environmental Quality January 1985

4 5

Process Design Manual for Dewatering Municipal Wastewater Sludges
U. S. Environmental Protection Agency
Office of REsearch and Development Municipal Environmental Research
Laboratory
October 1982 EPA - 625/1-82-014

#### Metal Limitations

See Table 4 for maximum recommended heavy metal loadings. The metals listed in Table 4 are those which are most common in domestic sludges. For other industrial contributors See Table 4-A and contact the Department for any other parameters. Galculate which is the most limiting metal and the number of years to reach the limit at the proposed application rate. A sample worksheet is provided (Appendix B-1).

ppm metal x .002 = lbs. metal per dry ton

TABLE 4

Maximum Cumulative Amounts of Beavy Matals

Becommended for Privately Owned Paraland

Metol .		kg/ha (pounds/acre in parenthesis) Soil Cation Exchange Capacity (meg/100 g soil)						
•	CEC 0 - 5	CEC 5 - 15	CEC 15 +					
Çadmium	5 (4.5)	10 (9)	20 (18)					
Chromium	\$60 (500)	1120 (1000)	2250 (2000)					
Copper	140 (125)	280 (250)	560 (500)					
Lead	560 (500)	1120 (1000)	2250 (2000)					
Nickel	140 (125)	250 (250)	560 (500)					
Zinc	280 (250)	560 (500)	1120 (1000)					

Page 17 of DNR: Argricultural Use of Municipal Wastewater Sludge

Pacifity		Addrs ==				Date	
STEP 1 - LAB DATA (nee page 27	1		516P 4 -	METALS AVAILUAT	IOR		
A) SERRICE ANALYSIS (Expresse	ed on dry dollius	basish	A) SLI	DEE APPLICATE	ON RATE	tonsfacrefyes	r from Step 2 or Step
	ppa	lbs/dry ton	or	lover melected	frate.		
Total Rjeldahl Mittogen	x .1	102 Q					
Coomicm (Cd)	<u></u>	_0_	B) HET	TALS ADDITIONS	(See Page 17	£ 19)	
Chronius (Cr)	17,053	26.106		(1)	(2)	(3)	<b>{4}</b> *
Copper (Cu)	24 967	4 <u>8.97</u> 8		CURULATIVE	LBS METAL	TOTAL SLUDGE	NITALS APPLIED
Bickel (N1)	1/2.58	0.225		HETAL LIMITS	PER DRY TON	LIHIT	PER YEAR
Zine (Zn)	4,161	8.322		LBS/ACRE	SLODCE	DRY TOHS/ACRE	lbs/acri
Other		128 340	HETAL	(7sble 4)	(Step 1)	(Col 1 : Col 2)	(Col 2 & Step 4A)
Other Solids	ppm + 10,000	- 1		. 0			
			Cd	18			
B) SOIL TEST AHALYSIS (See P	age 13)		C7	2000	26.106	76,611	<del></del>
pH limestone no	edeð	ENN	Cu	500	48.924	10-219	****
Cation Exchange Copactiy	(LEC)	TIC	Ma	300	0.225	2222. 222	-
			In	1000	8.322	120.163	****
TEP 2 - CROP AND SITE INFORMATIO	8 (See Page 23 4	. 26)	Other		4	grand and the same of the same	
Previous Crop	·			* Column 4 sh	ould not be m	ore than 10-15 % of	Coloum 1.
Puture Crop	·	and the same time		<b>a</b> .			
Slope Builer A				U Mos	t Liaiting He	tal (lovest in Colu	.mm 3)
Geologic Restrictiona		and the state of t		10.219 Dry	Tons/Acre To	tal Sludge Limit (l	ovest Column 3)
Pathogen Reduction	· · · · · · · · · · · · · · · · · · ·						
Cattle Crating		uftrællingssallraginalitäters i 1884. Stran	c) s11	TE LIFE FOR NE	TALS LOADING		
Other		Algorith and the American American American		D	ry Tona/Acre	Total Sludge Limit	(Step 48)
Location1/4, Sec	,Tvp,kge	, County		- <u>p</u>	ry Tons/Acre	Sludge Applied Frev	iously
				b	ry Tons/Acre	Sludge Remaining to	Reach Metal Limit
TP 3 ~ APPLECATION RAYE				+D:	ry Tone/Acre/	Year Sludge Applice	tion (Step 41)
150 lbs/scre Total H r	lbs Total H	per dry ton of		R	. Years To R	each Metala Limits	
# a ludge (Step 1) =	des constaceat	ant of aludan					

Page 43 DNR: Agricultural Use of Municipal Wastewater Sludge.



# ENVIRODYNE ENGINEERS

12161 Luckland Road. St Louis, Minet P and the 374.4:4.49-7.

REPORT OF ANALYSIS

CLIENT: Valda Nationev

missouri Engineering Post Office Box 13 Rolla, NO 65401

REPORT DATE:

April 19, 1986

SAMPLE ANALYZED: Ten sludge samples for

aetais analysis.

DATE RECEIVED:

March 7,1986

PROJ. N: 3222-00353


F.O. 8:


Parameter	1 1	1 2	<b>1</b> J	1 (	4.5	4 6	1 7
Alexand (MED)	F5744	17105	22//3	65*14	70600	47100	<b>#1</b> / ^ ^
Chrosius (M6/L)	55700 12400	67400 24300	97000 28900	85300 19000	79200 24300	47100 12300	52000 15600
Cadejua (Mô/L)	₹ 26.0	< 25.4	< 35.7	( 13.3	: 26.0	< 23.2	< 27.8
Copper (#6/L)	28800	24396	15160	52400	22600	34900	18700
Leso (MG/L):	(101	( 97.1	(139	150	< 101	146	153
Nickel (Ro/L)	9:.0	110	179	215	110	85.9	89.0
line (#6/L)	4910	4170	4530	5700	3810	4510	3710


Parameter	1 8	<b>\$</b> 9	4 10
********	******	:::::::::	
Aluminum (MS/L)	55200	55160	\$1200
Chrosius (Mô/L)	11400	6430	15900
Cadaina MS/Li	( 9.50	: 22.8	( 18.2
Copper (Ma/L)	4340	15290	30106
Lead (Mô/L)	113	155	125
hickel (M6/L)	46.5	77.4	111
Zine (He/L)	2920	3470	3620

All results have been corrected for percent solids. thi! concentrations have been corrected for Elurique interference. See reverse side for "STANDARD CLAUSES".


/61 St 25







# STATE OF MISSOURI DEPARTMENT OF NATURAL RESOURCES WALLACE B HOWE STATE GEOLOGIST





9 L 1 W 2 C D 20 4 4 4 W

REPORT OF ANALISIS

CLIENT: Valda Mahoney

Missouri Engineering Post Difice Box 13 Rolla, MO 65401

REPORT DATE:

April 19, 1988

SAMPLE ANALYIED: Ten sludge samples for

metals analysis.

DATE RECEIVED:

March 7, 1988

PROJ. 1: 3222-00353

P.O. 1:

					-		
Parameter	* 1	1 2	* 3	1 4	<b>*</b> 5	4 6	\$ 7
	*******						
Aluminum (Mô/L)	55700	67400	97000	89300	79200	47100	52000
Chrosius (MS/L)	12400	24300	28900	19000	24300	12390	15600
Cadeium (M6/L)	₹ 26.0	₹ 25.4	€ 35.7	< 13.3	€ 25.0	< 23.2	< 27.8
Copper (M5/L)	18800	24396	15100	52400	22600	34900	18700
Lead (MS/L) :	(101	₹ 97.1	(139	150	< 101	:45	153
Nickel (Mo/L)	91.0	119	179	215	110	85.9	67.0
linc (M6/L)	4910	4170	4530	5760	3810	4910	3710

Parameter	<b>6</b> 6	• 9	1 16
*********	*******	******	
Alueinum (MS/L)	53200	55100	51200
Chrosius (Mô/L)	11400	6430	15900
Cadeiue (MS/L)	( 9.90	< 22.8	€ 18.2
Copper (Mo/L)	4540	13200	30100
Lead (M6/L)	113	155	125
Nickel (M6/L)	48.5	77.4	111
Zinc (M6/L)	2920	3470	3620

Ail results have been corrected for percent solids.

#All concentrations have been corrected for Aluminum interference.

See reverse side for "STANDARD CLAUSES".

APPENDIX VI Page 1

/disk 25

AFPROVED:

## Missouri Engineering Corporation ENGINEERING CONSULTANTS

P O BOX 13 ROLLA, MISSOURI 65401 • PHONE. 314-364-4003 Former Hulett Lagoon Site Combined PA/SI Reference 30

July 21, 1989

### SLUDGE REMOVAL PROJECT HULETT LAGOON - CAMDENTON, MO

Mr. Ron Macormic approached me concerning the spreading of the sludge on the 22 acre area at the airport. This sludge is currently being stockpiled.

His proposal is basically as outlined below.

- 1. Spreading of sludge complete \$2.25 per cu. yd. We have estimated this at 1500 cu yc. or \$3375.00.
- Clearing, bush-hogging, or cutting to be able to utilize the area. May be up to 4 acres.

  His proposal is \$400 per acre or \$1600.00
- Discing of the field after sludge application to create a mixture and seed bed.
  A lum sum cost of \$560 00.
- 4. For seeding of the 22 acre tract with 15 lbs per acre of fescue and 1 bushel per acre of cover crop at a cost of \$45.00 per acre or a total of \$990.00.

Based upon our estimated quantities, this would create a change order increase of a total of \$6525.00. If you wish to pursue this method of completing the disposal, please let me know.

MISSOURI ENGINEERING CORP.

Charles Ray

Contrac	ctor's			
Change	Order	No.	1	

City of Camdenton, Misso	ura of	Camden	County
(Owner)	<del></del>	State of Misson	County,

To McCormick Gravel & Excavating for REMOVAL & STOCKPILING HULETT LAGOON

Section of Project

You are hereby directed to make the following changes from the contract

1. Description, location and reason for change of each item and effect on completion date. (Attach additional sheets if required)

Spreading stockpiled sludge on the 22 acre area at the airport. See Attachment A. Time extension due to poor weather conditions

2. Cost of work affected by this change order.

Item No.	Item Description	Units Provided for	Units To Be Built	Units Add or Deduct	Contract or Unit Price	Amount Added	Amount Deducted
4	Spreading Sludge	1	1500	+ 1500	2 25,	3,375.00	
,	hogging	· 0	4	+ 4	400 00	1,600 00	,
	Discing	0	1	+ 1	LS	560 00	
	Seeding	0	22	+ 22	45 00	990.00	
	30 day time exten	asion C	ompletion (	date revis	ed to Septe	mber 9, 1989	•
		,					
	10 g 1		,				
	r ,			Totals		6,525.00	

-	_				
l.	Contract	Amount	519.	530	OO -

2. Add or Deduct this Change Order
(Additions - Deductions) + \$6,525 00

3. Add or Deduct Previous

Change Orders

4. Total Add or Deduct to Date + \$6,525 00

5. Adjusted Contract Amount \$26,055 00

Muthatian Mala & 8/14/89 Nor Informit 8/15/89

Engineer Date Contractor Date

Owner Date

To Mo	Owner)  Cormick Gravel			of	Camden State of	Missouri	County,
You are		& Excavati		,			
You are		& Excavati		المنوع الم			
1. Des	homoby dimosto		.ng			KPILING HUL	ETT LAGOO
1. Des		d to make	the follow	una chanca	Section of	f Project	
com	cription, locat	ion and rea	ason for c	hange of e	ach item ar	ad effect or	
	pletion date.	(Attach add	ditional s	heets if r	equired)		
Time	extension due	to incleme	nt weather	r.			
		F-11 .3	•	•			
	t of work affec	•	_				
Item No.	Item Description	Units Provided	Units To Be	Units Add or	Contract or Unit	Amount	Amount
		for	Built	Deduct	Price	Added ———————	Deduct
T				1		j	
				Totals			
				Totals	1	<u></u>	
Add (Add B. Add Ch	ract Amount or Deduct this iditions - Deduct or Deduct Previange Orders il Add or Deduct	tons)		00			

Macidality 9/25/89
Owner Date

Change	e Order No. 3	<u>.</u>		٠,	r	1 <sup>2</sup> 1.	4
Cit	y of Camdenton,	Missouri	ı	of Ca	mden	₹ <sub>₹</sub> 1	,
	(Owner)		-		State of	Missouri	Count(,
To M	cCormick Gravel	& Excavati	ng	for Rem		kpiling Hul	ett Lagoon
You ar	re hereby directe	d to make	the follo	wing change	s from the	f Project contract	
1. De	escription, locat empletion date.	ion and re	ason for	change of e	ach'item a	nd effect or	7.
	,			1	-	, , , , , , , , , , , , , , , , , , ,	
2. Co Item No.	ost of work affec Item Description	Units, Provided for	Units To Be Built	Units Add or Deduct	Contract or Unit Price	Amount Adaed	Amount Deducted
,	Removal of excessoils to complete lagoon abandonme	e e	1	+1	LS	7,000 00	
!	Adjustment for spreading of materials at airport for clea	ring		ı			
	brush, spreading sludge and soils discing, and seeding		1	+1	LS	1,363 50	
		<u> </u>	<u></u>	Tarala			
		10 520	00	Totals	<u> </u>	<u> </u>	
Ad	ntract Amount d or Deduct this Additions - Deduc	_		50			
B. Add or Deduct Previous  Change Orders + \$6,525			00				
4. Total Add or Deduct to Date + \$14,888				8 50	,		
6. Adjusted Contract Amount \$34,418				50		•	
	·					1	

Contractor

Date

Owner Date

Attached herewith you will find a letter dated November 01 1989 written to Attorney David Welch from Charlie Ray with Missouri Engineering Corporation, along with the Information for Bidders, Proposal Form, additional information for the contractor, and Change Order Nos 3 and 4 concerning the sludge removal at the Hulett Lagoon.

I personally inspected the sludge site at the airport with Kent and Charlie on Wednesday, October 25, 1989. Upon our inspection, it was found that there is soil that was removed from the lagoon, but there are traces of sludge mixed in with the soil.

I will be the first to admit that I am by far no expert on sludge, but is my feeling that if sludge was present at the lagoon, that it should be removed. This being not only to satisfy my concerns, but maybe more importantly, to satisfy DNR. I believe you will agree that we do not want any trouble with DNR over this lagoon sludge removal.

I realize the Mayor or Council was not advised of the additional loads being removed from the lagoon at the time, but let's just suppose we had been told beforehand that additional loads needed to be removed. . . then, would we have said no? Would we have been expert enough to know that no more sludge needed to be removed from the lagoon? Please just take a minute and think about it.

As Charlie states in his letter, weather conditions were not ideal at the time sludge was being pumped from the lagoon, and there were delays, plus each time the rains came, this caused the sludge to spread back over the area of the lagoon, which I feel would need to be removed. Apparently, the contractor felt it necessary to remove the additional soil, as it was contaminated with sludge. Although, after the sludge was removed and taken to the stockpile sight and dried out, the majority removed was soil, BUT there was a percentange of sludge in the soil that was tested.

Charles also states that more tests can be performed on the soil at the stockpile sit, but you will note that the eight tests that were run cost \$1000.00. Do we want to keep testing the soil and spending thousands of dollars for this?

You will note in the information attached to Charlie's letter, on page GC-20 under No. 30 ARBITRATION, that disputes will be settled by arbitration. Although, some of you may not be too familiar with arbitration, I deal with it everyday in my work, and it has been my experience that this is not the easiest way to prove a point. You may think your case is airtight, but the arbitration committee can easily blow your case right out of the water. I personally believe that if the arbitration committee saw that there was a percentage of sludge in the excess soil removed from the lagon, that they would rule in favor of the contractor Be advised this is my personal opinion, but also, I have dealt with arbitration committees for several years. Our attorney may disagree with me totally, but I do feel very strongly on this point.

I feel we can sit in the council chambers and argue and hash this matter out for several hours, and never settle the dispute. As you know, each of us are separate individuals with our own way of thinking. I am not trying to persuade any one of you in any way, but please take a little time and think carefully about this matter and just maybe, you may reconsider allowing this matter to be resolved by paying the contractor on these change orders.

I do have information from a very reliable and trustworthy individual that McCormick has alread been told that an additional \$3000 00+ that he has spent on this sludge removal project will not be taken into consideration for payment, and they have apparently accepted this fact

This matter can be discussed to some extent Tuesday night, but let's not drag it out for any length of time. Please be advised that I do intend to make a motion for this additional money to be paid to McCormick and it will be up to the rest of the council to either agree or disagree. Remember, in the meantime, the sludge is just sitting idle at the airport waiting to be spread.

Thank you for taking the time to read this and reconsidering all the facts involved in this matter

Again, I respect each and everyone of you in the decisions we make as a council, and I do feel that we are a strong and aggressive council who face may tough decisions each time we sit in the council chambers

Sincerely,

## Missouri Engineering Corporation ENGINEERING CONSULTANTS

P O BOX 13 ROLLA, MISSOURI 66401 4 PHONE. 314-364-4003

November 1, 1989

Dave Welch Attorney at Law 190 Court Circle Camdenton, MO 65020

Dear Dave:

Since our meeting Tuesday morning, I have tried to summarize the overall situation of payment on the Hulett Lagoon Sludge Removal and Stockpiling project. I have taken a set of the contract documents and marked what I felt was pertinent information regarding this matter. Mr. McCormick feels that he is due additional funds for sludge removal. I am in agreement with him that he has removed additional material but disagree that it was actually sludge.

The specifications were very clear that the quantities shown were only estimates and that final payment would be made on the quantities actually removed and measured. On GC-8, 13.1, it states that final measurements shall not be considered changes in the work. It also states in the specifications that differing site conditions or weather conditions can govern the work to be performed and paid for. This project is very unique and the conditions encountered during the removal period were not ideal. As you are aware, the Department of Natural Resources had complete control on the approval of this material being removed, but it was at a total cost paid by the City of Camdenton.

The scope of the project included complete removal of the sludge from the lagoon site and stockpiling of this material at the south end of the airport property. I have had conversations with Mr. McCormick over concerns of the project and will try to highlight those in the following statements.

- 1. I have been told that even though the contractor was prepared to begin removal of the sludge during the last weeks of June, that he was told by the city to not start until after the July 4th holiday period. We lost two weeks of very favorable working days.
- 2. The removal process began on July 11, 1989. They had hauled approximately 650 cubic yards through July 12 at 1:30 p.m. At that time my inspector told me that they were way less than one-half done with the area. I asked how much dirt was being removed with the sludge. Was it a clean separation? The answer was that the excavation was being made to a level that showed clay material. I aksed my inspector to have Mr. McCormick to contact me.

- 3. Mr. McCormick called me to discuss the problems. He assured me that there was very little dirt being removed and absolutely no more than was necessary. I told him at that time, that if there was going to be more sludge, I had to take the increase to the council. His statement was that he felt that the total yardage would not exceed the 1500 cubic yards in the proposal by very much, maybe a hundred yards.
- 4. The sludge was left to dry after July 12. Rainfall filled the bottom of the lagoon during the following weeks and created additional pumping. The contractor attempted removal again on August 18 and 19. Rain again stopped the project on August 19.
- 5. After pumping on the lagoon again and drying the sludge, the contractor again started hauling on September 7 and 8. When work had stopped on August 19, I was advised by my inspector that they were nearly done and if it had not rained, they would have probably finished that day. They were at approximately 1485 cubic yards. After the rains and the contractor continued, he hauled approximately another 910 cubic yards.

In my opinion and as shown at the lagoon site, much of the soils were contaminated with copper each time the lagoon was refilled with rainwater. The reason this, showed was because the copper settled out and oxidized causing the soils to appear as the same color of the sludge. Each time the contractor reworked the areas, he was forced to remove additional materials that must have appeared to be sludge when it was wet. After it dried at the stockpile site, it was obvious to me that most of it was soils. The test results that we had performed reflect that this is actually the case.

In eight samples taken from the stockpiled materials, an analysis was made, to determine the sludge quantity. These are as follows:

- 1. 3.08% bludge
- 2. 0.37% sludge
- 3. 1.05% sludge
- 4. 1.53% sludge
- 5. 8.10% sludge
- 6. 33.35% sludge
- 7. 1.68% sludge
- 8. 2.03% sludge

Also the metals test show a considerable drop from the sludge samples analyzed before the project began. Concentrations of copper dropped from a high of 50,000 parts per million to a high of 5500 parts per million.

#### Page 3

It is impossible to test every particle of the stockpiled materials to determine if this is totally representative, but I believe that is as valid comparison. There are approximately 50 loads that would have to be tested to get an actual sludge analysis. These eight tests cost \$1000.

I know that the council feels as if they were left out of this decision, but I do not think that they could have ever reached any other answer other than to continue to remove all necessary materials. This has always been the goal in order to satisfy DNR requirements.

it is my opinion, that the contractor did the work required in order to achieve the completion of the total sludge removal and should be compensated for the additional material removal in the amount of \$7,826.50. In addition to this, if we continue with the project and spread the material at the airport, there would be an additional cost of \$1,800 to spread the additional materials.

Hopefully this information will be of benefit to you. I would certainly like to see this issue resolved and the project completed.

Sincercly,

MISSOURI ENGINEERING CORP.

Charles Kery

Charles Ray

CR/vm

Mr. Hipson & Council Members. This letter is in regard to the cost overrun involved in the Hulett Sayon Project. I was in constant contact with Musour Engineering at all stages of the for. There was an inspector on the job at all times. Missoure Engeneering was well informed of all additional work necessary to complete the job, including additional pumping, extra clime + more sludge to be removed than Messoure Engineerings cestimate. I was assured it was not a problem because I was to be paid by the yard for the semoral. I also want to add that I wantold that if there was less than , 500 yards of slidge, I would be gaid less. of there was more, I would be gaid more. I accepted both possibilities as I assumed the crancil did as you all know, the weather posed a problem, with an unusual frequency of rainfall. This was no one's failt but it did not allow the sleedge to shrink down as it dried the way it should have This kept the bottom of the lagoor soft, making it impossible to prevent getting a small amount of

mud along with the sludge. at no time was more removed than was absolutely recessary in order to get all the sludge out. at the bed opening for this jot, I said in the presence of. Mrs. Ray, the mayor & the just esty administrator that I knew there was a lot men than 1500 yards of sludge in there. The yardage was discussed with Missour Engineering numerous times and I was always assured it was no problem my bid was quite fair. I did not Excate" on overrun for my cherefit. It would have been to my benefit if there had been only 1500 yards. The pices I submitted for spreading the sludge , a believe you will also find ivery reasonable. But, again, all prices are unit prices. I will attend the November ? meeting + hope to help clear up any questions as best Dan. Sincerely;

Sincerely; Ron McCornick

## City of Camden and

112 Court Circle P O Box 1048 Camdenton MO 65020 314-346-3600

Ronnie Testerman Department of Natural Resources P O Box 176 Jefferson City, Mo 65102 April 9, 1990

RE Hulett Lagoon Sludge Disposal Work Completion Summary

Dear Ronnie,

As per the \_proved sludge disposal plan for this project, I am submitting to DNR a work completion summary. The following is a tehronological recounting of the events surrounding the project.

January 1989 The fields at the airport were limed in order to improve the pH levels to 6

June, July, August 1989 The contractor mixed the sludge with lime in the lagoon and transported it to the storage site at the airport Rain delays and traffic considerations added to the length of time needed for this work

December, 1989 After allowing it to dry, the contractor began spreading the material via dry sludge applicator on the designated fields at the airport, mixing it with additional soil and discing the sludge into the ground. Soils tests were taken to insure the loading rate did not exceed set limits. Rain and show delayed completion of the spreading.

March, 1990 Mixing, spreading and discing were completed. Soils test were taken and demonstrated that the loading was below the specified levels. The fields have been seeded with a mix of Timothy and Fescue grasses in order to provide ground cover and prevent eros.on

April, 1990. The fields that are below a pH level of 6 will be limed to bring them up as needed.

I hope that this summary statement fulfills the requirements of the approved sludge disposal specifications. Should you have any questions or require further information, please feel free to contact me

Your cooperation and assistance in helping the city is very much appreciated

Sincerely,

Kernt L Hixson

City of Camden Refere

112 Court Circle P O Box 1048 Camdenton MO 65020 314-346-3600

Mr Paul Kieler Jacobs Engineering Group 10901 W 84th Terrace Suite 210 Lenexa, Kansas 66214 March 23, 1992

RE Hulett Lagoon Clousre Process

Dear Mr Kieler,

Enclosed are some documents relevant to the closing of Hulett Lagoon This is the sewer lagoon that Modine, formerly Sunstrand, discharged into The lagoon was built in 1962-63 and was taken out of service in 1986-87 after Sunstrand constructed the pre-treatment facility

The actual lagoon closure wasn't completed until late 1989 I had only recently been hired by the City and was not involved in the development of the closure plan

I do know that all the sludge was taken to the municipal airport and land applied then tilled into the soil according to the DNR guidelines. The berms of Hulett lagoon were turned in and mixed with on a 1 to 1 ratio

The City is in the process of leveling off the site and opening it up for a neighborhood park

If you have any questions or require further information, please feel free to contact me

Sincerely.

City Administrator

PRELIMINARY ASSESSMENT SUNDSTRAND CAMDEN COUNTY, MISSOURI

January 31, 1992

Missouri Department of Natural Resources Hazardous Waste Program

Prepared By:

(1)

John Madras, Fnvironmental Specialist

John Madras

Reviewed By:

Jım Belcher,

Chief

Planning and Pre-Remedial Unit Approved By:

Edwin D Knight,

Chief

Superfund Section

Date: January 31, 1992

Prepared by: John Madras

Missouri Department of Natural Resources

Site: Sundstrand

City of Camdenton, Camden County, Missouri

EPA ID No.: MOD

#### 1. INTRODUCTION

Under the authority of the Comprehensive Environmental Response, Compensation and Liability Act (CERCLA) and the Superfund Amendments and Reauthorization Act of 1986 (SARA), the Missouri Department of Natural Resources, through a cooperative agreement with the U.S. Environmental Protection Agency, conducted a Preliminary Assessment (PA) at the Sundstrand site. The purpose of this investigation was to collect information concerning conditions at the site sufficient to assess the threat posed to human health and the environment, and to determine the need for addition investigation under CERCLA/SARA or other action. The scope of this investigation included review of available file information, a comprehensive source survey, a comprehensive target survey, and an on-site reconnaissance.

#### 2. SITE DESCRIPTION, OPERATIONAL HISTORY, AND WASTE CHARACTERISTICS

#### 2.1 Location

The Sundstrand site is located in the City of Camdenton, Missouri, at the center of Canden County, Missouri (Figure 1). The geographic coordinates are 38° 00′ 32.5′′N latitude and 92° 45′ 26′′W longitude (Reference 1). The site is located about one-half mule west of the intersections of U.S. Route 54 and Missouri Route 5/7. The site can be accessed by turning west onto Sunset Drive from Missouri Route 5/7.

Camden County is characterized by a temperate climate. Summers are warm and humid with daily temperatures reaching  $90^{\circ}F$  or higher. The winter months are generally cold with normal daily temperatures of  $22^{\circ}$  to  $42^{\circ}F$ . Net annual precipitation for the area is 42 inches (Reference 2, pages 1, 13, 43).

#### 2.2 Site Description

The suspected area of contamination includes soil beneath the manufacturing facility, and soil and fill material comprising loading areas and parking lot adjacent to the facility on the west (Reference 3,4). Trichloroethylene (TCE) and 1,1,1-trichloroethane (TCA) have been detected in the soil below the facility and in borings in the adjacent areas outside of the facility (Reference 5). Groundwater may be affected.

Concentrations of TCE and TCA detected at the facility are shown on Figure 2 (from Reference 5)

Sundstrand - PA Report January 31, 1992

The facility is located on a gently, sloping terrain which drops steeply toward a permanently flowing tributary of Lake of the Ozarks.

The Sundstrand site appears to be the sole source of potential TCE or TCA contamination in the vicinity of the site itself. Other potential sources are present in the Camdenton area (Reference 6; Electrovert USA site).

Sundstrand was an interim status hazardous waste treatment, storage, and disposal facility (EPA ID# MOD06249351). The Department requested a Part B application to be submitted. The facility was sold to Modine Heat Transfer, Inc , a wholly owned subsidiary of Modine Manufacturing Company. The new owner stated their intention to complete the closure begun by Sundstrand and operate the facility as a "generator only" facility (Reference 7).

Wastewater from the facility was discharged to the City of Camdenton sanitary discharge system. At the time of the alleged release, that discharge was delivered to the City's "Factory" lagoon. This lagoon was subsequently closed and discharges were transferred to the City's new wastewater treatment facility

#### 2.3 Operational History and Waste Characteristics

To date, no governmental agencies have conducted sampling at this site. Routine water well sampling has been conducted for the City of Camdenton wells, the closest of which is about 200 feet from the site. No contamination was detected (Reference 8).

Modine Heat Transfer, Inc., the present owner and operator of the facility, expressed an interest in conducting sampling following a meeting with the Department of Natural Resources on March 11, 1991 (Reference 9). A sampling plan was submitted; however, it was not approved (Reference 10).

After one revision of the plan, the owner decided to proceed without approval by the Department (Reference 11). Sampling was conducted October 5-8, 1991, without approval of the plan or oversight of the sampling by the U S Environmental Protection Agency or the state.

No removal actions or other response actions have occurred at the site.

#### 3 GROUNDWATER PATHWAY

#### 3.1 Hydrogeologic Setting

The following information is reported from the Missouri Division of Geology and Land Survey (Reference 12)

Sundstrand - PA Report January 31, 1992

The bedrock at the site is the Roubidoux Formation The surficial materials developed overlying the bedrock are composed of stratified layers of hard, broken chert and sandstone fragments in red, silty clay

Beds of massive boulders, some over three feet thick are not uncommon This residuum is three to nine feet thick

The area is underlain by a thick sequence of Ordovician and Cambrian aged rocks. The sequence is primarily dolomite, and may be up to 1,800 feet thick. The section that includes the principle aquifers through the Potosi Dolomite is uninterrupted by a consistent confining bed. This part of the section is approximately 1,000 feet thick, and is made up of dolomites except for the Roubidoux Formation, which contains intervals of dolomitic sandstone, and the Gunter Sandstone Member of the Gasconade Dolomite. Though some units in this sequence may act as relative confining layers, the entire section from the Potosi Dolomite up through the Roubidoux formation should be considered one aquifer.

The Davis Formation contains the only persistent confining shale bed in the section. It serves as a boundary between the lower part of the Cambrian sequence, and the Potosi and stratigraphically higher formations. Vertical circulation of water has enlarged openings along joints and fractures, allowing freer passage of water from the surface through the Potosi Dolomite.

There are no major geologic structures in the target area to constitute an aquifer discontinuity. There are also no topographic features which transect an aquifer within the target area.

The aquifer underlying the site is a karst aquifer. Karst features are particularly well developed in the Roubidoux Formation, which is the uppermost bedrock beneath the site. Segments of the unnamed stream downgradient from the site are losing

#### 3 2 Groundwater Targets

The majority of the population within a 4-mile radius relies on public water supplies, either the City of Camdenton or one of the other public water supplies. The Camdenton public water supply is a blended system that draws water from three wells. All three wells are within one mile of the site, and together they serve the population of 2,561 (Reference 13). Sampling of the City of Camdenton wells in 1987 and 1991 did not detect contamination by the hazardous substances of concern at this site (Reference 8).

In addition, there are many other public water supply wells located in the vicinity of the site, including the wells for the City of Linn Creek (see Table 1) There are approximately 374 homes within four miles which use private wells for drinking water (Reference 1) At 2 4 persons per household (the average for Camden County, Reference 14), this equates to 898 residents

Sundstrand - PA Réport January 31, 1992

The residence using a private well and located closest to a suspected source of the contamination is about 3,700 feet from the western side of the Modine plant. No residences relying on private wells are located within a 0.25-mile radius of this potential source (Reference 1).

。" 诗篇

All water wells in the area produce from the same aquifer. Most of the lake homes, restaurants, condominiums, and subdivisions have private water supplies, as there are no rural water districts in the area. There is no wellhead protection area in the vicinity of the site.

#### 3.3 Groundwater Conclusions

A release of hazardous substances to the Cambro-Ordovician aquifer is possible through the on-site disposal of solvents. TCE has been detected in area springs in the vicinity of the site, although dye trace work in the Camdenton areas has not been successful in identifying the recharge area of the spring. Due to the relatively high conductivity of the aquifer, potential widespread migration of contaminants is high. There are no residents whose wells are within 0.25 mile of the potential source. TCE and TCA are very mobile contaminants and the direction of groundwater flow is unknown. As no well contamination has been detected in wells close to the site, the remainder of residents dependent upon private wells within four miles are considered to be secondary targets.

#### 4. SURFACE WATER PATHWAY

#### 4.1 Hydrologic Setting

The site is located near the divide between two small branches of an unnamed stream which drains west to the Niangua Arm of the Lake of the Ozarks. Water appears to run off the site to the south and southwest. There are no runoff containment structures on-site. Discharge from the drainage pipe on the west side of the parking lot runs through an excavated area and into a well defined gully west of the site. The two drainage pipes on the south side of the facility do not appear to ever discharge large quantities of water since there is no channel leading from the pipe. The site is less than one-half mile southwest of the divide between the Linn Creek drainage and the Niangua River drainage. The two-year 24-hour rainfall for the site is 3.5 inches.

Drainage from the site flows overland to the south and southwest down a steep slope for approximately 700 feet before it enters an unnamed stream, which flows southwest to the Lake of the Ozarks. This unnamed stream contains losing segments The drainage area of the site is less than 50 acres The site is not located in a floodplain

Since this is a karst area, water issuing from springs within the groundwater target area should be considered for the surface water pathway. This would

Sundstrand - PA Report January 31, 1992

include Ha Ha Tonka Spring and an unnamed spring near the City of Linn Creek TCE has been previously detected in Ha Ha Tonka Spring

#### 4 2 Surface Water Targets

The unnamed tributary is a permanently flowing water body at the probable point of entry of contaminants from the site (Reference 1). This tributary is not a classified stream in the Missouri Water Quality Standards. It is subject to the general criteria for protection of all waters of the State of Missouri (Reference 15, page 11). Lake of the Ozarks, into which this unnamed creek flows, is classified for the protection of livestock and wildlife watering, the protection of warm water aquatic life and human health/fish consumption, whole body contact recreation, and boating and canoeing (Reference 15, page 32)

There are no identified drinking water intakes in the vicinity of the site

There are no identified wetlands in the vicinity of the site. There are sensitive environments present in the vicinity of the site (References 16, 17), although they do not occur in surface waters

#### 4 3 Surface Water Conclusions

There are no present indications that hazardous substances have been released into surface waters or into areas that drain toward permanently flowing surface waters. The waters of the unnamed tributary appear to be recharged at least partially from shallow groundwater, which is suspected to be contaminated. There are no water intakes located on the tributary or on the Lake of the Ozarks. No identified wetlands are present in the vicinity of the site. A federally designated endangered species, as well as other sensitive environments, are present in the vicinity of the site. Primary targets include the fisheries of the tributary and Lake of the Ozarks, and the sensitive environments.

#### 5 SOIL EXPOSURE AND AIR PATHWAYS

#### 5 1 Physical Conditions

At this point, no areas of surface soil contamination have been identified Hazardous substances have been detected at shallow depths in parking areas west of the building, and in soil below the floor of the building (the pit under the vapor degreaser)

#### 5 2 Soul and Aur Targets

The potential source of the contamination is an active facility. Residences are located on properties adjacent to the facility. The residence nearest any of the potential sources is located about 200 feet from the former west wall of

Sundstrand - PA Report January 31, 1992

the facility (the alleged disposal area). There are 808 residences located within 0.25 mile of this location. The Modine property is fenced with a gate at the road entrance. The total population within a 4-mile radius of the lagoon is 6,394 (Reference 14).

There are no wetlands of at least five acres in the vicinity of the site Smaller wetlands may be present. The Gray Bat (Myotis griesescens) is federally and state listed as endangered. The bat is known from four caves in the vicinity of Camdenton. The first cave is 2 1 miles from the site. Spinulose shield fern (Dryopteris carthusiana) is known to occur in the vicinity of the site in Red Sink Natural Area and is state listed endangered. Other sensitive environments are also present in the vicinity of the site (References 16 and 17).

#### 5.3 Soil Exposure and Air Pathway Conclusions

The soil exposure pathway appears to pose a minimal threat at the site due to the inaccessibility of the closest potential source. Although TCE is volatile when exposed to air, a release of TCE to air is not suspected because of the length of time since releases were alleged to have occurred. In addition, many of the sites are covered with pavement, buildings, or vegetation.

#### 6. SUMMARY AND CONCLUSIONS

The Sundstrand site is located in the City of Camdenton, Missouri, at the center of Camden County, Missouri (Figure 1). The site is located about one-half mule west of the intersections of U.S. Route 54 and Missouri Route The suspected area of contamination includes soil beneath the Modine Heat Transfer (formerly Sundstrand) manufacturing facility, and soil and fill material comprising loading areas and parking lot adjacent to the facility on the west. The contaminants are known to include trichloroethylene (TCE) and 1,1,1-trichloroethane (TCA). Due to the relatively high conductivity of the aguifer, potential widespread migration of contaminants is high residents whose private wells are within 0.25 mile of the potential source TCE and TCA are very mobile contaminants and the direction of groundwater flow There are no present indications that hazardous substances have been released into surface waters or into areas that drain toward permanently flowing surface waters. There are no water intakes located on the tributary or on Lake of the Ozarks No identified wetlands are present in the vicinity of the site. Primary targets include the fisheries of the tributary and Lake of the Ozarks, a federally designated endangered species, and other sensitive The soil exposure pathway appears to pose a minimal threat at the site due to the inaccessibility of the closest potential source.

#### REFERENCES

- U S Geological Survey, 7 1/2 minute topographic quadrangle maps showing site location (Green Bay Terrace, Camdenton, Decaturville, Ha Ha Tonka)
- 2 The Climatic Atlas of the United States, U.S. Department of Commerce, 1983
- 3 Original complaint
- 4 Former employee's statement
- 5 Law Environmental, Inc report
- 6 CERCLIS, Camden County sites
- 7 MDNR hazardous waste files Hazardous Waste Registrations, Modine correspondence of 12/3/90 and 12/10/91, Sundstrand correspondence of 9/6/90
- 8 MDNR sampling results
- 9 Record of Modine/MDNR meeting
- 10 MDNR comment letter on sampling plan
- 11 Modine letter stating that it would proceed with sampling
- 12 Edith Starbuck, Missouri Division of Geology and Land Survey, Memorandum, 1/13/92
- 13 Phone call with Rick Hixson, 1/24/92
- 14 Census Bureau, 1990 data
- 15 Missouri Water Quality Standards, 10 CSR 20-7 031
- Dan Dichkneite, Missouri Department of Conservation, letter dated 9/6/91
- Jerry Brabender, U S Fish and Wildlife Service, letter dated 9/16/91

Sundstrand PA January 31, 1992

#### TABLE 1

#### GROUNDWATER TARGETS

Pub.	lıc	Water	Supp.	lıes

City of Camdenton #3 (Rodeo): total depth 940 feet; cased depth 450 feet; aquifer Cambrian-Ordovician; capacity 320 gpm; distance from site 1.0 mules population served 622.

City of Camdenton #4 (Blair): total depth 1045 feet; cased depth 400 feet; aquifer Cambrian-Ordovician; capacity 300 gpm; distance from site 0 6 miles; population served 576.

City of Camdenton #6 (Mulberry): total depth 900 feet; cased depth 400 feet; aquifer Cambrian-Ordovician; capacity 575 gpm; distance from site 08 miles; population served 1105.

City of Linn Creek #1: total depth 385 feet; cased depth 170 feet; aquifer Cambrian-Ordovician; capacity 100 gpm; distance from site 2.9 miles; population served \_\_\_\_.

City of Linn Creek #2: total depth 860 feet; cased depth 528 feet; aquifer Cambrian-Ordovician; capacity 50 gpm; distance from site 3 1 miles; population served \_\_\_.

Camden PWSD #2: total depth 848 feet; cased depth 330 feet; aquifer Cambrian-Ordovician; capacity 100 gpm; distance from site 4 0 miles; population served \_\_\_.

Autumn Village: cased depth 260 feet; aquifer Cambrian-Ordovician; capacity 50 gpm; distance from site 1.4 miles; population served \_\_\_.

Camdenton Medical Center: total depth 1.3 feet; cased depth \_\_\_ feet; aquifer Cambrian-Ordovician; capacity \_\_\_ gpm; distance from site 1.4 miles; population served \_\_\_

Camdenton Windsor Estates: total depth 600 feet; cased depth 400 feet; aquifer Cambrian-Ordovician; capacity 140 gpm; distance from site 1 5 miles; population served \_\_\_

Cape of the Woods: total depth \_\_\_ feet; cased depth \_\_\_ feet; aquifer Cambrian-Ordovician; capacity \_\_\_ gpm; distance from site \_\_\_ miles; population served \_\_\_

Department of Conservation: elevation \_\_\_ feet; total depth \_\_\_ feet; cased depth \_\_\_ feet; aquifer Cambrian-Ordovician; capacity \_\_\_ gpm; distance from site \_\_\_ miles; population served \_\_\_.

### TABLE 1

### (continued)

New Tribes: total depth feet; cased depth feet; aquifer Cambrian-Ordovician; capacity gpm; distance from site 4.0 miles; population served
Oak Bluff Condominiums: total depth 545 feet; cased depth 350 feet; aquifer Cambrian-Ordovician; capacity 60 gpm; distance from site 2.7 miles; population served
Southway Terrace MHC: total depth 505 feet; cased depth 350 feet; aquifer Cambrian-Ordovician; capacity gpm; distance from site 2.5 miles; population served
Watkins Subdivision: total depth 690 feet; cased depth 440 feet; aquifer Cambrian-Ordovician; capacity 60 gpm; distance from site 1.8 miles; population served
Whispering Hills: total depth feet; cased depth feet; aquifer Cambrian-Ordovician; capacity gpm; distance from site miles; population served
means no information obtained.
Private Water Supplies
Many motels, hotels, and restaurants along Highway 54 south of Camdenton.
All of the residences not served by the above systems

Former Hulett Lagoon Site

MISSOURI DEPARIMENT OF NATURAL REFERENCE 36
DIVISION OF ENVIRONMENTAL QUALTITY
ENVIRONMENTAL SERVICES PROGRAM

Site Sampling Report

Sundstrand Site

Camdenton, MO

July 20 through July 31, 1992

RECEIVE

JAN 4 1993

HAZARDOUS WASTE PROGRAM
MISSOURI DEPARTMENT OF
NATURAL RELIGIONOLE

#### INTRODUCTION

As part of a site inspection authorized by the Federal Comprehensive Environmental Response, Compensation, and Liability Act, sampling was conducted at the Sundstrand Site in Camdenton, Missouri. The sampling was requested by the Missouri Department of Natural Resources (MDNR), Hazardous Waste Program (HWP), to determine whether hazardous substance releases from the Sundstrand Tubular Products facility (presently Modine Heat Transfer) has caused groundwater contamination in the area. Previous sampling conducted by Modine contractors indicated that soils around the site have been contaminated with trichloroethylene (TCE), 1,1,1 trichloroethane (TCA), tetrachloroethylene (PCE) and vinyl chloride.

Sampling during this inspection included soil and groundwater produced from the construction of monitoring wells on Modine Heat Transfer property, neighboring private wells, surface water from a creek downgradient from the site, and a spring David Mosby of the MDNR, Environmental Services Program (ESP), collected samples and provided contractor oversite. Edith Starbuck of the MDNR, Division of Geology and Land Survey, was present throughout the inspection to provide technical support during well drilling. Floyd Chilcutt and Bert Williams operated the drill rig for Layne-Western Company, subcontractors for the site. Don Mans of Modine Manufacturing Company split some of the samples collected during the inspection. The sampling data will be used in scoring the site according to the U.S. EPA's hazard ranking system.

#### METHODS

Two monitoring wells (MW#1 and MW#2) were drilled and sampled during the site inspection. An air-rotary drill rig was used for well construction. Monitoring well #1 (MW#1) was drilled south of the facility parking lot at a location considered downgradient of the contaminated area. Monitoring well #2 (MW#2) was drilled near the northeast side of the facility at a location considered to be upgradient of the contamination. (See Appendix A for sampling locations.)

During drilling, soil was collected at five-foot intervals with a split spoon sampler and placed in containers with stainless steel spoons. Surface samples at both drilling locations were collected as direct grabs with stainless steel spoons because samples at this depth could not be collected with the split spoon sampler. Soil samples and drilling activities were monitored for organic vapors using a flame ionization detector (FID) or a photoionization detector (PID).

Sampling Report Sundstrand Site Camdenton, MO Page Two

Drilling of wells ceased when sufficient water was encountered in the desired monitoring zone. After drilling was completed, wells were cased, screened, and grouted by Layne-Western and developed by MDNR and Layne-Western personnel. Wells were developed with a Grundfos submersible pump and/or stainless steel or Teflon bailer. Wells were purged until water turbidity decreased or until field parameters of conductivity, pH, and temperature, measured after each well volume, stabilized within 10% of the prior reading. Three volumes were purged from both wells during development.

Wells were sampled no earlier than the following day after development. Prior to sampling, one to three additional well volumes were purged depending on field parameter stability. Samples were collected by lowering a stainless steel or Teflon bailer to the bottom of the water column, pulling the bailer back up through the well, and filling sample containers directly

Groundwater was sampled from three private wells located downgradient from the site at the E.M Gillemberg, Robert E. Bailey, and Steve Fera residences. Samples were collected from an outside tap after running water out of the lines for three to five minutes.

Two grab samples were collected of surface water downgradient of the site by submersing the appropriate containers into the water body. A small creek, which flows through Jarvis Hollow (just below MW#1) and Ha Ha Tonka Spring, which flows into the Lake of the Ozarks approximately  $2^{1}/_{4}$  miles south of the site, were sampled.

An equipment blank was collected of the rinsate from the decontamination of the pump and hose used to develop and purge the wells. This sample was collected after sampling MW#1 and before sampling MW#2. Tap water from the facility was used as the rinse water.

The following samples were collected at the above mentioned locations:

SAMPLE #	LOCATION	SAMPLE TYPE	DATE
92-6915	MW#1 10-12 feet deep	soil boring	7/20/92
92-6916	MW#1 15-17 feet deep	soil boring	7/20/92
92-6917	MW#1 20-20.5 feet deep	soil boring	7/20/92
92-6918	creek below site in Jarvis Hollow		7/22/92
92-6919	Ha Ha Tonka Spring at state park	surface water	7/22/92
92-6920	E.M. Gillemberg residence	groundwater	7/28/92
92-6921	Robert E. Bailey residence	groundwater	7/28/92
92-6922	Steve Fera residence	groundwater	7/28/92
92-6923	MW#2 0-3 inches deep	soil grab	7/28/92
92-6924	MW#2 5-5.5 feet deep	soil boring	7/28/92
92-6925	MW#2 10-12 feet deep	soil boring	7/28/92
92-6926	MW#2 15-16 feet deep	soil boring	7/28/92
92-6927	MW#2 20-22 feet deep	soil boring	7/28/92
92-6928	MW#1	groundwater	7/30/92
92-6930	Sundstrand Site	rınsate blank	7/30/92
92-6931	MW#2	groundwater	7/31/92
92-6932	MW#1 0-3 inches deep	soil grab	7/31/92

Sampling Report Sundstrand Site Camdenton, MO Page Three

All samples were analyzed for volatile organics at the state's environmental laboratory within the Environmental Services Program in Jefferson City. Each sample was given a numbered tag and the corresponding number was recorded on a chain-of-custody form. Other laboratory procedures were followed according to the requirements and standard operating procedures of the Preliminary Assessment/Site Inspection Quality Assurance Project Plan for Fiscal Year 1992.

#### OBSERVATIONS

Voids at the bedrock/soil interface or in the competent rock itself impeded drilling progress and well construction at MW#1. An outer casing of steel had to be set 80 feet deep and grouted around the outside in order to advance this well to the desired depth.

Total well depth of MW#1 was 161 feet and MW#2 was 197 feet. Static water levels were 144 feet and 174.5 feet for MW#1 and MW#2, respectively.

Water in the monitoring wells changed from turbid and reddish-brown, to silty and grey, and finally to colorless and clear during development and purging. Since well samples were collected from the bottom of the water column, they were grey and silty, even though water from the top of the water column was colorless and clear.

No organic vapors were detected in the soil borings or drilling air returns from any of the wells.

Soil samples were predominantly composed of red clay Amounts of chert, limestone, topsoil, sandstone, and stringers of tan-colored clay varied with depth and location. Soil from the boring of MW#2 contained more tan clay and sand than MW#1.

Don Mans reported in a phone conversation to Dave Mosby that the sample they split of MW#2 contained low levels of TCE below the detection level used by the MDNR laboratory. Modine did not split the water sample of MW#1.

#### RESULTS

See Appendix B for sample results.

Sampling Report Sundstrand Site Camdenton, MO Page Four

Submitted by

David E Mosoy

Environmental Specialist

Superfund Unit

Environmental Services Program

Date

Approved by

James H Long

Director

Environmental Services Program


JHL dmd

Julie Bloss, Environmental Specialist, PA/SI Unit, Superfund Section, Hazardous Waste Program

### APPENDIX A

SAMPLING REPORT SUNDSTRAND SITE CAMDENION, MO

Site.Map



### APPENDIX B

SAMPLING REPORT SUNDSTRAND SITE CAMDENION, MO

Sampling Data
July 20 through July 31, 1992

Sample No 92-6915

**RESULTS** 

< '5 ug/kg / 25 ug/kg

< 25 ug/Kg

< 25 ug/kg

Reported to DAVID MOSBY Affiliation SPFD

Date 12/30/92 Project Code 3658/3000

Sample Description

PARAMETERS

Carbon Disulfide

Chlorobenzene

Chloroethane

Carbon Tetrachloride

SUNDSTRAND (MODINE MANUFACTURING CO ) SITE CAMDENTON, MO , GRAB OF BOREHOLE CORE OF SOIL AT 10-12 FT , MW# 1

Collected by DAVID MOSBY Affiliation SPFD

Date 07/20/92

1110112110	1000010		
1,1,1-Trichloroethane	<	25	ug/Kg
1,1,2,2-Tetrachloroethane		25	ug/Kg
1,1,2-Trichloroethane		25	ug/Kg
1,1-Dichloroethane		25	ug/Kg
1,1-Dichloroethylene		25	
1,2-Dichloroethane			ug/Kg
1,2-Dichloroethene (Total)		25	
1,2-Dichloropropane		25	
2-Butanone		100	ug/Kg
2-Hexanone		100	ug/Kg
4-Methyl-2-Pentanone		100	
Acetone			ug/Kg
Benzene			ug/Kg
Bromodichloromethane			ug/Kg
Bromoform			ug/Kg
Bromomethane	<	25	ua/Kg

Page 2 Sample no 92-6915 Date 12/30/92

PARAMETERS			REST	JLTS
Chloroform		<	25	ug/Kg
Chloromethane		<	25	ug/Kg
cis-1,3-Dichloropropene		<	25	ug/Kg
Dibromochloromethane		<	25	ug/Kg
Ethylbenzene		<	25	ug/Kg
Methylene Chloride		<	25	ug/Kg
Styrene		<	25	ug/Kg
Tetrachloroethene		<	25	ug/Kg
Toluene		<	25	ug/Kg
trans-1,3-Dichloropropene		<	25	ug/Kg
Trichloroethene		<	25	ug/Kg
Vinyl Acetate		<	100	ug/Kg
'inyl Chloride/Chloroethene		<	25	ug/Kg
Aylenes (Total)		<	25	ug/Kg
COMMENTS Analyzed by GC/MS at	the M	lıss	our	DNR
laboratory				

Sample No 92-6916

Reported to DAVID MOSBY Date 12/30/92
Affiliation SPFD Project Code 3658/3000

Sample Description
SUNDSTRAND SITE (MODINE HEAT TRANSFER)
CAMDENTON, MO , GRAB OF BOREHOLE CORE
OF SOIL AT 15-17 FT , MW# 1

Collected by DAVID MOSBY Affiliation SPFD

Date 07/20/92

# PARAMETERS RESULTS ,1,1-Trichloroethane < 25 ug/K

1,1,1-Trichloroethane	<	25	ug/Kg
1,1,2,2-Tetrachloroethane	<	25	ug/Kg
1,1,2-Trichloroethane	<	25	ug/Kg
1,1-Dichloroethane	<	25	ug/Kg
1,1-Dichloroethylene	<	25	ug/Kg
1,2-Dichloroethane	<	25	ug/Kg
1,2-Dichloroethene (Total)	<	25	ug/Kg
1,2-Dichloropropane	<	25	ug/Kg
2-Butanone	<	100	ug/Kg
2-Hexanone	<	100	ug/Kg
4-Methyl-2-Pentanone	<	100	ug/Kg
Acetone	<	100	ug/Kg
Benzene	<	25	ug/Kg
Bromodichloromethane	<	25	ug/Kg
Bromoform	<	25	ug/Kg
Bromomethane	<	25	ug/Kg
Carbon Disulfide	<	25	ua/kg
Carbon Tetrachloride	-	25	na/kg
Chlorobenzene		25	ua/Kg
Chloroethane	<	25	ug/Kg

Page 2 Sample no 92-6916 Date 12/30/92

PARAMETERS			RESU	ULTS
Chloroform			25	ug/Kg
Chloromethane		<	25	ug/Kg
cis-1,3-Dichloropropene		<	25	ug/Kg
Dibromochloromethane		<	25	ug/Kg
Ethylbenzene		<	25	ug/Kg
Methylene Chloride		<	25	ug/Kg
Styrene		<	25	ug/Kg
Tetrachloroethene		<	25	ug/Kg
Toluene		<	25	ug/Kg
trans-1,3-Dichloropropene		<	25	ug/Kg
Trichloroethene		<	25	ug/Kg
Vinyl Acetate		<	100	ug/Kg
inyl Chloride/Chloroethene		<	25	ug/Kg
ylenes (Total)		<	25	ug/Kg
COMMENTS Analyzed by GC/MS at laboratory	the 1	Mıss	our	L DNR

Sample No 92-6917

Reported to DAVID MOSBY Affiliation SPFD

Date 12/30/92 Project Code 3658/3000

Sample Description

SUNDSTRAND SITE (MODINE HEAT TRANSFER) CAMDENTON, MO , GRAB OF BOREHOLE CORE OF SOIL AT 20-20 5 FT , MW# 1

Collected by DAVID MOSBY Affiliation SPFD

Date 07/20/92

# <u>PARAMETERS</u> <u>RESULTS</u>

1,1,1-Trichloroethane 1,1,2,2-Tetrachloroethane 1,1,2-Trichloroethane 1,1-Dichloroethane 1,1-Dichloroethylene 1,2-Dichloroethane 1,2-Dichloroethene (Total) 1,2-Dichloropropane 2-Butanone 2-Hexanone 4-Methyl-2-Pentanone Acetone Benzene Bromodichloromethane Bromoform Bromomethane Carbon Disulfide	< < < < < < < < < < < < < < < < < < <	25 25 100 100 100 25 25 25 25	ug/Kg
Carbon Tetrachloride		25	ug/Kg
Chlorobenzene		25	ug/Kg
Chloroethane	<	25	ug/Kg

Page 2 Sample no 92-6917 Date 12/30/92

PARAMETERS		RES	ULTS
Chloroform Chloromethane cis-1,3-Dichloropropene Dibromochloromethane Ethylbenzene Methylene Chloride Styrene Tetrachloroethene Toluene tians-1,3-Dichloropropene Trichloroethene Vinyl Acetate 'inyl Chloride/Chloroethene %ylenes (Total) COMMENTS Analyzed by GC/MS at	< </td <td>25 25 25 25 25 25 25 25 25 25 25 25 25 2</td> <td>ug/Kg ug/Kg ug/Kg ug/Kg ug/Kg ug/Kg ug/Kg ug/Kg ug/Kg ug/Kg</td>	25 25 25 25 25 25 25 25 25 25 25 25 25 2	ug/Kg
laboratory			

Sample No 92-6918

Reported to DAVID MOSBY Affiliation SPFD

Date 12/30/92 Project Code 3658/3000

Sample Description

SUNDSTRAND SITE (MODINE HEAT TRANSFER)
CAMDENTON, MO , GRAB OF CREEK DOWN HILL FROM FACILITY

Date 07/22/92

Collected by DAVID MOSBY Affiliation SPFD

PARAMETERS	RESULTS
1,1,1-Trichloroethane 1,1,2,2-Tetrachloroethane 1,1,2-Trichloroethane 1,1-Dichloroethane 1,1-Dichloroethylene 1,2-Dichloroethane 1,2-Dichloroethene (Total) 1,2-Dichloropropane 2-Butanone 2-Hexanone 4-Methyl-2-Pentanone Acetone Benzene Bromodichloromethane Bromoform Bromomethane Carbon Disulfide Carbon Tetrachloride Chlorobenzene	<pre></pre>
Chloroethane Chloroform	< 5 0 ug/L < 5 0 ug/L

Page 2 Sample no 92-6918 Date 12/30/92

PARAMETERS			RI	EST	JLTS
Chloromethane					ug/L
cis-1,3-Dichloropropene		<	5	0	ug/L
Dibromochloromethane		<	5	0	ug/L
Ethylbenzene		<	5	0	ug/L
Methylene Chloride		<	5	0	ug/L
Styrene		<	5	0	ug/L
Tetrachloroethene		<	5	0	ug/L
Toluene		<	5	0	ug/L
trans-1,3-Dichloropropene		<	5	0	ug/L
Trichloroethene		<	5	0	ug/L
Vinyl Acetate		<	10	00	ug/L
Vinyl Chloride/Chloroethene		<	5	0	ug/L
(ylenes (Total)		<	5	0	ug/L
LOMMENTS Analyzed by GC/MS at	the Mis	350	oui	cı	DNR
Environmental Services Program	laborat	to	cv		

Sample No 92-6919

< 5 0 ug/L

< 5 0 ug/L

Reported to DAVID MOSBY
Affiliation SPFD
Date 12/30/92
Project Code 3658/3000

Sample Description
SUNDSTRAND SITE (MODINE HEAT TRANSFER)
CAMDENTON, MO , GRAB OF HA HA TONKA SPRING
HA HA TONKA STATE PARK

Collected by DAVID MOSBY Affiliation SPFD

Chlorobenzene

Chloroethane

Date 07/22/92

PARAMETERS	RESULTS
1,1,1-Trichloroethane 1,1,2,2-Tetrachloroethane 1,1,2-Trichloroethane 1,1-Dichloroethane	< 5 0 ug/L < 5 0 ug/L < 5 0 ug/L < 5 0 ug/L
1,1-Dichloroethylene	< 5 0  ug/L
1,2-Dichloroethane	< 5 0 ug/L
1,2-Dichloroethene (Total)	< 5 0 ug/L
1,2-Dichloropropane	< 5 0 ug/L
2-Butanone	< 100 ug/L
2-Hexanone	< 100 ug/L
4-Methyl-2-Pentanone	< 100 ug/L
Acetone	< 100 ug/L
Benzene	< 5 0 ug/L
Bromodichloromethane	< 5 0 ug/L
Bromoform	< 5 0 ug/L
Bromomethane	< 5 0 ug/L
Carbon Disulfide	< 5 0  ug/L
Carbon Tetrachloride	< 5 0  ug/L

Page 2 Sample no 92-6919 Date 12/30/92

PARAMETERS		RESU	<u>JLTS</u>
Chloroform	<	5 0	ug/L
Chloromethane	<	5 0	ug/L
cis-1,3-Dichloropropene	<	5 0	ug/L
Dibromochloromethane	<	5 0	ug/L
Ethylbenzene	<	5 0	ug/L
Methylene Chloride	<	5 0	ug/L
Styrene	<	5 0	ug/L
Tetrachloroethene	<	5 0	ug/L
Toluene	<	5 0	ug/L
trans-1,3-Dichloropropene	<	5 0	ug/L
Trichloroethene	<	5 0	ug/L
Vınyl Acetate	<	100	ug/L
<pre>inyl Chloride/Chloroethene</pre>	<	5 0	ug/L
Kylenes (Total)	<	5 0	ug/L
COMMENTS Analyzed by GC/MS at	the Misso	ourı	DNR
Environmental Services Program	laborator	:y	

Sample No 92-6920

Reported to DAVID MOSBY Affiliation SPFD

Date 9/02/92 Project Code 3658/3148

Sample Description

SUNDSTRAND SITE (MODINE HEAT TRANSFER) CAMDENTON, MO

GRAB OF WELL FROM E M GILLENBERG HOUSEHOLD

Collected by DAVID MOSBY Affiliation SPFD

Date 07/28/92

PARAMETERS		RESULTS
1 1 1 Marchlessekhane		E 0~/T
1,1,1-Trichloroethane		5 0 ug/L
1,1,2,2-Tetrachloroethane		5 0 ug/L
1,1,2-Trichloroethane	<	5 0 ug/L
1,1-Dichloroethane	<	5 0 ug/L
1,1-Dichloroethylene	<	5 0 ug/L
1,2-Dichloroethane	<	5 0 ug/L
1,2-Dichloroethene (Total)	<	5 0 ug/L
1,2-Dichloropropane	<	5 0 ug/L
2-Butanone	<	100 ug/L
2-Hexanone	<	50 ug/L
4-Methyl-2-Pentanone	<	50 ug/L
Acetone	<	100 ug/L
Benzene	<	5 0 ug/L
Bromodichloromethane	<	5 0 ug/L
Bromoform		5 0 ug/L
Bromomethane	<	5 0 ug/L
Carbon Disulfide	<	5 0 ug/L
Carbon Tetrachloride		5 0 ug/L
Chlorobenzene	<	5 0 ug/L
Chloroethane	<	$5 \ 0 \ ug/L$

Page 2 Sample no 92-6920 Date 9/02/92

PARAMETERS	RESULTS
PARAMETERS  Chloroform Chloromethane cis-1,3-Dichloropropene Dibromochloromethane Ethylbenzene Methylene Chloride Styrene Tetrachloroethene Toluene trans-1,3-Dichloropropene Trichloroethene	RESULTS  < 5 0 ug/L  < 5 0 ug/L
Vinyl Acetate /inyl Chloride/Chloroethene Xvlenes (Total)	< 100 ug/L < 5 0 ug/L < 5 0 ug/L
<pre>Xylenes (Total) COMMENTS Analyzed by GC/MS</pre>	< 5 0 ug/L at Continental
Analytical Services, Inc	

Sample No 92-6921

< 5 0 ug/L < 5 0 ug/L

< 5 0 ug/L

Reported to DAVID MOSBY Affiliation SPFD

Date 9/02/92 Project Code 3658/3148

Sample Description

SUNDSTRAND SITE (MODINE HEAT TRANSFER)

CAMDENTON, MO

GRAB OF WELL FROM ROBERT E BAILEY HOUSEHOLD

Collected by DAVID MOSBY Affiliation SPFD

Carbon Tetrachloride

Chlorobenzene

Chloroethane

Date 07/28/92

PARAMETERS		RESULTS
1,1,1-Trichloroethane	<	5 0 ug/L
1,1,2,2-Tetrachloroethane	<	5 0 ug/L
1,1,2-Trichloroethane	<	5 0 ug/L
1,1-Dichloroethane	<	5 0 ug/L
1,1-Dichloroethylene	<	5 0 ug/L
1,2-Dichloroethane	<	5 0 ug/L
1,2-Dichloroethene (Total)	<	5 0 ug/L
1,2-Dichloropropane	<	5 0 ug/L
2-Butanone	<	100 ug/L
2-Hexanone	<	50 ug/L
4-Methyl-2-Pentanone	<	50 ug/L
Acetone	<	100 ug/L
Benzene	<	5 0 ug/L
Bromodichloromethane	<	5 0 ug/L
Bromoform	<	5 0 ug/L
Bromomethane	<	5 0 ug/L
Carbon Disulfide	<	5 0 ug/L

Page 2 Sample no 92-6921 Date 9/02/92

PARAMETERS	RESULTS
Chloroform	< 5 0 ug/L
Chloromethane	< 5 0 ug/L
cis-1,3-Dichloropropene	< 5 0 ug/L
Dibromochloromethane	< 5 0 ug/L
Ethylbenzene	< 5 0 ug/L
Methylene Chloride	< 5 0 ug/L
Styrene	< 5 0 ug/L
Tetrachloroethene	< 5 0 ug/L
Toluene	< 5 0 ug/L
trans-1,3-Dichloropropene	< 5 0 ug/L
Trichloroethene	< 5 0 ug/L
Vinyl Acetate	< 100 ug/L
/inyl Chloride/Chloroethene	< 5 0 ug/L
Xylenes (Total)	< 5 0 ug/L
COMMENTS Analyzed by GC/MS Analytical Services, Inc	at Continental

Sample No 92-6922

Reported to DAVID MOSBY

Affiliation SPFD

Date 9/02/92

Project Code 3658/3148

Sample Description
SUNDSTRAND SITE (MODINE HEAT TRANSFER)
CAMDENTON, MO
GRAB OF WELL FROM STEVE FERRA HOUSEHOLD

Collected by DAVID MOSBY Affiliation SPFD

Date 07/28/92

PARAMETERS	RESULTS			
1,1,1-Trichloroethane	<	5 0 ug/L		
1,1,2,2-Tetrachloroethane		5 0 ug/L		
1,1,2-Trichloroethane		5 0 ug/L		
1,1-Dichloroethane		5 0 ug/L		
1,1-Dichloroethylene		5 0 ug/L		
1,2-Dichloroethane		5 0 ug/L		
1,2-Dichloroethene (Total)	<	5 0 ug/L		
1,2-Dichloropropane		5 0 ug/L		
2-Butanone	<	100 ug/L		
2-Hexanone	<	50 ug/L		
4-Methyl-2-Pentanone	<	50 ug/L		
Acetone		100 ug/L		
Benzene	<	5 0 ug/L		
Bromodichloromethane	<	5 0 ug/L		
Bromoform		5 0 ug/L		
Bromomethane		5 0 ug/L		
Carbon Disulfide		5 0 ug/L		
Carbon Tetrachloride		5 0 ug/L		
Chlorobenzene		5 0 ug/L		
Chloroethane	<	5 0 ug/L		

Page 2 Sample no 92-6922 Date 9/02/92

PARAMETERS			R	ESU	<u>JLTS</u>
Chloroform		<	5	0	ug/L
Chloromethane		<	5	0	ug/L
cis-1,3-Dichloropropene		<	5	0	ug/L
Dibromochloromethane		<	5	0	ug/L
Ethylbenzene		<	5	0	ug/L
Methylene Chloride					ug/L
Styrene		<	5	0	ug/L
Tetrachloroethene		<	5	0	ug/L
Toluene		<	5	0	ug/L
trans-1,3-Dichloropropene		<	5	0	ug/L
Trichloroethene		<	5	0	ug/L
Vinyl Acetate		<	1	00	ug/L
Vinyl Chloride/Chloroethene		<	5	0	ug/L
ylenes (Total)		<	5	0	ug/L
COMMENTS Analyzed by GC/MS	at	Continen	ta	l	-
Analytical Services, Inc					

Sample No 92-6923

Reported to DAVID MOSBY
Affiliation SPFD
Date 9/02/92
Project Code 3658/3148

Sample Description
SUNDSTRAND SITE (MODINE HEAT TRANSFER)
CAMDENTON, MO
GRAB OF SOIL FROM MW #2 FROM 0-3 INCHES DEEP

Collected by DAVID MOSBY Affiliation SPFD

Date 07/28/92

### PARAMETERS RESULTS

1,1,1-Trichloroethane	<	5 0	ug/Kg
1,1,2,2-Tetrachloroethane	<	5 0	ug/Kg
1,1,2-Trichloroethane	<	5 0	ug/Kg
1,1-Dichloroethane	<	5 0	ug/Kg
1,1-Dichloroethylene	<	5 0	ug/Kg
1,2-Dichloroethane	<	5 0	ug/Kg
1,2-Dichloroethene (Total)			ug/Kg
1,2-Dichloropropane			ug/Kg
2-Butanone	<	100	ug/Kg
2-Hexanone	<	50	ug/Kg
4-Methyl-2-Pentanone	<	50	ug/Kg
Acetone	<	100	ug/Kg
Benzene	<	5 0	ug/Kg
Bromodichloromethane	<	5 0	ug/Kg
Bromoform	<	5 0	ug/Kg
Bromomethane			ug/Kg
Carbon Disulfide	<	5 0	ug/Kg
Carbon Tetrachloride			ug/Kg
Chlorobenzene	<	5 0	ug/Kg
Chloroethane			ug/Kg
			_

Page 2 Sample no 92-6923 Date 9/02/92

PARAMETERS		RES	ULTS
Chloroform			ug/Kg
Chloromethane	<	5 0	ug/Kg
cis-1,3-Dichloropropene			ug/Kg
Dibromochloromethane			ug/Kg
Ethylbenzene	<	5 0	ug/Kg
Methylene Chloride	<	5 0	ug/Kg
Styrene			ug/Kg
Tetrachloroethene	<	5 0	ug/Kg
Toluene	<	5 0	ug/Kg
trans-1,3-Dichloropropene			ug/Kg
Trichloroethene	<	5 0	ug/Kg
Vınyl Acetate	<	100	ug/Kg
'inyl Chloride/Chloroethene	<	5 0	ug/Kg
ylenes (Total)	<	5 0	ug/Kg
COMMENTS Analyzed by GC/MS at Analytical Services, Inc	Continent	:al	-

Sample No 92-6924

RESULTS

Reported to DAVID MOSBY Affiliation SPFD

Date 9/02/92 Project Code 3658/3148

Sample Description

SUNDSTRAND SITE (MODINE HEAT TRANSFER) CAMDENTON, MO

PARAMETERS

GRAB OF SOIL FROM MW #2 FROM 5 - 5 5 FT DEEP

Collected by DAVID MOSBY Affiliation SPFD

Date 07/28/92

IMIGHIDIBIO		TABO.	<u> </u>
1,1,1-Trichloroethane 1,1,2,2-Tetrachloroethane 1,1,2-Trichloroethane 1,1-Dichloroethane 1,1-Dichloroethylene 1,2-Dichloroethane 1,2-Dichloroethene (Total) 1,2-Dichloropropane 2-Butanone	< < < < < <	5 0 5 0 5 0 5 0 5 0 5 0 5 0 5 0	ug/Kg ug/Kg ug/Kg ug/Kg ug/Kg ug/Kg ug/Kg
2-Hexanone			ug/Kg
4-Methyl-2-Pentanone			ug/Kg
Acetone	<	100	ug/Kg
Benzene	<	5 0	ug/Kg
Bromodichloromethane	<	5 0	ug/Kg
Bromoform	<	5 0	ug/Kg
Bromomethane			ug/Kg
Carbon Disulfide	<	5 0	ug/Kg
Carbon Tetrachloride			ug/Kg
Chlorobenzene			ug/Kg
Chloroethane	<	5 0	ug/Kg

Page 2 Sample no 92-6924 Date 9/02/92

PARAMETERS	<u>:</u>	RESULTS
Chloroform		5 0 ug/Kg
Chloromethane		5 0  ug/Kg
cis-1,3-Dichloropropene	<	5 0  ug/Kg
Dibromochloromethane	< .	5 0 ug/Kg
Ethylbenzene	<	5 0 ug/Kg
Methylene Chloride	<	5 0 ug/Kg
Styrene	<	5 0  ug/Kg
Tetrachloroethene		5 0 ug/Kg
Toluene	<	5 0 ug/Kg
trans-1,3-Dichloropropene	<	5 0 ug/Kg
Trichloroethene	6 8 u	
Vınyl Acetate		100 ug/Kg
'inyl Chloride/Chloroethene		5 0  ug/Kg
ylenes (Total)	<	5 0 ug/Kg
COMMENTS Analyzed by GC/MS Analytical Services, Inc	at Continent	al

#### Sample No 92-6925

Reported to DAVID MOSBY
Affiliation SPFD
Date 9/02/92
Project Code 3658/3148

Sample Description
SUNDSTRAND SITE (MODINE HEAT TRANSFER)
CAMDENTON, MO
GRAB OF SOIL FROM BORING FOR MW #2 FROM 10 - 12 FT DEEP

Collected by DAVID MOSBY Date 07/28/92 Affiliation SPFD

### PARAMETERS RESULTS

1,1,1-Trichloroethane 1,1,2,2-Tetrachloroethane 1,1,2-Trichloroethane 1,1-Dichloroethane 1,1-Dichloroethylene 1,2-Dichloroethane 1,2-Dichloroethene (Total) 1,2-Dichloropropane 2-Butanone 2-Hexanone	< < < < < < < < < < < < < < < < < < <	5 5 5 5 5 5 5 5 5 5 5 5	0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	ug/Kg ug/Kg ug/Kg ug/Kg ug/Kg ug/Kg ug/Kg ug/Kg
4-Methyl-2-Pentanone Acetone				ug/Kg ug/Kg
Benzene				ug/Kg
Bromodichloromethane				ug/Kg
Bromoform				ug/Kg
Bromomethane	<	5	0	ug/Kg
Carbon Disulfide				ug/Kg
Carbon Tetrachloride	<	5	0	ug/Kg
Chlorobenzene				ug/Kg
Chloroethane	<	5	0	ug/Kg

Page 2 Sample no 92-6925 Date 9/02/92

PARAMETERS	RESUL			JLTS
Chloroform Chloromethane cis-1,3-Dichloropropene Dibromochloromethane Ethylbenzene	< < <	5 5 5 5 5	0 0 0 0	ug/Kg ug/Kg ug/Kg ug/Kg ug/Kg
Methylene Chloride Styrene Tetrachloroethene	<	5	0	ug/Kg ug/Kg ug/Kg
Toluene				ug/Kg
trans-1,3-Dichloropropene				ug/Kg
Trichloroethene				ug/Kg
Vinyl Acetate				ug/Kg
Vinyl Chloride/Chloroethene				ug/Kg
<pre>Xylenes (Total) COMMENTS Analyzed by GC/MS at Cont Analytical Services, Inc</pre>				ug/Kg

Sample No 92-6926

Reported to DAVID MOSBY Affiliation SPFD

Date 12/30/92 Project Code 3658/3148

Sample Description

SUNDSTRAND SITE (MODINE HEAT TRANSFER)

CAMDENTON, MO

GRAB OF SOIL FROM BORING FOR MW #2 FROM 15 - 16 FT DEEP

Collected by DAVID MOSBY Affiliation SPFD

Date 07/28/92

### PARAMETERS

#### RESULTS

<del></del>			
1,1,1-Trichloroethane	<	5 0	ug/Kg
1,1,2,2-Tetrachloroethane	<	5 0	ug/Kg
1,1,2-Trichloroethane	<	5 0	ug/Kg
1,1-Dichloroethane	<	5 0	ug/Kg
1,1-Dichloroethylene	<	5 0	ug/Kg
1,2-Dichloroethane	<	5 0	ug/Kg
1,2-Dichloroethene (Total)			ug/Kg
1,2-Dichloropropane	<	5 0	ug/Kg
2-Butanone	<	100	ug/Kg
2-Hexanone	<	50	ug/Kg
4-Methyl-2-Pentanone	<	50	ug/Kg
Acetone	<	100	ug/Kg
Benzene	<	5 0	ug/Kg
Bromodichloromethane	<	5 0	ug/Kg
Bromoform			ug/Kg
Bromomethane	<	5 0	ug/Kg
Carbon Disulfide	<	5 0	ug/Kg
Carbon Tetrachloride	-	L ()	ng/kg
Chlorobenzene	<	5 0	ug/Kg
Chloroethane	<	5 0	uq/Kg

Page 2 Sample no 92-6926 Date 12/30/92

PARAMETERS	RESU				JLTS
Chloroform		<	5	0	uq/Kg
Chloromethane		<	5	0	ug/Kg
cis-1,3-Dichloropropene		<	5	0	ug/Kg
Dibromochloromethane		<	5	0	ug/Kg
Ethylbenzene		<	5	0	ug/Kg
Methylene Chloride		<	5	0	ug/Kg
Styrene		<	5	0	ug/Kg
Tetrachloroethene					ug/Kg
Toluene					ug/Kg
trans-1,3-Dichloropropene		<	5	0	ug/Kg
Trichloroethene	37	ug/Kg			
Vınyl Acetate		<	10	00	ug/Kg
Vinyl Chloride/Chloroethene		<	5	0	ug/Kg
Xylenes (Total)		<	5	0	ug/Kg
COMMENTS Analyzed by GC/MS at Analytical Services, Inc	Contine	ent	ta.	l	

Sample No 92-6927

Reported to DAVID MOSBY Affiliation SPFD

Date 9/02/92 Project Code 3658/3148

Sample Description

SUNDSTRAND SITE (MODINE HEAT TRANSFER)

CAMDENTON, MO

GRAB OF SOIL FROM BORING FOR MW #2 FROM 20 - 22 FT DEEP

Collected by DAVID MOSBY Affiliation SPFD

Date 07/28/92

#### **PARAMETERS** RESULTS

1,1,1-Trichloroethane	<	5	0	ug/Kg
1,1,2,2-Tetrachloroethane	<	5	0	ug/Kg
1,1,2-Trichloroethane	<	5	0	ug/Kg
1,1-Dichloroethane	<	5	0	ug/Kg
1,1-Dichloroethylene	<	5	0	ug/Kg
1,2-Dichloroethane	<	5	0	ug/Kg
1,2-Dichloroethene (Total)	<	5	0	ug/Kg
1,2-Dichloropropane	<	5	0	ug/Kg
2-Butanone	<	10	00	ug/Kg
2-Hexanone	<	5(	)	ug/Kg
4-Methyl-2-Pentanone	<	5(	)	ug/Kg
Acetone	<	10	00	ug/Kg
Benzene	<	5	0	ug/Kg
Bromodichloromethane	<	5	0	ug/Kg
Bromoform	<	5	0	ug/Kg
Bromomethane	<	5	0	ug/Kg
Carbon Disulfide	<	5	0	ug/Kg
Carbon Tetrachloride	<	5	0	ug/Kg
Chlorobenzene	<	5	0	ug/Kg
Chloroethane	<	5	0	ug/Kg

Page 2 Sample no 92-6927 Date 9/02/92

PARAMETERS	RESULTS
Chloroform	< 5 0 ug/Kg
Chloromethane	< 5 0 ug/Kg
cıs-1,3-Dıchloropropene	< 5 0 ug/Kg
Dibromochloromethane	< 5 0 ug/Kg
Ethylbenzene	< 5 0 ug/Kģ
Methylene Chloride	< 5 0 ug/Kg
Styrene	< 5 0 ug/Kg
Tetrachloroethene	< 5 0 ug/Kg
Toluene	< 5 0 ug/Kg
trans-1,3-Dichloropropene	< 5 0 ug/Kg
Trichloroethene	7 1 ug/Kg
Vinyl Acetate	< 100 ug/Kg
Vinyl Chloride/Chloroethene	< 5 0 ug/Kg
Xylenes (Total)	< 5 0 ug/Kg
COMMENTS Analyzed by GC/MS Analytical Services, Inc	at Continental

#### Sample No 92-6928

< 100 ug/L < 50 ug/L

< 50 ug/L

< 100 ug/L

Reported to DAVID MOSBY

Affiliation SPFD

Date 9/02/92

Project Code 3658/3000

Sample Description
SUNDSTRAND SITE (MODINE HEAT TRANSFER)
CAMDENTON, MO , GRAB OF MW #1

Collected by DAVID MOSBY Affiliation SPFD

2-Butanone

4-Methyl-2-Pentanone

2-Hexanone

Acetone

Date 07/30/92

PARAMETERS		RESULTS			
TEMPERATURE COMMENTS	ANALYZED IN FIELD	16 9 DEGREES C			
pH COMMENTS	ANALYZED IN FIELD	9 8			
SPECIFIC CONDUC		219 umhos/cm			
1,1,1-Trichloro 1,1,2,2-Tetrach 1,1,2-Trichloro 1,1-Dichloroeth 1,1-Dichloroeth 1,2-Dichloroeth 1,2-Dichloroeth 1,2-Dichloroeth	loroethane ethane ane ylene ane ene (Total)	< 5 0 ug/L < 5 0 ug/L			

Page 2 Sample no 92-6928 Date 9/02/92

PARAMETERS			RESULTS		
Benzene		<	5	0	ug/L
Bromodichloromethane		<	5	0	ug/L
Bromoform		<	5	0	ug/L
Bromomethane		<	5	0	ug/L
Carbon Disulfide		<	5	0	ug/L
Carbon Tetrachloride		<	5	0	ug/L
Chlorobenzene		<	5	0	ug/L
Chloroethane		<	5	0	ug/L
Chloroform		<	5	0	ug/L
Chloromethane		<	5	0	ug/L
cis-1,3-Dichloropropene					ug/L
Dibromochloromethane		<	5	0	ug/L
Ethylbenzene					ug/L
Methylene Chloride		<	5	0	ug/L
Styrene		<	5	0	ug/L
Tetrachloroethene		<	5	0	ug/L
Toluene		<	5	0	ug/L
trans-1,3-Dichloropropene					ug/L
Trichloroethene					ug/L
Vinyl Acetate					ug/L
Vinyl Chloride/Chloroethene					ug/L
Xylenes (Total)					ug/L
COMMENTS Analyzed by GC/MS	at				J
Analytical Services, Inc					

# ENVIRONMENTAL SERVICES PROGRAM RESULT OF SAMPLE ANALYSIS

Sample No 92-6930

Reported to DAVID MOSBY Date 9/02/92 Affiliation SPFD Project Code 3658/3000

Sample Description
SUNDSTRAND SITE (MODINE HEAT TRANSFER)
CAMDENTON, MO , RINSATE BLANK OF PUMP AND HOSE

**PARAMETERS** 

Chlorobenzene

Chloroethane Chloroform

Collected by DAVID MOSBY Date 07/30/92 Affiliation SPFD

RESULTS

< 5 0 ug/L

< 5 0 ug/L

< 5 0 ug/L

1,1,1-Trichloroethane	<	5 0 ug/L
1,1,2,2-Tetrachloroethane	<	5 0 ug/L
1,1,2-Trichloroethane	<	5 0 ug/L
1,1-Dichloroethane	<	5 0 ug/L
1,1-Dichloroethylene	<	5 0 ug/L
1,2-Dichloroethane	<	5 0  ug/L
1,2-Dichloroethene (Total)		5 0 ug/L
1,2-Dichloropropane		5 0 ug/L
2-Butanone		100  ug/L
2-Hexanone		50 ug/L
4-Methyl-2-Pentanone		50  ug/L
Acetone		100  ug/L
Benzene		5 0  ug/L
Bromodichloromethane		5 0 ug/L
Bromoform		5 0 ug/L
Bromomethane		5 0  ug/L
Carbon Disulfide		5 0 ug/L
Carbon Tetrachloride	<	5 0 ug/L

Page 2 Sample no 92-6930 Date 9/02/92

PARAMETERS	RI	ESULTS
Chloromethane		0 ug/L
cis-1,3-Dichloropropene	< 5	0 ug/L
Dibromochloromethane	< 5	0 ug/L
Ethylbenzene	< 5	0 ug/L
Methylene Chloride	< 5	0 ug/L
Styrene	< 5	0 ug/L
Tetrachloroethene	< 5	0 ug/L
Toluene	< 5	0 ug/L
trans-1,3-Dichloropropene	< 5	0 ug/L
Trichloroethene	< 5	0 ug/L
Vinyl Acetate		00 ug/L
Vinyl Chloride/Chloroethene	< 5	0 ug/L
Yylenes (Total)	< 5	0 ug/L
LOMMENTS Analyzed by GC/MS		
Analytical Services, Inc		

# ENVIRONMENTAL SERVICES PROGRAM RESULT OF SAMPLE ANALYSIS

Sample No 92-6931

 $< 100 \, ug/L$ 

< 50 ug/L < 50 ug/L

< 100 ug/L

Reported to DAVID MOSBY

Affiliation SPFD

Date 9/02/92

Project Code 3658/3000

Sample Description

SUNDSTRAND SITE (MODINE HEAT TRANSFER) CAMDENTON, MO, GRAB OF MW #2

Collected by DAVID MOSBY Affiliation SPFD

2-Butanone

2-Hexanone

Acetone

4-Methyl-2-Pentanone

Date 07/31/92

PARAMETERS		RESULTS
TEMPERATURE COMMENTS	ANALYZED IN FIELD	16 0 DEGREES C
pH COMMENTS	ANALYZED IN FIELD	7 5
SPECIFIC CONDUC COMMENTS		831 umhos/cm
1,1,1-Trichlord 1,1,2,2-Tetrach 1,1,2-Trichlord 1,1-Dichloroeth 1,1-Dichloroeth 1,2-Dichloroeth 1,2-Dichloroeth 1,2-Dichloropto	nloroethane Dethane Dane Dane Dane Dene (Total)	<pre>&lt; 5 0 ug/L &lt; 5 0 ug/L</pre>

Page 2 Sample no 92-6931 Date 9/02/92

PARAMETERS			RESULTS
Benzene Bromodichloromethane Bromoform Bromomethane Carbon Disulfide Carbon Tetrachloride Chlorobenzene Chloroethane		< < < < <	5 0 ug/L 5 0 ug/L
Chloroform Chloromethane		<	5 0 ug/L 5 0 ug/L 5 0 ug/L
Cis-1,3-Dichloropropene Dibromochloromethane Ethylbenzene		< <	5 0 ug/L 5 0 ug/L
Methylene Chloride Styrene Tetrachloroethene		<	5 0 ug/L 5 0 ug/L 5 0 ug/L
Toluene trans-1,3-Dichloropropene		< <	5 0 ug/L 5 0 ug/L
Trichloroethene Vinyl Acetate Vinyl Chloride/Chloroethene		<	5 0 ug/L 100 ug/L 5 0 ug/L
Xylenes (Total) COMMENTS Analyzed by GC/MS Analytical Services, Inc	at	<	5 0 ug/L

# ENVIRONMENTAL SERVICES PROGRAM RESULT OF SAMPLE ANALYSIS

Sample No 92-6932

Reported to DAVID MOSBY Affiliation SPFD

Date 9/02/92 Project Code 3658/3000

Sample Description
SUNDSTRAND SITE (MODINE HEAT TRANSFER)
CAMDENTON, MO, GRAB OF SOIL
NEAR BOREHOLE MW #1 FROM O-3 INCHES

Collected by DAVID MOSBY Affiliation SPFD

Date 07/31/92

# PARAMETERS

		RI	ESI	ULTS
	_	_	_	/-

1,1,1-Trichloroethane	<	5 0	ug/Kg
1,1,2,2-Tetrachloroethane	<	5 0	ug/Kg
1,1,2-Trichloroethane	<	5 0	ug/Kg
1,1-Dichloroethane	<	5 0	ug/Kg
1,1-Dichloroethylene	<	5 0	ug/Kg
1,2-Dichloroethane	<	5 0	ug/Kg
1,2-Dichloroethene (Total)	<	5 0	ug/Kg
1,2-Dichloropropane	<	5 0	ug/Kg
2-Butanone	<	100	ug/Kg
2-Hexanone	<	50	ug/Kg
4-Methyl-2-Pentanone	<	50	ug/Kg
Acetone	<	100	ug/Kg
Benzene	<	5 0	ug/Kg
Bromodichloromethane	<	5 0	ug/Kg
Bromoform	<	5 0	ug/Kg
Bromomethane	<	5 0	ug/Kg
Carbon Disulfide	<	5 0	ug/Kg
Carbon Tetrachloride	<	5 0	ug/Kg
Chlorobenzene	<	5 0	ug/Kg
Chloroethane			ug/Kg

Page 2 Sample no 92-6932 Date 9/02/92

PARAMETERS		RE	ESU	<u>JLTS</u>
Chloroform	<	5	0	ug/Kg
Chloromethane	<	5	0	ug/Kg
cis-1,3-Dichloropropene	<	5	0	ug/Kg
Dibromochloromethane	<	5	0	ug/Kg
Ethylbenzene	<	5	0	ug/Kg
Methylene Chloride	<	5	0	ug/Kg
Styrene	<	5	0	ug/Kg
Tetrachloroethene	<	5	0	ug/Kg
Toluene	<	5	0	ug/Kg
trans-1,3-Dichloropropene	<	5	0	ug/Kg
Trichloroethene	<	5	0	ug/Kg
Vinyl Acetate	<	10	00	ug/Kg
<pre>Jinyl Chloride/Chloroethene</pre>				ug/Kg
Xylenes (Total)	<	5	0	ug/Kg
COMMENTS Analyzed by GC/MS at Analytical Services, Inc	Continent	:a]	L	



#### **MEMORANDUM**

DATE

September 8, 1998

TO

Gary Behrns Chief

Superfund Section Hazardous Waste Program

**FROM** 

Arthur H Groner Chief
Permits Section Hazardous Waste Program

SUBJECT Former Hulett Lagoon Camdenton Missouri

The Hazardous Waste Program Permits Section is referring the former Hulett Lagoon in Camdenton, Missouri, to the Hazardous Waste Program Superfund Section. The Hulett Lagoon was operated by the City of Camdenton from 1961 to 1988. The City of Camdenton is the current owner of the property. The lagoon is located on the east side of Dawson Road, and is approximately 1/4 mile northeast of Modine Manufacturing Company (Modine). It received process wastewater from Modine's predecessors. Dawson Metal Products from 1967 to 1972 and Sundstrand Tubular Products from 1972 to 1986. Wastewater from the facility contained volatile organic compounds (VOCs) cyanide, and various metals. In addition to receiving wastewater from the facility, the lagoon also received domestic sewage from the surrounding residences. A dye trace study of the City of Camdenton's sewer system performed by the Division of Geology and Land Survey (DGLS) on August 5, 1998, verified that facility wastewater mixes with domestic sewage prior to entering city property. Therefore, the domestic sewage exemption of 40 CFR 261.4 most likely applied during the facility's operating discharges.

Closure of the Hulett Lagoon was completed in 1988 by the City of Camdenton pursuant to an Industrial Development Grant overseen by the Missouri Department of Natural Resources Water Pollution Control Program (WPCP) Sampling and analysis of the sludge was limited to metals and total solids. High levels of chromium, lead, and nickel were detected in the sludge. The sludge from the lagoon was removed and applied on

Memo to Gary Behrns Chief September 8, 1998 Page 2

the runways at the municipal airport. The lagoon berms were turned in and mixed with the surrounding soil. The domestic sewage exemption of 40 CFR 261.4 may have applied to the wastewater discharge but is not applicable to the sludges applied on the airport runways. The lagoon closure was not designed to meet the substantive requirements of the Hazardous Waste Management Law relative to corrective action. At the time of closure, no sampling and analysis for VOCs or cyanide were performed, and the horizontal and vertical extent and rate of migration of contamination in environmental media associated with the lagoon were not determined during the 1988 lagoon closure process. Hence, the sludge sampling performed was not sufficient for RCRA determinations.

Modine has four on-site groundwater monitoring wells and one off-site well located at the southwest edge of the Hulett Lagoon. Based on potentiometric maps and a bedrock fracture system study, prepared by Dames & Moore consultants for Modine, the groundwater flow direction is to the southwest. Sampling results from one of the on-site wells (MW-4) and the off-site well (MW-5) have shown levels of trichloroethene (TCE) at 173 parts per billion (ppb) and 484 ppb, respectively. The Environmental Services Program (ESP) sampled a residential well on April 23. 1998 located across the street from the facility and down gradient of monitoring well MW-5. TCE was detected in this well at 210 ppb.

TCE was also detected in the City of Camdenton's Mulberry Well as high as 6 3 ppb, which is above the EPA Maximum Contaminant Level (MCL) of 5 ppb. The Mulberry Well is located approximately 1/4 mile east of Modine and ½ mile southeast of the Hulett Lagoon. The Mulberry Well was the city s highest volume producing well. The well is drilled to a total depth of 900 ft below ground surface (bgs) and has a maximum pumping rate of 600 gallons per minute (gpm). The city has taken the Mulberry Well off line and is in the process of drilling a new well.

The city has been monitoring the Mulberry Well monthly and the two remaining municipal wells quarterly since February 1998. The two remaining wells have been non detect for TCE and all other constituents. During the last sampling event, the city sampled a residential well located southwest of the municipal airport. TCE was detected in this well at 13.1 ppb. Current speculation is that the contamination in this well may have been caused by the application of sludge from the Hulett Lagoon on the airport runways.

Due to the close proximity of the Hulett Lagoon and Modine Manufacturing Company and the nature of the groundwater contamination close coordination between the Superfund Section, the Permits Section the Enforcement Section Public Drinking Water Program Jefferson City Regional Office, and the Division of Geology and Land

Memo to Gary Behrns, Chief September 8 1998 Page 3

Survey will be necessary If you have any questions or require additional information regarding this matter, please contact Chris Kump, of my staff, at 751-3068

# AHG ckm

 c Lyle Crocker, HWP-Enforcement Section Robert Hentges, JCRO
 Cindy Kemper HWP-Director's Office Ed Knight, WPCP
 Terry Timmons PDWP
 Diana Travis DGLS
 Shelley Woods AGO bc Christine Kump, HWP
John Jurgensmeyer HWP

# **OB MISSOURI** NT OF NATURAL RESOURCES

DIVISION OF ENVIRONMENTAL QUALITY PO Box 176 Jefferson City MO 65102 0176

#### **MEMORANDUM**

DATE

March 24 1999

TO

Gary Behrns Chief

Superfund Section, Hazardous Waste Program

THROUGE Arthur H Groner Chief

Permits Section Hazardous Waste Program

**FROM** 

Christine M Kump Environmental Engineer

Permits Section Hazardous Waste Program

SUBJECT

Clarification on Referral Memo - Former Hulett Lagoon Camdenton

Missouri

Valerie Wilder, Environmental Specialist, Superfund Section requested I clarify a sentence located in paragraph two of the referral memo sent to you dated September 8 1998 (please see attached letter)

The sentence Ms Wilder requested clarification on reads "The domestic sewage" exemption of 40 CFR 261 4 may have applied to the wastewater discharge but is not applicable to the sludges applied on the runways " In consultation with Shelley Woods AGO and other members of the corrective action team prior to writing the referral memo we concluded that Superfund's CERCLA authority would be more inclusive and have stronger support to require action should hazardous constituents be found at or near the runway The corrective action team felt CERCLA's authority would be more defensible in litigation since CERCLA is authorized to pursue hazardous constituents regardless of whether the waste was or is an exempt RCRA hazardous waste

CMK sw

Attachment

# Combined Preliminary Assessment/Site Inspection Sampling Report

10

Former Hulett Lagoon Site Camdenton, Missouri Camden County

Field Activities Conducted January 6-7, 1999 January 21, 1999

Prepared For:

Missouri Department of Natural Resources Division of Environmental Quality Hazardous Waste Program

Prepared By.

Missouri Department of Natural Resources Division of Environmental Quality Environmental Services Program

# **Table of Contents**

1.0	Introduction	I
2.0	Site Information	1
	2.1 Location	1
	2.2 Description	1
	2.3 History/Contaminants of Concern	2
3.0	Methods	
	3.1 General Field Procedures	
	3.2 Groundwater Sampling	
	3.2.1 Residential well/Municipal well samples	
	3.2.2 Monitoring well samples	
	3.3 Soil Sampling	
	3.4 Sample Quantity	
	3.5 Analyses Requested	
	3.6 Chain of Custody	
4.0	Data Quality	
1.0	4.1 Field Methods	
	4.2 Field Decontamination	
	4.3 Quality Assurance/Quality Control Samples	
	4.3.1 Trip blank	
	4.3.2 Duplicate samples (waters)	
	4.3.3 Replicate sample (soil)	
5.0	Investigation Derived Wastes (IDW)	
6.0	Observations	
0.0	6.1 General	
	6.2 Groundwater Sampling	
	6.3 Soil Sampling	
7.0	Analytical Results	
7.0	Allarytical Results	>
A ttoo	hmentslocated at the back of docume	ant
Allac	Tables	CIII
	Table 1 – Sample Listing Table 2 – GPS Data Points	
	Table 3 – Monitoring Well Data	
	Appendix A – Site Maps	
	Appendix B – MIP Data Logs	
	Appendix C – Analytical Results	

#### 1.0 Introduction

As authorized under the federal Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA) and the Superfund Amendments and Reauthorization Act of 1986, the Missouri Department of Natural Resources (MDNR), Hazardous Waste Program (HWP), Site Evaluation Unit is conducting a combined preliminary assessment/site inspection (PA/SI) on the Former Hulett Lagoon site. The MDNR, HWP requested the MDNR, Environmental Services Program (ESP) prepare and implement a sampling plan as part of the combined PA/SI.

Initially, the Former Hulett Lagoon site consisted of two separate areas of concern. After field activities associated with both areas were complete, HWP personnel requested the site be split into two separate sites, each with its own sampling report. This report covers field activities conducted in association with the actual former Hulett lagoon. A separate report has been prepared which covers field activities associated with the newly established "Camdenton Sludge Disposal Area" site.

Field activities were conducted throughout the month of January. Initial groundwater sampling was conducted on January 6-7, 1999. A soil sampling investigation was conducted on January 21, 1999. ESP personnel involved with the various field activities included Environmental Specialists Brian Allen, Ken Hannon, and Doug Thompson. HWP Environmental Specialist Valerie Wilder was present during all field activities conducted. Information learned from field observations and sampling will be used by the HWP in scoring the site's potential as a hazardous waste site under the CERCLA Hazard Ranking System.

#### 2.0 Site Information

#### 2.1 Location

The Former Hulett Lagoon site is located just east of Dawson Road in Camdenton, MO, approximately ¼ mile northeast of the Modine Manufacturing Company facility. The legal description of the former lagoon is SW ¼ SW ¼ Sec. 24, T. 38 N., R. 17 W.

### 2.2 Description

The Former Hulett Lagoon site is on property owned by the City of Camdenton. The former lagoon is located in a mixed residential/industrial area. The lagoon, closed since 1989, has been vegetated and is generally flat with remnants of the former berm still visible. Surface runoff from this area flows to the northwest and enters a nearby intermittent drainage that travels to the west.

# 2.3 History/Contaminants of Concern

The former Hulett lagoon was one of five lagoons operated by the City of Camdenton prior to the construction of a municipal wastewater treatment plant. The lagoon was in operation from 1961 until approximately 1988, when the City of Camdenton began closure. In addition to municipal wastes, the Hulett lagoon also received wastes generated from a nearby manufacturing facility (discussed below).

In 1967, Dawson Metal Products built a manufacturing facility located approximately ¼ mile southwest of the Hulett lagoon and began operations. Sundstrand Tubular Products purchased the facility in 1972 and continued operations until 1990, when it was purchased by Modine Heat Transfer, Inc., a wholly owned subsidiary of Modine Manufacturing Company. Modine Manufacturing Company currently owns and operates the facility.

From 1967 to the present, manufacturing operations at this facility have consisted of producing air conditioning coils and feeder parts from aluminum and copper tubing, which have included electroplating and the use of solvents. Prior to the construction of the municipal wastewater treatment plant or any facility pretreatment processes, wastes generated from the facility were discharged, in part at least, to the nearby Hulett lagoon.

The primary contaminants of concern at the site include metals and solvents associated with the manufacturing processes from this facility. Specific metals of concern include copper, chromium, lead, and nickel. Various solvents have been used at the facility, including the primary contaminant of concern for this investigation, trichloroethene (TCE). TCE was reportedly used beginning in the early 1970s and continuing to December 1990. It is likely TCE wastes generated at the facility would have been present in the wastestream discharged to the Hulett lagoon.

As part of the Hulett lagoon closure, the city received approval from MDNR to land apply lagoon sludge to an area immediately south of the Camdenton Airport runway currently identified by the MDNR as the Camdenton Sludge Disposal Area site. Information indicates sampling of the sludge was apparently limited to determining the levels of metals prior to approving the disposal method and that no analyses were conducted for the presence of any volatile organic compounds The lagoon closure was completed in 1989

A preliminary assessment and site inspection were conducted of the manufacturing facility property in 1992, which did not include any off-site investigations of the former lagoon or sludge disposal area. Investigations at that time confirmed the presence of chlorinated solvents, including TCE, in the soils and groundwater. Contamination at the facility is likely a result of historic waste handling practices and spills.

The facility is currently negotiating a Corrective Action Abatement Order on Consent through the Resource Conservation and Recovery Act (RCRA) Unit of the MDNR, HWP. As a result of a specific RCRA exclusion, the current and future RCRA work at the manufacturing facility will not include any investigation of or relating to the former lagoon. Investigation of the former lagoon and sludge disposal area must be conducted under CERCLA authority

In March 1993, 2.1 parts per billion (ppb) TCE were detected in a City of Camdenton municipal well, known as the Mulberry Well, which is located near the manufacturing facility. TCE has consistently been detected in this municipal well since 1997 at levels reaching a high of 11.8 ppb. At least one private well, located directly north of the facility, has been shown to contain TCE at 210 ppb.

The MDNR, HWP has extensive file information on the manufacturing facility and the lagoon closure, which should be referenced for a more comprehensive review of historic regulatory activities.

#### 3.0 Methods

#### 3.1 General Field Procedures

A health and safety briefing was conducted on-site and personnel read and signed the site-specific health and safety plan prior to initiating field activities.

Missouri One-Call was notified of proposed field activities prior to ESP personnel arriving onsite, and all applicable underground utilities marked.

Field instruments. including a photoionization detector (PID), pH, specific conductivity, and temperature meters were calibrated on-site following manufacturers' specifications.

ESP personnel employed established standard operating procedures for the collection of various samples. Containers for each sample were filled based upon the volatility of the analytes of concern with the most volatile analytes being collected first. All samples were collected in certified-clean containers and preserved in the field as appropriate.

ESP personnel collected depth-discrete soil grab samples in selected source areas and groundwater samples from selected private wells, municipal/public wells, and monitoring wells in an effort to determine the types of hazardous wastes which may be present, whether a hazardous substance release has occurred to the environment, and whether the substances have impacted, or may impact, human health and/or the environment. Background samples were also collected of each media sampled from areas that would not appear to be impacted from the site.

An ESP global positioning system (GPS) unit was taken to the field and used to determine the geographic coordinates of each sample location. All sample locations and descriptions were noted in a bound field logbook and locations noted on a site map.

# 3.2 Groundwater Sampling

Specific conductivity, pH, and temperature were determined for each sample at the time of collection. In addition, turbidity was determined on each sample collected from monitoring wells that was submitted for metals analyses. Personnel attempted to gain pertinent information on each well sampled (age, construction, depth, casing length, screened interval, location of tap, etc.) and record such into the field logbook.

Groundwater grab samples were collected of the City of Camdenton's Mulberry and Blair municipal wells, monitoring wells located on the current Modine Manufacturing Company facility and adjacent to the former lagoon, a private well located immediately north of the facility, and a private well considered to be located downgradient of the former lagoon area.

# 3.2.1 Residential well/Municipal well samples

In general, samples were collected from taps nearest the well heads after opening the tap at a high flow for approximately five minutes. Sample containers were then filled directly from the taps at a low flow.

#### 3.2.2 Monitoring well samples

Samples were collected by first laying clean plastic sheeting on the ground around each well casing. Personnel then accessed each well and determined the total depth (or referred to well logs) and depth to water, then calculated one well volume. A clean or field decontaminated 2-inch submersible pump using clean food-grade polyethylene tubing or a clean, disposable Teflon® or polyethylene bailer, with clean rope, were used to evacuate one well volume (at a low flow if the pump was used). Personnel determined water quality parameters (pH. specific conductivity, and temperature) and evacuation continued until one of three criteria was met: 1) water quality parameters stabilized (pH within 0.1 units, temperature and specific conductivity within 10%) between two consecutive evacuations; 2) three well volumes were removed; or, 3) the well was evacuated dry.

In the event the well was determined to be going dry, a grab sample was collected as soon as the well had recharged sufficiently. Otherwise, once evacuation was complete, the sample was collected by gently lowering a bailer to the bottom of the well and retrieving water back to the surface. A clean, disposable, volatile organic compound (VOC) bottom-emptying device was used to transfer water directly to sample containers.

## 3.3 Soil Sampling

A membrane interface probe (MIP) was employed to generate soil gas data of the subsurface within and surrounding the boundaries of the former lagoon area. The soil gas data was used, in part, to determine actual sampling locations.

Soil grab samples were collected from discrete depths utilizing a track-mounted hydraulic soil probe. Clean disposable acetate liners were used in conjunction with the soil probe and inserted into stainless steel macro core samplers fitted with clean cutting shoes. The core samplers were advanced to the desired sampling depth via push tubes and the samplers and soil retrieved. The acetate liners were removed and cut open exposing the soil. Personnel immediately collected soils to be submitted for volatile organics analyses with clean EnCore® sampling devices (two 5gm aliquots). An additional aliquot for volatile organics analyses was collected in a 2-oz glass jar, as a backup. Soils to be submitted for the additional analytes of concern were transferred with clean stainless steel spoons to clean aluminum foil pans, homogenized, then placed into appropriate sample containers.

# 3.4 Sample Quantity

A total of nine soil grab samples and 13 water grab samples were collected during field activities associated with the Former Hulett Lagoon site and submitted to the ESP laboratory for analyses. These sample numbers include quality assurance/quality control samples. Refer to Table 1 for a listing of all samples collected.

### 3.5 Analyses Requested

Based on the history of the site and HWP data needs, the following analyses were requested. All water grab samples and soil grab samples were submitted for volatile organics and total metals (As, Ba, Cr, Cd, Cu, Pb, Ni, Hg, Se, Ag) analyses. Water grab samples of monitoring wells were also submitted for dissolved metals (same metals as above) analyses. Instructions were relayed to analytical personnel that if a sample's total analyte results were 80% of twenty times the Toxicity Characteristic Leaching Procedure (TCLP) regulatory limit, TCLP analysis was to be performed on that sample. Additionally, drinking water detection limits were requested for the public and private well samples, as well as any monitoring well samples, where no contaminants were observed above the standard practical quantitation limits.

### 3.6 Chain of Custody

All samples received a numbered label and the corresponding number was entered onto a chain of custody form indicating the location, date and time of collection, and analytes requested. Samples were stored and transported on ice in coolers. ESP field personnel maintained custody of the samples until relinquishing them to a sample custodian at the state's environmental laboratory within the Environmental Services Program in Jefferson City for analyses.

## 4.0 Data Quality

To help ensure precise, accurate, representative, complete, and comparable data were achieved, all field work and analyses were conducted in accordance with the Fiscal Year 1999 Quality Assurance Project Plan for Pre-Remedial Site Assessments dated August 14, 1998. Unless otherwise noted, ESP field personnel utilized standard operating procedures established within the ESP, Field Services Section for all samples collected.

#### 4.1 Field Methods

Clean disposable nitrile gloves were worn by sampling personnel and clean equipment utilized for each separate sample collected to minimize the possibility of cross-contamination.

Field personnel noted all observations, sample locations, descriptions, and methods in a bound field logbook.

#### 4.2 Field Decontamination

Field decontamination of sampling equipment was not required during the sampling event.

## 4.3 Quality Assurance/Quality Control Samples

### 4.3.1 Trip blank

One trip blank was submitted for the sampling event. The trip blank was taken to the field and accompanied water grab samples collected and transported back to the ESP laboratory. The trip blank received a numbered label, was entered onto the chain-of-custody form, and submitted for volatile organics analyses.

#### 4.3.2 Duplicate samples (waters)

Two duplicate water grab samples were collected/submitted for the sampling event. The duplicate samples were collected at the same location and time as their respective true samples, using similar technique and equipment. Each duplicate sample received a numbered label, was entered onto the chain-of-custody form, and submitted for the same analytes as their respective true samples.

#### 4.3.3 Replicate sample (soil)

One replicate soil grab sample was collected/submitted for the sampling event. The replicate sample was collected by dividing the true sample evenly into two separate samples and submitting each for laboratory analyses. The portion of each true/replicate sample pair submitted for volatile organics was not homogenized prior to collection. The remaining soil was homogenized prior to splitting the true sample into two samples. The replicate sample received a numbered label, was entered onto the chain-of-custody form, and submitted for the same analytes as its true sample.

# 5.0 Investigation Derived Wastes (IDW)

Efforts were made to minimize IDW generation. IDW included soil, aqueous liquids (groundwater), disposable sampling equipment, and disposable personal protective equipment (PPE).

Field personnel returned unused soils to their source immediately after generation. IDW generated during private and public well evacuation was discharged to the ground. IDW generated during monitoring well evacuations was containerized and discharged to the Modine Manufacturing Company's pretreatment wastewater system. Disposable PPE and disposable sampling equipment were handled as solid waste, containerized, and properly disposed.

#### 6.0 Observations

#### 6.1 General

A significant snow event occurred on January 2, 1999. As a result of the snow-cover diminishing ground visibility and equipment access, field activities conducted on January 6-7, 1999, were limited to the collection of groundwater samples only. The weather on January 6, 1999, was sunny and approximately 30 degrees Fahrenheit with winds light and variable. The weather on January 7, 1999, was overcast and approximately 10 degrees Fahrenheit with winds light and variable.

Personnel returned to the site on January 21, 1999, once snow had melted, to conduct the soil/source investigation and sampling. The weather on January 21, 1999, was overcast and ranged from 40 to 45 degrees Fahrenheit with winds light and variable Light, intermittent rains occurred throughout the day.

GPS coordinates of all sampling points were post-processed at ESP and entered onto a map of the site. Refer to Table 2 for a listing of all sampling point coordinates and Appendix A for the locations of all samples collected.

# 6.2 Groundwater Sampling

As to not interfere with any planned investigations under the RCRA Corrective Action Abatement Order, work conducted on the Modine Manufacturing facility property was limited to collecting groundwater samples from monitoring wells located on the facility property (no soil investigations were conducted on the Modine Manufacturing property).

Personnel were required to make adjustments to the monitoring well sampling procedures due to the considerable depths of the monitoring wells (depths ranged from 161 to 197 feet) and well diameters. Due to the significant well depths, personnel were not able to accurately field-determine the depth of each well and, instead, relied upon well logs to determine the total depths

of several wells. As a result of the considerable well volumes associated with the 4-inch monitoring wells, personnel recorded water quality parameters at timed intervals, instead of after each well volume, to determine when the parameters were stable and acceptable to collect a sample. This procedure minimized the volume of evacuation water which was generated. Personnel ensured water quality parameters had stabilized in each well prior to sample collection.

An obstruction in the well casing was encountered in monitoring well (MW-) 2, a two-inch well installed by MDNR, at the approximate 150 foot depth, which did not allow personnel to extend the submersible pump to the screened depth for evacuation. Personnel were able to reach the bottom of the well with a clean, disposable bailer and clean rope, which was used to complete evacuation and sampling.

With HWP personnel's knowledge and permission, ESP collected two grab samples for volatile organics analyses from MW-4 to tentatively compare the effects varying collection methods have on analytical results. One sample (991461) was collected using the submersible pump and the second sample (991462) was collected using a bailer. There were no apparent significant discrepancies noted in the analytical results of the two samples that could be attributed to the collection methods.

MW-3 was evacuated dry after approximately 20 gallons were removed (1 well volume was calculated to be 11 gallons). Therefore, the well was allowed to recharge sufficiently, and the grab sample was collected with a bailer.

ESP personnel collected two sets of 40-ml vials for volatile organics analyses on all water grab samples collected on January 6-7, 1999. The first set of vials in each sample was submitted for volatile organics analyses using the standard practical quantitation limits for water samples (as specified in the QAPP). Per a request from HWP, in the event contaminant levels in a given sample were low enough, the second set of vials was analyzed to realize the lower drinking water detection limits.

All samples collected from public and private wells were noted to be clear and colorless. The descriptions of samples collected from monitoring wells were noted as follows (turbidity was determined in the field and is reported in nephelometric units (NTUs)). There were no separate, free-phase liquids noted in any of the water grab samples.

MW-1	Slightly cloudy (143 NTUs) and light white in color.
MW-2	Cloudy (372 NTUs) and light white in color.
MW-3	Cloudy (951 NTUs) and light reddish-brown in color.
MW-4	Slightly cloudy (86.6 NTUs) and light brown in color.
MW-5	Cloudy (456 NTUs) and transparent white in color.

Refer to Table 3 for monitoring well information.

### 6.3 Soil Sampling

During the MIP investigation and soil sampling, personnel generally encountered refusal at depths ranging from five to six feet at the former lagoon. A total of ten MIP borings were performed in and around the former lagoon during the field activities. Samples were collected from specific MIP locations based upon the soil gas data generated and the boring locations relative to the areas of concern. Soil samples collected were generally noted to consist of reddish-brown cherty clays with varying amounts of gravel interspersed. Due to the nature of the matrix, sample homogenization was difficult.

Personnel unsuccessfully attempted to collect depth-discrete sediment/soil samples of the intermittent drainage which receives surface drainage from the former lagoon area (as proposed in the sampling plan). Due to the gravel/rock matrix of the drainage bed, no adequate samples could be collected.

Refer to Appendix B for the MIP data logs generated for each boring and the site map for the MIP boring and soil sampling locations. The logs indicate detections noted on the MIP's PID, identified as "Detector 1" and the flame ionization detector "Detector 2".

### 7.0 Analytical Results

The analytical results of samples collected are attached as Appendix C.

Submitted by:

Brian J. Allen/

Environmental Specialist Superfund/RCRA Unit

**Environmental Services Program** 

Date:

3/12/99

Approved by:

James H. Long

Director

Environmental Services Program

JHL:bac

c: Valerie Wilder, Environmental Specialist, HWP Robert Hentges, Regional Director, JCRO TABLES Former Hulett Lagoon Site Camdenton, Missouri

Table I Former Hulett Lagoon Site Sample Listing

Sample #	Sample Media/Type	Location Collected	Date/Time Collected
991450	QA/QC sample (Trip blank)	ESP laboratory	1/5/99
991451	Water grab	Paul Buckwalter residential well (Box 45A Normac Estates, Camdenton, MO), located apparently downgradient of the former Hulett Lagoon approximately 2 miles. Sample collected after approximately 5 minutes evacuation.	1/6/99 @ 1025
991452	Water grab	Dave Burnau residential well (178 Sunset Drive, Camdenton, MO), located directly north (across the street) of Modine Manufacturing Sample collected after approximately 5 minutes evacuation time.	1/6/99 @ 1105
991453	QA/QC sample (Duplicate)	Duplicate sample of 991452	1/6/99 @ 1105
991458	Water grab	City of Camdenton municipal well #4 (AKA "Blair" well) Sample collected after approximately 5 minutes evacuation time	1/6/99 @ 1305
991459	Water grab	City of Camdenton municipal well known as the "Mulberry" well Sample collected after approximately 5 minutes evacuation time	1/6/99 @ 1325
991460	Water grab	Monitoring well (MW-) 3, located on the south edge of the Modine Manufacturing facility lot, southwest of the facility building	1/6/99 @ 1530
991461	Water grab	MW-4, located at the main entrance to Modine Manufacturing All sample analytes collected using a submersible pump.	1/6/99 @ 1650
991462	Water grab	MW-4. Sample submitted for volatile organics analyses and collected with a bailer. Sample was collected to compare results with 991461 analytical results for volatile organics.	1/6/99 @ 1720
991463	Water grab	MW-2, located on the northeast side of the Modine Manufacturing facility building Sample was collected with a bailer.	1/7/99 @ 0940
991464	Water grab	MW-1, located in the western gravel parking lot of the Modine Manufacturing facility property. Sample was collected with a bailer.	1/7/99 @ 1100
991465	Water grab	MW-5, located adjacent, southwest edge, of the former Hulett Lagoon. Sample was collected with a bailer.	1/7/99 @ 1230
991466	QA/QC sample (Duplicate)	Duplicate sample of 991465.	1/7/99 @ 1230
991467	Soil grab	Boring "Hulett-03", collected from the 3-4 ft depth.	1/21/99 @ 1030
991468	Soil grab	Boring "Hulett-03", collected from the 4.5-5.5 ft depth.	1/21/99 @ 1045
991469	Soil grab	Boring "Hulett-01", collected from the 4 5-5 ft depth	1/21/99 @ 1135
991470	Soil grab	Boring "Hulett-02", collected from the 6 5-7 ft depth.	1/21/99 @ 1205
991471	Soil grab	Boring "Hulett-04", collected from the 7.5-8 ft depth.	1/21/99 @ 1355
991472	Soil grab	Boring "Hulett-07", collected from the 5.5-6 ft depth.	1/21/99 @ 1450
991473	Soil grab	Boring "Hulett-09", collected from the 6-7 ft depth	1/21/99 @ 1605
991474	QA/QC sample (Replicate)	Replicate sample of 991473	1/21/99 @ 1605
991475	Soil grab	Boring "Hulett-10", collected from the 10 5-11 ft depth	1/21/99 @ 1630

Table 2
Former Hulett Lagoon Site A
GPS Data Points


GPS	Location/	Location/ Latitude Longitude	ArcView Data Points (UTM)		
Identification	Description	(Degrees N)	(Degrees W)	Easting	Northing
A010619A	"Blair" municipal well	+38 001726°	-92.760299°	521045	4206034
A010619B	"Mulberry" municipal well	+38.008235°	-92.754798°	521526	4206757
A010620A	MW-3 Modine Mfr.	+38.008161°	-92.757634°	521277	4206748
A010623A	MW-4 Modine Mfr.	+38 009836°	-92.757792°	521262	4206934
A010714A	MW-2 Modine Mfr.	+38.009324°	-92.756490°	521377	4206877
A010716A	MW-1 Modine Mfr	+38.009287°	-92 758428°	521207	4206873
A010717A	MW-5 Former lagoon	+38.011261°	-92.755284°	521482	4207093
A010617A	Burnau residential well	+38 010320°	-92.757711°	521269	4206988
A010519A	Buckwalter residential well	+38 000833°	-92.786944°	521269	4206988
A012115A	Boring "Hulett 01"	+38 011315°	-92 755011°	521506	4207099
A012115B	Boring "Hulett 02"	+38.011403°	-92 754850°	521520	4207109
A012116A	Boring "Hulett 03"	+38.011508°	-92 754867°	521519	4207120
A012119A	Boring 'Hulett 04"	+38.011421°	-92.754655°	521496	4207096
A012120A	Boring "Hulett 05"	+38.011291°	-92.755130°	521495	4207109
A012120B	Boring "Hulett 06"	+38 011406°	-92.755135°	521505	4207120
A012120C	Boring "Hulett 07"	+38 011507°	-92.755024°	521487	4207123
A012120D	Boring "Hulett 08"	+38.011531°	-92.755222°	521481	4207106
A012121A	Boring "Hulett 09"	+38 010986°	-92 754827°	521537	4207111
A012122A	Boring "Hulett 10"	+38 011379°	-92 755299°	521522	4207062


ω), «Δ(

Table 3
Former Hulett Lagoon Site
Monitoring Well Data

Well Identification	Diameter (inches)/ Riser construction	Total well depth (feet) from TOC	Depth to water (feet) from TOC	Water column (feet)	One well volume (gallons)
MW-1	2" PVC	161' (per well log)	153.22	7.78	1.2
MW-2	2" PVC	197' (per well log)	165.72	31.28	5.1
MW-3	4" Metal	170' (per well log)	153.12	16.88	11
MW-4	4" Metal	194.3' (per well log)	158.55	35.75	23.3
MW-5	2" PVC	120.4' (field determined)	102.75	17.65	2.8


APPENDIX A
Site Maps
Former Hulett Lagoon Site
Camdenton, Missouri






APPENDIX B MIP Data Logs Former Hulett Lagoon Site Camdenton, Missouri


Log: C:\DIRIM95\LOGFILES\Hulett01.dat




Log: C. JIRIM95\LOGFILES\Hulett02.dat




Log: C:\DIRIM95\LOGFILES\Hulett03.dat



Log: C:\DIRIM95\LOGFILES\Hulett04.dat



Log: C:\DIRIM95\LOGFILES\Hulett05.dat



Log: C: \_IRIM95\LOGFILES\Hulett06.dat Conductivity (mS/M) 50\_ 25\_ 0\_ 40\_ Speed(ft/min) -20 Detector 1 (uV) 8E+5 6E+5\_ 4E+5 2E+5 0E+0\_ Detector 2 (uV) 8E+5\_ 6E+5 4E+5\_ The same


**Temperature (Celsius)** 


2E+5\_

-5E+3\_


100\_

Log: C:\DIRIM95\LOGFILES\Hulett07.dat






Log: C:\DIRIM95\LOGFILES\Hulett09.dat



APPENDIX C Analytical Results Former Hulett Lagoon Site Camdenton, Missouri





STATE OF MISSOURI

# DEPARTMENT OF NATURAL RESOURCES

DIVISION OF ENVIRONMENTAL QUALITY -P.O. Box 176 Jefferson City, MO 65102-0176

# ENVIRONMENTAL SERVICES PROGRAM

# RESULTS OF SAMPLE ANALYSES

Sample Number: 991450 Lab Number: 99-D9

Reported To: BRIAN ALLEN

Affiliation: **ESP** 

Project Code: 4054/9096

1/26/99 1/ 5/99 1/ 7/99

Date Collected: Date Received:

Report Date:

Sample Collected by:

Sampling Location:

Sample Description:

County:

FORMER HULETT LAGOON SITE

TRIP BLANK

BRIAN ALLEN, ESP

Analysis Performed	Results		Analyzed	Method
VOC Results:		<del></del>	· <del></del>	
Dichlorodifluoromethane	< 200	ug/L	1/12/99	502.2
Chloromethane	< 2.5	ug/L	1/12/99	502.2
Vinyl Chloride	< 0.5	ug/L	1/12/99	502.2
Bromomethane	< 9.0	ug/L	1/12/99	502.2
Chloroethane	< 2.5	ug/L	1/12/99	502.2
Trichlorofluoromethane	< 2.5	ug/L	1/12/99	502.2
1,1-Dichloroethene	< 0.5	ug/L	1/12/99	502.2
Methylene Chloride	< 0.5	ug/L	1/12/99	
Methyl-tert-butyl ether	< 2.0	ug/L	1/12/99	
trans-1,2-Dichloroethene	< 0.5	ug/L	1/12/99	
1,1-Dichloroethane	< 1.0	ug/L	1/12/99	
2,2-Dichloropropane	< 1.0	ug/L	1/12/99	502.2
cls-1,2-Dichloroethene	< 0.5	ug/L	1/12/99	502.2
Chloroform	4.6	ug/L	1/12/99	
Bromochloromethane	< 1.0	ug/L	1/12/99	
1,1,1-Trichloroethane	< 0.5	ug/L	1/12/99	
1,1-Dichloropropene	< 1.0	ug/L	1/12/99	
Carbon Tetrachloride	< 0.5	ug/L	1/12/99	
Benzene	< 0.5	ug/L	1/12/99	
1,2-Dichloroethane	< 0.5	ug/L	1/12/99	
Trichloroethene	< 0.5	ug/L	1/12/99	
1,2-Dichloropropane	< 0.5	ug/L	1/12/99	
Bromodichloromethane	< 0.5	ug/L	1/12/99	
Dibromomethane	< 1.0	ug/L	1/12/99	502.2

Lab Number: 99-D9
Sample Number: 991450

January 26, 1999

Analysis Performed	Results			Analyzed	Method
cis-1,3-Dichloropropane		2.0	ug/L	1/12/99	502.2
Toluene		0.6	ug/L	1/12/99	502.2
trans-1,3-Dichloropropane		1.0	ug/L	1/12/99	502.2
1,1,2-Trichloroethane		0.5	ug/L	1/12/99	502.2
Tetrachloroethene		0.5	ug/L	1/12/99	502.2
1,3-Dichloropropane		2.0	ug/L	1/12/99	502.2
Dibromochloromethane		0.5	ug/L	1/12/99	502.2
1,2-Dibromoethane		2.0	ug/L	1/12/99	502.2
Chlorobenzene		0.5	ug/L	1/12/99	502.2
Ethylbenzene		0.5	ug/L	1/12/99	502.2
1,1,1,2-Tetrachloroethane		1.0	ug/L	1/12/99	502.2
Total Xylenes		0.5	ug/L	1/12/99	502.2
Styrene	<	0.5	ug/L	1/12/99	502.2
Isopropylbenzene		2.0	ug/L	1/12/99	502.2
Bromoform		0.5	ug/L	1/12/99	502.2
1,1,2,2-Tetrachloroethane		1.0	ug/L	1/12/99	502.2
1,2,3-Trichloropropane		1.0	ug/l	1/12/99	502.2
n-Propylbenzene		2.0	ug/L	1/12/99	502.2
Bromobenzene		1.0	ug/L	1/12/99	502.2
2-Chlorotoluene		2.0	ug/L	1/12/99	502.2
4-Chlorotoluene		2.0	ug/L	1/12/99	502.2
1,3,5-Trimethylbenzene		2.0	ug/L	1/12/99	502.2
tert-Butylbenzene		2.0	ug/L	1/12/99	502.2
1,2,4-Trimethylbenzene		1.0	ug/L	1/12/99	502.2
sec-Butylbenzene		2.0	ug/L	1/12/99	502.2
p-isopropyltoluene		2.0	ug/L	1/12/99	502.2
1,3-Dichlorobenzene		1.0	ug/L	1/12/99	502.2
1,4-Dichlorobenzene		0.5	ug/L	1/12/99	502.2
n-Butylbenzene		2.0	ug/L	1/12/99	502.2
1,2-Dichlorobenzene		0.5	ug/L	1/12/99	502.2
1,2-Dibromo-3-Chloroprop		5.0	ug/L	1/12/99	502.2
1,2,4-Trichlorobenzene		0.5	ug/L	1/12/99	502.2
Hexachlorobutadiene		1.0	ug/L	1/12/99	502.2
Naphthalene		20.0	ug/L	1/12/99	502.2
1,2,3-Trichlorobenzene	<	2.0	ug/L	1/12/99	502.2

The analysis of this sample was performed in accordance with procedures approved or recognized by the U.S. Environmental Protection Agency.

James H. Long Director

Environmental (Services Program Division of Environmental Quality

# Mel Carnahan, Governor • Stephen M. Mahfood, Director ENT OF NATURAL RESOURCES DIVISION OF ENVIRONMENTAL QUALITY

P.O Box 176 Jefferson City, MO 65102-0176

Report Date:

Date Collected:

Date Received:

2/10/99 1/6/99

1/ 7/99

# ENVIRONMENTAL SERVICES PROGRAM

# RESULTS OF SAMPLE ANALYSES

Sample Number: 991451 Lab Number: 99-D10

Reported To: BRIAN ALLEN

Affiliation: ESP

Project Code: 4054/9096

Sample Collected by: Sampling Location:

Sample Description:

BRIAN ALLEN, ESP FORMER HULETT LAGOON SITE WATER GRAB OF PAUL BUCKWALTER

RESIDENTIAL WELL

(BOX 45A, NORMAC ESTATES)

County:

Analysis Performed F	Results		Analyzed	Method
Specific Conductivity Comment: Analyzed in field	918	umhos/cm	1/ 6/99	120.1
рн	7.03		1/ 6/99	150.1
Comment: Analyzed in field Temperature - C	15	Degrees C	1/ 6/99	
Comment: Analyzed in field Silver, Total Arsenic, Total Barium, Total Cadmium, Total Chromium, Total Copper, Total Mercury, Total Nickel, Total Lead, Total Selenium, Total	< 5.00 < 1.2 62.8 < 1.00 < 2.00 44.7 < 0.20 < 3.00 < 2.5 < 1.0	ug/L ug/L ug/L ug/L ug/L ug/L ug/L ug/L	1/13/99 1/14/99 1/13/99 1/13/99 1/13/99 1/29/99 1/13/99 1/14/99 1/14/99	200.7 200.7 200.7 245.1 200.7 239.2
VOC Results: Dichlorodifluoromethane Chloromethane Vinyl Chloride Bromomethane Chloroethane Trichlorofluoromethane	< 200 < 2.5 < 0.5 < 9.0 < 2.5 < 2.5	ug/L ug/L ug/L ug/L ug/L ug/L	1/12/99 1/12/99 1/12/99 1/12/99 1/12/99 1/12/99	502.2 502.2

Page 2 Lab Number: 99-D10 Sample Number: 991451 February 10, 1999

Analysis Performed	Results			Analyzed	Method
1,1-Dichloroethene		0.5	ug/L	1/12/99	502.2
Methylene Chloride		0.5	ug/L	1/12/99	502.2
Methyl-tert-butyl ether		2.0	ug/L	1/12/99	502.2
trans-1,2-Dichloroethene		0.5	ug/L	1/12/99	502.2
1,1-Dichloroethane		1.0	ug/L	1/12/99	502.2
2,2-Dichloropropane		1.0	ug/L	1/12/99	502.2
cis-1,2-Dichloroethene		0.5	ug/L	1/12/99	502.2
Chloroform		0.5	ug/L	1/12/99	502.2
Bromochloromethane		1.0	ug/L	1/12/99	502.2
1,1,1-Trichloroethane	<	0.5	ug/L	1/12/99	502.2
1,1-Dichloropropene		1.0	ug/L	1/12/99	502.2
Carbon Tetrachloride	<	0.5	ug/L	1/12/99	502.2
Benzene	<	0.5	ug/L	1/12/99	502.2
1,2-Dichloroethane		0.5	ug/L	1/12/99	502.2
Trichloroethene		0.5	ug/L	1/12/99	502.2
1,2-Dichloropropane		0.5	ug/L	1/12/99	502.2
Bromodichloromethane	<	0.5	ug/L	1/12/99	502.2
Dibromomethane	<	1.0	ug/L	1/12/99	502.2
cis-1,3-Dichloropropane	<	2.0	ug/L	1/12/99	502.2
Toluene	<	0.6	ug/L	1/12/99	502.2
trans-1,3-Dichloropropane	<	1.0	ug/L	1/12/99	502.2
1,1,2-Trichloroethane	<	0.5	ug/L	1/12/99	502.2
Tetrachloroethene	<	0.5	ug/L	1/12/99	502.2
1,3-Dichloropropane	<	2.0	ug/L	1/12/99	502.2
Dibromochloromethane	<	0.5	ug/L	1/12/99	502.2
1,2-Dibromoethane	<	2.0	ug/L	1/12/99	502.2
Chlorobenzene	<	0.5	ug/L	1/12/99	502.2
Ethylbenzene		0.5	ug/L	1/12/99	502.2
1,1,1,2-Tetrachloroethane	<	1.0	ug/L	1/12/99	502.2
Total Xylenes	<	0.5	ug/L	1/12/99	502.2
Styrene	<	0.5	ug/L	1/12/99	502.2
Isopropylbenzene	<	2.0	ug/L	1/12/99	502.2
Bromoform	<	0.5	ug/L		502.2
1,1,2,2-Tetrachloroethane		1.0	ug/L	1/12/99	502.2
1,2,3-Trichloropropane		1.0	ug/l	1/12/99	502.2
n-Propylbenzene		2.0	ug/L	1/12/99	502.2
Bromobenzene		1.0	ug/L	1/12/99	502.2
2-Chlorotoluene		2.0	ug/L	1/12/99	502.2
4-Chlorotoluene		2.0	ug/L	1/12/99	502.2
1,3,5-Trimethylbenzene		2.0	ug/L	1/12/99	502.2
tert-Butylbenzene		2.0	ug/L	1/12/99	502.2
1,2,4-Trimethylbenzene		1.0	ug/L	1/12/99	502.2
sec-Butylbenzene		2.0	ug/L	1/12/99	502.2
p-isopropyltoluene		2.0	ug/L	1/12/99	502.2
1,3-Dichlorobenzene		1.0	ug/L	1/12/99	502.2
1,4-Dichlorobenzene		0.5	ug/L	1/12/99	502.2
n-Butylbenzene		2.0	ug/L	1/12/99	502.2
1,2-Dichlorobenzene		0.5	ug/L	1/12/99	502.2
1,2 21011010001120110	······································		~9/ ~		302.2

Lab Number: 99-D10 Sample Number: 991451 February 10, 1999


Analysis Performed	Results		Analyzed	Method
1,2-Dibromo-3-Chloroprop 1,2,4-Trichlorobenzene Hexachlorobutadiene Naphthalene 1,2,3-Trichlorobenzene	< 5.0 < 0.5 < 1.0 < 20.0 < 2.0	ug/L ug/L ug/L ug/L ug/L	1/12/99 1/12/99 1/12/99 1/12/99 1/12/99	502.2 502.2

The analysis of this sample was performed in accordance with procedures approved or recognized by the U.S. Environmental Protection Agency.

James H. Long, Director

Nicuplus/ Edinidefor

Environmental Services Program Division of Environmental Quality



# NT OF NATURAL RESOURCES

DIVISION OF ENVIRONMENTAL QUALITY -P.O. Box 176 Jefferson City, MO 65102-0176

# ENVIRONMENTAL SERVICES PROGRAM

# RESULTS OF SAMPLE ANALYSES

Sample Number: 991452 Lab Number: 99-D11

BRIAN ALLEN Reported To:

Affiliation: ESP

Project Code: 4054/9096

Report Date:

2/10/99 1/ 6/99 1/ 7/99 Date Collected: Date Received:

Sample Collected by:

Sampling Location:

Sample Description:

BRIAN ALLEN, ESP

FORMER HULETT LAGOON SITE, WATER GRAB OF DAVE BURNAN RESIDENTIAL WELL (178 SUNSET DR), LOCATED

DIRECTLY NORTH OF MODINE MFG

County:

Analysis Performed	Results		Analyzed	Method
Specific Conductivity Comment: Analyzed in f	649	umhos/cm	1/ 6/99	120.1
рн	7.55		1/ 6/99	150.1
Comment: Analyzed in f Temperature - C Comment: Analyzed in f	12	Degrees C	1/ 6/99	
Silver, Total	< 5.00	ug/L	1/13/99	200.7
Arsenic, Total	< 1.2	ug/L	1/14/99	206.2
Barium, Total	67.5	ug/L	1/13/99	200.7
Cadmium, Total	< 1.00	ug/L	1/13/99	200.7
Chromium, Total	< 2.00	ug/L	1/13/99	200.7
Copper, Total	27.5	ug/L	1/13/99	200.7
Mercury, Total	< 0.20	ug/L	1/29/99	245.1
Nickel, Total	11.2	ug/L	1/13/99	200.7
Lead, Total	< 2.5		1/14/99	239.2
Selenium, Total	< 1.0	ug/L	1/14/99	270.2
VOA Results:		,		
Chloromethane	< 5.0	ug/L	1/14/99	8260
Vinyl Chloride	< 5.0	ug/L	1/14/99	8260
Bromomethane	< 5.0	ug/L	1/14/99	8260
Chloroethane	< 5.0	ug/L	1/14/99	8260
1,1-Dichloroethene	< 5.0	ug/L	1/14/99	8260
Acetone	< 20.0	ug/L	1/14/99	8260

Page 2 Lab Number: 99-D11 Sample Number: 991452 February 10, 1999

Analysis Performed	Results		Analyzed	Method
Carbon Disulfide	< 5.0	ug/L	1/14/99	8260
Methylene Chloride	< 20.0	ug/L	1/14/99	8260
Methyl Tert-Butyl Ether	< 5.0	ug/L	1/14/99	8260
trans-1,2-Dichloroethene	< 5.0	ug/L	1/14/99	8260
1,1-Dichloroethane	< 5.0	ug/L	1/14/99	8260
2-Butanone	< 20.0	ug/L	1/14/99	8260
cis-1,2-Dichloroethene	13.0	ug/L	1/14/99	8260
Chloroform	< 5.0	ug/L	1/14/99	8260
1,1,1-Trichloroethane	< 5.0	ug/L	1/14/99	8260
Carbon Tetrachloride	< 5.0	ug/L	1/14/99	8260
Benzene	< 5.0	ug/L	1/14/99	8260
1,2-Dichloroethane	< 5.0	ug/L	1/14/99	8260
Trichloroethene	240	ug/L	1/14/99	8260
1,2-Dichloropropane	< 5.0	ug/L	1/14/99	8260
Bromodichloromethane	< 5.0	ug/L	1/14/99	8260
2-Hexanone	< 20.0	ug/L	1/14/99	8260
Trans-1,3-Dichloropropene	< 5.0	ug/L	1/14/99	8260
Toluene	6.1	ug/L	1/14/99	8260
CIS-1,3-Dichloropropene	< 5.0	ug/L	1/14/99	8260
1,1,2-Trichloroethane	< 5.0	ug/L	1/14/99	8260
4-Methyl-2-Pentanone	< 20.0	ug/L	1/14/99	8260
Tetrachloroethene	< 5.0	ug/L	1/14/99	8260
Dibromochloromethane	< 5.0	ug/L	1/14/99	8260
Chlorobenzene	< 5.0	ug/L	1/14/99	8260
Ethylbenzene	5.3	ug/L	1/14/99	8260
Total Xylenes	15.0	ug/L	1/14/99	8260
Styrene	< 5.0	ug/L	1/14/99	8260
Bromoform	< 5.0	ug/L	1/14/99	8260
1,1,2,2-Tetrachloroethane	< 5.0	ug/L	1/14/99	8260
1,3-Dichlorobenzene	< 5.0	ug/L	1/14/99	8260
1,4-Dichlorobenzene	< 5.0	ug/L	1/14/99	8260
1,2-Dichlorobenzene	< 5.0	ug/L	1/14/99	8260


Lab Number: 99-D11 Sample Number: 991452 February 10, 1999

VOA Comments:

A 1:2 dilution was employed to quantitate TCE.

The analysis of this sample was performed in accordance with procedures approved or recognized by the U.S. Environmental Protection Agency.

James H. Long, Director Environmental Services Program Division of Environmental Quality



Report Date:

Date Collected:

Date Received:

2/10/99 1/ 6/99

1/ 7/99

# Mel Carnahan, Governor • Stephen M. Mahtood. Director MENT OF NATURAL RESOURCES DIVISION OF ENVIRONMENTAL QUALITY P.O Box 176 Jefferson City, MO 65102-0176

# ENVIRONMENTAL SERVICES PROGRAM

### RESULTS OF SAMPLE ANALYSES

Sample Number: 991453 Lab Number: 99-D12

BRIAN ALLEN Reported To:

Affiliation: ESP

Project Code: 4054/9096

BRIAN ALLEN, ESP

Sample Collected by: Sample Description:

FORMER HULETT LAGOON SITE, WATER GRAB OF DAVE BURNAN RESIDENTIAL WELL (178 SUNSET DR), LOCATED

DIRECTLY NORTH OF MODINE MFG, (DUPL)

County:

Analysis Performed	Results		Analyzed	Method
Specific Conductivity Comment: Analyzed in field	649	umhos/cm	1/ 6/99	120.1
pH	7.55		1/ 6/99	150.1
Comment: Analyzed in field Temperature - C Comment: Analyzed in field	12	Degrees C	1/ 6/99	
Silver, Total	< 5.00	ug/L	1/13/99	200.7
Arsenic, Total	< 1.2	ug/L	1/14/99	206.2
Barium, Total	66.6	ug/L	1/13/99	200.7
Cadmium, Total	< 1.00	ug/L	1/13/99	200.7
Chromium, Total	< 2.00	ug/L	1/13/99	200.7
Copper, Total	16.3	ug/L	1/13/99	200.7
Mercury, Total	< 0.20	ug/L	1/29/99	245.1
Nickel, Total	60.4	ug/L	1/13/99	
Lead, Total	< 2.5	ug/L	1/14/99	239.2
Selenium, Total	< 1.0	ug/L	1/14/99	270.2
VOA Results:		,		
Chloromethane	< 5.0	ug/L	1/14/99	8260
Vinyl Chloride	< 5.0	ug/L	1/14/99	8260
Bromomethane	< 5.0	ug/L	1/14/99	8260
Chloroethane	< 5.0	ug/L	1/14/99	8260
1,1-Dichloroethene	< 5.0	ug/L	1/14/99	8260
Acetone	< 20.0	ug/L	1/14/99	8260

Page 2 Lab Number: 99-D12 Sample Number: 991453 February 10, 1999

Analysis Performed	Results		Analyzed	Method
Carbon Disulfi <b>de</b>	< 5.0	ug/L	1/14/99	8260
Methylene Chl <b>oride</b>	< 20.0	ug/L	1/14/99	8260
Methyl Tert-Butyl Ether	< 5.0	ug/L	1/14/99	8260
trans-1,2-Dichloroethene	< 5.0	ug/L	1/14/99	8260
1,1-Dichloroethane	< 5.0	ug/L	1/14/99	8260
2-Butanone	< 20.0	ug/L	1/14/99	8260
cis-1,2-Dichloroethene	13.0	ug/L	1/14/99	8260
Chloroform	< 5.0	ug/L	1/14/99	8260
1,1,1-Trichloroethane	< 5.0	ug/L	1/14/99	8260
Carbon Tetrachloride	< 5.0	ug/L	1/14/99	8260
Benzene	< 5.0	ug/L	1/14/99	8260
1,2-Dichloroethane	< 5.0	ug/L	1/14/99	8260
Trichloroethene	230	ug/L	1/14/99	8260
1,2-Dichloropropane	< 5.0	ug/L	1/14/99	8260
Bromodichloromethane	< 5.0	ug/L	1/14/99	8260
2-Hexanone	< 20.0	ug/L	1/14/99	8260
Trans-1,3-Dichloropropene	< 5.0	ug/L	1/14/99	8260
Toluene	< 5.0	ug/L	1/14/99	8260
CIS-1,3-Dichloropropene	< 5.0	ug/L	1/14/99	8260
1,1,2-Trichloroethane	< 5.0	ug/L	1/14/99	8260
4-Methyl-2-Pentanone	< 20.0	ug/L	1/14/99	8260
Tetrachloroeth <b>ene</b>	< 5.0	ug/L	1/14/99	8260
Dibromochloromethane	< 5.0	ug/L	1/14/99	8260
Chlorobenzene	< 5.0	ug/L	1/14/99	8260
Ethylbenzene	< 5.0	ug/L	1/14/99	8260 '
Total Xylenes	< 5.0	ug/L	1/14/99	8260
Styrene	< 5.0	ug/L	1/14/99	8260
Bromoform	< 5.0	ug/L	1/14/99	8260
1,1,2,2-Tetrachloroethane	< 5.0	ug/L	1/14/99	8260
1,3-Dichlorobenzene	< 5.0	ug/L	1/14/99	8260
1,4-Dichlorobenzene	< 5.0	ug/L	1/14/99	8260
1,2-Dichlorobenzene	< 5.0	ug/L	1/14/99	8260

Lab Number: 99-D12 Sample Number: 991453 February 10, 1999


VOA Comments:

A 1:2 dilution was employed to quantitate TCE.

The analysis of this sample was performed in accordance with procedures approved or recognized by the U.S. Environmental Protection Agency.

James H. Long, Director

Environmental Services Program Division of Environmental Quality



# NT OF NATURAL RESOURCES

DIVISION OF ENVIRONMENTAL QUALITY -P.O. Box 176 Jefferson City, MO 65102-0176

# ENVIRONMENTAL SERVICES PROGRAM

# RESULTS OF SAMPLE ANALYSES

Sample Number: 991458 Lab Number: 99-D17

Reported To: BRIAN ALLEN

Affiliation: ESP

Project Code: 4054/9096

Report Date: 2/10/99 Date Collected:

1/ 6/99 1/ 7/99 Date Received:

Sample Collected by:

Sampling Location:

BRIAN ALLEN, ESP

Sample Description:

FORMER HULETT LAGOON SITE, WATER

GRAB OF CAMDENTON CITY WELL #4

(BLAIR WELL)

County:

Analysis Performed	Results		Analyzed	Method
Specific Conductivity Comment: Analyzed in field	569	umhos/cm	1/ 6/99	120.1
рН	7.68		1/ 6/99	150.1
Comment: Analyzed in field Temperature - C	16	Degrees C	1/ 6/99	
Comment: Analyzed in field Silver, Total Arsenic, Total Barium, Total Cadmium, Total Chromium, Total Copper, Total Mercury, Total Nickel, Total Lead, Total	< 5.00 < 1.2 45.3 < 1.00 < 2.00 21.7 < 0.20 < 3.00 4.4	ug/L ug/L ug/L ug/L ug/L ug/L ug/L	1/13/99 1/14/99 1/13/99 1/13/99 1/13/99 1/13/99 1/29/99 1/13/99 1/14/99	200.7 206.2 200.7 200.7 200.7 200.7 245.1 200.7 239.2
Selenium, Total VOC Results: Dichlorodifluoromethane Chloromethane Vinyl Chloride	< 1.0 < 200 < 2.5 < 0.5	ug/L ug/L ug/L ug/L	1/14/99 1/13/99 1/13/99 1/13/99	270.2 502.2 502.2 502.2
Bromomethane Chloroethane Trichlorofluoromethane 1,1-Dichloroethene	< 9.0 < 2.5 < 2.5 < 0.5	ug/L ug/L ug/L ug/L	1/13/99 1/13/99 1/13/99 1/13/99	502.2 502.2 502.2 502.2 502.2

Page 2 Lab Number: 99-D17 Sample Number: 991458 February 10, 1999

Analysis Performed	Results		Analyzed	Method
Methylene Chloride	< 0.5	ug/L	1/13/99	502.2
Methyl-tert-butyl ether	< 2.0	ug/L	1/13/99	502.2
trans-1,2-Dichloroethene	< 0.5	ug/L	1/13/99	502.2
1,1-Dichloroethane	< 1.0	ug/L	1/13/99	502.2
2,2-Dichloropropane	< 1.0	ug/L	1/13/99	502.2
cis-1,2-Dichloroethene	< 0.5	ug/L	1/13/99	502.2
Chloroform	< 0.5	ug/L	1/13/99	502.2
Bromochloromethane	< 1.0	ug/L	1/13/99	502.2
1,1,1-Trichloroethane	< 0.5	ug/L	1/13/99	502.2
1,1-Dichloropropene	< 1.0	ug/L	1/13/99	502.2
Carbon Tetrachloride	< 0.5	ug/L	1/13/99	502.2
Benzene	< 0.5	ug/L	1/13/99	502.2
1,2-Dichloroethane	< 0.5	ug/L	1/13/99	502.2
Trichloroethene	< 0.5	ug/L	1/13/99	502.2
1,2-Dichloropropane	< 0.5	ug/L	1/13/99	502.2
Bromodichloromethane	< 0.5	ug/L	1/13/99	502.2
Dibromomethane	< 1.0	ug/L	1/13/99	502.2
cis-1,3-Dichloropropane	< 2.0	ug/L	1/13/99	502.2
Toluene	< 0.6	ug/L	1/13/99	502.2
trans-1,3-Dichloropropane	< 1.0	ug/L	1/13/99	502.2
1,1,2-Trichloroethane	< 0.5	ug/L	1/13/99	502.2
Tetrachloroethene	< 0.5	ug/L	1/13/99	502.2
1,3-Dichloropropane	< 2.0	ug/L	1/13/99	502.2
Dibromochloromethane	< 0.5	ug/L	1/13/99	502.2
1,2-Dibromoethane	< 2.0	ug/L	1/13/99	502.2
Chlorobenzene	< 0.5	ug/L	1/13/99	502.2
Ethylbenzene	< 0.5	ug/L	1/13/99	502.2
1,1,1,2-Tetrachloroethane	< 1.0	ug/L	1/13/99	502.2
Total Xylenes	< 0.5	ug/L	1/13/99	502.2
Styrene	< 0.5	ug/L	1/13/99	502.2
Isopropylbenzene	< 2.0	ug/L	1/13/99	502.2
Bromoform	< 0.5	ug/L	1/13/99	502.2
1,1,2,2-Tetrachloroethane	< 1.0	ug/L	1/13/99	502.2
1,2,3-Trichloropropane	< 1.0	ug/l	1/13/99	502.2
n-Propylbenzene	< 10.0	ug/L	1/13/99	502.2
Bromobenzene	< 1.0	ug/L	1/13/99	502.2
2-Chlorotoluene	< 2.0	ug/L	1/13/99	502.2
4-Chlorotoluene	< 2.0	ug/L	1/13/99	502.2
1,3,5-Trimethylbenzene	< 2.0	ug/L	1/13/99	502.2
tert-Butylbenzene	< 2.0	ug/L	1/13/99	502.2
1,2,4-Trimethylbenzene	< 1.0	ug/L	1/13/99	502.2
sec-Butylbenzene	< 2.0	ug/L	1/13/99	502.2
p-isopropyltoluene	< 2.0	ug/L	1/13/99	502.2
1,3-Dichlorobenzene	< 1.0	ug/L	1/13/99	502.2
1,4-Dichlorobenzene	< 0.5	ug/L	1/13/99	502.2
n-Butylbenzene	< 2.0	ug/L	1/13/99	502.2
1,2-Dichlorobenzene	< 0.5	ug/L	1/13/99	502.2
1,2-Dibromo-3-Chloroprop	< 5.0	ug/L	1/13/99	502.2

Lab Number: 99-D17 Sample Number: 991458

February 10, 1999

Analysis Performed	Results		Analyzed	Method
1,2,4-Trichlorobenzene Hexachlorobutadiene Naphthalene 1,2,3-Trichlorobenzene	< 0.5 < 1.0 < 20.0 < 2.0	ug/L ug/L ug/L ug/L	1/13/99 1/13/99 1/13/99 1/13/99	502.2 502.2

The analysis of this sample was performed in accordance with procedures approved or recognized by the U.S. Environmental Protection Agency.

James H. Long, Director

Environmental Services Program Division of Environmental Quality



Mel Carnahan, Governor - Stephen M. Mahfood, Director

# DEPARTMENT OF NATURAL RESOURCES

-DIVISION OF ENVIRONMENTAL QUALITY -P.O. Box 176 Jefferson City, MO 65102-0176

Report Date:

Date Collected:

Date Received:

2/10/99 1/ 6/99

1/ 7/99

### ENVIRONMENTAL SERVICES PROGRAM

# RESULTS OF SAMPLE ANALYSES

Sample Number: 991459 Lab Number: 99-D18

Reported To: BRIAN ALLEN

Affiliation: ESP

Project Code: 4054/9096

Ploject code: 4034/9090

BRIAN ALLEN, ESP

Sample Collected by: Sampling Location:

Sample Description:

FORMER HULETT LAGOON SITE, WATER GRAB OF CAMDENTON CITY WELL KNOWN

AS MULBERRY WELL

County:

Analysis Performed	Results		Analyzed	Method
Specific Conductivity Comment: Analyzed in f	526	umhos/cm	1/ 6/99	120.1
рн	7.74		1/ 6/99	150.1
Comment: Analyzed in f Temperature - C Comment: Analyzed in f	15	Degrees C	1/ 6/99	
Silver, Total	< 5.00	ug/L	1/13/99	200.7
Arsenic, Total	< 1.2	ug/L	1/14/99	206.2
Barium, Total	45.3	ug/L	1/13/99	200.7
Cadmium, Total	< 1.00	ug/L	1/13/99	
Chromium, Total	< 2.00	ug/L	1/13/99	200.7
Copper, Total	31.7	ug/L	1/13/99	200.7
Mercury, Total	< 0.20 < 3.00	ug/L	1/29/99	
Nickel, Total Lead, Total	15.7	ug/L ug/L	1/13/99 1/14/99	239.2
Selenium, Total	< 1.0	ug/L	1/14/99	270.2
VOC Results:	1.0	ug/L	1/14/33	270.2
Dichlorodifluoromethane	< 200	ug/L	1/13/99	502.2
Chloromethane	< 2.5	ug/L	1/13/99	
Vinyl Chloride	< 0.5	ug/L	1/13/99	
Bromomethane	< 9.0	ug/L	1/13/99	
Chloroethane	< 2.5	ug/L	1/13/99	
Trichlorofluoromethane	< 2.5	ug/L	1/13/99	
1,1-Dichloroethene	< 0.5	ug/L	1/13/99	502.2

Page 2 Lab Number: 99-D18 Sample Number: 991459 February 10, 1999

Analysis Performed	Results		Analyzed	Method
Methylene Chloride	< 0.5	υσ /T		
Methyl-tert-butyl ether	< 2.0	ug/L	1/13/99	502.2
trans-1,2-Dichloroethene	< 0.5	ug/L	1/13/99	502.2
1,1-Dichloroethane	< 1.0	ug/L	1/13/99	502.2
2,2-Dichloropropane	< 1.0	ug/L	1/13/99	502.2
cis-1,2-Dichloroethene	< 0.5	ug/L	1/13/99	502.2
Chloroform	< 0.5	ug/L	1/13/99	502.2
Bromochloromethane	< 1.0	ug/L	1/13/99	502.2
1,1,1-Trichloroethane		ug/L	1/13/99	502.2
1,1-Dichloropropene	< 0.5	ug/L	1/13/99	502.2
Carbon Tetrachloride	< 1.0 < 0.5	ug/L	1/13/99	502.2
Benzene		ug/L	1/13/99	502.2
	< 0.5	ug/L	1/13/99	502.2
1,2-Dichloroethane	< 0.5	ug/L	1/13/99	502.2
Trichloroethene	5.3	ug/L	1/13/99	502.2
1,2-Dichloropropane	< 0.5	ug/L	1/13/99	502.2
Bromodichloromethane	< 0.5	ug/L	1/13/99	502.2
Dibromomethane	< 1.0	ug/L	1/13/99	502.2
cis-1,3-Dichloropropane	< 2.0	ug/L	1/13/99	502.2
Toluene	< 0.6	ug/L	1/13/99	502.2
trans-1,3-Dichloropropane	< 1.0	ug/L	1/13/99	502.2
1,1,2-Trichloroethane	< 0.5	ug/L	1/13/99	502.2
Tetrachloroethene	< 0.5	ug/L	1/13/99	502.2
1,3-Dichloropropane	< 2.0	ug/L	1/13/99	502.2
Dibromochloromethane	< 0.5	ug/L	1/13/99	502.2
1,2-Dibromoethane	< 2.0	ug/L	1/13/99	502.2
Chlorobenzene	< 0.5	ug/L	1/13/99	502.2
Ethylbenzene	< 0.5	ug/L	1/13/99	502.2
1,1,1,2-Tetrachloroethane	< 1.0	ug/L	1/13/99	502.2
Total Xylenes	< 0.5	ug/L	1/13/99	502.2
Styrene	< 0.5	ug/L	1/13/99	502.2
Isopropylbenzene	< 2.0	ug/L	1/13/99	502.2
Bromoform	< 0.5	ug/L	1/13/99	502.2
1,1,2,2-Tetrachloroethane	< 1.0	ug/L	1/13/99	502.2
1,2,3-Trichloropropane	< 1.0	ug/l	1/13/99	502.2
n-Propylbenzene	< 10.0		1/13/99	502.2
Bromobenzene	< 1.0	ug/L	1/13/99	502.2
2-Chlorotoluene	< 2.0	ug/L	1/13/99	502.2
4-Chlorotoluene	< 2.0	ug/L	1/13/99	502.2
1,3,5-Trimethylbenzene	< 2.0	ug/L	1/13/99	502.2
tert-Butylbenzene	< 2.0	ug/L	1/13/99	502.2
1,2,4-Trimethylbenzene	< 1.0	ug/L	1/13/99	502.2
sec-Butylbenzene	< 2.0	ug/L	1/13/99	502.2
p-isopropyltoluene	< 2.0	ug/L	1/13/99	502.2
1,3-Dichlorobenzene	< 1.0	ug/L	1/13/99	502.2
1,4-Dichlorobenzene	< 0.5	ug/L	1/13/99	502.2
n-Butylbenzene	< 2.0	ug/L	1/13/99	502.2
1,2-Dichlorobenzene	< 0.5	ug/L	1/13/99	502.2
1,2-Dibromo-3-Chloroprop	< 5.0	ug/L	1/13/99	502.2

Lab Number: 99-D18 Sample Number: 991459 February 10, 1999

Analysis Performed	Results		Analyzed	Method
1,2,4-Trichlorobenzene Hexachlorobutadiene Naphthalene 1,2,3-Trichlorobenzene	< 0.5 < 1.0 < 20.0 < 2.0	ug/L ug/L ug/L ug/L	1/13/99 1/13/99 1/13/99 1/13/99	502.2 502.2

The analysis of this sample was performed in accordance with procedures approved or recognized by the U.S. Environmental Protection Agency.

James H. Long, Director

Environmental Services Program
Division of Environmental Quality



Mel Carnahan, Governor + Stephen M. Mahlood, Director

# ENT OF NATURAL RESOURCES

DIVISION OF ENVIRONMENTAL QUALITY -PO. Box 176 Jefferson City, MO 65102-0176

Report Date:

Date Collected:

Date Received:

2/10/99 1/ 6/99

1/ 7/99

### ENVIRONMENTAL SERVICES PROGRAM

### `RESULTS OF SAMPLE ANALYSES

Sample Number: 991460 Lab Number: 99-D19

Reported To: BRIAN ALLEN

ESP Affiliation:

Project Code: 4054/9096

BRIAN ALLEN, ESP

Sample Collected by: Sampling Location:

Sample Description:

FORMER HULETT LAGOON SITE, WATER GRAB OF MW-3, LOCATED ON SOUTH END

OF LOT, SOUTHWEST OF MODINE

MANUFACTURING BUILDING

County:

Analysis Performed	Results		Analyzed	Method
Turbidity	951	NTU	1/ 6/99	180.1
Comment: Analyzed in Specific Conductivity	field 701	umhos/cm	1/ 6/99	120.1
Comment: Analyzed in		,	• •	
pH Commont. Analyzed in	7.48		1/ 6/99	150.1
Comment: Analyzed in Temperature - C	15	Degrees C	1/ 6/99	
Comment: Analyzed in	field < 5.00	ug/L	1 /12 /00	200.7
Silver, Dissolved Arsenic, Dissolved	< 1.2	ug/L ug/L	1/13/99 1/14/99	206.2
Barium, Dissolved	69.6	ug/L	1/13/99	200.7
Cadmium, Dissolved	< 1.00	ug/L	1/13/99	200.7
Chromium, Dissolved Copper, Dissolved	< 2.00 < 3.00	ug/L ug/L	1/13/99 1/13/99	200.7 200.7
Mercury, Dissolved	< 0.20	ug/L	1/29/99	245.1
Nickel, Dissolved	< 3.00	ug/L	1/13/99	200.7
Lead, Dissolved	< 2.5 < 1.0	ug/L	1/14/99	239.2
Selenium, Dissolved Silver, Total	< 5.00	ug/L ug/L	1/14/99 1/13/99	270.2 200.7
Arsenic, Total	6.0	ug/L	1/14/99	206.2
Barium, Total	151	ug/L	1/13/99	200.7
Cadmium, Total Chromium, Total	2.26 45.7	ug/L ug/L	1/13/99 1/13/99	200.7 200.7
<u></u>			· · · · · · · · · · · · · · · · · · ·	

Page 2 Lab Number: 99-D19 Sample Number: 991460 February 10, 1999


Analysis Performed	Results		Analyzed	Method
Copper, Total	51.2	ug/L	1/13/99	200.7
Mercury, Total	< 0.20	ug/L	1/29/99	245.1
Nickel, Total	29.7	ug/L	1/13/99	
Lead, Total	97.6	ug/L	1/14/99	239.2
Selenium, Total	< 1.0	ug/L	1/14/99	270.2
VOC Results:			, ,	
Dichlorodifluoromethane	< 200	ug/L	1/13/99	502.2
Chloromethane	< 2.5	ug/L	1/13/99	502.2
Vinyl Chloride	< 0.5	ug/L	1/13/99	502.2
Bromomethane	< 9.0	ug/L	1/13/99	502.2
Chloroethane	< 2.5	ug/L	1/13/99	502.2
Trichlorofluoromethane	< 2.5	ug/L	1/13/99	502.2
1,1-Dichloroethene	< 0.5	ug/L	1/13/99	502.2
Methylene Chloride	< 0.5	ug/L	1/13/99	502.2
Methyl-tert-butyl ether	< 2.0	ug/L	1/13/99	502.2
trans-1,2-Dichloroethene	< 0.5	ug/L	1/13/99	502.2
1,1-Dichloroethane	< 1.0	ug/L	1/13/99	502.2
2,2-Dichloropropane	< 1.0	ug/L	1/13/99	502.2
cis-1,2-Dichloroethene	< 0.5	ug/L	1/13/99	502.2
Chloroform	< 0.5	ug/L	1/13/99	502.2
Bromochloromethane	< 1.0	ug/L	1/13/99	502.2
1,1,1-Trichloroethane	< 0.5	ug/L	1/13/99	502.2
1,1-Dichloropropene	< 1.0	ug/L	1/13/99	502.2
Carbon Tetrachloride	< 0.5	ug/L	1/13/99	502.2
Benzene	< 0.5	ug/L	1/13/99	502.2
1,2-Dichloroethane	< 0.5	ug/L	1/13/99	502.2
Trichloroethene	< 0.5	ug/L	1/13/99	502.2
1,2-Dichloropropane	< 0.5	ug/L	1/13/99	502.2
Bromodichloromethane	< 0.5	ug/L	1/13/99	502.2
Dibromomethane	< 1.0	ug/L	1/13/99	
cis-1,3-Dichloropropane	< 2.0	ug/L	1/13/99	502.2
Toluene	< 0.6	ug/L	1/13/99	
trans-1,3-Dichloropropane	< 1.0	ug/L	1/13/99	
1,1,2-Trichloroethane	< 0.5	ug/L	1/13/99	502.2
Tetrachloroethene	< 0.5	ug/L	1/13/99	502.2
1,3-Dichloropropane	< 2.0	ug/L	1/13/99	502.2
Dibromochloromethane	< 0.5	ug/L	1/13/99	502.2
1,2-Dibromoethane	< 2.0	ug/L	1/13/99	502.2
Chlorobenzene	< 0.5	ug/L	1/13/99	502.2
Ethylbenzene	< 0.5	ug/L	1/13/99	502.2
1,1,1,2-Tetrachloroethane	< 1.0	ug/L	1/13/99	502.2
Total Xylenes	< 0.5	ug/L	1/13/99	502.2
Styrene	< 0.5	ug/L	1/13/99	502.2
Isopropylbenzene	< 2.0	ug/L	1/13/99	502.2
Bromoform	< 0.5	ug/L	1/13/99	502.2
1,1,2,2-Tetrachloroethane	< 1.0	ug/L	1/13/99	502.2
	< 1.0		1/13/99	
1,2,3-Trichloropropane	V 1.0	ug/l	1/13/33	502.2

Lab Number: 99-D19 Sample Number: 991460 February 10, 1999

Analysis Performed	Results		Analyzed	Method
Analysis Performed  Bromobenzene 2-Chlorotoluene 4-Chlorotoluene 1,3,5-Trimethylbenzene tert-Butylbenzene 1,2,4-Trimethylbenzene sec-Butylbenzene p-isopropyltoluene 1,3-Dichlorobenzene 1,4-Dichlorobenzene n-Butylbenzene 1,2-Dichlorobenzene 1,2-Dichlorobenzene 1,2-Dichlorobenzene 1,2-Dibromo-3-Chloroprop 1,2,4-Trichlorobenzene	<pre>Results  &lt; 1.0 &lt; 2.0 &lt; 2.0 &lt; 2.0 &lt; 2.0 &lt; 1.0 &lt; 2.0 &lt; 1.0 &lt; 2.0 &lt; 2.0 &lt; 5.0 &lt; 0.5 &lt; 0.5 &lt; 0.5</pre>	ug/L ug/L ug/L ug/L ug/L ug/L ug/L ug/L	1/13/99 1/13/99 1/13/99 1/13/99 1/13/99 1/13/99 1/13/99 1/13/99 1/13/99 1/13/99 1/13/99 1/13/99 1/13/99 1/13/99	Method  502.2 502.2 502.2 502.2 502.2 502.2 502.2 502.2 502.2 502.2 502.2 502.2 502.2
Hexachlorobutadiene Naphthalene 1,2,3-Trichlorobenzene	< 1.0 < 20.0 < 2.0	ug/L ug/L ug/L	1/13/99 1/13/99 1/13/99	502.2 502.2 502.2

The analysis of this sample was performed in accordance with procedures approved or recognized by the U.S. Environmental Protection Agency.

James H. Long, Director Environmental Services Program Division of Environmental Quality





# DEPARTMENT OF NATURAL RESOURCES

-DIVISION OF ENVIRONMENTAL QUALITY -P.O. Box 176 Jefferson City, MO 65102-0176

Report Date:

Date Collected:

Date Received:

2/10/99

1/6/99

1/ 7/99

### ENVIRONMENTAL SERVICES PROGRAM

# RESULTS OF SAMPLE ANALYSES

Sample Number: 991461 Lab Number: 99-D20

Reported To: BRIAN ALLEN

Affiliation: ESP

Project Code: 4054/9096

Sample Collected by: BRIAN ALLEN, ESP

Sampling Location: Sample Description:

FORMER HULETT LAGOON SITE, WATER GRAB OF MW-4, LOCATED AT MAIN ENTRANCE TO MODINE MFG PROPERTY COLLECTED VIA SUBMERSIBLE PUMP

County: CAMDEN

Analysis Performed	Results	Ana	lyzed	Method
Turbidity		NTU 1/	6/99	180.1
Comment: Analyzed in fiel Specific Conductivity	687	umhos/cm 1/	6/99	120.1
Comment: Analyzed in fiel pH Comment: Analyzed in fiel	7.22	1/	6/99	150.1
Temperature - C Comment: Analyzed in fiel	15	Degrees C 1/	6/99	
Silver, Dissolved Arsenic, Dissolved Barium, Dissolved Cadmium, Dissolved Chromium, Dissolved Copper, Dissolved Mercury, Dissolved Nickel, Dissolved Lead, Dissolved Selenium, Dissolved Silver, Total Arsenic, Total Barium, Total Cadmium, Total	< 5.00 < 1.2 81.6 < 1.00 < 2.00 < 3.00 < 0.20     5.81 < 2.5 < 1.0 < 5.00 < 1.2 88.3 < 1.00	ug/L       1/         ug/L       1/	/13/99 /14/99 /13/99 /13/99 /13/99 /13/99 /14/99 /14/99 /13/99 /13/99 /13/99 /13/99	200.7 200.7 200.7 200.7 245.1 200.7 239.2 270.2 200.7 206.2 200.7

Page 2 Lab Number: 99-D20 Sample Number: 991461 February 10, 1999

Analysis Performed	Results	<del> </del>	Analyzed	Method
Copper, Total	< 5.00	NG /T		
Mercury, Total	< 0.20	ug/L ug/L	1/13/99	200.7
Nickel, Total	7.61		1/29/99	245.1
Lead, Total	38.7	ug/L	1/13/99	200.7
Selenium, Total	< 1.0	ug/L	1/14/99	239.2
VOC Results:	1.0	ug/L	1/14/99	270.2
Dichlorodifluoromethane	< 200	υσ/T	1 /12 /00	F 0 0 0
Chloromethane	< 2.5	ug/L	1/13/99	502.2
Vinyl Chloride	< 0.5	ug/L	1/13/99	502.2
Bromomethane	< 9.0	ug/L	1/13/99	502.2
Chloroethane	< 2.5	ug/L	1/13/99	502.2
Trichlorofluoromethane	< 2.5	ug/L	1/13/99	502.2
1		ug/L	1/13/99	502.2
1,1-Dichloroethene	< 0.5	ug/L	1/13/99	502.2
Methylene Chloride	< 0.5	ug/L	1/13/99	502.2
Methyl-tert-butyl ether	< 2.0	ug/L	1/13/99	502.2
trans-1,2-Dichloroethene	< 0.5	ug/L	1/13/99	502.2
1,1-Dichloroethane	< 1.0	ug/L	1/13/99	502.2
2,2-Dichloropropane	< 1.0	ug/L	1/13/99	502.2
cis-1,2-Dichloroethene	2.1	ug/L	1/13/99	502.2
Chloroform	< 0.5	ug/L	1/13/99	502.2
Bromochloromethane	< 1.0	ug/L	1/13/99	502.2
1,1,1-Trichloroethane	< 0.5	ug/L	1/13/99	502.2
1,1-Dichloropropene	< 1.0	ug/L	1/13/99	502.2
Carbon Tetrachloride	< 0.5	ug/L	1/13/99	502.2
Benzene	< 0.5	ug/L	1/13/99	502.2
1,2-Dichloroethane	< 0.5	ug/L	1/13/99	502.2
Trichloroethene	64.1	ug/L	1/13/99	502.2
1,2-Dichloropropane	< 0.5	ug/L	1/13/99	502.2
Bromodichloromethane	< 0.5	ug/L	1/13/99	502.2
Dibromomethane	< 1.0	ug/L	1/13/99	502.2
cis-1,3-Dichloropropane	< 2.0	ug/L	1/13/99	502.2
Toluene	< 0.6	ug/L	1/13/99	502.2
trans-1,3-Dichloropropane	< 1.0	ug/L	1/13/99	502.2
1,1,2-Trichloroethane	< 0.5	ug/L	1/13/99	502.2
Tetrachloroethene	< 0.5	ug/L	1/13/99	502.2
1,3-Dichloropropane	< 2.0	ug/L	1/13/99	502.2
Dibromochloromethane	< 0.5	ug/L	1/13/99	502.2
1,2-Dibromoethane	< 2.0	ug/L	1/13/99	502.2
Chlorobenzene	< 0.5	ug/L	1/13/99	502.2
Ethylbenzene	< 0.5	ug/L	1/13/99	502.2
1,1,1,2-Tetrachloroethane	< 1.0	ug/L	1/13/99	502.2
Total Xylenes	< 0.5	ug/L	1/13/99	502.2
Styrene	< 0.5	ug/L	1/13/99	502.2
Isopropylbenzene	< 2.0	ug/L	1/13/99	502.2
Bromoform	< 0.5	ug/L		
1,1,2,2-Tetrachloroethane	< 1.0		1/13/99	502.2
1,2,2-lettachioloethane 1,2,3-Trichloropropane	< 1.0	ug/L	1/13/99	502.2
n-Propylbenzene	< 2.0	ug/l	1/13/99	502.2
I rropyrbenzene	` 2.0	ug/L	1/13/99	502.2


Lab Number: 99-D20 Sample Number: 991461 February 10, 1999

Analysis Performed	Results		Analyzed	Method
Bromobenzene 2-Chlorotoluene 4-Chlorotoluene 1,3,5-Trimethylbenzene tert-Butylbenzene 1,2,4-Trimethylbenzene sec-Butylbenzene p-isopropyltoluene 1,3-Dichlorobenzene 1,4-Dichlorobenzene n-Butylbenzene 1,2-Dichlorobenzene 1,2-Dibromo-3-Chloroprop 1,2,4-Trichlorobenzene Hexachlorobutadiene	<pre></pre>	ug/L ug/L ug/L ug/L ug/L ug/L ug/L ug/L	1/13/99 1/13/99 1/13/99 1/13/99 1/13/99 1/13/99 1/13/99 1/13/99 1/13/99 1/13/99 1/13/99 1/13/99 1/13/99 1/13/99 1/13/99 1/13/99 1/13/99	502.2 502.2 502.2 502.2 502.2 502.2 502.2 502.2 502.2 502.2 502.2 502.2 502.2
Naphthalene 1,2,3-Trichlorobenzene	< 20.0 < 2.0	ug/L ug/L	1/13/99 1/13/99	502.2 502.2

The analysis of this sample was performed in accordance with procedures approved or recognized by the U.S. Environmental Protection Agency.

Nouglas N. Showelfor

James H. Long, Director Environmental Services Program Division of Environmental Quality





STATE OF MISSOURI

# TMENT OF NATURAL RESOURCES

DIVISION OF ENVIRONMENTAL QUALITY -P.O. Box 176 Jefferson City, MO 65102-0176

# ENVIRONMENTAL SERVICES PROGRAM

# RESULTS OF SAMPLE ANALYSES

Sample Number: 991462 Lab Number: 99-D21

Reported To: BRIAN ALLEN

Affiliation: ESP

Project Code: 4054/9096

Report Date:

1/26/99

Date Collected:

1/ 6/99 1/ 7/99

Date Received:

Sample Collected by:

Sampling Location: Sample Description: BRIAN ALLEN, ESP

FORMER HULETT LAGOON SITE, WATER

GRAB OF MW-4, LOCATED AT MAIN

ENTRANCE TO MODINE MFG PROPERTY

COLLECTED VIA BAILER

County:

Analysis Performed	Results		Analyzed	Method
VOC Results:			<del></del>	
Dichlorodifluoromethane	< 200	ug/L	1/13/99	502.2
Chloromethane	< 2.5	ug/L	1/13/99	502.2
Vinyl Chloride	< 0.5	ug/L	1/13/99	502.2
Bromomethane	< 9.0	ug/L	1/13/99	502.2
Chloroethane	< 2.5	ug/L	1/13/99	502.2
Trichlorofluoromethane	< 2.5	ug/L	1/13/99	502.2
1,1-Dichloroethene	< 0.5	ug/L	1/13/99	
Methylene Chloride	< 0.5	ug/L	1/13/99	
Methyl-tert-butyl ether	< 2.0	ug/L	1/13/99	
trans-1,2-Dichloroethene	< 0.5	ug/L	1/13/99	
1,1-Dichloroethane	< 1.0	ug/L	1/13/99	
2,2-Dichloropropane	< 1.0	ug/L	1/13/99	502.2
cis-1,2-Dichloroethene	2.3	ug/L	1/13/99	502.2
Chloroform	< 0.5	ug/L	1/13/99	
Bromochloromethane	< 1.0	ug/L	1/13/99	
1,1,1-Trichloroethane	< 0.5	ug/L	1/13/99	
1,1-Dichloropropene	< 1.0	ug/L	1/13/99	
Carbon Tetrachloride	< 0.5	ug/L	1/13/99	
Benzene	< 0.5	ug/L	1/13/99	
1,2-Dichloroethane	< 0.5	ug/L	1/13/99	
Trichloroethene	76.5	ug/L	1/13/99	
1,2-Dichloropropane	< 0.5	ug/L	1/13/99	502.2

Page 2 Lab Number: 99-D21 Sample Number: 991462 January 26, 1999


Analysis Performed	Results			Analyzed	Method
Bromodichloromethane		0.5	ug/L	1/13/99	502.2
Dibromomethane		1.0	ug/L	1/13/99	502.2
cis-1,3-Dichloropropane		2.0	ug/L	1/13/99	502.2
Toluene		0.6	ug/L	1/13/99	502.2
trans-1,3-Dichloropropane		1.0	ug/L	1/13/99	502.2
1,1,2-Trichloroethane		0.5	ug/L	1/13/99	502.2
Tetrachloroethene		0.5	ug/L	1/13/99	502.2
1,3-Dichloropropane		2.0	ug/L	1/13/99	502.2
Dibromochloromethane		0.5	ug/L	1/13/99	502.2
1,2-Dibromoethane		2.0	ug/L	1/13/99	502.2
Chlorobenzene		0.5	ug/L	1/13/99	502.2
Ethylbenzene		0.5	ug/L	1/13/99	502.2
1,1,1,2-Tetrachloroethane		1.0	ug/L	1/13/99	502.2
Total Xylenes	<	0.5	ug/L	1/13/99	502.2
Styrene	<	0.5	ug/L	1/13/99	502.2
Isopropylbenzene	<	2.0	ug/L	1/13/99	502.2
Bromoform	<	0.5	ug/L	1/13/99	502.2
1,1,2,2-Tetrachloroethane	<	1.0	ug/L	1/13/99	502.2
1,2,3-Trichloropropane	<	1.0	ug/l	1/13/99	502.2
n-Propylbenzene		2.0	ug/L	1/13/99	502.2
Bromobenzene	<	1.0	ug/L	1/13/99	502.2
2-Chlorotoluene	<	2.0	ug/L	1/13/99	502.2
4-Chlorotoluene	<	2.0	ug/L	1/13/99	502.2
1,3,5-Trimethylbenzene	<	2.0	ug/L	1/13/99	502.2
tert-Butylbenzene	<	2.0	ug/L	1/13/99	502.2
1,2,4-Trimethylbenzene	<	1.0	ug/L	1/13/99	502.2
sec-Butylbenzene	<	2.0	ug/L	1/13/99	502.2
p-isopropyltoluene		2.0	ug/L	1/13/99	502.2
1,3-Dichlorobenzene		1.0	ug/L	1/13/99	502.2
1,4-Dichlorobenzene	<	0.5	ug/L	1/13/99	502.2
n-Butylbenzene		2.0	ug/L	1/13/99	502.2
1,2-Dichlorobenzene		0.5	ug/L	1/13/99	502.2
1,2-Dibromo-3-Chloroprop	<	5.0	ug/L	1/13/99	502.2
1,2,4-Trichlorobenzene	<	0.5	ug/L	1/13/99	502.2
Hexachlorobutadiene	<	1.0	ug/L	1/13/99	502.2
Naphthalene		20.0	ug/L	1/13/99	502.2
1,2,3-Trichlorobenzene	<	2.0	ug/L	1/13/99	502.2

Lab Number: 99-D21 Sample Number: 991462

January 26, 1999

The analysis of this sample was performed in accordance with procedures approved or recognized by the U.S. Environmental Protection Agency.

James H. Long, Director Environmental Services Program Division of Environmental Quality



# ENT OF NATURAL RESOURCES

DIVISION OF ENVIRONMENTAL QUALITY -P.O. Box 176 Jefferson City, MO 65102-0176

# ENVIRONMENTAL SERVICES PROGRAM

# RESULTS OF SAMPLE ANALYSES

Sample Number: 991463 Lab Number: 99-D22

BRIAN ALLEN Reported To:

Affiliation: ESP

Project Code: 4054/9096

Report Date:

2/10/99

Date Collected:

1/ 7/99

Date Received:

Sample Collected by:

Sampling Location: Sample Description:

BRIAN ALLEN, ESP

FORMER HULETT LAGOON SITE, WATER

GRAB OF MW-2, LOCATED ON NORTHEAST

SIDE OF MODINE MFG BUILDING

County:

Analysis Performed I	Results		Analyzed	Method
Turbidity	372	NTU	1/ 7/99	180.1
Comment: Analyzed in field Specific Conductivity Comment: Analyzed in field	796	umhos/cm	1/ 7/99	120.1
pH Comment: Analyzed in field	7.16		1/ 7/99	150.1
Temperature - C Comment: Analyzed in field	13	Degrees C	1/ 7/99	
Silver, Dissolved Arsenic, Dissolved Barium, Dissolved Cadmium, Dissolved Chromium, Dissolved Copper, Dissolved Mercury, Dissolved Nickel, Dissolved Lead, Dissolved Selenium, Dissolved	< 5.00 < 1.2 91.0 < 1.00 < 2.00 < 3.00 < 0.20 < 3.00 < 2.5 < 1.0	ug/L ug/L ug/L ug/L ug/L ug/L ug/L ug/L	1/13/99 1/14/99 1/13/99 1/13/99 1/13/99 1/13/99 1/13/99 1/14/99	
Silver, Total Arsenic, Total Barium, Total Cadmium, Total Chromium, Total Copper, Total	< 5.00 < 1.2 112 < 1.00 14.3 7.85	ug/L ug/L ug/L ug/L ug/L	1/13/99 1/14/99 1/13/99 1/13/99 1/13/99	

Page 2 Lab Number: 99-D22 Sample Number: 991463 February 10, 1999

Analysis Performed	Results		Analyzed	Method
Mercury, Total	< 0.20	ug/L	1/29/99	245.1
Nickel, Total	8.45	ug/L	1/13/99	200.7
Lead, Total	37.2	ug/L	1/14/99	239.2
Selenium, Total	< 1.0	ug/L	1/14/99	270.2
VOC Results:			, ,, = =	
Dichlorodifluoromethane	< 200	ug/L	1/13/99	<b>502.</b> 2
Chloromethane	< 2.5	ug/L	1/13/99	502.2
Vinyl Chloride	< 0.5	ug/L	1/13/99	502.2
Bromomethane	< 9.0	ug/L	1/13/99	502.2
Chloroethane	< 2.5	ug/L	1/13/99	502.2
Trichlorofluoromethane	< 2.5	ug/L	1/13/99	502.2
1,1-Dichloroethene	< 0.5	ug/L	1/13/99	502.2
Methylene Chloride	< 0.5	ug/L	1/13/99	502.2
Methyl-tert-butyl ether	< 2.0	ug/L	1/13/99	502.2
trans-1,2-Dichloroethene	< 0.5	ug/L	1/13/99	502.2
1,1-Dichloroethane	< 1.0	ug/L	1/13/99	502.2
2,2-Dichloropropane	< 1.0	ug/L	1/13/99	502.2
cis-1,2-Dichloroethene	< 0.5	ug/L	1/13/99	502.2
Chloroform	< 0.5	ug/L		
Bromochloromethane	< 1.0	ug/L	1/13/99	502.2
1,1,1-Trichloroethane	< 0.5		1/13/99	502.2
1,1-Dichloropropene	< 1.0	ug/L	1/13/99	502.2
Carbon Tetrachloride	< 0.5	ug/L	1/13/99	502.2
		ug/L	1/13/99	502.2
Benzene	< 0.5	ug/L	1/13/99	502.2
1,2-Dichloroethane	< 0.5	ug/L	1/13/99	502.2
Trichloroethene	2.5	ug/L	1/13/99	502.2
1,2-Dichloropropane	< 0.5	ug/L	1/13/99	502.2
Bromodichloromethane	< 0.5	ug/L	1/13/99	502.2
Dibromomethane	< 1.0	ug/L	1/13/99	502.2
cis-1,3-Dichloropropane	< 2.0	ug/L	1/13/99	502.2
Toluene	< 0.6	ug/L		502.2
trans-1,3-Dichloropropane	< 1.0	ug/L	1/13/99	502.2
1,1,2-Trichloroethane	< 0.5	ug/L	1/13/99	502.2
Tetrachloroethene	< 0.5	ug/L	1/13/99	502.2
1,3-Dichloropropane	< 2.0	ug/L	1/13/99	502.2
Dibromochloromethane	< 0.5	ug/L	1/13/99	502.2
1,2-Dibromoethane	< 2.0	ug/L	1/13/99	502.2
Chlorobenzene	< 0.5	ug/L	1/13/99	502.2
Ethylbenzene	< 0.5	ug/L	1/13/99	502.2
1,1,1,2-Tetrachloroethane	< 1.0	ug/L	1/13/99	502.2
Total Xylenes	< 0.5	ug/L	1/13/99	502.2
Styrene	< 0.5	ug/L	1/13/99	502.2
Isopropylbenzene	< 2.0	ug/L	1/13/99	502.2
Bromoform	< 0.5	ug/L	1/13/99	502.2
1,1,2,2-Tetrachloroethane	< 1.0	ug/L	1/13/99	
1,2,3-Trichloropropane	< 1.0			502.2
n-Propylbenzene	< 10.0	ug/l	1/13/99	502.2
u troblineuseus	< 1.0	ug/L	1/13/99	502.2


Lab Number: 99-D22 Sample Number: 991463 February 10, 1999

Analysis Performed	Results		Analyzed	Method
2-Chlorotoluene 4-Chlorotoluene 1,3,5-Trimethylbenzene tert-Butylbenzene 1,2,4-Trimethylbenzene sec-Butylbenzene p-isopropyltoluene 1,3-Dichlorobenzene 1,4-Dichlorobenzene	<pre></pre>	ug/L ug/L ug/L ug/L ug/L ug/L ug/L ug/L	1/13/99 1/13/99 1/13/99 1/13/99 1/13/99 1/13/99 1/13/99 1/13/99 1/13/99	502.2 502.2 502.2 502.2 502.2 502.2 502.2 502.2 502.2
n-Butylbenzene 1,2-Dichlorobenzene 1,2-Dibromo-3-Chloroprop 1,2,4-Trichlorobenzene Hexachlorobutadiene Naphthalene 1,2,3-Trichlorobenzene	< 2.0 < 0.5 < 5.0 < 0.5 < 1.0 < 20.0 < 2.0	ug/L ug/L ug/L ug/L ug/L ug/L	1/13/99 1/13/99 1/13/99 1/13/99 1/13/99 1/13/99	502.2 502.2 502.2 502.2 502.2 502.2 502.2

The analysis of this sample was performed in accordance with procedures approved or recognized by the U.S. Environmental Protection Agency.

James H. Long, Director

Environmental Services Program Division of Environmental Quality



# MENT OF NATURAL RESOURCES

DIVISION OF ENVIRONMENTAL QUALITY -P.O. Box 176 Jefferson City, MO 65102-0176

### ENVIRONMENTAL SERVICES PROGRAM

# RESULTS OF SAMPLE ANALYSES

Sample Number: 991464 Lab Number: 99-D23

Reported To: BRIAN ALLEN

Affiliation: ESP

Project Code: 4054/9096

Report Date:

2/10/99

Date Collected:

Date Received:

1/ 7/99 1/ 7/99

Sample Collected by:

Sampling Location:

Sample Description:

BRIAN ALLEN, ESP

FORMER HULETT LAGOON SITE, WATER GRAB OF MW-1, LOCATED IN WESTERN

GRAVEL PARKING LOT ON MODINE

MANUFACTURING PROPERTY

County:

Analysis Performed	Results		Analyzed	Method
Turbidity	143	NTU	1/ 7/99	180.1
Comment: Analyzed in fie Specific Conductivity Comment: Analyzed in fie	532	umhos/cm	1/ 7/99	120.1
рн	7.62		1/ 7/99	150.1
Comment: Analyzed in fie Temperature - C Comment: Analyzed in fie	13	Degrees C	1/ 7/99	
Silver, Dissolved Arsenic, Dissolved Barium, Dissolved Cadmium, Dissolved Chromium, Dissolved Copper, Dissolved Mercury, Dissolved Nickel, Dissolved Lead, Dissolved Selenium, Dissolved Selenium, Dissolved Silver, Total Arsenic, Total Barium, Total Cadmium, Total Chromium, Total	<pre></pre>	ug/L ug/L ug/L ug/L ug/L ug/L ug/L ug/L	1/13/99 1/14/99 1/13/99 1/13/99 1/13/99 1/13/99 1/14/99 1/13/99 1/14/99 1/13/99 1/13/99 1/13/99 1/13/99 1/13/99	200.7 206.2 200.7 200.7 200.7 245.1 200.7 239.2 270.2 200.7 206.2 200.7 200.7

Page 2 Lab Number: 99-D23 Sample Number: 991464 February 10, 1999

		<del></del>		
Analysis Performed	Results		Analyzed	Method
Copper, Total	6.94	ug/L	1/13/99	200.7
Mercury, Total	< 0.20	ug/L	1/29/99	245.1
Nickel, Total	< 3.00	ug/L	1/13/99	200.7
Lead, Total	14.1	ug/L	1/14/99	239.2
Selenium, Total	< 1.0	ug/L	1/14/99	270.2
VOC Results:		_,	, ,	
Dichlorodifluoromethane	< 200	ug/L	1/13/99	502.2
Chloromethane	< 2.5	ug/L	1/13/99	502.2
Vinyl Chloride	< 0.5	ug/L	1/13/99	502.2
Bromomethane	< 9.0	ug/L	1/13/99	502.2
Chloroethane	< 2.5	ug/L	1/13/99	502.2
Trichlorofluoromethane	< 2.5	ug/L	1/13/99	502.2
1,1-Dichloroethene	< 0.5	ug/L	1/13/99	502.2
Methylene Chloride	< 0.5	ug/L	1/13/99	502.2
Methyl-tert-butyl ether	< 2.0	ug/L	1/13/99	502.2
trans-1,2-Dichloroethene	< 0.5	ug/L	1/13/99	502.2
1,1-Dichloroethane	< 1.0	ug/L	1/13/99	502.2
2,2-Dichloropropane	< 1.0	ug/L	1/13/99	502.2
cis-1,2-Dichloroethene	< 0.5	ug/L	1/13/99	502.2
Chloroform	< 0.5	ug/L	1/13/99	502.2
Bromochloromethane	< 1.0	ug/L	1/13/99	502.2
1,1,1-Trichloroethane	< 0.5	ug/L	1/13/99	502.2
1,1-Dichloropropene	< 1.0	ug/L	1/13/99	502.2
Carbon Tetrachloride	< 0.5	ug/L	1/13/99	502.2
Benzene	< 0.5			
1,2-Dichloroethane	< 0.5	ug/L	1/13/99	502.2 502.2
Trichloroethene	10.1	ug/L	1/13/99	
1,2-Dichloropropane	< 0.5	ug/L	1/13/99	502.2
Bromodichloromethane	< 0.5	ug/L	1/13/99	502.2 502.2
Dibromomethane	< 1.0	ug/L	1/13/99	
	< 2.0	ug/L	1/13/99	502.2
cis-1,3-Dichloropropane Toluene	< 0.6	ug/L	1/13/99	502.2
(i)	< 1.0	ug/L	1/13/99	502.2
trans-1,3-Dichloropropane 1,1,2-Trichloroethane	< 0.5	ug/L	1/13/99	502.2
Tetrachloroethene	< 0.5	ug/L	1/13/99	502.2 502.2
		ug/L	1/13/99	
1,3-Dichloropropane Dibromochloromethane	< 2.0 < 0.5	ug/L	1/13/99	502.2
$\Omega$		ug/L	1/13/99	
1,2-Dibromoethane	< 2.0	ug/L	1/13/99	
Chlorobenzene	< 0.5	ug/L	1/13/99	
Ethylbenzene	< 0.5	ug/L	1/13/99	
1,1,1,2-Tetrachloroethane	< 1.0	ug/L	1/13/99	502.2
Total Xylenes	< 0.5	ug/L	1/13/99	502.2
Styrene	< 0.5	ug/L	1/13/99	502.2
Isopropylbenzene	< 2.0	ug/L	1/13/99	502.2
Bromoform	< 0.5	ug/L	1/13/99	502.2
1,1,2,2-Tetrachloroethane	< 1.0	ug/L	1/13/99	502.2
1,2,3-Trichloropropane	< 1.0	ug/l	1/13/99	502.2
n-Propylbenzene	< 2.0	ug/L	1/13/99	502.2


Lab Number: 99-D23 Sample Number: 991464 February 10, 1999

Analysis Performed	Results		Analyzed	Method
Bromobenzene 2-Chlorotoluene 4-Chlorotoluene 1,3,5-Trimethylbenzene tert-Butylbenzene 1,2,4-Trimethylbenzene sec-Butylbenzene p-isopropyltoluene 1,3-Dichlorobenzene 1,4-Dichlorobenzene n-Butylbenzene 1,2-Dichlorobenzene 1,2-Dichlorobenzene 1,2-Trichlorobenzene Hexachlorobutadiene Naphthalene	<pre></pre>	ug/L ug/L ug/L ug/L ug/L ug/L ug/L ug/L	1/13/99 1/13/99 1/13/99 1/13/99 1/13/99 1/13/99 1/13/99 1/13/99 1/13/99 1/13/99 1/13/99 1/13/99 1/13/99 1/13/99 1/13/99 1/13/99 1/13/99 1/13/99 1/13/99	502.2 502.2 502.2 502.2 502.2 502.2 502.2 502.2 502.2 502.2 502.2 502.2 502.2 502.2 502.2
1,2,3-Trichlorobenzene	< 2.0	ug/L	1/13/99	502.2

The analysis of this sample was performed in accordance with procedures approved or recognized by the U.S. Environmental Protection Agency.

James H. Long, Director

Environmental Services Program Division of Environmental Quality



# DEPARTMENT OF NATURAL RESOURCES

DIVISION OF ENVIRONMENTAL QUALITY P.O. Box 176 Jefferson City, MO 65102-0176

Report Date:

Date Collected:

Date Received:

2/10/99 1/ 7/99 1/ 7/99

#### ENVIRONMENTAL SERVICES PROGRAM

#### RESULTS OF SAMPLE ANALYSES

Sample Number: 991465 Lab Number: 99-D24

Reported To: BRIAN ALLEN

Affiliation: ESP

Project Code: 4054/9096

Sample Collected by: Sampling Location: Sample Description: BRIAN ALLEN, ESP FORMER HULETT LAGOON SITE, WATER GRAB OF MW-5, LOCATED ADJACENT

(SOUTHWEST) TO FORMER HULETT LAGOON

County:

CAMDEN

Analysis Performed	Result	ts		Analyzed	Method
Turbidity	<u> </u>	456	NTU	1/ 7/99	180.1
Comment: Analyzed in Specific Conductivity		709	umhos/cm	1/ 7/99	120.1
Comment: Analyzed in :	field	7.50		1/ 7/99	150.1
Comment: Analyzed in Temperature - C		12	Degrees C	1/ 7/99	
Comment: Analyzed in Silver, Dissolved	field	< 5.00	ug/L	1/13/99	200.7
Arsenic, Dissolved Barium, Dissolved		< 1.2 55.7	ug/L ug/L	1/14/99 1/13/99	206.2 200.7
Cadmium, Dissolved Chromium, Dissolved		< 1.00 < 2.00	ug/L ug/L	1/13/99 1/13/99	200.7
Copper, Dissolved Mercury, Dissolved		< 3.00 < 0.20	ug/L ug/L	1/13/99 1/29/99	200.7 245.1
Nickel, Dissolved Lead, Dissolved		< 3.00 < 2.5	ug/L ug/L	1/13/99 1/14/99	200.7
Selenium, Dissolved		< 1.0 < 5.00	ug/L	1/14/99	270.2
Silver, Total Arsenic, Total		< 1.2	ug/L ug/L	1/13/99	200.7
Barium, Total Cadmium, Total		67.9 1.25	ug/L ug/L	1/13/99 1/13/99	200.7 200.7
Chromium, Total Copper, Total		9.39 7.52	ug/L ug/L	1/13/99 1/13/99	200.7 200.7

Page 2 Lab Number: 99-D24 Sample Number: 991465 February 10, 1999

Analysis Performed	Results		Analyzed	Method
Mercury, Total	< 0.20	ug/L	1/29/99	245.1
Nickel, Total	5.16	ug/L	1/13/99	200.7
Lead, Total	12.7	2/	1/14/99	239.2
Selenium, Total	< 1.0	ug/L	1/14/99	270.2
VOA Results: Chloromethane	- F 0	/~		
	< 5.0	ug/L	1/ 8/99	8260
Vinyl Chloride Bromomethane	< 5.0	ug/L	1/8/99	8260
Chloroethane	< 5.0	ug/L	1/8/99	8260
1,1-Dichloroethene	< 5.0 < 5.0	ug/L	1/8/99	8260
Acetone	< 20.0	ug/L	1/ 8/99	8260
Carbon Disulfide	< 5.0	ug/L	1/ 8/99	8260
Methylene Chloride	< 20.0	ug/L ug/L	1/8/99	8260 8260
Methyl Tert-Butyl Ether	< 5.0	ug/L	1/ 8/99 1/ 8/99	8260
trans-1,2-Dichloroethene	< 5.0	ug/L	1/ 8/99	8260
1,1-Dichloroethane	< 5.0	ug/L	1/ 8/99	8260
2-Butanone	< 20.0	ug/L	1/ 8/99	8260
cis-1,2-Dichloroethene	35.0	ug/L	1/ 8/99	8260
Chloroform	< 5.0	ug/L	1/ 8/99	8260
1,1,1-Trichloroethane	< 5.0	ug/L	1/ 8/99	8260
Carbon Tetrachloride	< 5.0	ug/L	1/ 8/99	8260
Benzene	< 5.0	ug/L	1/ 8/99	8260
1,2-Dichloroethane	< 5.0	ug/L	1/ 8/99	8260
Trichloroethene	1,400	ug/L	1/ 8/99	8260
1,2-Dichloropropane	< 5.0	ug/L	1/ 8/99	8260
Bromodichloromethane	< 5.0	ug/L	1/ 8/99	8260
2-Hexanone	< 20.0	ug/L	1/ 8/99	8260
Trans-1,3-Dichloropropene	< 5.0	ug/L	1/ 8/99	8260
Toluene	< 5.0	ug/L	1/ 8/99	8260
CIS-1,3-Dichloropropene	< 5.0	ug/L	1/ 8/99	8260
1,1,2-Trichloroethane	< 5.0	ug/L	1/ 8/99	8260
4-Methyl-2-Pentanone	< 20.0	ug/L	1/ 8/99	8260
Tetrachloroethene	< 5.0	na\r	1/8/99	8260
Dibromochloromethane	< 5.0	ug/L	1/ 8/99	8260
Chlorobenzene	< 5.0	ug/L	1/ 8/99	8260
Ethylbenzene	< 5.0	ug/L	1/8/99	8260
Total Xylenes Styrene	< 5.0 < 5.0	ug/L	1/8/99	8260
Bromoform	< 5.0	ug/L	1/8/99	8260
1,1,2,2-Tetrachloroethane	< 5.0	ug/L ug/L	1/ 8/99 1/ 8/99	8260 8260
1,3-Dichlorobenzene	< 5.0	ug/L	1/ 8/99	8260
1,4-Dichlorobenzene	< 5.0	ug/L ug/L	1/ 8/99	8260 8260
1,2-Dichlorobenzene	< 5.0	ug/L ug/L	1/ 8/99	8260
Z, Z DIONIOLODONIDONO	· J. ·	49/11	1/ 0/99	

Lab Number: 99-D24 Sample Number: 991465 February 10, 1999

The analysis of this sample was performed in accordance with procedures approved or recognized by the U.S. Environmental Protection Agency.

James H. Long, Director

Environmental Services Program Division of Environmental Quality



Mel Carnahan, Governor + Stephen M. Mahfood, Director

# TENT OF NATURAL RESOURCES

-DIVISION OF ENVIRONMENTAL QUALITY -P.O. Box 176 Jefferson City, MO 65102-0176

#### ENVIRONMENTAL SERVICES PROGRAM

#### RESULTS OF SAMPLE ANALYSES

Sample Number: 991466 Lab Number: 99-D25

BRIAN ALLEN Reported To:

Affiliation: ESP

Project Code: 4054/9096

Report Date: 2/10/99 1/ 7/99 1/ 7/99 Date Collected:

Date Received:

Sample Collected by:

Sampling Location:

Sample Description:

BRIAN ALLEN, ESP

FORMER HULETT LAGOON SITE, WATER GRAB OF MW-5, LOCATED ADJACENT

(SOUTHWEST) TO FORMER HULETT LAGOON

(DUPLICATE)

County:

CAMDEN

Analysis Performed	Results		Analyzed	Method
Turbidity	456	5 NTU	1/ 7/99	180.1
Comment: Analyzed in Specific Conductivity	709	umhos/cm	1/ 7/99	120.1
Comment: Analyzed in pH	7	7.50	1/ 7/99	150.1
Comment: Analyzed in Temperature - C Comment: Analyzed in	12	Degrees C	1/ 7/99	
Silver, Dissolved Arsenic, Dissolved Barium, Dissolved Cadmium, Dissolved Chromium, Dissolved Copper, Dissolved Mercury, Dissolved Nickel, Dissolved Lead, Dissolved Selenium, Dissolved Silver, Total Arsenic, Total Barium, Total Cadmium, Total	< 5 < 1 < 2 < 3 < 0 < 3 < 1 < 2 < 3 < 1	5.00 ug/L 1.2 ug/L 1.6 ug/L 1.00 ug/L 2.00 ug/L 3.00 ug/L 0.20 ug/L 0.20 ug/L 1.0 ug/L 1.0 ug/L 1.2 ug/L 1.3 ug/L 1.97 ug/L 1.97 ug/L	1/13/99 1/14/99 1/13/99 1/13/99 1/13/99 1/13/99 1/14/99 1/14/99 1/13/99 1/13/99 1/13/99 1/13/99 1/13/99	200.7 200.7 200.7 200.7 245.1 200.7 239.2 270.2 200.7 206.2 200.7

Page 2 Lab Number: 99-D25 Sample Number: 991466 February 10, 1999

Analysis Performed	Results		Analyzed	Method
Copper, Total	8.97	ug/L	1/13/99	200.7
Mercury, Total	< 0.20	ug/L	1/29/99	245.1
Nickel, Total	4.26	ug/L	1/13/99	200.7
Lead, Total	15.3	ug/L	1/14/99	239.2
Selenium, Total	< 1.0	ug/L	1/14/99	270.2
VOA Results:		-,	, ,	
Chloromethane	< 5.0	ug/L	1/ 8/99	8260
Vinyl Chloride	< 5.0	ug/L	1/ 8/99	8260
Bromomethane	< 5.0	ug/L	1/ 8/99	8260
Chloroethane	< 5.0	ug/L	1/8/99	8260
1,1-Dichloroethene	< 5.0	ug/L	1/ 8/99	8260
Acetone	< 20.0	ug/L	1/ 8/99	8260
Carbon Disulfide	< 5.0	ug/L	1/ 8/99	8260
Methylene Chloride	< 20.0	ug/L	1/ 8/99	8260
Methyl Tert-Butyl Ether	< 5.0	ug/L	1/ 8/99	8260
trans-1,2-Dichloroethene	< 5.0	ug/L	1/ 8/99	8260
1,1-Dichloroethane	< 5.0			
·	< 20.0	ug/L	1/8/99	8260
2-Butanone		ug/L	1/ 8/99	8260
cis-1,2-Dichloroethene	23.0	ug/L	1/ 8/99	8260
Chloroform	< 5.0	ug/L	1/ 8/99	8260
1,1,1-Trichloroethane	< 5.0	ug/L	1/8/99	8260
Carbon Tetrachloride	< 5.0	ug/L	1/ 8/99	8260
Benzene	< 5.0	ug/L	1/ 8/99	8260
1,2-Dichloroethane	< 5.0	ug/L	1/ 8/99	8260
Trichloroethene	1,500	ug/L	1/ 8/99	8260
1,2-Dichloropropane	< 5.0	ug/L	1/ 8/99	8260
Bromodichloromethane	< 5.0	ug/L	1/ 8/99	8260
2-Hexanone	< 20.0	ug/L	1/ 8/99	8260
Trans-1,3-Dichloropropene	< 5.0	ug/L	1/ 8/99	8260
Toluene	< 5.0	ug/L	1/ 8/99	8260
CIS-1,3-Dichloropropene	< 5.0	ug/L	1/ 8/99	8260
1,1,2-Trichloroethane	< 5.0	ug/L	1/ 8/99	8260
4-Methyl-2-Pentanone	< 20.0	ug/L	1/ 8/99	8260
Tetrachloroethene	< 5.0	ug/L	1/ 8/99	8260
Dibromochloromethane	< 5.0	ug/L	1/ 8/99	8260
Chlorobenzene	< 5.0	ug/L	1/ 8/99	8260
Ethylbenzene	< 5.0	ug/L	1/ 8/99	8260
Total Xylenes	< 5.0	ug/L	1/ 8/99	8260
<b>-</b>	< 5.0	ug/L	1/ 8/99	8260
Styrene	< 5.0		1/ 8/99	8260
Bromoform	< 5.0	ug/L	1/ 8/99	8260
1,1,2,2-Tetrachloroethane	< 5.0	ug/L	1/ 8/99	8260
1,3-Dichlorobenzene		ug/L		
1,4-Dichlorobenzene	< 5.0	ug/L	1/8/99	8260
1,2-Dichlorobenzene	< 5.0	ug/L	1/ 8/99	8260


Lab Number: 99-D25 Sample Number: 991466

February 10, 1999

The analysis of this sample was performed in accordance with procedures approved or recognized by the U.S. Environmental Protection Agency.

James/H. Long, Director

Environmental Services Program
Division of Environmental Quality





### IT OF NATURAL RESOURCES

P.O. Box 176 Jefferson City, MO 65102-0176

#### ENVIRONMENTAL SERVICES PROGRAM

#### RESULTS OF SAMPLE ANALYSES

Sample Number: 991467 Lab Number: 99-D136

Reported To: BRIAN ALLEN

Affiliation: ESP

Project Code: 4054/9096

ESP

Report Date: 2/24/99 Date Collected: 1/21/99

Date Received: 1/21/99

Sample Collected by:

Sampling Location:

BRIAN ALLEN, ESP

FORMER HULETT LAGOON SITE

Sample Description:

SOIL GRAB OF BORING "HULETT-03"

COLLECTED FROM 3-4 FT DEPTH

County: CAMDEN

Analysis Performed	Results		Analyzed	Method
Silver, Total	< 1,000	ug/kg	2/ 3/99	200.7
Arsenic, Total	13,600	ug/kg	2/ 4/99	206.2
Barium, Total	244,000	ug/kg	2/ 3/99	200.7
Cadmium, Total	304	ug/kg	2/3/99	200.7
Chromium, Total	55,500	ug/kg	2/ 3/99	200.7
Copper, Total	33,600	ug/kg	2/ 3/99	200.7
Mercury, Total	107	ug/kg	1/29/99	245.1
Nickel, Total	49,400	ug/kg	2/3/99	200.7
Lead, Total	118,000	ug/kg	2/ 3/99	239.2
Selenium, Total	< 1,000	ug/kg	2/4/99	270.2
Lead, TCLP	77.2	ug/L	2/19/99	239.2
VOA Results:				
Chloromethane	< 25.0	ug/kg	1/25/99	8260
Vinyl Chloride	< 25.0	ug/kg	1/25/99	8260
Bromomethane	< 25.0	ug/kg	1/25/99	8260
Chloroethane	< 25.0	ug/kg	1/25/99	8260
1,1-Dichloroethene	< 25.0	ug/kg	1/25/99	8260
Acetone	< 100	ug/kg	1/25/99	8260
Carbon Disulfide	< 25.0	ug/kg	1/25/99	8260
Methylene Chloride	< 100	ug/kg	1/25/99	8260
Methyl Tertiary Butyl Eth	< 25.0	ug/kg	1/25/99	8260
trans-1,2-Dichloroethene	< 25.0	ug/kg	1/25/99	8260
1,1-Dichloroethane	< 25.0	ug/kg	1/25/99	8260
2-Butanone	< 100	ug/kg	1/25/99	8260


Lab Number: 99-D136 Sample Number: 991467 February 24, 1999

Analysis Performed	Results		Analyzed	Method
cis-1,2-Dichloroethene	< 25.0	ug/kg	1/25/99	8260
Chloroform	< 25.0	ug/kg	1/25/99	8260
1,1,1-Trichloroethane	< 25.0	ug/kg	1/25/99	8260
Carbon Tetrachloride	< 25.0	ug/kg	1/25/99	8260
Benzene	< 25.0	ug/kg	1/25/99	8260
1,2-Dichloroethane	< 25.0	ug/kg	1/25/99	8260
Trichloroethene	< 25.0	ug/kg	1/25/99	8260
1,2-Dichloropropane	< 25.0	ug/kg	1/25/99	8260
Bromodichloromethane	< 25.0	ug/kg	1/25/99	8260
2-Hexanone	< 100	ug/kg	1/25/99	8260
Trans-1,3-Dichloropropene	< 25.0	ug/kg	1/25/99	8260
Toluene	< 25.0	ug/kg	1/25/99	8260
CIS-1,3-Dichloropropene	< 25.0	ug/kg	1/25/99	8260
1,1,2-Trichloroethane	< 25.0	ug/kg	1/25/99	8260
4-Methyl-2-Pentanone	< 100	ug/kg	1/25/99	8260
Tetrachloroethene	< 25.0	ug/kg	1/25/99	8260
Dibromochloromethane	< 25.0	ug/kg	1/25/99	8260
Chlorobenzene	< 25.0	ug/kg	1/25/99	8260
Ethylbenzene	< 25.0	ug/kg	1/25/99	8260
Total Xylenes	< 25.0	ug/kg	1/25/99	8260
Styrene	< 25.0	ug/kg	1/25/99	8260
Bromoform	< 25.0	ug/kg	1/25/99	8260
1,1,2,2-Tetrachloroethane	< 25.0	ug/kg	1/25/99	8260
1,3-Dichlorobenzene	< 25.0	ug/kg	1/25/99	8260
1,4-Dichlorobenzene	< 25.0	ug/kg	1/25/99	8260
1,2-Dichlorobenzene	< 25.0	ug/kg	1/25/99	8260

Metals results are reported on a dry weight basis

The analysis of this sample was performed in accordance with procedures approved or recognized by the U.S. Environmental Protection Agency.

James H. Long, Birector Environmental Services Program Division of Environmental Quality





### TOF NATURAL RESOURCES

DIVISION OF ENVIRONMENTAL QUALITY P.O. Box 176 Jefferson City, MO 65102-0176

#### ENVIRONMENTAL SERVICES PROGRAM

#### RESULTS OF SAMPLE ANALYSES

Sample Number: 991468 Lab Number: 99-D137

BRIAN ALLEN Reported To:

Affiliation: **ESP** 

Project Code: 4054/9096

Report Date: 2/24/99 1/21/99 Date Collected:

1/22/99 Date Received:

Sample Collected by:

Sampling Location:

FORMER HULETT LAGOON SITE

BRIAN ALLEN, ESP

SOIL GRAB OF BORING "HULETT-03" Sample Description:

COLLECTED FROM 4.5-5.5 FT DEPTH

CAMDEN County:

Analysis Performed	Results		Analyzed	Method
Silver, Total	< 1,000	ug/kg	2/ 3/99	200.7
Arsenic, Total	12,500	ug/kg	2/ 4/99	206.2
Barium, Total	519,000	ug/kg	2/ 3/99	200.7
Cadmium, Total	386	ug/kg	2/ 3/99	200.7
Chromium, Total Copper, Total Mercury, Total Nickel, Total	61,300 37,500 139 69,600	ug/kg ug/kg ug/kg ug/kg	2/ 3/99 2/ 3/99 1/29/99 2/ 3/99	200.7
Lead, Total Selenium, Total Barium, TCLP Lead, TCLP	951,000	ug/kg	2/ 3/99	239.2
	< 1,000	ug/kg	2/ 4/99	270.2
	442	ug/L	2/19/99	200.7
	143	ug/L	2/19/99	239.2
VOA Results: Chloromethane Vinyl Chloride Bromomethane	< 25.0	ug/kg	1/25/99	8260
	< 25.0	ug/kg	1/25/99	8260
	< 25.0	ug/kg	1/25/99	8260
Chloroethane 1,1-Dichloroethene Acetone Carbon Disulfide	< 25.0	ug/kg	1/25/99	8260
	< 25.0	ug/kg	1/25/99	8260
	< 100	ug/kg	1/25/99	8260
	< 25.0	ug/kg	1/25/99	8260
Methylene Chloride Methyl Tertiary Butyl Eth trans-1,2-Dichloroethene 1,1-Dichloroethane	< 100	ug/kg	1/25/99	8260
	< 25.0	ug/kg	1/25/99	8260
	< 25.0	ug/kg	1/25/99	8260
	< 25.0	ug/kg	1/25/99	8260

Lab Number: 99-D137 Sample Number: 991468 February 24, 1999


Analysis Performed	Results		Analyzed	Method
2-Butanone	< 100	ug/kg	1/25/99	8260
cis-1,2-Dichloroethene	< 25.0	ug/kg	1/25/99	8260
Chloroform	< 25.0	ug/kg	1/25/99	8260
1,1,1-Trichloroethane	< 25.0	ug/kg	1/25/99	8260
Carbon Tetrachloride	< 25.0	ug/kg	1/25/99	8260
Benzene	< 25.0	ug/kg	1/25/99	8260
1,2-Dichloroethane	< 25.0	ug/kg	1/25/99	8260
Trichloroethene	< 25.0	ug/kg	1/25/99	8260
1,2-Dichloropropane	< 25.0	ug/kg	1/25/99	8260
Bromodichloromethane	< 25.0	ug/kg	1/25/99	8260
2-Hexanone	< 100	ug/kg	1/25/99	8260
Trans-1,3-Dichloropropene	< 25.0	ug/kg	1/25/99	8260
Toluene	< 25.0	ug/kg	1/25/99	8260
CIS-1,3-Dichloropropene	< 25.0	ug/kg	1/25/99	8260
1,1,2-Trichloroethane	< 25.0	ug/kg	1/25/99	8260
4-Methyl-2-Pentanone	< 100	ug/kg	1/25/99	8260
Tetrachloroethene	< 25.0	ug/kg	1/25/99	8260
Dibromochloromethane	< 25.0	ug/kg	1/25/99	8260
Chlorobenzene	< 25.0	ug/kg	1/25/99	8260
Ethylbenzene	< 25.0	ug/kg	1/25/99	8260
Total Xylenes	< 25.0	ug/kg	1/25/99	8260
Styrene	< 25.0	ug/kg	1/25/99	8260
Bromoform	< 25.0	ug/kg	1/25/99	8260
1,1,2,2-Tetrachloroethane	< 25.0	ug/kg	1/25/99	8260
1,3-Dichlorobenzene	< 25.0	ug/kg	1/25/99	8260
1,4-Dichlorobenzene	< 25.0	ug/kg	1/25/99	8260
1,2-Dichlorobenzene	< 25.0	ug/kg	1/25/99	8260

Metals results are reported on a dry weight basis

The analysis of this sample was performed in accordance with procedures approved or recognized by the U.S. Environmental Protection Agency.

James H. Long, Director

Environmental Services Program
Division of Environmental Quality





### ENT OF NATURAL RESOURCES

DIVISION OF ENVIRONMENTAL QUALITY P.O. Box 176 Jefferson City, MO 65102-0176

#### ENVIRONMENTAL SERVICES PROGRAM

#### RESULTS OF SAMPLE ANALYSES

Sample Number: 991469 Lab Number: 99-D138

Reported To: BRIAN ALLEN

Affiliation: ESP

Project Code: 4054/9096

Report Date: 2/24/99 Date Collected: 1/21/99

Date Received: 1/22/99

Sample Collected by:

BRIAN ALLEN, ESP

Sampling Location:

FORMER HULETT LAGOON SITE

Sample Description:

County:

SOIL GRAB OF BORING "HULETT-01" COLLECTED FROM 4.5-5 FT DEPTH

CAMDEN

Analysis Performed Results Analyzed Method 200.7 < 1,000 uq/kg 2/ 3/99 Silver, Total 16,100 ug/kg 2/ 4/99 206.2 Arsenic, Total 2/ 3/99 2/ 3/99 Barium, Total ug/kg 150,000 200.7 453 Cadmium, Total ug/kg 200.7 74,900 2/ 3/99 ug/kg 200.7 Chromium, Total 2/ 3/99 Copper, Total 39,900 ug/kg 200.7 Mercury, Total 1/29/99 102 ug/kg 245.1 43,300 Nickel, Total ug/kg 2/ 3/99 200.7 2/ 3/99 Lead, Total 239.2 116,000 ug/kg 2/ 4/99 Selenium, Total < 1,000 ug/kg 270.2 < 25.0 2/19/99 239.2 Lead, TCLP ug/L VOA Results: < 25.0 ug/kg 1/25/99 8260 Chloromethane < 25.0 ug/kg 1/25/99 8260 Vinyl Chloride Bromomethane < 25.0 ug/kg 1/25/99 8260 Chloroethane < 25.0 ug/kg 1/25/99 8260 < 25.0 ug/kg 1/25/99 8260 1,1-Dichloroethene < 100 ug/kg 1/25/99 8260 Acetone Carbon Disulfide < 25.0 1/25/99 ug/kg 8260 1/25/99 < 100 Methylene Chloride 8260 ug/kg < 25.0 ug/kg 1/25/99 Methyl Tertiary Butyl Eth 8260 < 25.0 trans-1,2-Dichloroethene ug/kg 1/25/99 8260 1,1-Dichloroethane < 25.0 1/25/99 8260 ug/kg < 100 2-Butanone ug/kg 1/25/99 8260

Page 2 Lab Number: 99-D138 Sample Number: 991469 February 24, 1999

Analysis Performed	Results		Analyzed	Method
cis-1,2-Dichloroethene	190	ug/kg	1/25/99	8260
Chloroform	< 25.0	ug/kg	1/25/99	8260
1,1,1-Trichloroethane	< 25.0	ug/kg	1/25/99	8260
Carbon Tetrachloride	< 25.0	ug/kg	1/25/99	8260
Benzene	< 25.0	ug/kg	1/25/99	8260
1,2-Dichloroethane	< 25.0	ug/kg	1/25/99	8260
Trichloroethene	9,500	ug/kg	1/25/99	8260
Comment: Dilution analyze	ed 1/26/99	3, 3	, ,	
1,2-Dichloropropane	< 25.0	ug/kg	1/25/99	8260
Bromodichloromethane	< 25.0	ug/kg	1/25/99	8260
2-Hexanone	< 25.0 < 100	ug/kg	1/25/99	8260
Trans-1,3-Dichloropropene	< 25.0	ug/kg	1/25/99	8260
Toluene	. < 25.0	ug/kg	1/25/99	8260
CIS-1,3-Dichloropropene	< 25.0	ug/kg	1/25/99	8260
1,1,2-Trichloroethane	< 25.0	ug/kg	1/25/99	8260
4-Methyl-2-Pentanone	< 100	ug/kg	1/25/99	8260
Tetrachloroethene	< 25.0	ug/kg	1/25/99	8260
Dibromochloromethane	< 25.0	ug/kg	1/25/99	8260
Chlorobenzene	< 25.0	ug/kg	1/25/99	8260
Ethylbenzene	< 25.0	ug/kg	1/25/99	8260
Total Xylenes	< 25.0	ug/kg	1/25/99	8260
Styrene	< 25.0	ug/kg	1/25/99	8260
Bromoform	< 25.0	ug/kg	1/25/99	8260
1,1,2,2-Tetrachloroethane	< 25.0	ug/kg	1/25/99	8260
1,3-Dichlorobenzene	< 25.0	ug/kg	1/25/99	8260
1,4-Dichlorobenzene	< 25.0	ug/kg	1/25/99	8260
1,2-Dichlorobenzene	< 25.0	ug/kg	1/25/99	8260
VOA TCLP Results:		3/ 3	, -,	
Vinyl Chloride (TCLP)	< 200	ug/L	2/ 8/99	8260
1,1-Dichloroethene (TCLP)		ug/L	2/8/99	8260
2-Butanone (TCLP)	< 800	ug/L	2/ 8/99	8260
Chloroform (TCLP)	< 200	ug/L	2/ 8/99	8260
Carbon Tetrachlor. (TCLP)	< 200	ug/L	2/ 8/99	8260
Benzene (TCLP)	< 200	ug/L	2/ 8/99	8260
1,2-Dichloroethane (TCLP)	< 200	ug/L	2/ 8/99	8260
Trichloroethene (TCLP)	< 200	ug/L	2/ 8/99	8260
Tetrachloroethene (TCLP)		ug/L	2/ 8/99	8260
Chlorobenzene (TCLP)	< 200	ug/L	2/ 8/99	8260
1,4-Dichlorobenz. (TCLP)	< 200	ug/L	2/ 8/99	8260
1,1 510.101050.12. (1051)		~9/ <del>1</del>	-, 0, 55	

Lab Number: 99-D138 Sample Number: 991469

February 24, 1999


Metals results are reported on a dry weight basis

The analysis of this sample was performed in accordance with procedures approved or recognized by the U.S. Environmental Protection Agency.

James H. Long, Director

Environmental Services Program Qivision of Environmental Quality

VALERIE WILDER, HWP c:



# MENT OF NATURAL RESOURCES

Report Date:

Date Collected:

Date Received:

2/17/99 1/21/99

1/22/99

DIVISION OF ENVIRONMENTAL QUALITY -PO. Box 176 Jefferson City, MO 65102-0176

#### ENVIRONMENTAL SERVICES PROGRAM

#### RESULTS OF SAMPLE ANALYSES

Sample Number: 991470 Lab Number: 99-D139

Reported To: BRIAN ALLEN

Affiliation: ESP

Project Code: 4054/9096

BRIAN ALLEN, ESP

FORMER HULETT LAGOON SITE

Sampling Location:

Sample Collected by:

Sample Description:

SOIL GRAB OF BORING "HULETT-02" COLLECTED FROM 6.5-7 FT DEPTH

County:

· CAMDEN

Analysis Performed	Results		Analyzed	Method
Silver, Total	< 1,000	ug/kg	2/ 3/99	200.7
Arsenic, Total	3,580	ug/kg	2/4/99	206.2
Barium, Total	62,400	ug/kg	2/ 3/99	200.7
Cadmium, Total	254	ug/kg	2/ 3/99	200.7
Chromium, Total	31,900	ug/kg	2/3/99	200.7
Copper, Total	15,700	ug/kg	2/ 3/99	200.7
Mercury, Total	< 40.0	ug/kg	1/29/99	245.1
Nickel, Total	12,500	ug/kg	2/ 3/99	200.7
Lead, Total	38,100	ug/kg	2/ 3/99	239.2
Selenium, Total	< 1,000	ug/kg	2/ 4/99	270.2
VOA Results:				
Chloromethane	< 25.0	ug/kg	1/25/99	8260
Vinyl Chloride	< 25.0	ug/kg	1/25/99	8260
Bromomethane	< 25.0	ug/kg	1/25/99	8260
Chloroethane	< 25.0	ug/kg	1/25/99	8260
1,1-Dichloroethene	< 25.0	ug/kg	1/25/99	8260
Acetone	< 100	ug/kg	1/25/99	8260
Carbon Disulfide	< 25.0	ug/kg	1/25/99	8260
Methylene Chloride	< 100	ug/kg	1/25/99	8260
Methyl Tertiary Butyl Eth	< 25.0	ug/kg	1/25/99	8260
trans-1,2-Dichloroethene	< 25.0	ug/kg	1/25/99	8260
1,1-Dichloroethane	< 25.0	ug/kg	1/25/99	
2-Butanone	< 100	ug/kg	1/25/99	
cis-1,2-Dichloroethene	140	ug/kg	1/25/99	8260

Lab Number: 99-D139 Sample Number: 991470 February 17, 1999

Analysis Performed	Results		Analyzed	Method
Chloroform	< 25.0	ug/kg	1/25/99	8260
1,1,1-Trichloroethane	< 25.0	ug/kg	1/25/99	8260
Carbon Tetrachloride	< 25.0	ug/kg	1/25/99	8260
Benzene	< 25.0	ug/kg	1/25/99	8260
1,2-Dichloroethane	< 25.0	ug/kg	1/25/99	8260
Trichloroethene	240	ug/kg	1/25/99	8260
1,2-Dichloropropane	< 25.0	ug/kg	1/25/99	8260
Bromodichloromethane	< 25.0	ug/kg	.1/25/99	8260
2-Hexanone	< 100	ug/kg	1/25/99	8260
Trans-1,3-Dichloropropene	< 25.0	ug/kg	1/25/99	8260
Toluene	< 25.0	ug/kg	1/25/99	8260
CIS-1,3-Dichloropropene	< 25.0	ug/kg	1/25/99	8260
1,1,2-Trichloroethane	< 25.0	ug/kg	1/25/99	8260
4-Methyl-2-Pentanone	< 100	ug/kg	1/25/99	8260
Tetrachloroethene	< 25.0	ug/kg	1/25/99	8260
Dibromochloromethane	< 25.0	ug/kg	1/25/99	8260
Chlorobenzene	< 25.0	ug/kg	1/25/99	8260
Ethylbenzene	< 25.0	ug/kg	1/25/99	8260
Total Xylenes	< 25.0	ug/kg	1/25/99	8260
Styrene	< 25.0	ug/kg	1/25/99	8260
Bromoform	< 25.0	ug/kg	1/25/99	8260
1,1,2,2-Tetrachloroethane	< 25.0	ug/kg	1/25/99	8260
1,3-Dichlorobenzene	< 25.0	ug/kg	1/25/99	8260
1,4-Dichlorobenzene	< 25.0	ug/kg	1/25/99	8260
1,2-Dichlorobenzene	< 25.0	ug/kg	1/25/99	8260

Metals results are reported on a dry weight basis

The analysis of this sample was performed in accordance with procedures approved or recognized by the U.S. Environmental Protection Agency.

James H. Long, Director

Environmental Services Program
Division of Environmental Quality



Mel Carnahan, Governor . Stephen M. Mahfood, Director

# TOF NATURAL RESOURCES

-DIVISION OF ENVIRONMENTAL QUALITY -P.O. Box 176 Jefferson City, MO 65102-0176

#### ENVIRONMENTAL SERVICES PROGRAM

#### RESULTS OF SAMPLE ANALYSES

Sample Number: 991471 Lab Number: 99-D140

Reported To: BRIAN ALLEN

Affiliation: ESP

Project Code: 4054/9096

Report Date: 2/24/99 Date Collected: 1/21/99

1/22/99 Date Received:

Sample Collected by: BRIAN ALLEN, ESP

Sampling Location:

FORMER HULETT LAGOON SITE

Sample Description:

SOIL GRAB OF BORING "HULETT-04"

COLLECTED FROM 7.5-8 FT DEPTH

CAMDEN County:

Analysis Performed	Results		Analyzed	Method
Silver, Total	< 1,000	ug/kg	2/ 3/99	200.7
Arsenic, Total	19,700	ug/kg	2/4/99	206.2
Barium, Total	750,000	ug/kg	2/ 3/99	200.7
Cadmium, Total	4,520	ug/kg	2/ 3/99	200.7
Chromium, Total	68,900	ug/kg	2/ 3/99	200.7
Copper, Total	64,300	ug/kg	2/ 3/99	200.7
Mercury, Total	195	ug/kg	1/29/99	245.1
Nickel, Total	90,100	ug/kg	2/ 3/99	200.7
Lead, Total	325,000	ug/kg	2/ 3/99	239.2
Selenium, Total	< 1,000	ug/kg	2/ 4/99	
Barium, TCLP	628	ug/L	2/19/99	200.7
Lead, TCLP	< 25.0	ug/L	2/19/99	239.2
VOA Results:			, ,	
Chloromethane	< 25.0	ug/kg	1/26/99	8260
Vinyl Chloride	< 25.0	ug/kg	1/26/99	8260
Bromomethane	< 25.0	ug/kg	1/26/99	8260
Chloroethane	< 25.0	ug/kg	1/26/99	8260
1,1-Dichloroethene	< 25.0	ug/kg	1/26/99	8260
Acetone	< 100	ug/kg	1/26/99	8260
Carbon Disulfide	< 25.0	ug/kg	1/26/99	8260
Methylene Chloride	< 100	ug/kg	1/26/99	8260
Methyl Tertiary Butyl Eth	< 25.0	ug/kg	1/26/99	8260
trans-1,2-Dichloroethene	< 25.0	ug/kg	1/26/99	8260
1,1-Dichloroethane	< 25.0	ug/kg	1/26/99	8260

Lab Number: 99-D140 Sample Number: 991471 February 24, 1999

Analysis Performed	Results		Analyzed	Method
2-Butanone	< 100	ug/kg	1/26/99	8260
cis-1,2-Dichloroethene	< 25.0	ug/kg	1/26/99	8260
Chloroform	< 25.0	ug/kg	1/26/99	8260
1,1,1-Trichloroethane	< 25.0	ug/kg	1/26/99	8260
Carbon Tetrachloride	< 25.0	ug/kg	1/26/99	8260
Benzene	< 25.0	ug/kg	1/26/99	8260
1,2-Dichloroethane	< 25.0	ug/kg	1/26/99	8260
Trichloroethene	< 25.0	ug/kg	1/26/99	8260
1,2-Dichloropropane	< 25.0	ug/kg	1/26/99	8260
Bromodichloromethane	< 25.0	ug/kg	1/26/99	8260
2-Hexanone	< 100	ug/kg	1/26/99	8260
Trans-1,3-Dichloropropene	< 25.0	ug/kg	1/26/99	8260
Toluene	< 25.0	ug/kg	1/26/99	8260
CIS-1,3-Dichloropropene	< 25.0	ug/kg	1/26/99	8260
1,1,2-Trichloroethane	< 25.0	ug/kg	1/26/99	8260
4-Methyl-2-Pentanone	< 100	ug/kg	1/26/99	8260
Tetrachloroethene	< 25.0	ug/kg	1/26/99	8260
Dibromochloromethane	< 25.0	ug/kg	1/26/99	8260
Chlorobenzene	< 25.0	ug/kg	1/26/99	8260
Ethylbenzene	< 25.0	ug/kg	1/26/99	8260
Total Xylenes	< 25.0	ug/kg	1/26/99	8260
Styrene Styrene	< 25.0	ug/kg	1/26/99	8260
Bromoform	< 25.0	ug/kg	1/26/99	8260
1,1,2,2-Tetrachloroethane	< 25.0	ug/kg	1/26/99	8260
1,3-Dichlorobenzene	< 25.0	ug/kg	1/26/99	8260
1,4-Dichlorobenzene	< 25.0	ug/kg	1/26/99	8260
1,2-Dichlorobenzene	< 25.0	ug/kg	1/26/99	8260

Metals results are reported on a dry weight basis

The analysis of this sample was performed in accordance with procedures approved or recognized by the U.S. Environmental Protection Agency.

James H. Long, Director

Environmental Services Program Division of Environmental Quality



Mel Carnahan, Governor + Stephen M. Mahfood. Director.

# IT OF NATURAL RESOURCES

DIVISION OF ENVIRONMENTAL QUALITY PO. Box 176 Jefferson City, MO 65102-0176

#### ENVIRONMENTAL SERVICES PROGRAM

#### RESULTS OF SAMPLE ANALYSES

Sample Number: 991472 Lab Number: 99-D141

Reported To: BRIAN ALLEN

Affiliation: **ESP** 

Project Code: 4054/9096

Report Date:

Date Collected:

2/24/99 1/21/99

Date Received:

1/22/99

Sample Collected by:

BRIAN ALLEN, ESP

Sampling Location: Sample Description: FORMER HULETT LAGOON SITE

SOIL GRAB OF BORING "HULETT-07" COLLECTED FROM 5.5-6 FT DEPTH

County:

CAMDEN

Analysis Performed	Results		Analyzed	Method
Silver, Total	< '1,000	ug/kg	2/ 3/99	200.7
Arsenic, Total	17,200	ug/kg	2/ 4/99	206.2
Barium, Total	257,000	ug/kg	2/ 3/99	200.7
Cadmium, Total	304	ug/kg	2/ 3/99	200.7
Chromium, Total	73,300	ug/kg	2/ 3/99	200.7
Copper, Total	38,800	ug/kg	2/ 3/99	200.7
Mercury, Total	141	ug/kg	1/29/99	245.1
Nickel, Total	36,200	ug/kg	2/ 3/99	200.7
Lead, Total	80,100	ug/kg	2/ 3/99	239.2
Selenium, Total	< 1,000	ug/kg	2/ 4/99	270.2
Lead, TCLP	< 25.0	ug/L	2/19/99	239.2
VOA Results:				
Chloromethane	< 25.0	ug/kg	1/26/99	8260
Vinyl Chloride	< 25.0	ug/kg	1/26/99	8260
Bromomethane	< 25.0	ug/kg	1/26/99	8260
Chloroethane	< 25.0	ug/kg	1/26/99	8260
1,1-Dichloroethene	< 25.0	ug/kg	1/26/99	8260
Acetone	< 100	ug/kg	1/26/99	8260
Carbon Disulfide	< 25.0	ug/kg	1/26/99	8260
Methylene Chloride	< 100	ug/kg	1/26/99	8260
Methyl Tertiary Butyl Eth	< 25.0	ug/kg	1/26/99	8260
trans-1,2-Dichloroethene	< 25.0	ug/kg	1/26/99	8260
1,1-Dichloroethane	< 25.0	ug/kg	1/26/99	8260
2-Butanone	< 100	ug/kg	1/26/99	8260

Lab Number: 99-D141 Sample Number: 991472 February 24, 1999

Analysis Performed	Results		Analyzed	Method
cis-1,2-Dichloroethene	110	ug/kg	1/26/99	8260
Chloroform	< 25.0	ug/kg	1/26/99	8260
1,1,1-Trichloroethane	< 25.0	ug/kg	1/26/99	8260
Carbon Tetrachloride	< 25.0	ug/kg	1/26/99	8260
Benzene	< 25.0	ug/kg	1/26/99	8260
1,2-Dichloroethane	< 25.0	ug/kg	1/26/99	8260
Trichloroethene	120	ug/kg	1/26/99	8260
1,2-Dichloropropane	< 25.0	ug/kg	1/26/99	8260
Bromodichloromethane	< 25.0	ug/kg	1/26/99	8260
2-Hexanone	< 100	ug/kg	1/26/99	8260
Trans-1,3-Dichloropropene	< 25.0		1/26/99	8260
Toluene	< 25.0	ug/kg	1/26/99	8260
CIS-1,3-Dichloropropene	< 25.0	ug/kg	1/26/99	8260
1,1,2-Trichloroethane	< 25.0	ug/kg	1/26/99	8260
4-Methyl-2-Pentanone	< 100	ug/kg	1/26/99	8260
Tetrachloroethene	< 25.0	ug/kg	1/26/99	8260
Dibromochloromethane	< 25.0	ug/kg	1/26/99	8260
Chlorobenzene	< 25.0	ug/kg	1/26/99	8260
Ethylbenzene	< 25.0	ug/kg	1/26/99	8260
Total Xylenes	< 25.0	ug/kg	1/26/99	8260
Styrene	< 25.0	ug/kg	1/26/99	8260
Bromoform	< 25.0	ug/kg	1/26/99	8260
1,1,2,2-Tetrachloroethane	< 25.0	ug/kg	1/26/99	8260
1,3-Dichlorobenzene	< 25.0	ug/kg	1/26/99	8260
1,4-Dichlorobenzene	< 25.0	ug/kg	1/26/99	8260
1,2-Dichlorobenzene	< 25.0	ug/kg	1/26/99	8260

Metals results are reported on a dry weight basis

The analysis of this sample was performed in accordance with procedures approved or recognized by the U.S. Environmental Protection Agency.

James H. Long, Director Environmental Services Program

Division of Environmental Quality

Mel Carnahan, Governor + Stephen M. Mahfood, Director

# DEPARTMENT OF NATURAL RESOURCES

DIVISION OF ENVIRONMENTAL QUALITY PO. Box 176 Jefferson City, MO 65102-0176

2/17/99

#### ENVIRONMENTAL SERVICES PROGRAM

#### RESULTS OF SAMPLE ANALYSES

Sample Number: 991473 Lab Number: 99-D142

Reported To: BRIAN ALLEN Report Date:

Affiliation: ESP Date Collected: 1/21/99
Project Code: 4054/9096 Date Received: 1/22/99

Sample Collected by: BRIAN ALLEN, ESP

Sampling Location: FORMER HULETT LAGOON SITE

Sample Description: SOIL GRAB OF BORING "HULETT-09"

COLLECTED FROM 6-7 FT DEPTH

County: CAMDEN

Analysis Performed	Results		Analyzed	Method
Silver, Total	< 1,000	ug/kg	2/ 3/99	200.7
Arsenic, Total	9,680	ug/kg	2/ 4/99	206.2
Barium, Total	103,000	ug/kg	2/ 3/99	200.7
Cadmium, Total	< 200	ug/kg	2/ 3/99	200.7
Chromium, Total	58,200	ug/kg	2/ 3/99	200.7
Copper, Total	6,470	ug/kg	2/ 3/99	200.7
Mercury, Total	< 40.0	ug/kg	1/29/99	245.1
Nickel, Total	9,760	ug/kg	2/ 3/99	200.7
Lead, Total	39,100	ug/kg	2/ 3/99	239.2
Selenium, Total	< 1,000	ug/kg	2/ 4/99	270.2
VOA Results:				
Chloromethane	< 25.0	ug/kg	1/25/99	8260
Vinyl Chloride	< 25.0	ug/kg	1/25/99	8260
Bromomethane	< 25.0	ug/kg	1/25/99	8260
Chloroethane	< 25.0	ug/kg	1/25/99	8260
1,1-Dichloroethene	< 25.0	ug/kg	1/25/99	8260
Acetone	< 100	ug/kg	1/25/99	8260
Carbon Disulfide	< 25.0	ug/kg	1/25/99	8260
Methylene Chloride	< 100	ug/kg	1/25/99	8260
Methyl Tertiary Butyl Eth	< 25.0	ug/kg	1/25/99	8260
trans-1,2-Dichloroethene	< 25.0	ug/kg	1/25/99	8260
1,1-Dichloroethane	< 25.0	ug/kg	1/25/99	8260
2-Butanone	< 100	ug/kg	1/25/99	8260
cis-1,2-Dichloroethene	< 25.0	ug/kg	1/25/99	8260

Lab Number: 99-D142 Sample Number: 991473 February 17, 1999

Analysis Performed	Results		Analyzed	Method
Chloroform	< 25.0	ug/kg	1/25/99	8260
1,1,1-Trichloroethane	< 25.0	ug/kg	1/25/99	8260
Carbon Tetrachloride	< 25.0	ug/kg	1/25/99	8260
Benzene	< 25.0	ug/kg	1/25/99	8260
1,2-Dichloroethane	< 25.0	ug/kg	1/25/99	8260
Trichloroethene	< 25.0	ug/kg	1/25/99	8260
1,2-Dichloropropane	< 25.0	ug/kg	1/25/99	8260
Bromodichloromethane	< 25.0	ug/kg	1/25/99	8260
2-Hexanone	< 100	ug/kg	1/25/99	8260
Trans-1,3-Dichloropropene	< 25.0	ug/kg	1/25/99	8260
Toluene	< 25.0	ug/kg	1/25/99	8260
CIS-1,3-Dichloropropene	< 25.0	ug/kg	1/25/99	8260
1,1,2-Trichloroethane	< 25.0	ug/kg	1/25/99	8260
4-Methyl-2-Pentanone	< 100	ug/kg	1/25/99	8260
Tetrachloroethene	< 25.0	ug/kg	1/25/99	8260
Dibromochloromethane	< 25.0	ug/kg	1/25/99	8260
Chlorobenzene	< 25.0	ug/kg	1/25/99	8260
Ethylbenzene	< 25.0	ug/kg	1/25/99	8260
Total Xylenes	< 25.0	ug/kg	1/25/99	8260
Styrene Styrene	< 25.0	ug/kg	1/25/99	8260
Bromoform	< 25.0	ug/kg	1/25/99	8260
1,1,2,2-Tetrachloroethane	< 25.0	ug/kg	1/25/99	8260
1,3-Dichlorobenzene	< 25.0	ug/kg	1/25/99	8260
1,4-Dichlorobenzene	< 25.0	ug/kg	1/25/99	8260
1,2-Dichlorobenzene	< 25.0	ug/kg	1/25/99	8260

Metals results are reported on a dry weight basis

The analysis of this sample was performed in accordance with procedures approved or recognized by the U.S. Environmental Protection Agency.

James H. Long, Director Environmental Services Program Division of Environmental Quality

Mcl Carnahan Governor - Stephen M. Mahfood, Director

### ENT OF NATURAL RESOURCES

DIVISION OF ENVIRONMENTAL QUALITY -P.O Box 176 Jefferson City, MO 65102-0176

#### ENVIRONMENTAL SERVICES PROGRAM

### RESULTS OF SAMPLE ANALYSES

Sample Number: 991474 Lab Number: 99-D143

BRIAN ALLEN Reported To:

Affiliation: ESP

Project Code: 4054/9096

Report Date:

2/17/99 1/21/99 Date Collected:

Date Received: 1/22/99

Sample Collected by:

Sampling Location:

BRIAN ALLEN, ESP

FORMER HULETT LAGOON SITE

Sample Description:

SOIL GRAB OF BORING "HULETT-09"

COLLECTED FROM 6-7 FT DEPTH

(REPLICATE)

County:

CAMDEN

Analysis Performed	Results		Analyzed	Method
Silver, Total	< 1,000	ug/kg	2/ 3/99	200.7
Arsenic, Total	4,600	ug/kg	2/ 4/99	206.2
Barium, Total	132,000	ug/kg	2/ 3/99	200.7
Cadmium, Total	204	ug/kg	2/ 3/99	200.7
Chromium, Total	39,800	ug/kg	2/ 3/99	200.7
Copper, Total	8,560	ug/kg	2/ 3/99	200.7
Mercury, Total	< 40.0	ug/kg	1/29/99	245.1
Nickel, Total	12,400	ug/kg	2/ 3/99	200.7
Lead, Total	61,800	ug/kg	2/ 3/99	239.2
Selenium, Total	< 1,000	ug/kg	2/4/99	270.2
VOA Results:				
Chloromethane	< 25.0	ug/kg	1/25/99	8260
Vinyl Chloride	< 25.0	ug/kg	1/25/99	8260
Bromomethane	< 25.0	ug/kg	1/25/99	8260
Chloroethane	< 25.0	ug/kg	1/25/99	8260
1,1-Dichloroethene	< 25.0	ug/kg	1/25/99	8260
Acetone	< 100	ug/kg	1/25/99	8260
Carbon Disulfide	< 25.0	ug/kg	1/25/99	8260
Methylene Chloride	< 100	ug/kg	1/25/99	8260
Methyl Tertiary Butyl Eth	< 25.0	ug/kg	1/25/99	8260
trans-1,2-Dichloroethene	< 25.0	ug/kg	1/25/99	8260
1,1-Dichloroethane	< 25.0	ug/kg	1/25/99	8260
2-Butanone	< 100	ug/kg	1/25/99	8260

Lab Number: 99-D143 Sample Number: 991474 February 17, 1999


Analysis Performed	Results		Analyzed	Method	
cis-1,2-Dichloroethene	< 25.0	ug/kg	1/25/99	8260	
Chloroform	< 25.0	ug/kg	1/25/99	8260	
1,1,1-Trichloroethane	< 25.0	ug/kg	1/25/99	8260	
Carbon Tetrachloride	< 25.0	ug/kg	1/25/99	8260	
Benzene	< 25.0	ug/kg	1/25/99	8260	1
1,2-Dichloroethane	< 25.0	ug/kg	1/25/99	8260	
Trichloroethene	< 25.0	ug/kg	1/25/99	8260	
1,2-Dichloropropane	< 25.0	ug/kg	1/25/99	8260	
Bromodichloromethane	< 25.0	ug/kg	1/25/99	8260	
2-Hexanone	< 100	ug/kg	1/25/99	8260	
Trans-1,3-Dichloropropene	< 25.0	ug/kg	1/25/99	8260	
Toluene	< 25.0	ug/kg	1/25/99	8260	
CIS-1,3-Dichloropropene	< 25.0	ug/kg	1/25/99	8260	
1,1,2-Trichloroethane	< 25.0	ug/kg	1/25/99	8260	
4-Methyl-2-Pentanone	< 100	ug/kg	1/25/99	8260	,
Tetrachloroethene	< 25.0	ug/kg	1/25/99	8260	
Dibromochloromethane	< 25.0	ug/kg	1/25/99	8260	
Chlorobenzene	< 25.0	ug/kg	1/25/99	8260	
Ethylbenzene	< 25.0	ug/kg	1/25/99	8260	
Total Xylenes	< 25.0	ug/kg	1/25/99	8260	
Styrene	< 25.0	ug/kg	1/25/99	8260	
Bromoform	< 25.0	ug/kg	1/25/99	8260	
1,1,2,2-Tetrachloroethane	< 25.0	ug/kg	1/25/99	8260	•
1,3-Dichlorobenzene	< 25.0	ug/kg	1/25/99	8260	:
1,4-Dichlorobenzene	< 25.0	ug/kg	1/25/99	8260	
1,2-Dichlorobenzene	< 25.0	ug/kg	1/25/99	8260	

Metals results are reported on a dry weight basis

The analysis of this sample was performed in accordance with procedures approved or recognized by the U.S. Environmental Protection Agency.

James H. Long, Director

Environmental Services Program Division of Environmental Quality



# NT OF NATURAL RESOURCES

DIVISION OF ENVIRONMENTAL QUALITY -P.O. Box 176 Jefferson City, MO 65102-0176

#### ENVIRONMENTAL SERVICES PROGRAM

#### RESULTS OF SAMPLE ANALYSES

Sample Number: 991475 Lab Number: 99-D144

Reported To: BRIAN ALLEN

Affiliation: ESP

Project Code: 4054/9096

Report Date:

2/24/99 Date Collected: 1/21/99

1/22/99 Date Received:

Sample Collected by:

Sampling Location:

BRIAN ALLEN, ESP

FORMER HULETT LAGOON SITE

Sample Description:

SOIL GRAB OF BORING "HULETT-10" COLLECTED FROM 10.5-11 FT DEPTH

CAMDEN County:

Analysis Performed	Results		Analyzed	Method
Silver, Total	< 1,000	ug/kg	2/ 3/99	200.7
Arsenic, Total	10,700	ug/kg	2/4/99	206.2
Barium, Total	203,000	ug/kg	2/ 3/99	200.7
Cadmium, Total	651	ug/kg	2/ 3/99	200.7
Chromium, Total	62,700	ug/kg	2/ 3/99	200.7
Copper, Total	36,800	ug/kg	2/ 3/99	200.7
Mercury, Total	94.7	ug/kg	1/29/99	245.1
Nickel, Total	32,500	ug/kg	2/ 3/99	200.7
Lead, Total	94,200	ug/kg	2/ 3/99	239.2
Selenium, Total	< 1,000	ug/kg	2/ 4/99	270.2
Lead, TCLP	< 25.0	ug/L	2/19/99	239.2
VOA Results:				
Chloromethane	< 25.0	ug/kg	1/26/99	8260
Vinyl Chloride	< 25.0	ug/kg	1/26/99	8260
Bromomethane	< 25.0	ug/kg	1/26/99	8260
Chloroethane	< 25.0	ug/kg	1/26/99	8260
1,1-Dichloroethene	< 25.0	ug/kg	1/26/99	8260
Acetone	< 100	ug/kg	1/26/99	8260
Carbon Disulfide	< 25.0	ug/kg	1/26/99	8260
Methylene Chloride	< 100	ug/kg	1/26/99	8260
Methyl Tertiary Butyl Eth	< 25.0	ug/kg	1/26/99	8260
trans-1,2-Dichloroethene	< 25.0	ug/kg	1/26/99	8260
1,1-Dichloroethane	< 25.0	ug/kg	1/26/99	8260
2-Butanone	< 100	ug/kg	1/26/99	8260

Lab Number: 99-D144 Sample Number: 991475 February 24, 1999

Analysis Performed	Results		Analyzed	Method
cis-1,2-Dichloroethene	< 25.0	ug/kg	1/26/99	8260
Chloroform	< 25.0	ug/kg	1/26/99	8260
1,1,1-Trichloroethane	< 25.0	ug/kg	1/26/99	8260
Carbon Tetrachloride	< 25.0	ug/kg	1/26/99	8260
Benzene	< 25.0	ug/kg	1/26/99	8260
1,2-Dichloroethane	< 25.0	ug/kg	1/26/99	8260
Trichloroethene	< 25.0	ug/kg	1/26/99	8260
1,2-Dichloropropane	< 25.0	ug/kg	1/26/99	8260
Bromodichloromethane	< 25.0	ug/kg	1/26/99	8260
2-Hexanone	< 100	ug/kg	1/26/99	8260
Trans-1,3-Dichloropropene	< 25.0	ug/kg	1/26/99	8260
Toluene	< 25.0	ug/kg	1/26/99	8260
CIS-1,3-Dichloropropene	< 25.0	ug/kg	1/26/99	8260
1,1,2-Trichloroethane	< 25.0	ug/kg	1/26/99	8260
4-Methyl-2-Pentanone	< 100	ug/kg	1/26/99	8260
Tetrachloroethene	< 25.0	ug/kg	1/26/99	8260
Dibromochloromethane	< 25.0	ug/kg	1/26/99	8260
Chlorobenzene	< 25.0	ug/kg	1/26/99	8260
Ethylbenzene	< 25.0	ug/kg	1/26/99	8260
Total Xylenes	< 25.0	ug/kg	1/26/99	8260
Styrene	< 25.0	ug/kg	1/26/99	8260
Bromoform	< 25.0	ug/kg	1/26/99	8260
1,1,2,2-Tetrachloroethane	< 25.0	ug/kg	1/26/99	8260
1,3-Dichlorobenzene	< 25.0	ug/kg	1/26/99	8260
1,4-Dichlorobenzene	< 25.0	ug/kg	1/26/99	8260
1,2-Dichlorobenzene	< 25.0	ug/kg	1/26/99	8260

Metals results are reported on a dry weight basis

The analysis of this sample was performed in accordance with procedures approved or recognized by the U.S. Environmental Protection Agency.

James H. Long, Birector Environmental Services Program Divished of Environmental Quality

VALERIE WILDER, HWP c:

Modine - Camdenton HW-TSD File



Former Hulett Lagoon Site Combined PA/SI Reference 41

November 4, 1996

Mr. Richard Nussbaum, P.E. Groundwater Enforcement Unit Chief Missouri Department of Natural Resources Division of Environmental Quality Hazardous Waste Program P. O. Box 176 Jefferson City, Missouri 65102-0176

RECEIVED

HAZARDO CONTRON TODORAM MISSEGAL COMARCINENT OF NATURAL RESOURCES

Re: Letter Report

Subsurface Investigation Former Hulett Lagoon Camdenton, Missouri Dames & Moore Job No. 27397-023-045

Dear Mr. Nussbaum:

On behalf of Modine Manufacturing Company (Modine), Dames & Moore is pleased to submit this letter report summarizing the results of the Subsurface Investigation at the former Hulett Lagoon in Camdenton, Missouri. The former city owned and operated lagoon is located approximately 1,000 feet northeast of the Modine Heat Transfer facility. Based upon the results of the field fracture survey, the former lagoon is strongly indicated as the source of the observed trichloroethene (TCE) impact to groundwater at the Modine facility. The purpose of this investigation was to determine the presence or absence of volatile organic compounds (VOCs), in particular TCE, in soil underlying the former Hulett Lagoon.

The field investigation was conducted on October 11, 1996. Four hydraulically driven probes were advanced in the area of the lagoon in which an inlet pipe from the former Sundstrand facility and an outlet or discharge pipe from the lagoon were previously located. A figure is attached illustrating the probe locations. The probes were continuously sampled and field screened using a photoionization detector (PID). The probe logs are included as an attachment to this letter report. The sample exhibiting the highest indication of VOC content from each probe was submitted to Inchcape Testing Services Environmental Laboratories in Richardson, Texas. The soil samples were analyzed for VOCs, with TCE as the primary constituent of concern. The samples were shipped in an iced cooler under proper chain of custody by an overnight courier.

# DAMES & MOORE

Mr. Richard Nussbaum Groundwater Enforcement Unit Chief Missouri Department of Natural Resources

Re: Subsurface Investigation

Modine Heat Transfer, Inc.

Camdenton, Missouri

November 4, 1996

Page -2-

The analytical report is included as an attachment to this letter and the analytical results summarized below.

Sample Location	<u>Depth</u>	Analyte Detected	Concentration in parts per billion (ppb)
GP-1	4-6'	Chloroform TCE	200 9,170
GP-2	4-5.5'	TCE	1,940
GP-3	4-5'	Chloroform cis-1,2-Dichloroethene TCE	9.4 91.4 Not detected
GP-4	4-6'	TCE	Not detected

The TCE concentrations encountered in the soil beneath the former lagoon supports our previous position of an off-site source as the source of the observed TCE impact to groundwater at the Modine facility. This analytical data and the geological data resulting from the field fracture survey strongly suggests that the former lagoon is the off-site source.

\_\_\_\_\_ans())3m

# DAMES & MOORE

Mr. Richard Nussbaum

Groundwater Enforcement Unit Chief

Missouri Department of Natural Resources

Re. Sul

Subsurface Investigation Modine Heat Transfer, Inc.

Camdenton, Missouri

November 4, 1996

Page -3-

If you have any questions or comments regarding the contents of this report, please contact either of the undersigned or Mr. Thomas Sanicola with Modine at (414) 636-1649.

Very truly yours,

**DAMES & MOORE** 

Miesche M. Francis Assistant Geologist

Daniel J. Price, P.G. Senior Geologist

DJP:lk

Attachments

cc:


Darleen Westcott - MDNR


Thomas Sanicola - Modine

P \045\NOV96\MISC\NUSSBA04.RPT

**ATTACHMENT 1** 

**FIGURE** 







# FIGURE 1 GEOPROBE LOCATIONS

FORMER HULETT LAGOON MODINE MANUFACTURING CO. CAMDENTON, MISSOURI

DATE: Oct. 30, 1996 JOB NO: 27397-023-045 DRAWN BY CHK'D BY JMS DJP SCALE:

1"=20'



721 EMERSON ROAD, SUITE 220 ST. LOUIS, MISSOURI 63141 PHONE: 314-993-4599 FAX: 314-993-4895 **ATTACHMENT 2** 

PROBE LOGS

Client: Modine Heat Transfer, Inc.   PROBE ID GP-1	Туре
Project: TCE Investigation Former Hulett Lagoon Location: Camdenton, Missouri  Cordination: Camdenton, Missouri  Driller: GeoEnvironmental  Borehole Logged By: Miesche Francis  Drilling Method: GeoProbe®  Date Installed: October 11, 1996  Surface Conditions: Grass   DESCRIPTION  DESCRIPTION	Туре
Location: Camdenton, Missouri  Driller: GeoEnvironmental  Borehole Logged By: Miesche Francis  Drilling Method: GeoProbe®  Date Installed: October 11, 1996  Surface Conditions: Grass   DESCRIPTION  DESCRIPTION  DESCRIPTION  DESCRIPTION  O' - 1" Top soil, with organic material, slight organic odor.  1" - 4' CLAY, yellowish red, with cherty gravel, soft, moist, slight solvent odor at 4'.  4'-6' CLAY, yellowish red, with cherty gravel, with cherty gravel, trace of organic material, tight, dry, slight solvent odor.  Ground Surface:  Measuring Pt:  Sand:  Top of Casing:  CC-Continuos Core  SS Split Spoons  WA - Wash Sample  Sam  CC - Continuos Core  SS Split Spoons  WA - Wash Sample  CC - Continuos Core  SS Split Spoons  WA - Wash Sample  CC - Continuos Core  ST Shodby Tube  Sam  CC - Continuos Core  ST Shodby Tube  CC - Continuos Core  ST Shodby Tube  CC - Continuos Core  ST Shodby Tube  CC - Continuos Core  CC - Continuos Core  SS Split Spoons  WA - Wash Sample  CC - Continuos Core  ST Shodby Tube  CC - Continuos Core  CC - Continuos Core  CC - Continuos Core  CC - Continuos Core  ST. Shodby Tube  CC - Continuos Core  CC - Cutae Core  CC -	Туре
Borehole Logged By: Miesche Francis  Drilling Method: GeoProbe®  Date Installed: October 11, 1996  Surface Conditions: Grass  DESCRIPTION  DESCRIPTION  DESCRIPTION  DESCRIPTION  O' - 1" Top soil, with organic material, slight organic odor.  1" - 4' CLAY, yellowish red, with cherty gravel, soft, moist, slight solvent odor at 4'.  4'-6' CLAY, yellowish red, with cherty gravel, with cherty gravel, trace of organic material, tight, dry, slight solvent odor.	Туре
Drilling Method: GeoProbe® Date Installed: October 11, 1996 Surface Conditions: Grass  DESCRIPTION  DESCRIPTI	Туре
Date Installed: October 11, 1996 Surface Conditions: Grass  DESCRIPTION  DESCRIPTION  DESCRIPTION  DESCRIPTION  DESCRIPTION  CT - Cuttings SS - Split Spoon WA - Wash Sample  Top soil, with organic material, slight organic odor.  1" - 4' CLAY, yellowish red, with cherty gravel, soft, moist, slight solvent odor at 4'.  4'-6' CLAY, yellowish red, with cherty gravel, with cherty gravel, trace of organic material, tight, dry, slight solvent odor.	Туре
Surface Conditions: Grass  DESCRIPTION  DESCRIPTION  DESCRIPTION  DESCRIPTION  Surface Conditions: Grass  DESCRIPTION  DESCRIPTION  DESCRIPTION  Surface Conditions: Grass  NA - Wash Sample  ST - Shelby Tube  Sam  Add (i)  Add Wash Sample  ST - Shelby Tube  Sam  Add Wash Sample  ST - Shelby Tube  Sam  Add Wash Sample  CL  The conditions: Grass  Surface Conditions: Grass	Туре
DESCRIPTION  DESCR	Туре
DESCRIPTION  O' - 1" Top soil, with organic material, slight organic odor.  1" - 4' CLAY, yellowish red, with cherty gravel, slight solvent odor at 4'.  4'-6' CLAY, yellowish red, with cherty gravel, with cherty gravel, trace of organic material, tight, dry, slight solvent odor.	Туре
0' - 1" Top soil, with organic material, slight organic odor.  1" - 4' CLAY, yellowish red, with cherty gravel, soft, moist, slight solvent odor at 4'.  4'-6' CLAY, yellowish red, with cherty gravel, with cherty gravel, trace of organic material, tight, dry, slight solvent odor.	
0' - 1" Top soil, with organic material, slight organic odor.  1" - 4' CLAY, yellowish red, with cherty gravel, soft, moist, slight solvent odor at 4'.  4'-6' CLAY, yellowish red, with cherty gravel, with cherty gravel, trace of organic material, tight, dry, slight solvent odor.	
trace of organic material, right, dry, stight solvent odor.	cc
trace of organic material, right, dry, slight solvent odor.	cc
trace of organic material, right, dry, slight solvent odor.	cc
trace of organic material, right, dry, stight solvent odor.	cc
trace of organic material, right, dry, stight solvent odor.	
trace of organic material, right, dry, stight solvent odor.	1
Refusal at 6'.	
1	
	1
25	

Client: Modine Heat Transfer, Inc.	T	PROBE ID GP-2								
Project Number: 27397-023-045	Mon	itoring	g Well D		Elevation:					
Project: TCE Investigation Former Hulett Lagoon	Pip	-			Datum:					
Location: Camdenton, Missouri	Scree	Screen:				Ground Surface:				
Driller: GeoEnvironmental	Slo	Slot:				Measuring Pt:				
Borehole Logged By: Miesche Francis	Sa	Sand:				Top of Casing:				
Drilling Method: GeoProbe®			Sa	mple T						
Date Installed: October 11, 1996		CT - Cutti			CC - Continuos Core RX - Rock Core					
Surface Conditions: Grass			h Sample		ST - Shelby Tube					
							Sample			
DESCRIPTION	USCS	Stratigraphy	Depth (ft.)	OVM (ppm)	Completion	Lab	Interval	Type		
0'-4' CLAY, yellowish red, with cherty gravel, soft, moist, abundant			0		***************************************					
	CT		1 -		BENTONITE		-			
organics at 3', musty odor (2' of recovery).	CL			6.80	D F					
			2 _							
			3		AR					
4! 5 1/2! CLAV wallowish and with shorty grown tight day troop of			4 -	640.2	GRANULAR	37	41 51/01	cc		
4'-5 1/2' CLAY, yellowish red, with cherty gravel, tight, dry, trace of			_	648.3	RAI	Y	4'-51/2'	CC		
organic material, slight solvent odor.			5		U U					
Refusal at 5 1/2'.			6							
			F 7 -							
			L -							
			8					1		
			9					١,		
			10							
			11							
			12							
			13							
ř ,										
			14					1 1		
			15							
			16							
			L -							
	1		17							
			18							
			19							
			20							
			21							
			22							
			23							
			L _							
			24							
			25							

Client: Modine Heat Transfer, Inc.	PROBE ID GP-3									
Project Number: 27397-023-045	Mon	itoring	g Well D		Elevation:					
Project: TCE Investigation Former Hulett Lagoon	Pipe:				Datum:					
Location: Camdenton, Missouri	Screen:				Ground Surface:					
Driller: GeoEnvironmental	Slot:				Measuring Pt:					
Borehole Logged By: Miesche Francis	Sand:				Top of Casing:					
Drilling Method: GeoProbe®			Sa	mple T						
Date Installed: October 11, 1996		T - Cutti			CC - Contin		e			
Surface Conditions: Grass							ST - Shelby Tube			
· ·		_				-	Sample			
DESCRIPTION	USCS	Stratigraphy	Depth (ft.)	OVM (ppm)	Completion	Lab	Interval	Type		
0'-1" Top soil with organic material.			0		ITE					
1"-4' CLAY, yellowish red, with cherty gravel, lower 6" wet,	CL		1	2.8	BENTONITE					
black discoloration at 3.5' (organic material), light gray clay lens			2		BEN					
at 4' with slight spice odor (2' of recovery).			3		GRANULAR					
4'-5' CLAY, yellowish red, with cherty gravel, some areas of discoloration			4	75.4	ANU	Y	4'-5'	CC		
slight musty odor.			5		8					
Refusal at 5'.			6							
			F 7 -							
			8 _							
			9							
			10							
			-	-						
			11							
			12							
			13							
			14	-						
			L -							
			15							
			16	1						
			17							
			L -							
			18							
			19							
			20							
			L -							
			21							
			22							
			23							
			L -							
			L _					1		
			25							
			24 25							

Client: Modine Heat Transfer, Inc.	PROBE ID GP-4									
Project Number: 27397-023-045	Moni	toring	Well D		Elevation:					
Project: TCE Investigation Former Hulett Lagoon	Pipe:				Datum:					
Location: Camdenton, Missouri	Screen:				Ground Surface:					
Driller: GeoEnvironmental	Slo	t:			Measuring Pt:					
Borehole Logged By: Miesche Francis	Sar	ıd:			Top of Casing:					
Drilling Method: GeoProbe®			Sai	mple T	ype					
Date Installed: October 11, 1996		T - Cuttin			CC - Continu		e			
Surface Conditions: Grass	SS - Split Spoon RX - Roci WA - Wash Sample ST - Shelt									
						_	Sample			
DESCRIPTION	USCS	Stratigraphy	Depth (ft.)	OVM (ppm)	Completion	Lab	Interval	Туре		
0'-1" Top soil with organic material.			0		TE					
1"-4' CLAY, yellowish red, with cherty gravel, moist, soft,	CL		1	0.0	GRANULAR BENTONITE					
sand lens at 4' with abundant organic material (2' of recovery).			2		3EN_					
Same tone at 1 mm administration (2 of 1000 for s).			- 3 -		AR E					
			4 -		NOL.			00		
4'-6' CLAY, yellowish red, with cherty gravel, moist, tight.				0.4	RAN	Y	4'-6'	CC		
			5		ŋ					
Refusal at 6'.			6							
		-	7 -							
			8 -							
								,		
			9 _							
			10							
			11							
			12							
			13							
			14							
			15							
			16							
			17 -							
			18							
			19							
			20							
			21							
			22							
			23							
			24							
			- <sub>25</sub> -							

### **ATTACHMENT 3**

ANALYTICAL REPORT



1089 E Collins Blvd. Richardson, TX 75081 Tel 214-238-5591 Fax. 214-238-5592

#### ANALYTICAL REPORT

DATE RECEIVED : 12-OCT-1996

REPORT NUMBER : D96-11513 REPORT DATE : 22-OCT-1996

SAMPLE SUBMITTED BY : Dames & Moore

ADDRESS: 2135 East Sunshine, Suite #150

: Springfield, MO 65804

ATTENTION : Miesche Francis

PROJECT: 27397-023 Modine Hulett Lagoon

Included in this data package are the analytical results for the sample group which you have submitted to Inchcape Testing Services for analysis. These results are representative of the samples as received by the laboratory.

The information contained herein has undergone extensive review and is deemed accurate and complete. Sample analysis and quality control were performed in accordance with all applicable protocols. Any deviations from these protocols or observations of interest are detailed in an accompanying Case Narrative. Please refrain from reproducing this report except in its entirety.

If you have any questions regarding this report and its associated materials please call your Project Manager at (214) 238-5591.

We appreciate the opportunity to serve you and look forward to providing continued service in the future.

Martin Jeffus General Manager

Martin Jeffus

DAMES & MOORE

OCT 2 5 1996

SPAINOFIELD, MU

~.mixE

CCT 3 1 1996

ST. LOUIS, WISSELL



DATE RECEIVED: 12-OCT-1996 REPORT NUMBER: D96-11513-1

REPORT DATE: 22-OCT-1996

SAMPLE SUBMITTED BY : Dames & Moore

ADDRESS: 2135 East Sunshine, Suite #150

: Springfield, MO 65804

ATTENTION : Miesche Francis

SAMPLE MATRIX : Soil

ID MARKS: GP-1 4-6'
PROJECT: 27397-023 Modine Hulett Lagoon
DATE SAMPLED: 11-OCT-1996

ANALYSIS METHOD : EPA 8010 /1

ANALYZED BY : JCH ANALYZED ON : 15-OCT-1996

DILUTION FACTOR: 100 METHOD FACTOR : 10

QC BATCH NO : 4-101496

VOLATILE HALOCARBONS				
TEST REQUESTED		ON LIMIT	RESUL	TS
Chioroform	100	µg/Кg	200	μg/Kg
Trichloroethene	100	μg/Kg	9170	μg/Kg

QUALITY CONTROL DATA		
SURROGATE COMPOUND	SPIKE LEVEL	SPIKE RECOVERED
Bromofluorobenzene (SS)	10.0 μg/Kg	114 %



DATE RECEIVED : 12-OCT-1996

REPORT NUMBER : D96-11513-1

REPORT DATE: 22-OCT-1996

SAMPLE SUBMITTED BY : Dames & Moore

ADDRESS: 2135 East Sunshine, Suite #150

: Springfield, MO 65804

ATTENTION : Miesche Francis

SAMPLE MATRIX : Soil

ID MARKS: GP-1 4-6'
PROJECT: 27397-023 Modine Hulett Lagoon
DATE SAMPLED: 11-OCT-1996

TEST REQUESTED		DETECTION LIMIT	RESULTS
Total Solids	/1	0.01 %	80.5 %



DATE RECEIVED : 12-OCT-1996 REPORT NUMBER : D96-11513-2

REPORT DATE: 22-OCT-1996

SAMPLE SUBMITTED BY : Dames & Moore

ADDRESS : 2135 East Sunshine, Suite #150

: Springfield, MO 65804

ATTENTION : Miesche Francis

SAMPLE MATRIX : Soil

ID MARKS : GP-2 4-5.5'

PROJECT: 27397-023 Modine Hulett Lagoon

DATE SAMPLED : 11-OCT-1996 ANALYSIS METHOD : EPA 8010 /1

ANALYZED BY : JCH

ANALYZED ON: 15-OCT-1996

DILUTION FACTOR : 100 METHOD FACTOR : 10

QC BATCH NO : 4-101496

VOLATILE HALOCARBONS		
TEST REQUESTED	DETECTION LIMIT	RESULTS
Trichloroethene	100 μg/Kg	1940 μg/Kg

QUALITY CONTROL DATA		
SURROGATE COMPOUND	SPIKE LEVEL	SPIKE RECOVERED
Bromofluorobenzene (SS)	10.0 μg/Kg	130 %



DATE RECEIVED: 12-OCT-1996 REPORT NUMBER: D96-11513-2

REPORT DATE: 22-OCT-1996

SAMPLE SUBMITTED BY : Dames & Moore

ADDRESS : 2135 East Sunshine, Suite #150

: Springfield, MO 65804

ATTENTION : Miesche Francis

SAMPLE MATRIX : Soil

ID MARKS: GP-2 4-5.5'
PROJECT: 27397-023 Modine Hulett Lagoon
DATE SAMPLED: 11-OCT-1996

EST REQUESTED		DETECTION LIMIT	RESULTS
Total Solids	/1	0.01 %	73.6 %



DATE RECEIVED : 12-OCT-1996

REPORT NUMBER : D96-11513-3

REPORT DATE: 22-OCT-1996

SAMPLE SUBMITTED BY : Dames & Moore
ADDRESS : 2135 East Sunshine, Suite #150

: Springfield, MO 65804

ATTENTION : Miesche Francis

SAMPLE MATRIX : Soil

ID MARKS : GP-3 4-5'

PROJECT: 27397-023 Modine Hulett Lagoon

DATE SAMPLED : 11-OCT-1996 ANALYSIS METHOD : EPA 8010 /1

ANALYZED BY : JCH

ANALYZED ON: 15-OCT-1996

DILUTION FACTOR : 5 METHOD FACTOR : 10

QC BATCH NO : 4-101496

VOLATILE HALOCARBONS		
TEST REQUESTED	DETECTION LIMIT	RESULTS
Chloroform	5.0 μg/Kg	9.4 μg/Kg
cis-1,2-Dichloroethene	5.0 μg/Kg	91.4 μg/Kg
Trichloroethene	5.0 μg/Kg	< 5.0 μg/Kg

QUALITY CONTROL DATA		
SURROGATE COMPOUND	SPIKE LEVEL	SPIKE RECOVERED
Bromofluorobenzene (SS)	10.0 μg/Kg	115 %



DATE RECEIVED : 12-OCT-1996 REPORT NUMBER : D96-11513-3

REPORT DATE : 22-OCT-1996

SAMPLE SUBMITTED BY : Dames & Moore

ADDRESS: 2135 East Sunshine, Suite #150

: Springfield, MO 65804

ATTENTION : Miesche Francis

SAMPLE MATRIX : Soil

ID MARKS : GP-3 4-5'

PROJECT : 27397-023 Modine Hulett Lagoon DATE SAMPLED : 11-OCT-1996

TEST REQUESTED		DETECTION LIMIT	RESULTS
Total Solids	/1	0.01 %	78.7 %

DATE RECEIVED : 12-OCT-1996 REPORT NUMBER : D96-11513-4

REPORT DATE: 22-OCT-1996

SAMPLE SUBMITTED BY : Dames & Moore

ADDRESS: 2135 East Sunshine, Suite #150

: Springfield, MO 65804

ATTENTION : Miesche Francis

SAMPLE MATRIX : Soil

ID MARKS : GP-4 4-6'

PROJECT: 27397-023 Modine Hulett Lagoon

DATE SAMPLED : 11-OCT-1996 ANALYSIS METHOD : EPA 8010 /1

ANALYZED BY : JCH

ANALYZED ON: 15-OCT-1996

DILUTION FACTOR: 5 METHOD FACTOR: 10

QC BATCH NO : 4-101496

VOLATILE HALOCARBONS			
TEST REQUESTED	DETECTION LIMIT		RESULTS
Trichloroethene	5.0 μg/Kg	<	5.0 μg/Kg

QUALITY CONTROL DATA		
SURROGATE COMPOUND	SPIKE LEVEL	SPIKE RECOVERED
Bromofluorobenzene (SS)	10.0 μg/Kg	122 %



DATE RECEIVED: 12-OCT-1996 REPORT NUMBER: D96-11513-4

REPORT DATE: 22-OCT-1996

SAMPLE SUBMITTED BY : Dames & Moore

ADDRESS: 2135 East Sunshine, Suite #150

: Springfield, MO 65804

ATTENTION : Miesche Francis

SAMPLE MATRIX : Soil

ID MARKS: GP-4 4-6'
PROJECT: 27397-023 Modine Hulett Lagoon
DATE SAMPLED: 11-OCT-1996

TEST REQUESTED	ļ	DETECTION LIMIT	RESULTS
Total Solids	/1	0.01 %	72.4 %



REPORT DATE : 22-OCT-1996 REPORT NUMBER

REPORT NUMBER : D96-11513


SAMPLE SUBMITTED BY : Dames & Moore

ATTENTION : Miesche Francis PROJECT : 27397-023 Modine Hulett Lagoon

LABORATORY QUALITY CONTROL REPORT

	<del></del>
ANALYTE	Trichloroethene
BATCH NO.	4-101496
LCS LOT NO.	AB709-55B
PREP METHOD	
PREPARED BY	
ANALYSIS METHOD	EPA 8010
ANALYZED BY	JCH
UNITS	mg/Kg
METHOD BLANK	< 1.00
SPIKE LEVEL	500
MS RESULT	470
MS RECOVERY %	94.0
MSD RESULT	420
MSD RECOVERY %	84.0
MS/MSD RPD %	11.2
BS RESULT	NA
BS RECOVERY %	NA
BSD RESULT	NA
BSD RECOVERY %	NA
BS/BSD RPD %	NA
DUPLICATE RPD %	NA
LCS LEVEL	20.0
LCS RESULT	16.5
LCS RECOVERY %	82.5
SPIKE SAMPLE ID	11513-3
DUP SAMPLE ID	
L	<del> </del>

Inchea Testing Services Environmental Laboratories	1089 East Ce* Blvc	d., #100 Richards	on, TX 75081 (214) 238-5591	CHAIN OF CUSTC 'ECORD
Report to: Invoice Company:		ANALYSIS		Lab use _ "y Due Date:
Company: Dames F Moore   Company: Address: 2135 ESUNShine 105 Address:		REQUESTER		
Spring field, M065804 Spring field, M065804	0001 ALM 1			/ / / Town of scalars
	HW CLL			Temp of coolers when received (C°).
Contact: Miesche Francis Contact: Phone: C410881-3927 Phone: UUD	071	/		/ / 1 1 3 4 5
Fax: (417)881 - 636 PO/SO #:		/		Custody Seal N/
Fax: <u>C41 1/081 1 (6.601</u> ) P0/50 #.		/ / /	arphi / / / / / .	/ / Intact N/Y
Sampler's Name Sampler's Signature			7	Screened
Misadortinuis III		/%/	'	For Radioactivity
Proj No   Project Name	No /Type of Containers			
Proj. No. 1-023 Project Name Hulett Lagon	No / Type of Comainers			/ /
Matrix Date Time C G Identifying Marks of Sample(s)	VOA A/G 250 P/O	3 / <b>9</b> /	/	
РБ	1 Lt ml	1/7/		Lab Sample ID (Lab Use Only)
S 10-11 1145 V GP-1 43-63	\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\	<del></del>	11513+	Report only
Sw.11 220 V GP-24-51/2	V			2 TCE unless
Shullall VGP-34-5				3 other constituent
S 10-11 1230 V GP-4 4-63	V			Lare identified
				in significant
				in significant quanties.
				querities.
	<del>                                     </del>			
Turn around time Depriority 1 of Standard Priority 2 or 50% Priority 3 or 100% [	I Priority 4 ERS •	• BTEX (602/8	1020). TPH (418 1 or 8015). VOLATILES	S (624/8240), IGNITABILITY, TOTAL LEAD (6010)
Refundational Date Time Received by (Signature)	ature) Date	e , Time	Remarks	<u></u>
Refinquistres by (819patu)e) Date: Time Received by (Signature)	WD 10	12/000	V. OTT AD	OUTE J
Refinquistres by (Signature) Date: Time Received by (Signature)	ature) Date	e Time	* SEE AB	200
Relinquished by (Signature) Date Time Received by (Signature)	ature) Date	e Time		## ## ## ## ## ## ## ## ## ## ## ## ##
Heiniquished by (Signature)	lidie)		and conditions contained in the Pr	tutes acceptance of Inchcape/ITS-Dallas terms nce Schedule
Matnx WW - Wastewater W - Water S - Soil SD - Solid L - Liquid		- Charcoal tube	SL · Sludge O · Oil In	nchcape cannot accept verbal changes.
<sup>2</sup> Container VOA - 40 ml vial A/G - Amber / Or Glass 1 Liter 250 ml - G	ilass wide mouth P.	VO - Plastic or other_		Please Fax written changes to 214-238-5592
OFFICE USE ONLY		_		



Mel Camihin, Governor • Stephen M. Militood, Director

7

### DEPARTMENT OF NATURAL RESOURCES

- DIVISION OF GEOLOGY AND LAND SURVEY

PO Box 250 111 Fairgrounds Rd Rolla, MO 65402-0250

(573) 368-2100

FAX (573) 368-2111

#### **MEMORANDUM**

DATE: March 29, 1999

TO: Valerie Wilder, Environmental Specialist

Superfund Section, HWP, DEQ

FROM: Neil Elfrink, Geologist

Environmental Geology Section, GSP, DGLS

SUBJECT: Hydrogeologic Report for the Former Hulett Lagoon Site

LOCATION SW 1/4, SW 1/4, SW 1/4, Section 24, T. 38 N, R. 17 W., Camden County,

Missouri; 38° 00' 42" North Latitude and 92° 45' 18" West Longitude.

The hydrogeologic report for the Former Hulett Lagoon site is enclosed. Please contact me at (573) 368-2162 if you have any questions regarding this report, or if additional information is required.

NE/lh

Attachments

## HYDROGEOLOGIC REPORT FOR THE FORMER HULETT LAGOON SITE CAMDENTON, MISSOURI, CAMDEN COUNTY

#### **GENERAL CONSIDERATIONS**

#### **Site Location**

The Former Hulett Lagoon site is located on the Green Bay Terrace 7.5-minute quadrangle map (Figure 1), in the Southwest Quarter (SW 1/4) of the Southwest Quarter (SW 1/4) of Section 24, Township 38 North, Range 17 West. Coordinates for the center of the former lagoon are approximately 38° 00' 42" north latitude and 92° 45' 18" west longitude. The Former Hulett Lagoon site is located on the east side of Dawson Road, north of Sunset Drive. The site is approximately ¼ mile northeast of Modine Manufacturing Site (Modine).

#### Physiographic Province

The site is situated on the Salem Plateau region of the Ozark Plateau physiographic province (Missouri Water Atlas, 1986). The topography of the Salem Plateau is characterized by a rolling upland surface with rugged hills dissected by entrenched, narrow stream valleys (Gann, 1976). Karst features, such as springs, sinkholes, and losing streams, are characteristic of the Salem Plateau.

#### **GROUNDWATER PATHWAY**

#### Stratigraphic Units

A stratigraphic column (Table 1) has been tabulated based upon the stratigraphy of nearby wells (Well Log File, 1999).

The youngest bedrock formations beneath the site are expected to be Ordovician-age sediments assigned to the Canadian Series. The Roubidoux Formation consists of dolomite, sandy dolomite, and sandstone (Thompson, 1991). In the Camdenton area, soluble portions of the Roubidoux have generally been removed by dissolution. Nearby well logs indicate that the Roubidoux Formation may have been completely removed by erosion in the vicinity of the site.

Underlying the Roubidoux Formation, the Gasconade Dolomite consists of cherty dolomite and is estimated to be approximately 300 feet thick in the vicinity of the site (Well Logs, 1999). A basal unit of the Gasconade Dolomite, known as the Gunter Sandstone Member, commonly separates the Ordovician- and Cambrian-age strata. The Gunter Sandstone is approximately 25 feet thick in the Camdenton area.

Cambrian rocks in the Camdenton area were deposited in a complex depositional environment. Camdenton is located near the western margin of a Cambrian-age intrashelf sedimentary basin known as the Central Missouri Basin (Palmer and Hayes, 1997). To the west lies the north-south trending Lebanon Arch, which consists of carbonate platform rocks, that in some areas, thin over Precambrian highlands (Gregg et. al., 1989). Dramatically different lithologies and abrupt facies changes are depicted in area well logs (Figure 2). In general, more shaly, basinal rocks to the east pinch-out against the Lebanon Arch.

Because of the tectonic setting, Cambrian beds in the Camdenton area are difficult to categorize, and "layer-cake" stratigraphy should not be assumed. The following descriptions are simplified. The upper-most Cambrian unit in the area is the Eminence Dolomite, which consists of approximately 300-635 feet of dolomite with minor amounts of chert. The Eminence Dolomite is underlain by about 25-230 feet of Potosi Dolomite, which consists of dolomite, chert, and drusy quartz. Beneath the Potosi Dolomite, in descending order, are the Derby-Doerun Dolomite, the shaly Davis Formation, the Bonneterre Formation, and the Lamotte Sandstone. The entire Cambrian section is estimated to be over 1,150 feet thick.

Cross-sections constructed using information from specific well logs (Well Log Files, 1999) are presented in Figures 2 and 3. The cross-section locations are shown on Figures 1 and 4.

#### **Aquifers**

The Ozark Aquifer, which includes all bedrock units above the Cambrian-age Derby-Doerun Dolomite, is the shallowest aquifer beneath site. The Ozark Aquifer is considered exposed at the surface at the Former Hulett Lagoon Site. The total thickness of the aquifer is approximately 950 feet. Each of the units which comprise the Ozark Aquifer have individual characteristics that control their water-bearing capabilities; however, in general, the Ozark Aquifer produces good-quality water, with production rates generally proportional to well depth. Extensive pumping of groundwater in the Camdenton area has created a downward vertical gradient, and the site is located in a groundwater recharge zone.

Because detailed hydrogeologic studies have not been conducted at the site, groundwater flow directions within the bedrock can only be approximated. Prior to pumping of the aquifer, groundwater beneath the site probably flowed westward or northward to discharge areas in the Niangua River valley, (Imes, 1990, Sheet 3). Pumping rates at the Camdenton municipal wells are high enough to engulf the site within the cones of depression that surround the municipal wells. The radius of influence of nearby production wells should be determined.

Groundwater flow in the saturated zone is controlled by gradient. Assertions that preferential pathways in the Ozark Aquifer substantially influence flow direction in the saturated zone (Dames and Moore, 1996; page 13) are incorrect. Water flows downhill; fractures or solution-enlarged channels cannot make water flow uphill. Monitoring well nests are needed to accurately determine the magnitude of the downward vertical gradient. The upper Gasconade Dolomite *may* inhibit the downward migration of contamination. However, fracturing and karst development may have resulted in a local increase in permeability within the otherwise relatively tight upper Gasconade Dolomite.

The Gunter Sandstone is generally highly porous and permeable and is an important source of domestic groundwater supplies in the area. Because the Gunter Sandstone generally yields adequate domestic water supplies, few private wells in the area penetrate the underlying Cambrian Formations. However, municipal wells in the Lake of the Ozarks area are generally cased through the Gunter Sandstone, in order to avoid possible bacterial contamination.

The Eminence and Potosi Dolomites are a major source of municipal drinking water throughout the Ozark area, including the City of Camdenton. The Eminence Dolomite is differentiated from the underlying Potosi Dolomite by the lack of druse. A druse is a rock cavity encrusted with finely crystalline quartz. The druse-rich Potosi Dolomite is the most permeable geologic unit within the Ozark Aquifer and generally has an extensive network of karstic channels.

The shallowest reliable aquitard beneath the site is the St. Francois Confining Unit, approximately 1,200 feet below the surface. The St. Francois Confining Unit separates the Ozark Aquifer from the deeper St. Francois Aquifer. The St. Francois Aquifer includes the Cambrian-age Bonneterre Formation and Lamotte Sandstone. The St. Francois Aquifer is not used as a water source in Camden County. Water losses in the Lamotte Sandstone are common in some parts of the Ozark Region, although the phenomenon is poorly understood. Outside the Cambrian outcrop area, few water wells penetrate the Lamotte Sandstone, since yields may actually be reduced. Groundwater flow directions in the deeper St. Francois Aquifer are generally unknown and may be complicated.

Baseline water-level and pumping rate data needs to be collected before informed decisions about groundwater movement in the Camdenton subsurface can be made. Static water levels should be measured at least monthly at any inactive wells. Detailed records of active wells should include volume of water pumped, length of pumping cycles, and drawdown measurements. The Mulberry City Well (which was shut down on January 26, 1999 because of TCE contamination) produced approximately three times the volume of the other two city wells, suggesting the aquifer is highly heterogeneous. The Mulberry Well probably intercepted more solution-enlarged cavities than the other city wells, although lithologic differences can also explain differences in well yield. Wide variations in aquifer parameters are common in

#### carbonate areas.

The three Camdenton city wells produced a total of 232,458,000 gallons in 1997. An estimate of the cone of depression produced by this pumping can be made by comparing Camdenton to the city of Rolla, which is located in a similar ridge-top geologic setting approximately 50 miles east of Camdenton (Vandike, 1992). In 1960, four Rolla city wells produced approximately 290,250,000 gallons of water from the Ozark Aquifer. The resulting cone of depression was over five miles wide (Vandike, 1992). By 1960, pumping of the Ozark Aquifer in the Rolla area had dropped water levels up to 150 feet compared to the predevelopment potentiometric surface. The relatively deep depth to groundwater in the Camdenton area suggests a similar radius of effect can be expected. Any potential site-related contaminants reaching the water table are expected to move toward the nearest Camdenton City Well. Until recently, hydraulic control beneath the Former Hulett Lagoon and Modine sites has been maintained by pumping at the Mulberry Well. Now that the Mulberry Well has been shut off, TCE contamination is expected to move toward another city well.

Wells at the Modine site are open to different depth intervals. Therefore, data from these wells cannot be used to create a potentiometric map. The fact that two of the four wells have gone dry in the past suggests that the vertical flow component is significant. Water levels in area wells tend to decrease with depth, supporting the statement that the vertical flow is downward. As previously mentioned, a downward gradient is to be expected in an active municipal well field, particularly if it is located on a ridge top. Static water levels measured during the construction of the newest Camdenton City Well (#7) also verify the downward gradient (Krehbiel Engineering, Inc., 1998). The Hickory Street Well is 1,100 feet deep with 462 feet of casing. The static water level before pressure-grout sealing of the well casing was 222 feet below the ground surface. Static water level after sealing was 260 feet below ground surface. indicating a downward vertical gradient. A large upland area that might provide recharge to the Camdenton City Wells does not exist. Groundwater monitored by the monitoring wells is essentially moving downward to recharge the pumping wells. Conclusions about lateral flow directions cannot be made based on water levels from the existing monitoring well network.

It has been suggested that contaminants reaching the saturated zone beneath Camdenton will follow "regional groundwater flow" and discharge at the Lake of the Ozarks (Dames & Moore, 1998; page 19). However, groundwater withdrawals averaging over 500,000 gallons per day will create a large cone of depression and obliterate "regional groundwater flow" in any Ozark ridge top setting. A 2-hour pump test of the new Hickory St. Well at 550 gpm caused a 176-foot drawdown in water level (Krehbiel Engineering, Inc., 1998). There is no evidence to suggest that potential contaminants reaching the water table from either the Former Hulett Lagoon or the Modine site can somehow escape the Camdenton well field.

#### **Aquifer Discontinuities**

Minor folds and faults in the area cannot be considered aquifer discontinuities. However, it should be noted that the Cambrian-age formations that form the most productive portions of the Ozark Aquifer beneath the site are highly variable in lithology. The aquifer cannot be considered isotropic, nor does it possess radial symmetry. Aquifer parameters may be so variable as to render groundwater modeling useless.

#### Wellhead Protection Area

The Former Hulett Lagoon site is located in a Wellhead Protection Area according to section 1428 of the Safe Drinking Water Act. In Missouri, Wellhead Protection Areas are designated by the Missouri Wellhead Protection Program. The Former Hulett Lagoon Area site is located within a 1-mile radius of a wellhead in a carbonate aquifer system (Public Drinking Water Program, 1994, page 15).

Revisions to the 1994 Missouri Wellhead Protection Program document are currently under review by EPA. However, the Former Hulett Lagoon site should remain in a designated Wellhead Protection Area under any new management program that may be approved.

In addition to the Wellhead Protection Area discussed above, Camdenton is also subject to Well Construction Rules under the Water Well Drillers Act, section 256.600 to 256.640 RSMo. Most of the Camdenton area is located in Area 1, as designated by the DGLS Wellhead Protection Section. Since September 1987, Area 1 bedrock wells have been required to have 80 feet of casing and penetrate at least 30 feet of bedrock. Wells within ¼ mile of the Lake of the Ozarks are located in Sensitive Area B and subject to additional requirements (Missouri Well Construction Rules, 1996).

#### **Karst Features**

The Camdenton area is considered karst (Missouri Water Atlas, 1986). Significant karst features are present within a 4-mile radius of the site. A monitoring well drilled at the site encountered numerous fractures and small voids (Dames & Moore, 1998). Over 5,000 gallons of water was lost during the drilling of the monitoring well.

#### **Geologic Structures**

Geophysical logging of monitoring wells at the Modine site suggests that formations beneath the site are essentially flat-lying. Small faults and folds have been mapped within a 4-mile target radius. The axis of a northwest-trending syncline, called the

Racetrack Hollow Syncline, has been mapped less than 2 miles south of the site (Brown, 1984). The Red Arrow Fault is located approximately 3 miles south of the site (Wedge, in preparation). The fault strikes northwest and, in general, the southwest side is downthrown approximately 100 feet. However, geology along the fault zone is complicated. LOGMAIN Well # 25162 (Figure 3) is located along the fault zone and indicates significant upward movement. Ha Ha Tonka Spring is located along the trace of The Red Arrow Fault.

The poorly defined Proctor anticline runs across Camden County (McCracken, 1971). The anticline is evident on the regional cross-section (Figure 3). The Proctor anticline roughly corresponds with the Lebanon Arch, an area of shallow-water carbonate deposition during the Cambrian Period. The anticline is probably related to a rejuvenated Precambrian fault. The effects of the structural deformation on groundwater are poorly understood, but the faulting and folding has probably increased hydraulic conductivities in some areas. Groundwater may flow along conduits within the structures.

#### **Travel Time Factor**

Rock layers that underlie the site are karst. The resulting Travel Time Factor Value is 35 (Federal Register, 1990).

#### **GROUNDWATER TARGETS**

#### **Target Distance Limit**

Groundwater use within the 4-mile groundwater target distance limit is extensive. The City of Camdenton has provided water service since 1952, with groundwater as the sole source of water. Most businesses and residences near the Former Hulett Lagoon site utilize on city water.

#### Wells

Over 195 well locations within the groundwater target distance limit are recorded in the databases available at the Division of Geology and Land Survey. The LOGMAIN database contains information on older wells. The DGLS Well Wellhead Protection Section's Water Well Information System (W.I.M.S) database contains information on wells drilled since 1987. Well site locations are presented on Figures 5 and 6, and the corresponding well data is tabulated in Table 2. Some locations may be estimated or based on section centroids. The vast majority of the wells on record are domestic supply wells. Some wells may no longer be active. Many active wells may not be recorded in DGLS databases.

According to databases available at DGLS, one private well is located with ¼ mile of the Former Hulett Lagoon Site. One community well is located with ½ mile of the Former Hulett Lagoon Site. A total of 4 wells are located between 0.5 and 1 mile of the site, including 2 community wells and 2 private wells. An additional 31 wells are located between 1 and 2 miles from the site, including 1 community well, 1 nontransient noncommunity well, 2 transient noncommunity wells and 27 private wells. 72 wells are located between 2 and 3 miles from the site, including 2 community wells, 1 nontransient noncommunity well, 9 transient noncommunity wells and 60 private wells. 96 wells are located between 3 and 4 miles of the site including 3 nontransient noncommunity well, 3 transient noncommunity wells and 90 private wells.

#### **Nearest Wells**

The nearest public drinking water supply well on record is The City of Camdenton Well #6 (Mulberry Well), located about 1/4 mile south of the Former Hulett Lagoon site. The well was closed in 1999 due to TCE contamination. The City of Camdenton has three other wells inside the 4-mile target distance limit. Total production from the three wells was 221,003,300 gallons in 1993. All of these wells draw water from the Ozark Aquifer.

The nearest possible private drinking water well on record is located approximately 1/4 mile east of the Former Hulett Lagoon site (Figure 5). The well was drilled in 1990 and its current status is unknown.

#### **SURFACE WATER PATHWAY**

#### **Hydrologic Setting**

The Former Hulett Lagoon site is situated near the headwaters of a small unnamed stream which drains southwest to the Niangua Arm of the Lake of the Ozarks. The site of the former lagoon has been leveled, while the surrounding terrain exhibits moderate natural relief (5% to 9% slopes). East of the site lies the City of Camdenton. West of the site, the landscape is more rugged, and forests extend down to the Lake of the Ozarks. The natural landforms and drainage patterns at the site have been obscured by lagoon construction and, later, by soil removal actions. Land use patterns for the surrounding upland areas near the Former Hulett Lagoon site include residential properties with some light-industrial and commercial use.

#### **Rainfall Data**

The average annual precipitation in the area of the Former Hulett Lagoon site is slightly more than 37 inches. Average annual run-off is around 10 inches, and

evapotranspiration amounts to about 28 inches per year; therefore, little precipitation is available for infiltration (Vandike, 1995). The 2-year, 24-hour rainfall for the area is about 3.5 inches (Rainfall Frequency Atlas, undated).

#### **Surface Water Migration Path**

Below the Former Hulett Lagoon Site, the receiving stream is fairly steep and the bedload consists mostly of cobbles and gravels. Any metals or solvents that may have reached the stream are unlikely to be detected in the sediments. Groundwater contamination is the main concern at the Former Hulett Lagoon Site.

In 1992 James Vandike, a DGLS geologist with the Water Resources Program, examined area streams as part of the Modine investigation (Vandike, March 18, 1992). The Former Hulett Lagoon site is located on the valley floor of an intermittent stream referred to by Van Dike as the "northeast branch" of an unnamed tributary to Jarvis Hollow (Figure 1). The "southeast branch" of the tributary drains the Modine site. The northeast and southeast branches join near the western corporate boundary of the City of Camdenton, approximately 0.6 miles downstream of the Former Hulett Lagoon Site. The lagoon was constructed near the headwaters of the northeast branch, just west of the ridge top where most of Camdenton is located. Water runs onto the site from the upper section of the northeast branch. This channel has been diverted around the northern edge of the former lagoon; thus, only the southern slope of the valley provides surface runoff to the site. The assigned Hazard Ranking System (HRS) Drainage Area Value is 1 (Federal Register, 1990).

Run-off from the site enters the northeast branch and flows toward the west for ¼ mile. Runoff then flows southwest approximately 1.6 miles and enters Jarvis Hollow in the NE ¼, NE ¼, SE1/4 of Section 34, Township 38 North, Range 17 West. According to the 7.5 minute Hahatonka topographic map, the 0.15-mile-long stream segment below this confluence appears to be perennial. Thus, the confluence of the unnamed tributary and the stream in Jarvis Hollow is considered the probable point of entry (PPE) to surface water. If the short stream segment is not perennially flowing, the PPE would then be located at the mouth of Jarvis hollow, where the stream enters the Lake of the Ozarks. Runoff from the Former Hulett Lagoon reaches the Lake of the Ozarks approximately 1.97 miles downstream of the site. Figure 1 illustrates drainage patterns and overland flow directions in the vicinity of the site.

The 1983 Green Bay Terrace 7.5-minute topographic map does not distinguish perennial from intermittent streams. All streams are shown as solid blue lines. However, the 1959 Green Bay Terrace map depicts the unnamed tributary that drains the site as intermittent.

Vandike noted that the unnamed tributary lost flow in some locations, especially when encountering the Gunter Sandstone. However, Vandike anticipated that any flow lost in

the streambed would stay in the valley. He noted that very little rainfall was necessary to generate surface flow throughout the reach of the stream. The receiving stream for the Former Hulett Lagoon Site has not been officially classified by DGLS, but based on available reports, the stream should be considered losing. The Gasconade Dolomite that forms much of the stream bed is not particularly karst. Many nearby streams have been classified as losing (Losing Stream File, 1999).

The 15-mile downstream limit (Figure 4) ends near Shepard Cove on the Osage River Arm of the Lake of the Ozarks, approximately 29.5 miles above Bagnell Dam. This point is located on the Camdenton, MO 7.5-minute quadrangle; SE ¼, Section 24, T. 39 N., R. 17 W. The Osage River flows in a north-easterly direction, toward the Missouri River.

#### **SURFACE WATER TARGETS**

#### **Drinking Water Intakes**

No known direct intake of stream water is located within 15 downstream miles of the PPE (Hahatonka, Green Bay Terrace, and Camdenton Quadrangles; DuCharme and Miller, 1996; and Inventory of Missouri Public Water Systems, 1997). The 15-mile surface water target distance limit is shown on Figure 4.

#### **SOIL / AIR PATHWAY**

Contaminated soils at the Former Hulett Lagoon were trucked off to the Camdenton Sludge Disposal Area in 1988. Potential downstream or downwind receptors are not likely to be affected by the Former Hulett Lagoon Site itself.

The native soil in the vicinity of the Former Hulett Lagoon site was the Clarksville-Gepp very cherty silt loam (Wolf, 1994). The Clarksville-Gepp soils are deep, well-drained soils typical of sloping uplands. Permeability is moderate. The content of organic material is moderately low. The shrink-swell potential is moderate. Grass at the site limits wind erosion.

The HRS Soil Group Designation from Table 4-4 is B (Federal Register, 1990).

#### REFERENCES

Anderson, K. H., et. al., Geologic Map of Missouri. Missouri Department of Natural Resources, Division of Geology and Land Survey, 1979, 1 sheet.

- Brown, James C., unpublished geologic map of the Hahatonka 7.5-Minute Quadrangle, SP-8426. Missouri Department of Natural Resources, Division of Geology and Land Survey, 1984, 1 sheet.
- Camdenton 7.5-Minute Topographic Quadrangle. Department of the Interior, United States Geological Survey, 1983, 1 sheet.
- Dames & Moore, Summary Report of Investigative and Remedial Activities Conducted to Achieve Closure of the Interim TSD Facility Modine Manufacturing Company Camdenton, Missouri, October 9, 1998, 33 pages and 17 figures.
- Dames & Moore, Final Report of Fracture System Investigation, Modine Heat Transfer, Inc., Camdenton, Missouri, July 17, 1996, 13 pages and 11 figures.
- Decaturville 7.5-Minute Topographic Quadrangle. Department of the Interior, United States Geological Survey, 1975, 1 sheet.
- DuCharme, C. B. and T. M. Miller, Missouri State Water Plan Series, Volume IV: Water Use of Missouri. Missouri Department of Natural Resources, Division of Geology and Land Survey, 1996, 150 pages.
- Federal Register, Volume 55, No. 241, Friday, December 14, 1990.
- Gann, E. E., Water Resources of South-Central Missouri, Hydrologic Investigations Atlas HA-550. Department of the Interior, United States Geological Survey, 1976, 4 sheets.
- Green Bay Terrace 7.5-Minute Topographic Quadrangle. Department of the Interior, United States Geological Survey, 1983, 1 sheet.
- Green Bay Terrace 7.5-Minute Topographic Quadrangle. Department of the Interior, United States Geological Survey, 1959, photorevised 1982, 1 sheet.
- Gregg, J. M., J. R. Palmer, and V. E. Kurtz, Field Guide to the Upper Cambrian of Southeastern Missouri: Stratigraphy, Sedimentology, and Economic Geology. Department of Geology and Geophysics, University of Missouri, Rolla MO 65401, 1989.
- Guidance for Performing Preliminary Assessments Under CERCLA, EPA/540/G-91/013, Publication 9345.0-01A, September 1991.
- Hahatonka 7.5-Minute Topographic Quadrangle. Department of the Interior, United States Geological Survey, 1982, 1 sheet.

- Harvey, E. J., John Skelton, and D. E. Miller, Hydrology of Carbonate Terrane Niangua, Osage Fork, and Grandglaize Basins, Missouri, Water Resources Report 35, Missouri Department of Natural Resources, Division of Geology and Land Survey, 1983.
- Imes, J. L., Major Geohydrologic Units in and Adjacent to the Ozark Plateaus Province, Missouri, Arkansas, Kansas, and Oklahoma, U.S. Geological Survey Hydrologic Investigations Atlas HA-711-A, scale 1:750,000, 1991, 1 sheet.
- Imes, J. L., Major Geohydrologic Units in and Adjacent to the Ozark Plateaus Province, Missouri, Arkansas, Kansas, and Oklahoma Ozark Aquifer, U.S. Geological Survey Hydrologic Investigations Atlas HA-711-E, scale 1:750,000, 1990, 3 sheets.
- Inventory of Missouri Public Water Systems, 1997. Missouri Department of Natural Resources, 210 pages, 1997.
- Krehbiel Engineering, Inc., Transmittal concerning the public-water-supply well on Hickory St., Camdenton, Missouri, (Including copies of pump test data and the pressure grout survey); addressed to James Vandike DNR-DGLS Water Resources Program, September 3, 1998.
- Losing Stream File. Missouri Department of Natural Resources, Division of Geology and Land Survey, February, 1999.
- McCracken, Mary H., Structural Features of Missouri, Report of Investigation Number 49. Missouri Geological Survey and Water Resources, 1971.
- Missouri Water Atlas. Missouri Department of Natural Resources, Division of Geology and Land Survey, 1986.
- Missouri Water Resources Law Annual Report, Water Resources Report Number 52. Missouri Department of Natural Resources, Division of Geology and Land Survey, 1996, 30 pages.
- Missouri Well Construction Rules, Private Water Wells, Heat Pump Systems, Pump Installations and Monitoring Wells, Authorizing Statutes 256.600 to 256.640 RSMo, Missouri Department of Natural Resources, Division of Geology and Land Survey, 1996.
- Missouri Wellhead Protection Program, Missouri Department of Natural Resources, Division of Environmental Quality, Public Drinking Water Program, December, 1994.
- Palmer, J. R and Hayes, T. S., Maps Showing Locations of Known Mississippi Valley-Type Deposits and Occurrences in the Ozark Mountains Region Relative to Late

- Cambrian Shaly Lithofacies and Other Shales, Missouri, Arkansas, Kansas, and Oklahoma. U.S. Geological Survey Miscellaneous Field Studies Map MF-1994-F, 1997.
- Rainfall Frequency Atlas of the United States, Technical Paper Number 40. United States Department of Commerce, undated.
- Soil Survey of Camden County, Missouri, United States Department of Agriculture Soil Conservation Service in cooperation with Missouri Agricultural Experiment Station, April 1989.
- Thompson, Thomas L., Paleozoic Succession in Missouri- Part 2, Ordovician System, Report of Investigations Number 70. Missouri Department of Natural Resources, Division of Geology and Land Survey, 1991.
- Vandike, J. E., Missouri State Water Plan Series, Volume 1: Surface Water Resources of Missouri, Water Resources Report Number 45. Missouri Department of Natural Resources, Division of Geology and Land Survey, 1995, 122 pages.
- Vandike, J. E., A Hydrologic Analysis of the Ozark Aquifer in the Rolla Area, Missouri, Water Resources Report Number 41. Missouri Department of Natural Resources, Division of Geology and Land Survey, 1992, 84 pages.
- Vandike, J. E., Memorandum to Mimi Garstang, Chief, Waste Management Unit, DGLS; Subject: Hydrolocic investigation of the Sundstrand (Modine) site area, Camden County, MO; Missouri Department of Natural Resources, Division of Geology and Land Survey, March 18, 1992, 3 pages.
- Water Resources Data, Missouri Water Year 1989, U.S. Geological Survey Water-Data Report MO-89-1. Department of the Interior, United States Geologic Survey, 1990, 354 pages.
- Wedge, Keith, Structural Features of Missouri. Missouri Department of Natural Resources, Division of Geology and Land Survey, in preparation.
- Well logs for the Camdenton area on file at DGLS, March, 1999.
- Wolf, David W., Soil Survey of Camden County, Missouri. U.S. Department of Agriculture, Soil Conservation Service, 1994, 127 pages.

Table 1. Stratigraphic Column for Former Hulett Lagoon, Camden County (after Harvey et. al.,1983)

System	Aquifer Group	Approximate Site - Specific Thickness (ft)	Formation	Hydraulic Conductivity (cm/sec)	Regional Thickness (ft)	Dominant Lithology	Water-bearing Character
Quaternary		8	Colluvium and residuum		0-90	Regolith of residual clay, sand, chert pebbles and cobbles	May contain small amounts of perched water.
Ordovician	Ozark Aquifer	0?	Roubidoux Formation	10 <sup>-3</sup>	0-90	Clayey residuum, sandstone and sandy dolomite	Not present in sufficient thickness in the Camdenton area to produce usable quantities of water.
		300	Gasconade Dolomite	10 <sup>-6</sup>	300-385	Cherty dolomite, minor sandstone, and shale	Yields moderate to large quantities of water to wells. Yields range from 20 to 75 gpm. Less-permeable Upper Gasconade may act as a leaky confining unit.
		25	Gunter Sandstone Member	10 <sup>-4</sup>	10-45	Sandstone	Contributes moderate to large quantities of water. Most wells open to other formations.
		500?	Eminence Dolomite	10 <sup>-5</sup>	240-600?	Cherty dolomite	Yields 6-100 gpm, the average being about 20 gpm
		150?	Potosi Dolomite	10 <sup>-4</sup>	30-330	Dolomite; contains abundant quartz druse	Yields large quantities of water to wells. Yields range from 100 to 750 gpm.
Cambrian	St. Francois	180	Derby-Doerun Dolomite	10 <sup>-7</sup>	80?-215	Shaley dolomites and shale	Reliable aquitard.
	Confining Unit	80	Davis Formation	10 <sup>-7</sup>	50-380?	Shaley dolornites and shale	Reliable aquitard.
	St. Francois	160	Bonneterre Formation	10 <sup>-5</sup>	85-200	Dolomite and limestone	Generally used only in outcrop
	Aquifer	240	Lamotte Sandstone	10-5	140-300	Sandstone and arkosic conglomerate	areas. May contribute additional 100-200 gpm to wells open to other formations.
Precambrian	Basement Confining Unit					Igneous and metamorphic rocks	Does not yield water to wells in this area

# able 2: Former Hulett Lagoon (PA/SI), Camden County, Missouri

Wells located 0 to 0.25 Miles from the Former Hulett Lagoon

Source	Well ID	Depth	CSE	Q1	Q2	Q3	SEC	TWN	RNS	Elev	SWL	Date	Use	Owner	Aquifer	PWSSDEXT D#	GPM
0 to	0.25	Mi	les	3													
WIMS	0054495A	407	105		SE	sw	24	38N	17W	0	0	10/17/90	Private Well	PRICE	Ozark		0
0.25	to 0	.5	Mil	es	3		·		,								
PDWP	40376	900	400	SW	NE	NW	25	38N	17W		95	1986	Community	CITY OF CAMDENTON #6 - Mulberry	Ozark	3010130103	600
0.5	to 1 N	Лilе	€														<u>:</u>
LOGMAIN	27877	1060	400	NE	NW	NE	25	38N	17W	1010	315	1974	Community	CITY OF CAMDENTON #4 - Blair	Ozark	3010130102	300
WIMS	0019268A	1100	463	SE	SE	SE	24	38N	17W	1024	260	11/16/98	Community	CITY OF CAMDENTON #7 - Hickory	Ozark		550
WIMS	0068392A	400	220	NE	sw	SE	23	38N	17W	230	220	11/13/91	Private Well		Ozark		30
WIMS	0084612A	420	100		SW	SE	23	38N	17W	0	210	4/27/92	Private Well	HULETT	Ozark		30
1 to	2 Mi	les	·-··-				·										
LOGMAIN	20180	1020	450		SE		25	38N	17W	1036	254	1961	Community	CITY OF CAMDENTON #3 - Rodeo	Ozark	3010130101	325
LOGMAIN	26540	600	403	NW	SE	sw	14	38N	17W	1006	165	1969	Nontransient	PROF NURSING HOME OF AM.	Ozark		140
LOGMAIN	28665		235				22	38N	17W	0		1987	Transient	MO.DEPT.CONSERVATION #2	Ozark		
PDWP	41987	0	0	0	0	0	0	0	0	0	0	0	Transient	Lake Dental Clinic	Ozark	3238244101	. 0
WIMS	0002076A		127			SE	04	30N		0		8/14/87	Private Well	GALLAGHER, SR	Ozark		- 33
WIMS	0004240A	0	0				30		16W	0	-	10/20/87	Private Well	DIAL	Ozark		0
WIMS	0005180A		84			NW			17W	0	120		Private Well	STINER	Ozark		20
WIMS	0005184A		170			SE	22		17W	0		9/25/87	Private Well	RAKEY	Ozark		40
WIMS	0006144A	0	0			NE	27		17W	0		5/16/88	Private Well	SULHAM	Ozark		0
WIMS	0014191A		235			NE	22		17W			8/17/87	Private Well	CONSERVATION	Ozark		35
WIMS	0015210A		440			SE	14		17W	0			Private Well	WATKINS	Ozark		80
WIMS	0016656A		166		NW		22		17W	0	280	7/6/89	Private Well	WEBB	Ozark		20
WIMS	0034711A		105		NW		27		17W	689	20	6/7/90	Private Well	BOYCE	Ozark		25
WIMS	0034716A		105			SE	27		17W	669	8	5/29/90	Private Well	FIFIELD	Ozark		0
WIMS	0046879A		140			NW	22		17W	689	40	5/20/91	Private Well	DICKEMANN	Ozark		40
WIMS	0046891A	498	122		SW	NE	22	38N	17W	0	325	11/7/93	Private Well	MARR	Ozark		18
WIMS	0052628A	210	120		SE	SW	22	38N	17W	0	35	5/1/92	Private Well	SPICER	Ozark		30
WIMS	0052656A	210	100		NM	NE	34	38N	17W	0	35	8/15/92	Private Well	SALLS	Ozark		20

- Mella located - Filo E Millea - Holli Hie Follifel Fildlett Fadooli	Wells located	1 to 2 Miles	from the Former Hulett Lagoon
---	---------------	--------------	-------------------------------

Source	Well ID	Depth	CSG	Q1	<b>Q2</b>	Q3	SEC	TWN	RNG	Elev	SWL	Date	Use	Owner	Aquifer	PWSSIDEXT ID#	CPM
WIMS	0054516A	407	168		NE	NW	13	38N	17W	0	220	10/25/90	Private Well		Ozark		40
WIMS	0059221A	215	106				27	38N	17W	690	22	12/6/90	Private Well	MONTGOMERY	Ozark		25
WIMS	0062723A	380	102		ΝE	SW	27	38N	17W	0	265	3/13/91	Private Well	MCKEVER	Ozark		30
WIMS	0066010A	260	121			sw	27	38N	17W	0	12	5/19/92	Private Well	BAILEY	Ozark		30
WIMS	0091425A	200	140	NE	SE	NW	27	38N	17W	698	18	8/26/93	Private Well	BRIGGS	Ozark		20
WIMS	0096827A	178	14	sw	ΝE	SW	27	38N	17W	0	23	12/16/93	Private Well		Ozark		15
WIMS	0096841A	340	220	NW	ΝE	NW	27	38N	17W	787	125	2/18/94	Private Well	BARE	Ozark		40
WIMS	0120553A	520	250	NW	SW	NE	22	38N	17W	0	350	9/14/94	Private Well	LEDBETTER	Ozark		25
WIMS	0120852A	235	174		NW	SE	22	38N	17W	0	80	6/27/94	Private Well	HOLLINGSWORTH	Ozark		25
WIMS	0120868A	293	110	NE	SE	SW	22	38N	17W	0	140	11/24/94	Private Well	ZEY	Ozark		25
WIMS	0173794A	220	143				27	38N	17W	0	30	10/31/92	Private Well	STONER	Ozark		35
WIMS	0186114A	320	142		NW	ŞE	27	38N	17W	0	20	9/25/97	Private Well	NEWILL	Ozark		65
WIMS	0190879A	230	160		NW	SE	27	38N	17W	0	20	5/22/97	Private Well	WOMACK	Ozark		0

## 2 to 3 Miles

LOGMAIN	006568	70	41	NW	SE	SE	16	38N	17W	671		1940	Private Well	SCOTT, L C #1	Ozark		50
LOGMAIN	014093	570	250	SE	SE	NW	15	38N	17W	990	195	1955	Private Well	SCOTT, L.C. #2	Ozark		55
LOGMAIN	25162	550	250	SE	NW	SE	33	38N	17W	764	78	1967	Transient	LAKE VALLEY COUNTRY CLUB	Ozark		93
LOGMAIN	26629	505	350	S2	N2	NW	32	38N	16W	1021	250	1970	Nontransient	VIRGIL EADES TRAILER CT	Ozark	3048141101	100
LOGMAIN	28620	860	528				17	38N	16W	0	90	1983	Community	CITY OF LINN CREEK	Ozark	3010471102	225
LOGMAIN	5698	296	170	SE	NW	NW	17	38N	16W	696	15	1939	Community	CITY OF LINN CREEK	Ozark		40
PDWP	41487	0	0	0	0	0	0	0	0	0	0	0	Transient	Cedar Green Resort	Ozark	3010130103	0
PDWP	41580	350	80	0	0	0	0	0	0	0	63	1978	Transient	Adam's Ale Resort Inc	Ozark	3191518101	0
PDWP	41581	140	20	0	0	0	0	0	0	0	20	1973	Transient	Rippling Waters Resort	Ozark	3191747101	25
PDWP	41615	300	0	0	0	0	0	0	0	0	0	1984	Transient	Lake Valley Condos	Ozark	3210248101	0
PDWP	42571	300	0	0	0	0	0	0	0	0	0	1985	Transient	Lake Valley Condos	Ozark	3258251101	0
PDWP	42572	340	0	0	0	0	0	0	0	0	0	1986	Transient	Lake Valley Condos	Ozark	3238026102	0
PDWP	42573	340	0	0	0	0	0	0	0	0	0	1987	Transient	Lake Valley Condos	Ozark	3238026103	0
PDWP	42611	150	20	0	0	0	0	0	0	0	30	1982	Transient	Rippling Waters Resort	Ozark	3238026104	25
WIMS	0000624A	138	82				28	38N	17W	0	50	6/15/87	Private Well	RESORT	Ozark		25
WIMS	0001841A	380	305				32	38N	16W	0	225	7/30/87	Private Well	BOND	Ozark		30
WIMS	0002012A	260	84				28	38N	17W	0	90	8/25/87	Private Well	ULIUS	Ozark		20
WIMS	0002249A	420	147				31	38N	16W	0	215	8/25/87	Private Well	MOSIER	Ozark		30
WIMS	0004060A	400	105		SW	NE	31	38N	16W	0	200	10/5/87	Private Well	DAUGHERTY, SR.	Ozark		30
WIMS	0005182A	198	84		NE	NW	03	37N	17W	685	38		Private Well	SUTTON	Ozark		20
WIMS	0005246A	195	105		SW	NE	28	38N	17W	0	30	4/21/88	Private Well	BRANY	Ozark		30
WIMS	0005557A	300	126				17	38N	16W	0	200	4/22/88	Private Well	ENTERPRISES	Ozark		25
WIMS	0005948A	217	88		SW	NE	28	38N	17W	0	0		Private Well		Ozark		30
WIMS	0005951A	340	105		SW	NE	34	38N	17W	0	145	11/21/87	Private Well	SALLS	Ozark		30

Wells located 2 to 3 Miles from the Former Hulett Lagoon

Source	Well ID	Depth	C86	Q1	<b>Q2</b>	<b>Q</b> 3	SEG	TWN	RNG	Elev	SWL	Date	Use	Owner	Aquifer PW88IDEXT ID#	GPM
WIMS	0005999A	178	105		NW	NW	03	37N	17W	0	25	7/25/87	Private Well	WEBB	Ozark	20
WIMS	0006000A	218	147		NW	NW	03	37N	17W	0	60		Private Well	HANKS	Ozark	25
WIMS	0007295A	380	126		SE	SE	17	38N	16W	0	270	7/27/88	Private Well	WILLIAMS	Ozark	40
WIMS	0007296A	380	85		sw	NE	17	38N	16W	٥	250	5/22/88	Private Well	KOWAL	Ozark	20
WIMS	0007306A	530	210		SE	NE	33	38N	17W	0	65	6/23/88	Private Well	LAKE VALLEY	Ozark	75
WIMS	0007320A	155	105		sw	NE	12	38N	17W	0	20	8/5/88	Private Well	WILBURN	Ozark	60
WIMS	0011103A	0	0	SE	ΝĘ	NW	03	37N	17W	0	12	6/24/88	Private Well	LUKOSIUS	Ozark	0
WIMS	0011741A	0	84		sw	NE	28	38N	17W	0	90	8/25/87	Private Well	ULIUS	Ozark	20
WIMS	0012040A	385	83		NE	SE	01	37N	17W	0	200	9/1/88	Private Well	JONES	Ozark	37
WIMS	0012651A	178	105		NE	NE	21	38N	17W	680	20	3/16/89	Private Well	STAUCH	Ozark	20
WIMS	0014203A	340	168				16	38N	17W	0	210	8/18/87	Private Well	THOMPSON	Ozark	35
WIMS	0015206A	343	103		NE	sw	32	38N	16W	0	140	6/15/89	Private Well	HICK	Ozark	25
WIMS	0015367A	170	108		SW	NE	28	38N	17W	0	0	2/15/89	Private Well	MORRIS	Ozark	30
WIMS	0026787A	343	105		NE	NE	28	38N	17W	0	60	11/14/89	Private Well	HEAD	Ozark	35
WIMS	0033740A	158	90		NW	NW	03	37N	17W	670	10	7/25/89	Private Well	SUTTON	Ozark	20
WIMS	0043289A	100	0		NE	NW	34	38N	17W	0	0		Private Well	LAMPERT	Ozark	0
WIMS	0044602A	380	139		sw	NW	32	38N	16W	0	205	6/18/89	Private Well	NEELEY	Ozark	25
WIMS	0044623A	200	126		NE	NE	21	38N	17W	690	43	10/27/89	Private Well	STAUCH	Ozark	20
WIMS	0044635A	220	126		ИW	NW	03	37N	17W	670	62	11/24/89	Private Well	PERSELS	Ozark	30
WIMS	0047228A	235	140		NE	sw	21	38N	17W	0	45	8/16/90	Private Well	MCADAMS	Ozark	30
WIMS	0052590A		175	SW	SW	SW	21	38N	17W	0	60	11/11/90	Private Well	COLLINS	Ozark	55
WIMS	0052595A	151	80	NE	NW	SW	34	38N	17W	680	10	12/13/90	Private Well	FOSTER	Ozark	25
WIMS	0052626A		110	sw	SE				17W	710	65	9/3/93	Private Well	DICKMAN	Ozark	25
WIMS	0054310A		120			sw			17W	660			Private Well	ROWE	Ozark	30
WIMS	0054311A		119			sw			17W				Private Well	BALMER	Ozark	30
WIMS	0054493A		126			sw			17W	0			Private Well	THOMASON	Ozark	. 35
WIMS	0058354A	360	126			NW				0	205	11/30/90		SIMMONS	Ozark	20
WIMS	0062718A		100	NW			20	38N		0	12	3/9/91	Private Well	BARCLAY	Ozark	60
WIMS	0062770A		107	NE	NW				17W	689	22	7/19/91	Private Well	STOVER	Ozark	30
WIMS	0064171A		124	0147		SE	10		17W	0	30	6/25/91	Private Well	OCAMPO	Ozark	30 35
WIMS	0064821A		153		SE				17W	730	78 45	11/3/94	Private Well	LUTHER	Ozark	25
WIMS	0068405A		100		NW		03		17W	680			Private Well	REAM	Ozark	20 25
WIMS	0077405A	_	80	NE	NE		15		17W	940	240		Private Well	BENBOW	Ozark	25 25
WIMS	0077412A		80			SW			17W	0			Private Well	ROBINSON	Ozark	25 20
WIMS	0077420A		80	N 15 A 1		NE	20		16W	0	195	11/1/92		SHMIDT	Ozark	20 35
WIMS	0077771A	-		ΝW	SW		34		17W	660	23	9/17/92	Private Well	LOMBARDO	Ozark	25 25
WIMS	0088177A		82	<b>.</b>		SW	28	38N		0	90	5/13/92	Private Well	CYROS	Ozark	25
WIMS	0091365A	195	140	NW	NW	SW	27	38N		689	42	5/22/93	Private Well	SWANSON	Ozark	30
WIMS	0120260A	180	120				21	38N	17W	0	15		Private Well	JACKSON	Ozark	20

Source	Well D	Depth	CSE	Q1	Q2	<b>Q</b> 3	SEC	TWN	RNG	Elev	SWL	Date	U88	Owner	Aquifer PWSSDEXT D#	GPN
WIMS	0120860A	352	80	NE	sw	NW	32	38N	16W	0	170	9/15/94	Private Well	BURNS	Ozark	20
WIMS	0120864A	375	100	SE	NW	SE	17	38N	16W	0	270	10/2/94	Private Well	SHRAUGEN	Ozark	20
WIMS	0120872A	393	100		SW	NE	17	38N	16W	0	260	11/9/94	Private Well	BOOKE	Ozark	25
WIMS	0120872A	393	100		SW	NE	17	38N	16W	0	260	11/9/94	Private Well	BOOKE	Ozark	25
WIMS	0138061A	310	80		sw	NE	17	38N	16W	0	170	4/10/96	Private Well	WITTE	Ozark	20
WIMS	0158044A	340	102		SE	sw	34	38N	17W	0	140	8/22/96	Private Well	GOLDSTEN	Ozark	20
WIMS	0169782A	300	97				10	38N	17W	0	175	5/28/97	Private Well	EBERT	Ozark	30
WIMS	0182558A	340	100		NW	NW	03	37N	17W	0	120	6/30/97	Private Well	WILSMAN	Ozark	15
3 to	4 Mil	es														
LOGMAIN	013462	275	66	NE	NE	SE	07	37N	16W	1065	225	1955	Private Well	CHANDLER, MOCK	Ozark	5
LOGMAIN	015081	365	Λ	SE	NE	SW	16	38N	16\\	979		1956	Private Well	PARKINGON IOHN	Ozark	30

LOGMAIN	013462	275	66	NE	NE	SE	07	37N	16W	1065	225	1955	Private Well	CHANDLER, MOCK	Ozark		5
LOGMAIN	015981	365	0	SE	NE	SW	16	38N	16W	979		1956	Private Well	PARKINSON, JOHN	Ozark		30
LOGMAIN	018777	140	28	С	SW	NW	09	38N	16W	790	20	1959	Private Well	BOND, GUY O.	Ozark		20
OGMAIN	27342	540	400	NW	SW	NE	17	38N	16W	800	150	1973	Nontransient	ST. MORITZ	Ozark		75
OGMAIN	27691	925	430	SE	NW	NE	02	38N	17W	886	230	1974	Nontransient	CAMELOT ESTATES	Ozark		
OGMAIN	28162	800	470	С	NW	sw	05	38N	16W	900			Nontransient	CAPE OF THE WOODS	Ozark		
PDWP	41567	300	150	0	0	0	0	0	0	0	20	1984	Transient	Clearwater Resort	Ozark 3	190757101	30
PDWP	41610	0	0	0	0	0	0	0	0	0	0	0	Transient	54 & A Truck Stop & Restaurant	Ozark 3	191748101	0
PDWP	41619	0	0	0	0	0	0	0	0	0	0	0	Transient	Windwood Condos	Ozark 3	238026101	0
VIMS	0000178A	200	84				01	38N	17W	0	82	4/15/87	Private Well	GROHE	Ozark		15
VIMS	0000428A	300	84				01	38N	17W	0	166	4/30/87	Private Well	SHUMATO	Ozark		15
VIMS	0001307A	138	103				03	37N	17W	0	15	6/4/87	Private Well	TALLEY	Ozark		20
VIMS	0002013A	300	84				16	38N	16W	0	0	8/31/87	Private Well	HENSON	Ozark		20
/IMS	0002293A	196	103				29	38N	17W	0	30	7/23/87	Private Well	KEARNS	Ozark		30
VIMS	0002386A	238	84				16	38N	16W	0	30	9/18/87	Private Well	CONSTRUCTION	Ozark		30
/IMS	0002387A	238	0				16	38N	16W	0	0	9/18/87	Private Well	CONSTRUCTION	Ozark		0
VIMS	0004178A	363	105		NE	sw	03	38N	17W	0	100		Private Well	CLARK	Ozark		0
VIMS	0005142A	360	105				09	38N	17W	0	160	2/12/88	Private Well	COLEMAN	Ozark		35
VIMS	0005995A	176	105		sw	NE	06	38N	16W	0	15	8/10/87	Private Well	DONOHO	Ozark		30
VIMS	0006398A	0	0				21	38N	16W	0	0	5/9/88	Private Well	BAHNMILLER	Ozark		0
VIMS	0006809A	360	0		NE	SW	29	38N	17W	0	140	2/15/88	Private Well	COLEMAN	Ozark		0
VIMS	0006866A	0	0				16	38N	16W	0	0	6/3/88	Private Well	EBLING	Ozark		0
VIMS	0008263A	220	105				06	38N	16W	0	30	4/8/88	Private Well	LONG	Ozark		10
VIMS	0008591A	322	106				09	37N	17W	0	25	9/3/88	Private Well	COLLINS	Ozark		40
VIMS	0008592A	385	84				29	38N	17W	0	180	9/10/88	Private Well	DAILEY	Ozark		30
VIMS	0008719A	400	181		NM	SE	28	38N	16W	0	155	8/25/88	Private Well	TRUITT	Ozark		30
VIMS	0008724A	477	87		SW	SW	33	38N	17W	0	260	8/28/88	Private Well	COY	Ozark		22
VIMS	0009625A	240	110		SE	SE	20	38N	17W	0	30		Private Well	WARD	Ozark		18
VIMS	0009676A	180	126		SW	NE	03	38N	17W	0	30	8/9/88	Private Well	DERRINGER	Ozark		40


Wells located 3 to 4 Miles from the Former Hulett Lagoon

Source	WeI ID	Depth	CSE	Q1	Q2	<b>Q</b> 3	SEC	TWN	RNG	Elev	SWL	Date	Use	Owner	Aquifer	PW88DEXT ID#	GPM
WIMS	0011489A	400	106		SE	NW	28	38N	16W	0	160	10/16/88	Private Well	RAYBURN	Ozark		25
WIMS	0011697A	375	80		NE	SE	20	38N	17W	0	0	7/26/88	Private Well	SHARP	Ozark		18
WIMS	0012606A	219	84				03	38N	17W	0	0	5/1/88	Private Well	HASTINGS	Ozark		40
WIMS	0015212A	651	405		sw	sw	33	38N	16W	0	170	5/16/89	Private Well		Ozark		90
WIMS	0015364A	200	92		NE	NE	07	38N	16W	0	10	3/18/89	Private Well		Ozark		40
WIMS	0015368A	210	87		NW	ΝE	04	37N	17W	0	30	2/1/89	Private Well	MORRIS	Ozark		12
WIMS	0019739A	480	202		NE	NE	01	38N	17W	0	140	12/9/96	Private Well	FRETHOLM	Ozark		50
WIMS	0026793A	198	190		SE	NW	04	37N	17W	720	0	1/23/90	Private Well	COLLINS	Ozark		60
WIMS	0035888A	333	121		NE	sw	28	38N	16W	0	210	6/25/91	Private Well	ROYALS	Ozark		20
WIMS	0035889A	332	80		SE	NW	16	38N	17W	0	180	5/10/94	Private Well	STIDHAM	Ozark		18
WIMS	0035905A	297	86		SW	NE	16	38N	16W	0	115	2/20/90	Private Well	EVANS	Ozark		100
WIMS	0035914A	353	128		NE	sw	16	38N	16W	0	180	12/9/89	Private Well	MABREY	Ozark		50
WIMS	0043866A	400	103		SE	NW	16	38N	17W	0	207	5/8/90	Private Well	LUX	Ozark		20
WIMS	0046869A	353	106		NE	sw	33	38N	17W	0	245	12/26/90	Private Well	MORRIS	Ozark		15
WIMS	0046884A	190	80		NE	NW	16	38N	16W	0	45	7/8/93	Private Well	EVELAND	Ozark		12
WIMS	0046895A	377	119		NE	NE	05	37N	16W	0	205	10/1/93	Private Well	GEORGE	Ozark		25
WIMS	0052598A	312	100		NW	sw	21	38N	16W	0	155	9/13/92	Private Well	BARTLETT	Ozark		25
WIMS	0052601A	210	140		NW	SE	20	38N	17W	0	40	5/2/93	Private Well	MCGRATH	Ozark		50
WIMS	0052623A	248	84		NE	NE	17	38N	16W	0	35	7/15/92	Private Well	JACKSON	Ozark		30
WIMS	0052632A	210	120	SE	SW	SE	20	38N	17W	665	45	7/1/92	Private Well	WERNER	Ozark		30
WIMS	0052650A	291	80		NW	sw	33	38N	17W	0	140	8/18/92	Private Well	RODGERS	Ozark		25
WIMS	0054161A	340	106		NW	SW	21	38N	16W	0	166	7/23/90	Private Well	STRINE	Ozark		22
WIMS	0054164A	355	170	SW	SW	ΝE	16	38N	17W	905	207	8/3/90	Private Well	SHERRELL	Ozark		30
WIMS	0057058A	210	100		SE	NW	33	38N	17W	0	55	2/22/94	Private Well	BULLOCK	Ozark		30
WIMS	0062753A	200	100				06	38N	16W	0	50	6/3/91	Private Well	ALSBACH	Ozark		20
WIMS	0062774A	360	144		NW	NW	21	38N	16W	0	205	7/30/91	Private Well	WEST	Ozark		30
WIMS	0066002A	260	182		NE	NE	04	37N	17W	0	90	3/31/92	Private Well	ICENOGLE	Ozark		25
WIMS	0068399A	200	100	NW	NW	NW	28	38N	17W	669	18		Private Well		Ozark		20
WIMS	0068406A	220	120	SE	SW	ΝE	20	38N	17W	679	18	10/1/91	Private Well	WHITE	Ozark		8
WIMS	0077419A	360	80		SE	NW	21	38N	16W	0	210	12/16/92	Private Well	WEBB	Ozark		40
WIMS	0091289A	250	103		NW	NE	04	37N	17W	0	23	12/1/93	Private Well	GRECO	Ozark		20
WIMS	0091290A	170	103		NW	NE	04	37N	17W	0	0	12/2/93	Private Well	FRUEH	Ozark		30
WIMS	0091373A	480	105	SW	SE	NW	16	38N	17W	0	290	7/14/93	Private Well	ROBBINS	Ozark		20
WIMS	0096836A	240	160	SW	NW	NW	03	37N	17W	680	50	3/26/94	Private Well	OVERBY	Ozark		30
WIMS	0100968A	460	167	ΝE	NW	NE	08	37N	16W	0	196	3/18/94	Private Well	ADAMS	Ozark		15
WIMS	0108332A	280	100	SW	SW	SE	03	37N	17W	0	102	12/30/94	Private Well	MIELKE	Ozark		20
WIMS	0108341A	260	160	SW	SW	NW	21	38N	17W	722	30	2/13/95	Private Well	FEUSER	Ozark		18
WIMS	0120261A	320	82			SE	29	38N	17W	0	160	5/11/94	Private Well	TURRICK	Ozark		25
WIMS	0120853A	273	84	SW	SW	NE	03	38N	17W	0	127	7/29/94	Private Well	ROOFENER	Ozark		35


Wells located 3 to 4 Miles from the Former Hulett Lagoon

Source	Wei id	Depth	CSE	Q1	Q2	<b>Q</b> 3	SEC	TWN	RNG	Elev	SWL	Date	Use	Owner	Aquifer	PWSSDEXT D#	GPM
WIMS	0120873A	170	110	sw	NW	NE	29	38N	17W	0	25	8/15/94	Private Well	WERNER	Ozark		20
WIMS	0138031A	351	100	sw	SW	NW	21	38N	16W	0	155	9/1/95	Private Well	STAMPER	Ozark		25
WIMS	0138062A	333	108		NW	SE	28	38N	16W	0	0	12/4/95	Private Well	LOCK	Ozark		25
WIMS	0138068A	230	80		SE	NW	16	38N	16W	0	70	3/15/96	Private Well	HARGROVE	Ozark		35
WIMS	0138069A	371	105		NW	sw	21	38N	16W	0	170	3/20/96	Private Well	SAMULSON	Ozark		25
WIMS	0138081A	310	80		NW	SE	28	38N	16W	0	145	10/22/96	Private Well	STAMPER	Ozark		20
WIMS	0138085A	310	80		SW	NE	16	38N	16W	0	125	4/10/97	Private Well	WILLIAMS	Ozark		25
WIMS	0141774A	395	100	ΝE	SW	NE	21	38N	16W	0	210	7/6/95	Private Well	LAKE WOOD CONS	Ozark		40
WIMS	0148329A	415	100				28	38N	16W	0	150	6/28/96	Private Well	DEVIS	Ozark		50
WIMS	0148588A	320	104	NW	SE	NW	21	38N	16W	0	110	12/15/95	Private Well	LATHROP	Ozark		40
WIMS	0154616A	300	120	NW	SE	NE	17	38N	16W	0	158	8/19/96	Private Well	OSTER	Ozark		25
WIMS	0157304A	375	82			sw	16	38N	16W	0	233	7/15/96	Private Well	KIMMBLE	Ozark		32
WIMS	0157305A	355	82			sw	16	38N	16W	0	188	7/15/96	Private Well		Ozark		24
WIMS	0157532A	460	100			NW	11	37N	17W	0	240	10/8/96	Private Well	NOBLE	Ozark		20
WIMS	0157785A	150	120				20	38N	17W	670	7	11/23/96	Private Well	BELL	Ozark		30
WIMS	0173793A	430	142				07	37N	16W	0	260	6/30/96	Private Well	ROTHOVE	Ozark		50
WIMS	0181020A	360	82	NE	SE	NW	03	38N	17W	258	220	7/7/97	Private Well	BARE	Ozark		15
WIMS	0185537A	300	180				80	38N	17W	0	90	9/8/97	Private Well	WRIGHT	Ozark		30
WIMS	0190450A	415	100		NW	NE	80	38N	16W	0	200	9/30/97	Private Well	WILLIAMS	Ozark		30

## Former Hulett Lagoon PA/SI Camdenton, Missouri Camden County Figure 1: Surface Water Pathway




# Former Hulett Lagoon PA/SI, Camdenton Missouri Figure 2: Cross-Section (see figure 1 for well locations)




# Former Hulett Lagoon PA/SI, Camdenton Missouri Figure 3 (see figure 4 for well locations)

Southwest Northeast



## Former Hulett Lagoon PA/SI Camden County

Figure 4: 15-Mile Surface Water Target Distance Limit




Former Hulett Lagoon Site Combined PA/SI Reference 44

This map is st to change as a information is Production Das.

November 05, 1998

2-24-44



Prepared by

Camdenton

6 wells, 2 chemical sites, 1 dealership

3010130



University of Missouri - Columbia

Wellhead

Chemical Site

Dealership

Half Mile Buffer

Dealership Area Site

Chemical

Area Site

Tank or WTP

One Mile Buffer

For base map symbols see the U.S. Geological Survey publication 'Topographic Map Symbols'



5000

Missouri Department of Natural Resources



Division of Environmental Quality Public Drinking Water Program

#### Camdenton 3010130 6 wells

\*Temporary DGLS well number. The correct well number is requested.

The information below represents the data currently associated with the water supply layers. The well/intake number corresponds to the well/intake numbers depicted on the accompanying map Blanks indicate missing data. This table is subject to change as additional information is acquired Source: Missouri Department of Natural Resources, Public Drinking Water Program.

Production Date: November 05, 1998

Temporary DGLS well number.	. The correct well number is re	quested.		Production Date: Nov	ember 05, 1998
Well Number	WI	W2 · -	W3	W4	W5
Extended PWS #	3010130101	3010130102	3010130103	30 <b>1013</b> 0104	3010130105
Local Well Name	City Hall	City Hall	Rodeo Grounds	Blair Hgts.	Kansas
DGLS Well #	46039*	46040*	20180	27 <b>877</b>	28356
Facility Type	City	City	City	City	City
Status	Abandoned	Abandoned	Active	Active	Inactive
Latitude	38 0 23.78 N	38 0 23.69 N	38 0 10.49 N	38 <b>0</b> 5.85 N	38 0 38.87 N
Longitude	92 44 39.29 W	92 44 39.41 W	92 44 18.82 W	92 45 36.61 W	92 44 22.34 W
USGS 7.5 Quadrangle	Camdenton	Camdenton	Camdenton	Green Bay Terrace	Camdenton
County	Camden	Camden	Camden	Camden	Camden
DNR Region	Jefferson City	Jefferson City	Jefferson City	Jefferson City	Jefferson City
Date Drilled (year)	1935	1940	1961	1974	1980
Material (C/U)	Consolidated	Consolidated	Consolidated	Consolidated	Consolidated
Yielding Strata	Potosi	Potosi	Potosi Dolomite	Potosi Dolomite	
Total Depth (feet)	794.0	800.0	940.0	1060.0	1100.0
Ground Elevation (ft)	1031.0	1031.0	,		
Top Seal	Yes	100 110	<del></del>	Satisfactory	Pressure Grout
Bottom Seal	Yes	•		Satisfactory	Pressure Grout
Casing Depth (feet)	80.0	75.0	450.0	400.0	435.0
Casing Size (inches)	12.0	6.0	8.0	10.0	10.0
Casing Type	Steel	Steel	Steel	Steel	Steel
Elev. of Casing Top (ft)	3.33.		5166.	545.	0.00.
Outer Casing Depth (ft)				46.0	20.0
Outer Casing Size (in)				16.0	16.0
Screen Length (feet)				10.0	1919
Screen Size (inches)			<del></del>	<del></del>	
Static Water Level (ft)	95.0	95.0	254.0	315.0	232.0
Well Yield (gpm)	100		380	100	
Head (feet)			50.0	100.0	
Draw Down (feet)			375.0	395.0	
Pump Test Date (year)			1984	1990	
Pump Type	Vertical Turbine	Vertical Turbine	Vertical Turbine	Vertical Turbine	
Pump Manufacturer	Worthington	Fairbanks Morse	Layne	Aurora	
Pump Depth (feet)			420	450	
Pump Capacity (gpm)	100	100	380	100	
Pump Meter (Y/N)		Y	Y	Y	
Standby Power (Y/N)		•	N	N	
VOC Detections (Y/N)			N	N	
Nitrate Detection (Y/N)			N	N	
Chlorination (Y/N)	<del></del>		N	N	
Filtration (Y/N)			N	N	
GWUDISW (Y/N)	·····		14	14	-,
State Approved (Y/N)		<del> </del>			
Surface Drainage	Satisfactory	Satisfactory		Satisfactory	
Date Abandoned (year)	1989	1989		Saustaciory	
Date Plugged (year)	1707	1707			
Location Method	Map Interpolation	Man Internalation			Man Internalation
	1300	Map Interpolation			Map Interpolation
Method Accuracy (feet)	1300	1300			100

# Camdenton 3010130 6 wells

The information below represents the data currently associated with the water supply layers. The well/intake number corresponds to the well/intake numbers depicted on the accompanying map Blanks indicate missing data. This table is subject to change as additional information is acquired Source: Missoun Department of Natural Resources, Public Drinking Water Program Production Date November 05, 1998 2-2

*Temporary DGLS well number.	. The correct well number is re	quested.	Production Date	November 05, 1998	2
Well Number	W6	W7			
Extended PWS #	3010130106				
Local Well Name	Mulberry Lane	HCKOTY			
DGLS Well #	40376*	•			
Facility Type	City	_			
Status	Active	Active			
Latitude	38 0 29.63 N				
Longitude	92 45 17.85 W				
USGS 7.5 Quadrangle	Green Bay Terrace				
County	Camden				
DNR Region	Jefferson City				
Date Drilled (year)	1986	1998			
Material (C/U)	Consolidated				
Yielding Strata	Potosi Dolomite	1100			
Total Depth (feet)	900.0				
Ground Elevation (ft)		ATTELYD GROUT			
Top Seal	Pressure Grout	pressure grout			
Bottom Seal	Pressure Grout	pressure groun			
Casing Depth (feet)	400.0	450 8			
Casing Size (inches)	12.0	•			
Casing Type	Steel	5166)			
Elev. of Casing Top (ft)					
Outer Casing Depth (ft)	48.0				
Outer Casing Size (in)	16.0				
Screen Length (feet)					
Screen Size (inches)					
Static Water Level (ft)	95.0				
Well Yield (gpm)	600	135			
Head (feet)	85.0				
Draw Down (feet)	265.0				
Pump Test Date (year)	1994	submersible			
Pump Type Pump Manufacturer	Vertical Turbine Fairbanks Morse				
Pump Depth (feet)	350	500		.خ. <u>ر</u>	
Pump Capacity (gpm)	100	500		<i>[1]</i> =	
Pump Meter (Y/N)	Υ		~		
Standby Power (Y/N)	N			) 	
VOC Detections (Y/N)	Y		**************************************	. <b>.</b>	
Nitrate Detection (Y/N)	N		1 .	-	
Chlorination (Y/N)	N				
Filtration (Y/N)	N		À	14	
GWUDISW (Y/N)			M.	-	
State Approved (Y/N)				•	
Surface Drainage	Satisfactory			-	
Date Abandoned (year)	<u></u>				
Date Plugged (year)					
Location Method		map interpolation			
Method Accuracy (feet)		100			

#### Camdenton 3010130 2 chemical sites.

The information below represents the data currently The information below represents the data currently associated with the water supply layers. The chemical site number corresponds to the chemical site numbers depicted on the accompanying map. Blanks indicate missing data. This table is subject to change as additional information is acquired. Source Missouri Department of Natural Resources, Public Drinking Water Program.

Production Date: November 05, 1998

Chemical Site #

CI

30035

C2 30036

Site ID# Latitude

38 0 32.69 N

38 041.53 N

Longitude

92 45 24.18 W

92 45 16.23 W

Name

Modine Heat Transfer, Inc.

Hulett Lagoon

Address

City

Camdenton

Camdenton

ZIP Code

Location Method

Map Interpolation

Map Interpolation

Method Accuracy (feet)

40

Chemical, Db

Trichloroethylene (TCE), Db 999 Cyanides, Db 999 Multiple Metals, Db 999 Multiple VOCs, Db 999

Cyanides, Db 999 Multiple Metals, Db 999 Multiple VOCs, Db 999

#### Camdenton 3010130 1 dealership

The information below represents the data currently associated with the water supply layers The dealership number corresponds to the dealership number corresponds to the dealership numbers depicted on the accompanying map. Blanks indicate missing data. This table is subject to change as additional information is acquired Source Missouri Department of Natural Resources, Public Drinking Water Program Production Date November 05, 1998

Dealership#

DI

Site ID#

20187

Latitude

38 0 19.8 N

Longitude

92 44 30.2 W

Name

Camdenton Farm & Garden

Address

Hwy 5 S

City

Camdenton

ZIP Code

65020

Database#

48

Location Method

Method Accuracy (feet)

Active

No

SUPPLY CAMPENTON	· · · · · · · · · · · · · · · · · · ·	Ĺ	•			
WELL DATA:	Down loved	Mounder			Rich of	
	Well No. 🕱	Well No. 7 2	Well No. 13	Well No. 4	Well No	Well No. 6
Date Drilled	1931	1931	1461	1974	1980	1986
Local Designation	CITY HALL	CITY HALL	Roden Grands	Black Hotz	Konzas A	Mulberry
Туре	DRILLED	DRILLED	DRILLED	Orilled	Drilled	Drilled
Total Depth	800'	794	940	10 45'	1100 < 1000	900.'
Depth and Size of Casing	79'-6"	80'-8"	450'- 8"	400' of 10"	435' % 10"	400' 4 12"
Casing Material	STEEL	STEEL	STEEL	Stee 1	Steel	Steel
Size Hole Below Casing Point	6"	87	8"	10"	10"	12"
Static Water Level	95'	95	254'	315' (rew) 2.6 9pm/fs.		
Draw Down and Yield	-170GPM	- 1706PM	- 325GM	(100) 210 97 744.		
Water-Bearing Strata	POTOSI SPLIT RING	POTOSI SPUT RING	ROUBIDOUX PUMP MOTOR			
Top Seal (Method)	SAN WELL SEAL		BASE PRESSURE	Pump Pater Buse	3-19-80	6-24-86
Bottom Seal	ļ	GROUT	GROUT 8/25/GI	Press. Great	Pres. Grout	Pres Grout
Pump Type	SUBMERSIBLE	SUBMERSIBLE	VERT. TURBINE	Vert. Turbine		Verl. Turb lub.
Manufacturer	REDA	REDA	LAYNE	Aurora		Towbanks Morse
Capacity	170+ GPM	170+6PM .	320 400+ GPM.	300 cpm	<del></del>	575
Pump Setting	350'	400'	420'			
Meter	YES	y <del>E</del> s	YES	Yes		y = S
Size and Length of Screen					<del></del>	/
Type of Standby Power				<u> </u>		
Surface Drainage	No Pump 9/87	No fing No	0. K.	OK.	1/0 Par 0/00	
Date Abandoned	110 FUMP 1157	NO PURIL 113			No Pump 9/87	
Date Plugged				 	<u></u>	<u> </u>

E 2.03 - Rev.

ELEUATION LOCATION

Former Hulett Lagoon Site Combined PA/SI Reference 45

FEBRUARY 24, 1999

PALERIE H. WILDER

DEPARTMENT OF NATURAL RESOURCES

P.O. BOX 176

DEFFERSON City Mo 65/02-0176

DEAR VALERYE!

THE MULBERRY WELL LUAS TAKEN

OFF LINE OF FEBRUARY 2, 1999

IN THE CITY OF CAMPENTON

FHAUE PUMPED THE MULBERRY WELL

TO WASTE ON THE 22, 26 AND 29

OF JANUARY 1999 FOR A TOTAL OF

5 HRS

ON FEBRUARY 2, 1999 BLAIR WELL

HAD ELECTRICAL PROBLEMS AND E

HAD TO PUT MULBERRY BACK ON UNE,

I SHUT MULBERRY OFF FEBRUARY 9, 1999

AND TOOK MULBERRY WELL OFF LINE.

I PUMPED A TOTAL OF 400,000 CALI

THAT TIME.

I DID NOT PUMP DULBERRY WELL.

AGAIN UNTIL FEBRUARY 12, 1999.

WHEN I HAD TO PUT THE WELL

BALL ON LINE WHEN WE HAD

(2)

PROBLEMS WITH OUR WATER CONTROLS

AND REPAIRS WERE MADE BY R. E.

PEDROTTI CO. I USED THE WELL FOR

FOUR DAYS AND PUMPED 1,314 GALS

INTO THE SYSTEM. MULBERRY WAS

TAXEN OUT OF LINE ON FEBRUARY 16,

1999. I HAUE NOT PUMPED MULBERRY

INTO THE SYSTEM TO PATE.

I HAVE PUMPED MULBERNY TO WASTE ON FEBRUARY 23, 1999 FOR ONE HOUR. AND HAVE MOT PUMPER THE WELL SENSE

FF YOU HAVE ANY QUESTIONS CONCERNING MULBERRY WELL PUMPAGE OR OTHER QUESTIONS PLEASE CONTACT ME AT (573) 346-7293

SINCERELY,

PINCENT COSTA
DIRECTOR PUBLIC WORK

VALERIE"

ب در ترکیس MULBERRY Pumps 570 to 600 G.P.M.

MULBERRY WAS OUR LEAD WELL UNTIL

TULY OF 1998. WHEN WE HAD OUR NEW

CONTROLS PUT IN THIS JULY WE WERE

ABLE TO SET OUR WELLS AS TOO THE

TIME TITTY WERE TO COME ON. I

PUT MULBERRY AS THE THIRD WELL.

WHEN WE HAD OUR OLD CONTROLS

MUNBERRY ALWAYS WAS THE FIRST

WELL TO RON. BLAIR WELL & RODEO

WELL RIN WHEN MULBERRY WAS NOT

ABLE TO HONDLE THE DEMAND. WE

AVERAGE ABOUT 600,000 PER DAY.


MULBERRY WITH THE OLD CONTROLS


PUMPED ABOUT 70 0/0 TOTE THE WATER

WITH THE NEW CONTROLS I WAS ABLE
TO CUT MULBEARY DOWN TO ABOUT
40 % OF THE WATER USAGE.

I HOPE THAT THIS WILL HELP YOU

# INVENTORY OF MISSOURI PUBLIC WATER SYSTEMS 1998





MAR 0 3 1900

HAZARDOUS W/ STE PROGRAM MISSO OF PEPARTMENT OF NATURAL RESULTOES

Missouri Department of Natural Resources Division of Environmental Quality

#### TABLE OF CONTENTS

I.	KEY INFORMATION	
	Key to Codes and Abbreviations	. 3
II.	STATISTICAL INVENTORY INFORMATION	
	Number of Regulated Systems by DNR-DEQ Region	. 5 . 6
III.	COMMUNITY WATER SYSTEM INVENTORY INFORMATION	
	City Water Systems	. 57 . 80 133
ıv.	NON-COMMUNITY WATER SYSTEM INVENTORY INFORMATION	
	Non-Community Water Systems	149
v.	FLUORIDATED WATER SYSTEM INFORMATION	
	Water Systems Containing Amounts of Natural Fluoride	193 196
VI.	SURFACE WATER SOURCE INFORMATION	
	Map of Surface Water System Locations	201

#### CITY WATER SYSTEMS

COMMUNITY WATER SY NAME	STEM	YEAR BEGAN	OPER LVL	own	POP SERV	SERV CON	PCT SUR	PCT GRD	PCT PUR SUR	PCT PUR GRD	SUPPLY CAPACITY M.G.D.	AVG DLY CONSUMP M.G.D.	FINISHED WATER STORAGE
CALIFORNIA ID NUMBER MO3010124	COUNTY LOCATION MONITEAU	1992	D	4	3,400	1,711	0	100	0	0	2.8000	1.1100	0.2250
CALLAO ID NUMBER MO2010125	COUNTY LOCATION MACON	1960	E	4	332	179	0	0	100	0	0.0432	0.0240	0.0500
CAMDENTON ID NUMBER M03010130	COUNTY LOCATION CAMDEN	1931	Е	4	3,010	1,260	0	100	0	0	1.2000	0.5000	0.4250
CAMERON ID NUMBER MO1010131	COUNTY LOCATION CLINTON	1919	В	4	8,300	1,900	100	0	0	0	3.1680	1.1500	1.9600
CAMPBELL ID NUMBER MO4010132	COUNTY LOCATION DUNKLIN	1911	E	4	2,350	1,216	0	100	0	0	1.1520	0.3260	0.3500
CANTON ID NUMBER MO2010134	COUNTY LOCATION LEWIS	1937	В	4	2,623	860	0	100	0	0	0.7200	0.2091	0.3630
CAPE GIRARDEAU ID NUMBER MO4010136	COUNTY LOCATION CAPE GIRARDEAU	1931	A	4	39,500	13,236	76	24	0	0	4.7400	3.6000	5.2550
CARDWELL ID NUMBER MO4010137	COUNTY LOCATION	1951	E	4	792	398	0	100	0	0	0.4320	0.1210	0.0750
CARL JUNCTION ID NUMBER MO5010138	COUNTY LOCATION JASPER	1910	D	4	3,875	1,550	0	100	0	0	1.8640	0.3500	0.3000
CARROLLTON ID NUMBER MO2010140	COUNTY LOCATION CARROLL	1941	A	4	4,406	2,117	0	100	0	0	2.4000	0.6750	0.8400
CARTERVILLE ID NUMBER MO5010141	COUNTY LOCATION JASPER	1910	E	4	1,972	754	0	100	0	0	0.0000	0.1260	0.0000
CARTHAGE ID NUMBER MO5010142	COUNTY LOCATION JASPER	1909	В	4	10,747	4,700	0	100	0	0	4.0000	2.8000	2.3900
					-14	_							

#### CITY WATER SYSTEMS

COMMUNITY WATER SY NAME	'STEM	YEAR BEGAN	OPER LVL	own	POP SERV	SERV CON	PCT SUR	PCT GRD		PCT PUR GRD	SUPPLY CAPACITY M.G.D.	AVG DLY CONSUMP M.G.D.	FINISHED WATER STORAGE
<b>LEWISTOWN</b> ID NUMBER MO2010463	COUNTY LOCATION LEWIS	1966	С	4	502	294	100	0	0	0	0.1580	0.0502	0.0711
LEXINGTON ID NUMBER MO1010464	COUNTY LOCATION LAFAYETTE	1884	В	2	5,200	2,278	100	0	0	0	1.2000	0.4640	0.2500
LIBERAL ID NUMBER MO5010465	COUNTY LOCATION BARTON	1937	D	4	867	347	0	100	0	0	0.6980	0.0700	0.0550
LIBERTY ID NUMBER MO1010466	COUNTY LOCATION	1962	A	4	28,000	7,800	0	100	0	0	9.0000	2.8500	5.0000
LICKING ID NUMBER MO4010467	COUNTY LOCATION TEXAS	1988	E	4	1,328	630	0	100	0	0	0.5330	0.1676	0.2500
LILBOURN ID NUMBER MO4010468	COUNTY LOCATION NEW MADRID	1946	D	4	1,500	600	0	100	0	0	0.6690	0.1685	0.1000
LINCOLN ID NUMBER MO3010469	COUNTY LOCATION BENTON	1950	D	4	860	450	0	100	0	0	0.5400	0.0900	0.0500
LINN ID NUMBER MO3010470	COUNTY LOCATION OSAGE	1937	E	4	1,220	605	0	100	0	0	0.9300	0.1250	0.3000
LINN CREEK ID NUMBER MO3010471	COUNTY LOCATION CAMDEN	1939	E	4	260	80	0	100	0	0	0.0700	0.0350	0.0300
LINNEUS ID NUMBER MO2010472	COUNTY LOCATION	1957	С	4	529	222	100	0	0	0	0.2160	0.0440	0.0640
LOCKWOOD  ID NUMBER  MO5010475	COUNTY LOCATION	1928	D	4	1,450	580	0	100	0	0	1.0800	0.1900	0.3500
LOUISBURG ID NUMBER MO5011068	COUNTY LOCATION	1991	D	4	157	63	0	100	0	0	0.4240	0.0150	0.0100
					2.2								

# SUBDIVISION, MOBILE HOME PARK, INSTITUTION, MISCELLANEOUS WATER SYSTEMS


COMMUNITY WATER SYSTEM NAME	YEAR BEGAN	OPER LVL	OWN	POP SERV	SERV CON	PCT SUR		PCT PUR SUR	PCT PUR GRD	SUPPLY CAPACITY M.G.D.	AVG DLY CONSUMP M.G.D.	FINISHED WATER STORAGE
SOUTHERN HILLS ESTATES SUBD  ID NUMBER COUNTY LOCATION MO5036259 NEWTON	1989 N	D	2	59	16	0	100	0	0	0.1970	0.0044	0.0005
SOUTHERN HILLS WATER CO  ID NUMBER COUNTY LOCATION MO3036065 PETTIS	1986 1	D	2	190	52	0	100	0	0	0.0700	0.0160	0.0020
SOUTHFORK MHP  ID NUMBER COUNTY LOCATION MO1048442 CASS	1991 1	С	2	800	480	0	0	100	0	0.0000	0.0000	0.0000
SOUTHGATE SUBDIVISION  ID NUMBER COUNTY LOCATION MO3036179 PETTIS	1992 1	Х	2	200	63	0	100	0	0	0.0600	0.0200	0.0080
SOUTHSIDE MHP LLC  ID NUMBER COUNTY LOCATION MO3048015 BOONE	1987 1	E	2	80	35	0	100	0	0	0.1250	0.0080	0.0002
SOUTHWAY TERRACE MHP  ID NUMBER COUNTY LOCATION MO3048141 CAMDEN	1970 N	X	2	85	35	0	100	0	0	0.0000	0.0070	0.0020
SOUTHWOOD ACRES SUBD  ID NUMBER COUNTY LOCATION MO3036066 PETTIS	1967 I	Х	2	75	20	0	100	0	0	0.0450	0.0070	0.0640
SPARTA MHP ID NUMBER COUNTY LOCATION MO5048154 CHRISTIAN	1971 I	Х	2	75	30	0	100	0	0	0.0432	0.0050	0.0004
SPOKANE HIGHLANDS  ID NUMBER COUNTY LOCATION MO5031093 CHRISTIAN	1994 I	E	2	25	1	0	100	0	0	0.0000	0.0000	0.0000
SPRING CREEK 2ND ADD  ID NUMBER COUNTY LOCATION MO5030391 TANEY	1992 I	D	2	35	15	0	100	0	0	0.0000	0.0000	0.0004
SPRING CREEK ADDITION MHP  ID NUMBER COUNTY LOCATION  MO5048221 TANEY	1983 N	Х	2	62	25	0	100	0	0	0.0000	0.0030	0.0006


# SUBDIVISION, MOBILE HOME PARK, INSTITUTION, MISCELLANEOUS WATER SYSTEMS

										~			
COMMUNITY WATER SYS NAME	TEM	YEAR BEGAN	OPER LVL	OWN	POP SERV	SERV CON	PCT SUR	PCT GRD	PCT PUR SUR	PUR	SUPPLY CAPACITY M.G.D.	AVG DLY CONSUMP M.G.D.	FINISHED WATER STORAGE
WHITSON SCENIC VIEW ID NUMBER MO3048132	MHP COUNTY LOCATION PHELPS	1965	Х	2	90	45	0	100	0	0	0.0200	0.0100	0.0005
WILD OAKS WATER COM ID NUMBER MO4036310	<b>PANY</b> COUNTY LOCATION WAYNE	1976	D	2	42	14	0	100	0	0	0.0000	0.0080	0.0001
WILDEN HEIGHTS SUBD ID NUMBER MO5036192	COUNTY LOCATION GREENE	1992	Х	2	52	21	0	100	0	0	0.0580	0.0040	0.0010
WILDERNESS CLUB INC ID NUMBER MO5031102	COUNTY LOCATION TANEY	1995	E	2	100	70	0	100	0	0	0.1296	0.0000	0.0300
WINDSOR BAY ID NUMBER MO5036168	COUNTY LOCATION BARRY	1989	X	2	35	137	0	100	0	0	0.1080	0.0010	0.0110
WINDSOR ESTATES NURS ID NUMBER MO3069006	SING HOME COUNTY LOCATION CAMDEN	1969	Х	2	70	1	0	100	0	0	0.0000	0.0090	0.0012
WINDWOOD ESTATES SUR ID NUMBER MO4031196	BD COUNTY LOCATION CAPE GIRARDEAU	1997	D	2	45	16	0	100	0	0	0.0000	0.0000	0.0000
WINEGARS TEAL BEND S ID NUMBER MO3036121	SUBD COUNTY LOCATION BENTON	1950	Х	2	400	140	0	100	0	0	0.1700	0.0150	0.0140
WINTERHAVEN MOBILE H ID NUMBER MO5048077	HOME ESTATE  COUNTY LOCATION  NEWTON	1990	E	2	120	48	0	100	0	0	0.0000	0.0080	0.0002
WOOD RIDGE ESTATES  ID NUMBER  MO5036071	COUNTY LOCATION STONE	1989	D	2	80	32	0	100	0	0	0.0576	0.0040	0.0200
WOODCREST MHP ID NUMBER	COUNTY LOCATION PHELPS	1968	E	2	292	146	0	100	0	0	0.0900	0.0290	0.0050

#### Missouri Public Drinking Water

## Surface Water Systems





Former Hulett Lagoon Site Combined PA/SI Reference 48

LANG COMMUNICATION OF

Population and Housing

Summary Population and Housing Characteristics

Missouri

STOCK # 003-024-07326-9

nas, Molly es A

obell, ira L i Ann /ade,

cooror**ge,** and

1 A ning. วหอ่ y.d วกร r₄nt a M ₫₿ iard iult, sey. e D rez, , S 101 10f

> re 13 fin. 13r es,

> > ηđ

Issued August 1991



U.S. Department of Commerce Robert A. Mosbacher, Secretary Rockwell A. Schnabel, Deputy Secretary

Economics and Statistics Administration Michael R. Darby, Under Secretary for Economic Affairs and Administrator

> BUREAU OF THE CENSUS Barbara Everitt Bryant, Director

#### TABLE FINDING GUIDE

#### Subjects by Type of Geographic Area and Table Number

Subjects covered in this report are shown on the left side, and types of geographic areas are shown at the top. For a description of area classifications, see appendix A. For definitions and explanations of subject characteristics, see appendix B.

			Pla	ce	County s	ubdivision	American Indian
ubject	The State	County	By county and county subdivision	Alphabeti- cally for the State	By county	Alphabeti- cally for the State <sup>1</sup>	and Alaska Native area
OPULATION CHARACTERISTICS							
ge	1,2	1,2	1	2	1	2	17
amilies and family characteristics	5,6	5,6	5	6	5	6	18
roup quarters	5,6	5,6	5	6	5	6	
ispanic origin	3,4	3,4	3	4	3	4	***
ouseholds and household characteristics .	5,6	5,6	5	6	5	6	18
opulation density	15,16	15,16	15	16	15	16	344
ace	3,4	3,4	3	4	3	4	
ex	3,4	3,4	3	4	3	4	17
OUSING CHARACTERISTICS							
ontract rent	11,12	11,12	11	12	11	12	18
spanic origin of householder	13,14	13,14	13	14	13	14	
eals included in rent	11,12	11,12	11	12	11	12	
ersons per occupied unit	9,10,11,12	9,10,11,12	9,11	10,12	9,11	10,12	
ersons per room	7,8	7,8	7	8	7	8	
ace of householder	13,14	13,14	13	14	13	14	
oms	7,8,9,10,11,12	7,8,9,10,11,12	7,9,11	8,10,12	7,9,11	8,10,12	
nure	9,10,11,12	9,10,11,12	9,11	10,12	9,11	10,12	18
nits in structure	7,8,9,10,11,12	7,8,9,10,11,12	7,9,11	8,10,12	7,9,11	8,10,12	***
icancy characteristics	7,8	7,8	7	8	7	8	
ilue	9,10	9,10	9	10	9	10	18
ND AREA	15,16	15,16	15	16	15	16	18

<sup>...</sup> Not applicable.

BLE FINDING GUIDE

<sup>&</sup>lt;sup>1</sup>County subdivisions within the State are shown alphabetically with places only in the reports for the following 12 States: Connecticut, Maine, assachusetts, Michigan, Minnesota, New Hampshire, New Jersey, New York, Pennsylvania, Rhode Island, Vermont, and Wisconsin.

#### \*Table 6. Household, Family, and Group Quarters Characteristics: 1990

[For definitions of terms and meanings of symbols, see text]


State			Fan	nily household:	s		Nonfamily	households		Persons	per —	Person	is in group q	uarters
County							House	eholder living	alone					
Place and [In Selected States] County				Married-	Female house- holder, no			65 years	and over				Institu-	Other per-
Subdivision	Persons in households	All house- holds	Total	couple family	husband present	Total	Total	Total	Female	Household	Family	Total	tionalized persons	group quarters
The State	4 971 676	1 961 206	1 368 334	1 104 723	208 175	592 872	510 684	221 516	177 384	2.54	3.08	145 397	80 854	64 543
COUNTY Adair CountyAndrew County	21 279 14 340	9 060 5 429	5 408 4 185	4 551 3 673	676 367	3 652 1 244	2 740 1 121	1 122 616	908 489	2 35 2 64	2 96 3 06	3 298 292	456 263	2 842 29
Atchison County	6 960 23 009	9 961 9 205	2 033 6 667	1 762 5 670	200 782	928 2 538	830 2 350	1 344	380 1 053	2 35 2 50	2 87 3.01	497 590	173 527	32: 63
Barry County	27 201 11 140	10 858 4 524	8 046 3 188	6 987 2 770	759 319	2 812 1 336	2 554 1 253	1 420 768	1 102 594	2 51 2 46	2.95 3.01	346 172	331	15
Bates County	14 733 13 651	5 918 5 764	4 303 4 212	3 710 3 727	432 359	1 615	1 503	903 826	724 607	2 49 2 37	2.98	292 208	243 179	49 29
Bolinger County	10 457 101 696	3 946 41 937	3 057 25 573	2 662 20 602	284 3 965	889 16 364	814 11 531	500 2 770	364 2 248	2 65 2 42	3.07	162 10 683	1 145	9 538
Buchanan County	80 649 38 003	32 486 15 334	22 319 10 970	17 669 8 859	3 717 1 730	10 167 4 364	8 990 3 922	4 500 2 027	3 646 1 587	2 48 2 48	3.04	2 434 762	1 698 597	736 165
Caldwell County	8 187 30 364	3 222 11 552	2 369 8 639	2 083 7 302	217 1 016	853 2 913	799 2 524	503 1 184	409 925	2.54 2.63	3 04 3 08	193 2 445	193	1 147
Camden County	27 190 58 261	11 305 23 390	8 596 16 158	7 685 13 550	648	2 709	2 331	1 061	778	2 41	2.76	305	253	52
Care Girardeau County	10 570	4 332	3 016	2 580	322	7 232 1 316	5 933 1 234	2 511 809	2 051 642	2 49 2 44	3 02	3 372 178	792 176	2 580
Carter County	5 456 62 988	2 128 22 892	1 520 17 839	1 266	187	608 5 053	564 4 379	2 057	1 722	2 56 2 75	3 10	59 820	59 634	186
Cedar County	11 833	5 003	3 525	3 080	340	1 478	1 371	873	186	2 37	2 86	260	260	-
Chariton County	9 055 32 280	3 661 11 937	2 597 9 510	2 295 8 264	954 954	1 064	1 009 2 125	639 966	477 792	2 47 2 70	3 02 3 07	147 364	146 364	1
Clark County	7 450 150 449	2 859 58 915	2 108 42 458	1 813 35 673	197 5 274	751 16 457	701 13 829	396 4 353	304 3 577	2 61	3 09 3 04	97 2 962	1 667	1 295
Clinton County	16 253 58 032	6 112	4 639 15 887	4 029 13 331	2 031	1 473 7 089	1 325 6 286	728 2 372	589 1 998	2 66 2 53	3 11	342 5 547	333 5 108	437
Cooper County	13 561 18 901	5 359 7 299	3 903 5 455	3 360 4 722	417	1 456	1 338	787	634	2 53	3 02	1 274	1 080	19:
Dade County	7 235 12 507	2 976 4 899	2 098 3 648	1 846 3 158	538 182 355	1 844 878 1 251	1 677 824 1 158	938 515 703	731 400 531	2 59 2 43 2 55	3 05 2 96 3 02	272 214 139	259 211 121	13
Daviess County	7 765	3 040	2 211	1 976	172	829	776	520	420	2 55	3 08	100	100	
DeKalb County	7 781 13 499	3 054 5 327	2 246 3 938	2 000 3 394	176 435	808 1 389	763 1 270	498 787	404 630	2 55 2 53	3 05 3 00	2 186 203	2 178	8 46
Douglas County	11 761 32 522	4 587 13 128	3 409 9 292	2 993 7 345	291	1 178 3 836	1 069	614 2 102	479	2.56	3 03	115	102	13
Franklin County	79 786	28 856	22 246	18 984	2 426	6 610	3 566 5 783	2 793	2 227	2 48 2 76	3 01	590 817	552 767	38 5,1
Gasconade County	13 735 6 618	5 543 2 756	3 959 1 909	3 461 1 682	342 172	1 584 847	1 430 808	851 556	656 466	2 48 2 40	2 99 2 96	271 230	263 213	17
Greene County	197 756 10 277	81 463 4 346	54 525 2 994	45 018 2 594	7 502 311	26 938 1 352	21 635 1 264	8 686 799	7 256 653	2 43 2 36	2 96 2 92	10 193 259	3 294 249	6 899 10
Harrison County	8 281 19 700	3 574 8 189	2 460 5 689	2 173 4 837	207 642	1 114 2 500	1 060 2 289	676	534 1 114	2 32	2 86	188	188	
Hickory County	7 224	3 183	2 349	2 123	164	834	776	1 400 485	350	2 41 2 27	2 94 2 67	344 111	309	33
Holt County	5 906 8 898	2 440 3 571	1 689 2 518	1 503 2 114	126 303	1 053	702 960	478 598	365 469	2.42	2 99 3 03	128 733	128	514
Howell County	30 876 10 308	12 283 3 995	9 027 2 970	7 683 2 520	1 036	3 256 1 025	3 002 937	1 707 554	1 370 423	2 51 2 58	2.98 3.04	571 418	513 353	58 65
Jackson County	621 967	252 582	164 361	121 736	34 400	88 221	74 760	26 937	21 661	2 46	3 08	11 265	7 634	3 631
Jefferson County	88 285 169 796	36 134 59 199	24 890 47 211	20 428 39 763	3 549 5 432	11 244	9 904 9 859	4 885 3 433	3 991 2 757	2 44 2 87	2 98 3 23	2 180 1 584	1 399	1 292
Johnson County	37 913 4 366	14 579 1 819	10 213	8 823	1 007	4 366 546	3 153 511	1 189 324	975 267	2 60 2 40	3 08 2 94	4 601	357 77	4 244
Laciede County	26 650 30 169	10 420 11 732	7 749 8 570	6 652 7 299	831	2 671	2 421	1 324	1 044	2 56	3 01	508	211	2.27
Lawrence County	29 670	11 724	8 487	7 255	. 921 928	3 162 3 237	2 907 2 950	1 714	1 386	2 57 2 53	3 07	938 566	741 555	197
Lewis County	9 326 28 539	3 745 10 316	2 655 7 913	2 284 6 851	264 758	1 090 2 403	989 2 137	578	461 817	2 49 2 77	3 02 3 21	907 353	253 285	654 63
Linn County	13 544 13 798	5 704 5 645	3 837 3 910	3 346 3 345	373 437	1 867 1 735	1 745	1 111	892	2 37	2 97	341	339	0.0
McDonald County	16 681	6 386	4 784	4 058	504	1 602	1 618	944 760	769 603	2 44 2 61	3 01	794 257	794 156	17
Macan County	15 017 10 966	6 160 4 344	4 376 3 205	3 829 2 683	405 388	1 784 1 139	1 663	1 029 623	838 486	2 44 2 52	2 96	328 161	326 161	2
Maries County	7 877 26 826	3 028 10 728	2 271 7 412	1 989 6 137	1 013	757 3 316	711 3 042	391	296	2 60	3 08	99	99	315
Mercer County	3 655	1 577	1 079	972	66	498	470	307	1 367 245	2 50 2 32	3 08 2 88	856 68	541	
Miller County	20 456 14 218	7 977 5 411	5 740 3 968	4 819 2 908	581 869	2 237	1 999	1 003 781	775 635	2 56 2 63	3 07	244 224	204 224	45
Manitedu County	11 876 8 900	4 583 3 471	3 328 2 466	2 896 2 175	324 217	1 255	1 169	707 528	575 411	2 59 2 56	3 13 3 14	422	422 167	12
Montgomery County	11 047	4 341	3 114	2 668	326	1 227	1 133	713	550	2 54	3 06	308	308	3.
Margan County	15 287 20 624	6 269 7 795	4 629 5 726	4 097 4 448	374 1 066	1 640 2 069	1 477	836 1 067	575 858	2 44 2 65	2 87 3 15	287 304	222 304	61
Newton County	43 745 18 905	16 886 7 620	12 678 4 996	10 982 4 330	1 267	4 208 2 624	3 736 2 065	1 937	1 540 816	2 59 2 48	3 04 3 05	700	471	277
Oregon County	9 359 11 848	3 851	2 820	2 406	285	1 031	971	580	440	2 43	2 89	2 804 111	252 108	2 552
Osage County	8 495	4 252 3 486	3 181 2 616	2 800 2 319	253 210	1 081 870	950 799	545 469	414 336	2 78 2 44	3 31 2 86	170	170	15
Perry County	21 549 16 296	8 210 6 111	5 757 4 537	4 086	427	2 453 1 574	2 268 1 439	1 340 857	1 043 662	2 62 2 67	3 21 3 17	372 352	327 314	45
Petris County	35 077	14 056	9 947	8 298	1 266	4 109	3 636	1 915	1 538	2 50	3 00	360	190	170
Phelps County Pike County	32 673 15 629	6 083	9 125 4 380	7 705 3 670	1 106	4 152 1 703	3 459 1 565	1 427	1 158 719	2 46 2 57	2 98 3 10		690 305	1 885 35
Platte County	57 117 20 455	22 142 8 031	16 077 5 899	13 694 5 189	1 754 523	6 065 2 132	5 063 1 837	1 198 1 059	925 848	2 58 2 55	3 06 3 00	1 371	502 454	24m
Pulaski County	35 214 4 994	12 397 2 166	9 882 1 472	8 451	1 110	2 515	2 235 657	905	709	2 84	3 23	6 093	231	5 867
Rails County	8 392 22 387	3 226 8 943	2 474 6 235	2 199 5 242	196	752	692	413	336 295	2 31	2 87 3 03		59 60	2¢ 24
Ray County	21 747	8 020	6 215	5 405	788 592	2 708 1 805	2 409 1 640	1 360	1 104	2 50 2 71	3 05 3 13	224	1 843 224	1.4
Reynolds County	6 558	2 542	1 950	1 677	191	592	534	306	244	2 58	2 97		87	16

#### ble 6. Household, Family, and Group Quarters Characteristics: 1990—Con.


For definitions of terms and meanings of symbols, see text

State			Fam	ily household	s		Nonfamily	households		Persons	per —	Person	s in group qu	uarters
County							House	eholder living a	lone					
Place and [In Selected States] County Subdivision	Persons in	Ail house-		Married- couple	female house- holder, no husband			65 years o	ind over				Institu-	Other sons in group
	households	holds	Total	family	present	Total	Total	Fotal	Female	Household	Family	Total	persons	quarters
PLACE AND COUNTY SUBDIVISION— Con.	327. 200.000													
Bel-Ridge village, St. Louis County	2 644 3 185 17 881	1 092 1 176 6 393	735 807 4 873	526 444 4 003	178 299 697	357 369	328	129 81	58 222	2 42 2 71	3.28	291	112	179
Belton city, Cass County Benton city, Scott County Benton City town, Audrain County	575 139	239	169	151	13	1 520 70 7	1 280 67	400 44 4	338 38 3	2 80 2 41 2 84	3 23 2 95 3 10	269	109	160
Berger city, Franklin County	247 12 423	94 4 280	71 3 279	58 1 946	1 120	1 001	22 853	262	7 200	2 63 2 90	3 11	27	16	11
Bernie city, Stoddard County Bertrand city, Mississippi County	1 847 655	783 266	546 202	427 156	98 40	237 64	224 62	139 35	114	2 36 2 46	2 88 2 83	37	37	-
Bethany city, Harrison County	2 817	1 307	815	696	96 7	492 30	474 29	* 302 20	250 13	1 92	2 79 2 74	188	188	-
Beverly Hills city. St. Louis County Bevier city. Macon County Bigelow village. Holt County	660 643 32	275 271 13	173 179 9	97 150 6	64 26 3	92	97 81 2	39 51	41	2 40 2 37 2 46	3 08 2 97 2 89	-	-	-
Big Lake village, Holt County	170 989	87 403	59 285	54 229	5 42	28 118	27 110	11 64	6	1 95	2 37	-	-	-
Birch Tree city Shannon County Birmingham village, Clay County	599 222	255 78	166 59	147 51	16	89 19	84 18	51 12	43	2 35 2 85	3 00 3 37	_	-	-
Bismarck city, St. Francois County Blackburn city	1 557 308	110	441 83	355 76	69	163	152	104	83 14	2 58 2 80	3 06	22	11	11
Lafayette County	22 286	103	6 77	6	3	1 26	25	18	13	3 14 2 78	3 50 3 27	-	-	-
Black Jack city St Louis County	5 857 221	2 000	1 596 64	1 295 54	234	404 28	339 24	121	106	2 93 2 40	3 33 2 86	271	271	-
Blairstown city, Henry County	185 640	75 257	50 176	43	20	25 81	23 69	12 39	33	2 47	3 10	- 11	-	-
Gasconade County	640	257	176	141	20	81	69	39	33	2 49	3 05	11	3 -	8
Bloomfield city, Stoddard County	202 1 709	81 744	58 494	43 391	12 86	23 250	21 236	157	139	2 49 2 30	3 00 2 88	91	91	
Bloomsdale city Ste Genevieve County	353 112 39 896	142 45 13 529	102 29 11 055	92 26 9 426	1 285	40 16 2 474	39 16 2 012	28 9 616	23 6 520	2 49 2 49 2 95	3 04 3 31 3 29	257	240	17
Blythedale village Harrison County	130 228	58 93	33	28 57	4 7	25 24	24 23	17	14	2 24 2 45	3 12 2 87	-	-	-
Bolivar city, Polk County	253 5 866	2 607	1 620	1 372	205	28 987	28 816	11 492	423	2 72 2 25	3 46 2 82	979	237	7.42
Bonne Terre city, St. Francois County	3 819 5 870	2 503	1 037	1 338	180 263	437 843	405 782	264 454	228 384	2 59 2 35	3.17 2.92	1 225	1 031	
Bosworth city. Carroll County	334 1 188 2 822	149 479 1 191	103 311 762	95 263 581	38 142	46 168 429	43 157 405	30 98 231	25 83 195	2 24 2 48 2 37	2 71 3 16	154	119	35
Bragg City town Pemiscot County	117	44 56	35 44	33	2	9	9	7 6	3	2 66 2 98	3 04 3 06 3 39	-	-	-
Branson city, Taney County	3 603 318	1 678 123	1 070 93	914	127	608 30	556 30	342 25	294	2 15 2 59	2 70 3 10	103	70	3.
Braymer city, Caldwell County	886 418 5 404	388 188 2 091	257 117 1 449	199 94 950	50 14 396	131 71 642	122 64 523	84 43 202	71 37 151	2 28 2 22	2 85 2 83	_	-	
Brentwood city St. Louis County	8 149 17 238	4 025 6 793	2 130 4 933	1 725 4 075	333 646	1 895	1 657	484	395	2 58	3 08 2 78	1	1	
Brimson village, Grundy County	72 211	27 88	21	21	9	1 860 6 27	1 534 6 27	555 3 13	463 3	2 54 2 67 2 40	3.00 3.14 2.95	541	541	
Brookfield city, Linn County Brookline village, Greene County	4 711 283	2 133	1 301 93	1 093 84	168	832	771 17	483 6	395 5	2 21 2 55	2 88 2 82	177	176	1
Brooklyn Heights village, Jasper County Browning city	331	146	35 94	31 75	3 14	52	50	28	24	2 52	2 77 2 86	-	-	
Sullivan County  Brownington town, Henry County	76 84	109 37 38	75 19 26	63 12 22	5	18 12	32 18 12	15	13	2 34 2 05 2 21	2 84 2.95 2 77		-	
Brunswick city, Chariton County	1 023	32 480	25 283	16	8	197	5	121	2	2 53	2 72 2 82	51	50	
Bucklin city, Linn County Buckner city, Jackson County	616 2 873	277 1 007	168 782	617	22 129	109 225	105 208	75 107	56 93	2 22 2 85	2 95 3 28	-	-	
Buffalo city Dallas County	2 312 341	1 039	644 95	479 78	137	395 49	377 44	264 27	220	2 23 2 37	2 88	102	102	
Bunker city Dent County Reynolds County	390 159 231	152 59 93	104 39 65	83 34 49	15 4 11	48 20 28	45 17 28	30 13 17	22 9 13	2 57 2 69 2 48	3 22 3 46 3 08	-	-	
Burgess town, Barton County Burlington Junction city, Nodoway County	97 624	31 267	22 169	20 147	2	9 98	7 97	5 63	3 56	3 13 2 34	3 91 3 06	10	-	1
Butler city, Bates County	3 913 248	1 717	1 133	903	180	584 25	545 21	360	309 10	2 28 2 53	2 84 2 96	186	186	
Byrnes Mill city, Jefferson County  Cabool city, Texas County	1 578 1 931	559 871	438 546	374 429	105	121 325	87 315	28 211	23 177	2 82 2 22	3.20 2.88	75	75	
Cainsville city Harrison County	387 282 142	110	116 74	99 64	9	73 36	71 36	48 26	37 19	2 05 2 56	2 68 3 30	-	-	
Caledonia village, Washington County	450 3 333	187 1 471	38 126 927	30 103 751	20 146	27 61 544	27 58 516	25 39 323	21 27 283	2 18 2 41 2 27	3 00 3 03 2 93	-	172	
Callao city, Macon County	332 1 404	137	93 408	82 343	10	44	36 101	20 43	13	2 42	3 00	-	132	
Camden city, Ray County	238 373	92 125	66 106	55 96	6 7	26 19	22	11	9	2 68 2 59 2 98	3 10 3 03 3 28	-	-	
Camdenton city, Camden County	2 544 4 632	1 105	717 1 293	540 1 054	148	388	352	201	178	2 30	2 90	1.7		
Clinton County	3 737 895	1 544	1 053	853 201	164	696 491 205	647 446 201	375 237 138	337 208 129	2 33 2 42 2 01	2 96 2 99 2 83	54	54	
Campbell city, Dunklin County	2 075 319	904 128	576 97	441 86	114	328 31	305 30	206	159	2 30 2 49	2 94	90		
Conton city Lewis County	1 969	870	533	444	63				154		2 95 2 91		-	65









Certified Mail P 917 752 129 Return Receipt Requested

July 2, 1997

Darleen Westcott Environmental Engineer Hazardous Waste Program Missouri Department of Natural Resources P.O. Box 176 Jefferson City, MO 65102-0176

Dear Ms. Westcott:

Enclosed are the latest quarterly groundwater sampling results from the well installed at the Modine Manufacturing Company Camdenton site. The results show 120 ppb in MW-4. If you have any questions, please contact me at (414) 636-1649 or at the letterhead address.

Sincerely,

Thomas S. Sanicola Environmental Engineer

Enclosure

cc: Modine Manufacturing - Camdenton

N. Gladding - Bryan Cave

file(2)



June 30, 1997

2135 East Sunshine, Suite 105 Springfield, Missouri 65804 417 881 3927 Tel 417 881 6361 Fax

Mr. Thomas S. Sanicola Environmental Engineer Modine Manufacturing Company 1500 DeKoven Avenue Racine, Wisconsin 53403

RE: JUNE 1997 QUARTERLY SAMPLING ANALYTICAL RESULTS FOR THE MODINE HEAT TRANSFER, INC. SITE CAMDENTON, MISSOURI

Dear Mr. Sanicola:

The purpose of this letter is to present the analytical results for the June 1997 quarterly sampling event at the Modine Heat Transfer, Inc. Site located in Camdenton, Missouri. The groundwater sample was collected on June 4, 1997 and was analyzed for volatile organic compounds (VOCs) with Trichloroethene (TCE) as the primary constituent of concern. The laboratory reporting limit for TCE was 5 parts per billion (ppb).

#### The results are as follows:

Well Identification	Location	<u>Results</u>
MW-1 MW-2 MW-3 MW-4	West of facility East of facility Southwest of facility Northwest of facility	Quarterly Sampling no longer required Quarterly Sampling no longer required Quarterly Sampling no longer required TCE detected at 120 ppb

Enclosed is a copy of the laboratory analytical results for this sampling event and a table comparing the results over the last seven sampling events.

Mr. Thomas S. Sanicola

Modine Manufacturing Company

Re:

Quarterly Sampling Analytical Results

Modine Heat Transfer, Inc.

June 30, 1997

Page 2

Please call either Mr. Price at (314) 993-4599 or Ms. Francis at (417) 881-3927 to discuss any comments or questions you may have.

Very truly yours,

**DAMES & MOORE** 

Miesche M. Francis

Staff Geologist

Daniel J. Price, P.G. Senior Geologist

**Enclosures** 

c: Don Mans - Modine Heat Transfer, Inc.

#### GROUNDWATER ANALYTICAL RESULTS MODINE HEAT TRANSFER, INC. CAMDENTON, MISSOURI AUGUST 1995 - JUNE 1997

	TCE CONCENTRATIONS									
Well ID	8/16, 22/95	11/16/95	2/15, 16/96	5/16/96	8/20/96	12/12/96	2/28/97, 3/3/97	6/4/97		
MW-1	11.8	9.4	ND (Dup. 5.4)	ND	ND	ND (Dup. ND)	NT	NT		
MW-2	ND (Dup. ND)	ND	ND	ND	NT	NT	NT	NT		
MW-3	8.0	ND	6.6	ND	ND (Dup. ND)	NS	ND	NT		
MW-4	88.9	142 (Dup. 154)	173.0	10.0	NS	NS	34 (Dup. 37)	120		

Results in this table are presented in parts per billion (ppb).

NT - Not Tested

ND - Not Detected at or above 5 ppb

NS - Not Sampled due to insufficient volume

#### American Technical & Analytical Services, inc.

875 Fee Fee Road • Maryland Heights, MO 63043 • (314) 434-4570 • FAX (314) 434-0080

June 18, 1997

Miesche Francis Dames & Moore 2135 E Sunshine Street, Suite 105 Springfield, MO 65804

RE: ATAS #19097.01 #27397-005-045 - Modine

Dear Mr. Francis:

Enclosed is the analytical report for the sample received in our laboratory on June 6, 1997.

If, in your review, you should have any questions or require additional information, please call Rhonda Tinker, Assistant Project Manager, or me at (314) 434-4570.

Thank you for choosing ATAS for your analytical needs.

Sincerely,

Richard H. Mannz

Project Manager

Enclosures

RHM/dms



875 Fee Fee Road • Maryland Heights, MO 63043 • (314) 434-4570 - FAX (314) 434-0080

CLIENT: DAMES & MOORE

REPORT: 1909701V(286)

2135 E SUNSHINE STREET, SUITE 105

SPRINGFIELD, MO 65804

DATE: 06-18-97

ATTN: MIESCHE FRANCIS

SAMPLE MATRIX: WATER : 19097.01 ATAS # DATE SUBMITTED: 06-06-97 DATE ANALYZED: 06-12-97

METHOD REF. : SW846-8240, EPA METHODOLOGY

PROJECT: #27397-005-045 - MODINE SAMPLE ID: MW-4

RESULTS REPORTED IN ug/L OR Parts Per Billion (PPB)

**VOLATILES** R.L. RESULTS TRICHLOROETHENE 5 120

#### QA/QC SURROGATE RECOVERIES

TOLUENE-d8(80-116) 101% BROMOFLUOROBENZENE(86-115) 103% 1,2-DICHLOROETHANE-D4(76-114) 103%

B = ANALYTE DETECTED IN METHOD BLANK, POSSIBLY BELOW THE REPORTING LIMIT.

RL = REPORTING LIMIT; DEFINED AS THE PRACTICAL QUANTITATION LIMIT PLUS ANY DILUTION, POSITIVE VALUES BELOW THIS LIMIT WERE NOT REPORTED.

ND = NOT DETECTED ABOVE REPORTING LIMIT

CLIENT: DAMES & MOORE

REPORT: 1909701V(286)

2135 E SUNSHINE STREET, SUITE 105

SPRINGFIELD, MO 65804 DATE : 06-18-97

ATTN: MIESCHE FRANCIS

SAMPLE MATRIX: WATER

ATAS # : METHOD BLANK

DATE SUBMITTED: 06-06-97

DATE ANALYZED: 06-12-97
METHOD REF.: SW846-8240, EPA METHODOLOGY

PROJECT : #27397-005-045 - MODINE SAMPLE ID : METHOD BLANK

RESULTS REPORTED IN ug/L OR Parts Per Billion (PPB)

VOLATILES R.L. RESULTS 5 TRICHLOROETHENE ND

#### QA/QC SURROGATE RECOVERIES

TOLUENE-d8(80-116) 101% BROMOFLUOROBENZENE(86-115) 103% 1,2-DICHLOROETHANE-D4(76-114) 86%

B = ANALYTE DETECTED IN METHOD BLANK, POSSIBLY BELOW THE REPORTING LIMIT.

RL = REPORTING LIMIT; DEFINED AS THE PRACTICAL QUANTITATION LIMIT PLUS ANY DILUTION, POSITIVE VALUES BELOW THIS LIMIT WERE NOT REPORTED.

<sup>=</sup> NOT DETECTED ABOVE REPORTING LIMIT

REPORT DATE: 06-18-97

A 4 ...



#### LABORATORY QUALITY CONTROL SEQUENCE

SAMPLE MATRIX : WATER

DATE ANALYZED: 06-12-97

METHOD REF. : SW846-8240, EPA METHODOLOGY

#### MATRIX SPIKE / MATRIX SPIKE DUPLICATE RECOVERY

COMPOUND	19085.05 MS % REC.	19085.05 MSD % REC.	RPD	QC RPD	ADVISORY LIMITS
1,1-DICHLOROETHENE	90	86	5	16	70-127
TRICHLOROETHENE	88	88	0	11	75-111
BENZENE	90	88	2	12	83-120
TOLUENE	90	88	2	10	80-122
CHLOROBENZENE	86	86	0	8	86-109



### AMERICAN TECHNICAL & ANALYTICAL SERVICES, Inc. 875 Fee Fee Road · Maryland Heights, MO 63043-3211 · Office (314) 434-4570 · FAX (314) 434-0080

#### CHAIN OF CUSTODY RECORD

ATAS Client Name				S					/	/	/	/	/ Preservative	Lab Use
Dames & Ma	re			le.	Type	of Analysis	1	/ /	/ /	/ /	/ /		Ice Chemical (see below)	Only
Project Name	I Project #		0115	of Containers		6	W		/					Initials
Modine	12139	7-005	·040·	네 첫	1	40	$\Gamma$	/ /	/ /	/ /				M
Form Completed By		PO#		Ιç	1	19								Date
	T T 6	<u> </u>		1 %	1 /	$\Delta V$	/	/ /		/ /				6-6-97
Sam Sam		Sample	Grab	Š		0/							/	Location/Temp
Sample ID Date		Matrix		-	/	7	<del>/</del>	$\leftarrow$	$\overline{}$			-	Remarks	2 13
MW-4 6-4-	9 1220	Water	У.	3	1						4	E	TOE at	19097.01
													a ve porting	
													limit of	
													Spab.	Casa San Maria
													- Office	
							1					$\neg$		
		<del> </del>					-		$\neg$	$\dashv$	$\dashv$	$\dashv$		(A) (CAP)
					$\vdash$	$\rightarrow$	<b>—</b>		-					
										$\perp$		_		
										$\rightarrow$				
									•					\$60x
Relinquished by:		ceived by:/		F	Relinquis	hed by:			Rec	eived by	y:		Turnaround Requir	
Muschelo	anast.	prewen											1 to 2 working	ng days
Signature	Signature		Sign	nature				Signatu	re				3 working da	ays
Missone Franc	is LIVA	SENETIC											5 working da	ays
			ited Name	d Name			Printed	Name				<b>V</b>		
Dames & Moor	E ATAS												10 working o	days
Firm	Firm		Firm	n				Firm					15 working d	ays
1220	16667	0945											Preservative codes	
Date/Time ,	) 6697 Date/Time	0/10	Dat	e/Time				Date/Tir	me		-		A - none B - HNO3	
. ,		١٨.	and.	T	7	. 010	X	1 144 -2	0	~ ' N	10	2400	C - H2SO4	
SEND RESULTS TO (N	ame & Company) :	:	SUN	24	var	ras_	0	une	<u>22</u>	- 1	2 CO	JIE	D - NaOH E - HCI	
		Origin	nal to ATAS/C	opy to Client						•			F	

## Continental Analytical Reference 50

Former Hulett Lagoon Site Combined PA/SI Reference 50

-----

Page: 30

Client: Missouri Dept. of Health

Attn: Larry Evert

307 W. McCarty

Jefferson City, MO 65101

Date Sample Rptd: 04/01/93 Date Sample Recd: 03/18/93

CAS File No: 92-5364 CAS Order No: 15740

Client P.O.:

Lab Number: 93031353 Date Sampled: 03/16/93 Sample Description: Mulberry Well 3010130Camdenton Time Sampled: 0715

			Date	
Analysis	Concentration	Units	Analyzed	Book/Page
MDNR Regulated Vocs			03/25/93	/
1,1,1-Trichloroethane	ND(0.5)	μg/L		1546/35
1,1-Dichloroethylene	ND(0.5)	μg/L		1546/35
1,2-Dichloroethane	ND(0.5)	μg/L		1546/35
1,2-Dichloropropane	ND (0.5)	μg/L		1546/35
Benzene	ND (0.5)	μg/L		1546/35
Carbon Tetrachloride	ND(0.5)	μg/L		1546/35
cis-1,2-Dichloroethylene	ND (0.5)	μg/L		1546/35
Chlorobenzene	ND (0.5)	μg/L		1546/35
Ethylbenzene	ND(0.5)	μg/L		1546/35
o-Dichlorobenzene	ND (0.5)	ug/L	-	1546/35
p-Dichlorobenzene	ND(0.5)	μg/L		1546/35
Styrene	ND(0.5)	μg/L		1546/35
Tetrachloroethylene	ND(0.5)	μg/L		1546/35
Toluene	ND(0.5)	μg/L		1546/35
trans-1,2-Dichloroethylene	ND(0.5)	μg/L		1546/35
Trichloroethylene	2.1	μg/L		1546/35
Vinyl Chloride/Chloroethene	ND(0.5)	μg/L		1546/35
Xylene	ND(0.5)	μg/L		1546/35
MDNR Unregulated Vocs			03/25/93	/
1,1,1,2-Tetrachloroethane	ND(0.5)	μg/L		1546/35
1,1,2,2-Tetrachloroethane	ND(0.5)	μg/L		1546/35
1,1,2-Trichloroethane	ND(0.5)	μg/L		1546/35
1,1-Dichloroethane	ND(0.5)	μg/L		1546/35
1,1-Dichloropropene	ND(0.5)	μg/L		1546/35
1,2,3-Trichloropropane	ND(0.5)	μg/L		1546/35
1,2,4-Trichlorobenzene	ND(0.5) Q	μg/L		1546/35
1,3-Dichloropropane	ND(0.5)	μg/L		1546/35
2,2-Dichloropropane	ND(0.5) Q	μg/L		1546/35
Bromobenzene	ND(0.5)	μg/L		1546/35
Bromodichloromethane	ND(0.5)	μg/L		1546/35
Bromoform	ND (0.5)	μg/L		1546/35
Bromomethane	ND (0.5)	μg/L		1546/35
Chloroethane	ND(0.5)	μg/L		1546/35
Chloroform	ND(0.5)	μg/L		1546/35
Chloromethane	Ĭ	μg/L		1546/35
cis-1,3-Dichloropropene	ND(0.5)	μg/L		1546/35
Dibromochloromethane	ND(0.5) Q	μg/L		1546/35
Dibromomethane	ND(0.5)	μg/L		1546/35
Dichloromethane	ND(0.5)	μg/L		1546/35
m-Dichlorobenzene	ND (0.5)	μg/L		1546/35

-Continued-

#### CONTINENTAL ANALYTICAL SERVICES, INC.

LABORATORY REPORT

Page: 31

Client: Missouri Dept. of Health

Lab Number: 93031353

Analysis	Concentration	Units	Date <u>Analyzed</u>	Book/Page	
o-Chlorotoluene	ND (0.5)	μg/L		1546/35	
p~Chlorotoluene	ND(0.5)	μg/L		1546/35	
trans-1,3-Dichloropropene	ND(0.5)	μg/L	1546/35		
	Date				
Analysis	Prepared	QC Batch	Analyst Analyt	ical Method	

Analysis Prepared QC Batch Analyst Analytical Method

MDNR Regulated Vocs NA 1GC4084 TEB MDNR/502.2M

MDNR Unregulated Vocs NA 1GC4084 TEB MDNR/502.2M

- Q This compound did not meet the method Quality Control criteria.
- I Matrix interferences were noted at the time of analysis.

Laboratory analyses were performed on samples utilizing procedures published in Title 40 of the Code of Federal Regulations part 136, July 1, 1986 or in EPA Publication, SW-846, 3rd edition, Nov. 1986. ND(), where noted, indicates none detected with the detection limit in parentheses.

Samples will be retained for thirty days unless otherwise notified.

CONTINENTAL ANALYTICAL SERVICES, INC.

Clifford J. Baker Laboratory Director

#### Continental Analytical SERVICES, INC.

Page: 32

Client: Missouri Dept. of Health

Attn: Larry Evert 307 W. McCarty

Jefferson City, MO 65101

Date Sample Rptd: 04/01/93 Date Sample Recd: 03/18/93

CAS File No: 92-5364 CAS Order No: 15740

Client P.O.:

Lab Number: 93031354 Date Sampled: 03/16/93 Sample Description: Blair Well 3010130 Camdenton Time Sampled: 0729

Analysis	Concentration	Units	Date Analyzed	Book/Page
MDNR Regulated Vocs			03/27/93	/
1,1,1-Trichloroethane	ND (0.5)	µg/L		1536/28
1,1-Dichloroethylene	ND(0.5)	μg/L		1536/28
1,2-Dichloroethane	ND(0.5)	μg/L		1536/28
1,2-Dichloropropane	ND(0.5)	μg/L		1536/28
Benzene	ND(0.5)	μg/L		1536/28
Carbon Tetrachloride	ND(0.5)	μg/L		1536/28
cis-1,2-Dichloroethylene	ND(0.5)	μg/L		1536/28
Chlorobenzene	ND(0.5)	μg/L		1536/28
Ethylbenzene	ND(0.5)	μg/L		1536/28
\ o-Dichlorobenzene	ND(0.5)	μg/L	•	1536/28
p-Dichlorobenzene	ND(0.5)	μg/L		1536/28
Styrene	ND(0.5)	μg/L		1536/28
Tetrachloroethylene	ND (0.5)	μg/L		1536/28
Toluene	ND(0.5)	μg/L		1536/28
trans-1,2-Dichloroethylene	ND(0.5)	μg/L		1536/28
Trichloroethylene	ND(0.5)	μg/L		1536/28
Vinyl Chloride/Chloroethene	ND(0.5)	μg/L		1536/28
Xylene	ND (0.5)	μg/L		1536/28
MDNR Unregulated Vocs			03/27/93	/
1,1,1,2-Tetrachloroethane	ND(0.5)	μg/L		1536/28
1,1,2,2-Tetrachloroethane	ND(0.5) Q	μg/L		1536/28
1,1,2-Trichloroethane	ND(0.5)	μg/L		1536/28
1,1-Dichloroethane	ND(0.5)	μg/L		1536/28
1,1-Dichloropropene	ND(0.5)	μg/L		1536/28
1,2,3-Trichloropropane	ND(0.5) Q	μg/L		1536/28
1,2,4-Trichlorobenzene	ND(0.5)	μg/L		1536/28
1,3-Dichloropropane	ND(0.5)	μg/L		1536/28
2,2-Dichloropropane	ND(0.5)	μg/L		1536/28
Bromobenzene	ND(0.5)	μg/L		1536/28
Bromodichloromethane	ND(0.5)	μg/L		1536/28
Bromoform	ND(0.5) Q	μg/L		1536/28
Bromomethane	ND(0.5)	μg/L		1536/28
Chloroethane	ND(0.5)	μg/L		1536/28
Chloroform	ND(0.5)	μg/L		1536/28
Chloromethane	ND(0.5)	μg/L		1536/28
cis-1,3-Dichloropropene	ND(0.5)	μg/L		1536/28
Dibromochloromethane	ND(0.5) Q	μg/L		1536/28
Dibromomethane	ND(0.5)	μg/L		1536/28
Dichloromethane	ND(0.5)	μg/L		1536/28
m-Dichlorobenzene	ND(0.5)	µg/L		1536/28

-Continued-

#### CONTINENTAL ANALYTICAL SERVICES, INC.

LABORATORY REPORT

Page: 33

Client: Missouri Dept. of Health

Lab Number: 93031354

Analysis	Concentration	Units		Date nalyzed	Book/Page
o-Chlorotoluene	ND (0.5)	μg/L			1536/28
p-Chlorotoluene	ND (0.5)	μg/L			1536/28
trans-1,3-Dichloropropene	ND(0.5)	μg/L			1536/28
	Date				
Analysis	Prepared	QC Batch	<u>Analyst</u>	Analyt	ical Method
MDNR Regulated Vocs	NA	1GC3085	DKT	MDNR/5	02.2M
MDNR Unregulated Vocs	NA	1GC3085	DKT	MDNR/5	02.2M

Q - This compound did not meet the method Quality Control criteria.

Laboratory analyses were performed on samples utilizing procedures published in Title 40 of the Code of Federal Regulations part 136, July 1, 1986 or in EPA Publication, SW-846, 3rd edition, Nov. 1986. ND(), where noted, indicates none detected with the detection limit in parentheses.

Samples will be retained for thirty days unless otherwise notified.

CONTINENTAL ANALYTICAL SERVICES, INC.

Clifford J. Baker Laboratory Director

## Continental Analytical

Page: 34

Client: Missouri Dept. of Health

Attn: Larry Evert 307 W. McCarty

Jefferson City, MO 65101

Date Sample Rptd: 04/01/93 Date Sample Recd: 03/18/93

CAS File No: 92-5364 CAS Order No: 15740

Client P.O.:

Date Sampled: 03/16/93 Time Sampled: 0740 Lab Number: 93031355 Sample Description: Rodeo Well 3010130 Camdenton

Analysis	Concentration	<u>Units</u>	Date Analyzed	Book/Page
MDNR Regulated Vocs			03/27/93	/
1,1,1-Trichloroethane	ND(0.5)	μg/L		1536/29
1,1-Dichloroethylene	ND(0.5)	μg/L		1536/29
1,2-Dichloroethane	ND(0.5)	μg/L		1536/29
1,2-Dichloropropane	ND(0.5)	μg/L		1536/29
Benzene	ND(0.5)	μg/L		1536/29
Carbon Tetrachloride	ND(0.5)	μg/L		1536/29
cis-1,2-Dichloroethylene	ND (0.5)	μg/L		1536/29
Chlorobenzene	ND(0.5)	μg/L		1536/29
Ethylbenzene	ND(0.5)	μg/L		1536/29
o-Dichlorobenzene	ND(0.5)	μg/L	•	1536/29
p-Dichlorobenzene	ND(0.5)	μg/L		1536/29
Styrene	ND (0.5)	μg/L		1536/29
Tetrachloroethylene	ND(0.5)	μg/L		1536/29
Toluene	ND (0.5)	μg/L		1536/29
trans-1,2-Dichloroethylene	ND(0.5)	μg/L		1536/29
Trichloroethylene	ND(0.5)	μg/L		1536/29
Vinyl Chloride/Chloroethene	ND(0.5)	μg/L		1536/29
Xylene	ND(0.5)	μg/L		1536/29
MDNR Unregulated Vocs			03/27/93	/
1,1,1,2-Tetrachloroethane	ND(0.5)	μg/L		1536/29
1,1,2,2-Tetrachloroethane	ND(0.5) Q	μg/L		1536/29
1,1,2-Trichloroethane	ND(0.5)	μg/L		1536/29
1,1-Dichloroethane	ND(0.5)	μg/L		1536/29
1,1-Dichloropropene	ND(0.5)	μg/L		1536/29
1,2,3-Trichloropropane	ND(0.5) Q	μg/L		1536/29
1,2,4-Trichlorobenzene	ND(0.5)	μg/L		1536/29
1,3-Dichloropropane	ND(0.5)	μg/L		1536/29
2,2-Dichloropropane	ND(0.5)	μg/L		1536/29
Bromobenzene	ND(0.5)	μg/L		1536/29
Bromodichloromethane	ND(0.5)	$\mu { t g}/{ t L}$		1536/29
Bromoform	ND(0.5) Q	μg/L		1536/29
Bromomethane	ND(0.5)	μg/L		1536/29
Chloroethane	ND(0.5)	μg/L		1536/29
Chloroform	ND(0.5)	μg/L		1536/29
Chloromethane	ND(0.5)	μg/L		1536/29
cis-1,3-Dichloropropene	ND(0.5)	μg/L		1536/29
Dibromochloromethane	ND(0.5) Q	μg/L		1536/29
Dibromomethane	ND(0.5)	μg/L		1536/29
Dichloromethane	ND(0.5)	μg/L		1536/29
m-Dichlorobenzene	ND(0.5)	μg/L		1536/29

-Continued-

#### CONTINENTAL ANALYTICAL SERVICES, INC.

LABORATORY REPORT

Page: 35

Client: Missouri Dept. of Health

Lab Number: 93031355

Analysis	Concentration	Units	Date <u>Analyzed</u>	Book/Page
o-Chlorotoluene	ND(0.5)	μg/L		1536/29
p-Chlorotoluene	ND (0.5)	μg/L		1536/29
trans-1,3-Dichloropropene	ND(0.5)	μg/L		1536/29
	Date			
Analysis	Prepared	QC Batch	Analyst Analyt	ical Method

Analysis

Prepared QC Batch Analyst Analytical Method

MDNR Regulated Vocs

NA 1GC3085 DKT MDNR/502.2M

MDNR Unregulated Vocs

NA 1GC3085 DKT MDNR/502.2M

Laboratory analyses were performed on samples utilizing procedures published in Title 40 of the Code of Federal Regulations part 136, July 1, 1986 or in EPA Publication, SW-846, 3rd edition, Nov. 1986. ND(), where noted, indicates none detected with the detection limit in parentheses.

Samples will be retained for thirty days unless otherwise notified.

CONTINENTAL ANALYTICAL SERVICES, INC.

(lifford J. Baker Clifford J. Baker Laboratory Director

Q - This compound did not meet the method Quality Control criteria.

## Continental Analytical

Page: 36

Client: Missouri Dept. of Health

Attn: Larry Evert

307 W. McCarty Jefferson City, MO 65101 Date Sample Rptd: 04/01/93 Date Sample Recd: 03/18/93

CAS File No: 92-5364 CAS Order No: 15740

Client P.O.:

Lab Number: 93031356 Date Sampled: / / Sample Description: Trip Blank 3010130 Camdenton Time Sampled:

			Date	
Analysis	Concentration	Units	Analyzed	Book/Page
MDNR Regulated Vocs			03/26/93	/
1,1,1-Trichloroethane	ND(0.5)	μg/L		1546/36
1,1-Dichloroethylene	ND (0.5)	μg/L		1546/36
1,2-Dichloroethane	ND (0.5)	μg/L		1546/36
1,2-Dichloropropane	ND(0.5)	μg/L		1546/36
Benzene	ND(0.5)	μg/L		1546/36
Carbon Tetrachloride	ND (0.5)	μg/L		1546/36
cis-1,2-Dichloroethylene	ND (0.5)	μg/L		1546/36
Chlorobenzene	ND (0.5)	μg/L		1546/36
Ethylbenzene	ND(0.5)	μg/L		1546/36
o-Dichlorobenzene	ND(0.5)	μg/L	•	1546/36
p-Dichlorobenzene	ND(0.5)	μg/L		1546/36
Styrene	ND (0.5)	μg/L		1546/36
Tetrachloroethylene	ND(0.5)	μg/L		1546/36
Toluene	ND(0.5)	μg/L		1546/36
trans-1,2-Dichloroethylene	ND (0.5)	μg/L		1546/36
Trichloroethylene	ND (0.5)	μg/L		1546/36
Vinyl Chloride/Chloroethene		μg/L		1546/36
Xylene	ND (0.5)	μg/L		1546/36
MDNR Unregulated Vocs	, ,		03/26/93	/
1,1,1,2-Tetrachloroethane	ND(0.5)	μg/L		1546/36
1,1,2,2-Tetrachloroethane	ND(0.5)	μg/L		1546/36
1,1,2-Trichloroethane	ND(0.5)	μg/L		1546/36
1,1-Dichloroethane	ND(0.5)	μg/L		1546/36
1,1-Dichloropropene	ND(0.5)	μq/L		1546/36
1,2,3-Trichloropropane	ND(0.5)	μg/L		1546/36
1,2,4-Trichlorobenzene	ND(0.5) Q	µg/L		1546/36
1,3-Dichloropropane	ND (0.5)	µg/L		1546/36
2,2-Dichloropropane	ND (0.5) Q	µg/L		1546/36
Bromobenzene	ND(0.5)	μg/L		1546/36
Bromodichloromethane	ND (0.5)	µg/L		1546/36
Bromoform	ND(0.5) Q	μg/L		1546/36
Bromomethane	ND (0.5)	μg/L		1546/36
Chloroethane	ND (0.5)	μg/L		1546/36
Chloroform	ND (0.5)	μg/L		1546/36
Chloromethane	I	μg/L	•	1546/36
cis-1,3-Dichloropropene	ND(0.5)	μg/L		1546/36
Dibromochloromethane	ND (0.5) Q	μg/L		1546/36
Dibromomethane	ND(0.5) ND(0.5)	μg/L		1546/36
Dichloromethane	ND (0.5)	μg/L		1546/36
m-Dichlorobenzene	ND (0.5)	μg/L μg/L		1546/36
w preutofoneuseue	MD (0.3)	μg/ L		1340/30

-Continued-

#### CONTINENTAL ANALYTICAL SERVICES, INC.

LABORATORY REPORT Page: 37

1GC4084

TEB

MDNR/502.2M

Client: Missouri Dept. of Health

Lab Number: 93031356

MDNR Unregulated Vocs

٠.,

Analysis	Concentration	Units		Date alyzed Book	:/Page
o-Chlorotoluene	ND(0.5)	μg/L		1546	/36
p-Chlorotoluene	ND(0.5)	μg/L		1546	/36
trans-1,3-Dichloropropene	ND (0.5)	µg/L		1546	/36
	Date				
Analysis	Prepared	QC Batch	Analyst	Analytical	Method
MDNR Regulated Vocs	NA	1GC4084	TEB	MDNR / 502 . 2N	ſ

Q - This compound did not meet the method Quality Control criteria.

NA

I - Matrix interferences were noted at the time of analysis.

Laboratory analyses were performed on samples utilizing procedures published in Title 40 of the Code of Federal Regulations part 136, July 1, 1986 or in EPA Publication, SW-846, 3rd edition, Nov. 1986. ND(), where noted, indicates none detected with the detection limit in parentheses.

Samples will be retained for thirty days unless otherwise notified.

CONTINENTAL ANALYTICAL SERVICES, INC.

Clifford J. Baker Laboratory Director

Mel Cirnahan, Governor • David A. Shorr, Director +,

## DEPARTMENT OF NATURAL RESOURCES

DIVISION OF ENVIRONMENTAL QUALITY P.O. Box 176 Jefferson City, MO 65102-0176

## ENVIRONMENTAL SERVICES PROGRAM RESULT OF SAMPLE ANALYSIS

Sample No. 94-C602

Reported to: TERRY TIMMONS

Affiliation: PDW

Date: 5/13/94

Project Code: 3404/3000

Sample Description:

CAMDENTON, MULBERRY WELL

MO3010130

Collected by: BOB MARSHALL

Affiliation: MISC

Date: 04/27/94

#### PARAMETERS

#### RESULTS

VOC Results:	
Benzene	<0.5 ug/L
Bromobenzene	<1.0 ug/L
Bromochloromethane	<1.0 ug/L
Bromodichloromethane	<1.0 ug/L
Bromoform	<2.5 ug/L
Bromomethane	<2.5 ug/L
n-Butylbenzene	<2.0 ug/L
sec-Butylbenzene	<2.0 ug/L
tert-Butylbenzene	<2.0 ug/L
Carbon tetrachloride	
Chlorobenzene	<0.5 ug/L
	<0.5 ug/L
Chloroethane	<2.5 ug/L
Chloroform	<1.0 ug/L
Chloromethane	<2.5 ug/L
2-Chlorotoluene	<2.0 ug/L
4-Chlorotoluene	<2.0 ug/L
Dibromochloromethane	$\sim 1.0 \text{ ug/L}$
1,2-Dibromo-3-chloropropane	<5.0 ug/L
1,2-Dibromoethane	<2.0 ug/L
Dibromomethane	<1.0 ug/L
	=

Mel Cirnahan, Governor • David A, Shorr, Director - +

## DEPARTMENT OF NATURAL RESOURCES

P O Box 176 Jefferson City, MO 65102-0176

Page 3 Sample no. 94-C602 Date 5/13/94

PARAMETERS	RESULTS
1,1,2-Trichloroethane Trichloroethene Trichlorofluoromethane 1,2,3-Trichloropropane 1,2,4-Trimethylbenzene 1,3,5-Trimethylbenzene Vinyl Chloride o-Xylene	<0.5 ug/L <0.5 ug/L <2.5 ug/L <1.0 ug/L <1.0 ug/L <2.0 ug/L <0.5 ug/L <0.5 ug/L
m&p-xylene	<0.5 ug/L

The analysis of this sample was performed in accordance with procedures approved or recognized by the U.S. Environmental Protection Agency.

Sames H. Long Director

Environmental Services Program Rivision of Environmental Quality

## DEPARTMENT OF NATURAL RESOURCES

- DIVISION OF ENVIRONMENTAL QUALITY -P.O. Box 176 Jefferson City MO 65102-0176

#### ENVIRONMENTAL SERVICES PROGRAM

BOB MARSHALL CITY HALL P.O. BOX 1048 CAMDENTON, MO 65020 Lab Number: 97-A758

Sample Number: 97-A466

RESULTS OF SAMPLE ANALYSES FOR PUBLIC WATER SUPPLIES

Report Date: February 24, 1997
Date Collected: January 29, 1997
Sample Location: MULBERRY WELL HOUSE

PWS County: CAMDEN PWS ID: MO3010130

PWS Name:

Analysis Performed	Results	MCL	Units
VOC Results:			
Dichlorodifluoromethane	< 20.0		ug/L
Chloromethane	< 2.5		ug/L
Vinyl Chloride	< 0.5	2.0	ug/L
Bromomethane	< 9.0	(	ug/L
Chloroethane	< 2.5	\ (	ug/L
Trichlorofluoromethane	< 2.5		ug/L
1,1-Dichloroethene	< 0.5	7.0	ug/L
Methylene Chloride	< 0.5	5.0	ug/L
Methyl-tert-butyl ether	< 5.0		ug/L
trans-1,2-Dichloroethene	< 0.5	100	ug/L
1,1-Dichloroethane	< 1.0		ug/L
2,2-Dichloropropane	< 1.0		ug/L
cis-1,2-Dichloroethene	< 0.5	70.0	ug/L
Chloroform	< 0.5	<b>-</b> -	ug/L
Bromochloromethane	< 1.0		ug/L
1,1,1-Trichloroethane	< 0.5	200	ug/L
1,1-Dichloropropene	< 1.0		ug/L
Carbon Tetrachloride	< 0.5	5.0	ug/L
Benzene	< 0.5	5.0	ug/L
1,2-Dichloroethane	< 0.5	5.0	ug/L
Trichloroethene	3.8	5.0	ug/L
1,2-Dichloropropane	< 0.5	5.0	ug/L
Bromodichloromethane	< 0.5	<b></b>	ug/L
Dibromomethane	< 1.0		ug/L
cis-1,3-Dichloropropane	< 2.0		ug/L
Toluene	< 0.5	1000	ug/L
trans-1,3-Dichloropropane	< 1.0		ug/L
1,1,2-Trichloroethane	< 0.5	5.0	ug/L

Page: 2 Lab Number: 97-A758 Report Date: February 24, 1997 Sample Number: 97-A466

Analysis Performed	Results	MCL	Units
Tetrachloroethene	< 0.5	5.0	ug/L
1,3-Dichloropropane	< 2.0		ug/L
Dibromochloromethane	< 0.5		ug/L
1,2-Dibromoethane	< 2.0	<b>~-</b>	ug/L
Chlorobenzene	< 0.5	100	ug/L
Ethylbenzene	< 0.5	700	ug/L
1,1,1,2-Tetrachloroethane	< 1.0	<b> </b>	ug/L
Total Xylenes	< 0.5	10000	ug/L
Styrene	< 0.5	100	ug/L
Isopropylbenzene	< 2.0		ug/L
Bromoform	< 0.5	∥	ug/L
1,1,2,2-Tetrachloroethane	< 1.0		ug/L
1,2,3-Trichloropropane	< 1.0		ug/l
n-Propylbenzene	< 2.0	<b></b>	ug/L
Bromobenzene	< 1.0	)	ug/L
2-Chlorotoluene	< 2.0		ug/L
4-Chlorotoluene	< 2.0		ug/L
1,3,5-Trimethylbenzene	< 2.0		ug/L
tert-Butylbenzene	< 2.0		ug/L
1,2,4-Trimethylbenzene	< 1.0		ug/L
sec-Butylbenzene	< 2.0		ug/L
p-isopropyltoluene	< 2.0	<b> </b>	ug/L
1,3-Dichlorobenzene	< 1.0		ug/L
1,4-Dichlorobenzene	< 0.5	75.0	ug/L
n-Butylbenzene	< 2.0		ug/L
1,2-Dichlorobenzene	< 0.5	600	ug/L
1,2-Dibromo-3-Chlorobenz	< 5.0	<b> </b>	ug/L
1,2,4-Trichlorobenzene	< 0.5	70.0	ug/L
Hexachlorobutadiene	< 1.0		ug/L
Naphthalene	< 2.0		ug/L
1,2,3-Trichlorobenzene	< 2.0		ug/L

MCL = Maximum Contaminant Level

-- = Not Applicable

The analysis of this sample was performed in accordance with procedures approved or recognized by the U.S. Environmental Protection Agency. If you have any questions, please contact Mr. Terry Timmons at 573/751-1188.

James H. Long, D (rector Environmental Services Program

### DEPARTMENT OF NATURAL RESOURCES

- DIVISION OF ENVIRONMENTAL QUALITY -P.O. Box 176 Jefferson City, MO 65102-0176

#### ENVIRONMENTAL SERVICES PROGRAM

#### RESULTS OF SAMPLE ANALYSES FOR PUBLIC WATER SUPPLIES

Sample Number: 97-0486 Lab Number: 97-A2244

Reported To: JIM HOULIHAN Report Date: 3/17/97 3/12/97 Affiliation: Date Collected: JCRO

Project Code: 3404/3000 Date Received: 3/12/97

Sample Collected by: JIM HOULIHAN, JCRO

PWS Supply Name: CAMDENTON PWS Identification: MO3010130 PWS County: CAMDEN

Sampling Location:

MULBERRY WELL CONFIRMATION SAMPLE Sample Description:

Analysis Performed	Results	MCL	Units
VOC Results: Dichlorodifluoromethane Chloromethane Vinyl Chloride Bromomethane Chloroethane Trichlorofluoromethane 1,1-Dichloroethene Methylene Chloride Methyl-tert-butyl ether trans-1,2-Dichloroethene 1,1-Dichloroethane 2,2-Dichloropropane cis-1,2-Dichloroethene Chloroform Bromochloromethane 1,1-Trichloroethane 1,1-Trichloroethane 1,1-Dichloropropene Carbon Tetrachloride Benzene 1,2-Dichloroethane Trichloroethene 1,2-Dichloropropane Bromodichloromethane Dibromomethane	< 20.0 < 2.5 < 0.5 < 9.0 < 2.5 < 2.5 < 0.5 < 0.5 < 0.5 < 1.0 < 0.5 < 1.0 < 0.5 < 1.0 < 0.5 < 1.0 < 0.5 < 1.0 < 0.5 < 1.0 < 0.5 < 1.0 < 0.5 < 1.0 < 0.5 < 1.0 < 0.5	2.0  2.0  7.0 5.0  100  70.0  200  200 5.0 5.0 5.0 5.0	ug/L ug/L ug/L ug/L ug/L ug/L ug/L ug/L

Lab Number: Page: 2 97-A2244 Report Date: March 17, 1997 Sample Number: 97-0486

<del></del>			<del></del>
Analysis Performed	Results	MCL	Units
cis-1,3-Dichloropropane	< 2.0		ug/L
Toluene	< 0.5	1000	ug/L
trans-1,3-Dichloropropane	< 1.0	₩	ug/L
1,1,2-Trichloroethane	< 0.5	∬ 5.0	ug/L
Tetrachloroethene	< 0.5	5.0	ug/L
1,3-Dichloropropane	< 2.0		ug/L
Dibromochloromethane	< 0.5	ļ	ug/L
1,2-Dibromoethane	< 2.0	∦ , <del></del>	ug/L
Chlorobenzene	< 0.5	100	ug/L
Ethylbenzene	< 0.5	700	ug/L
1,1,1,2-Tetrachloroethane	< 1.0		ug/L
Total Xylenes	< 0.5	10000	ug/L
Styrene	< 0.5	100	ug/L
Isopropylbenzene	< 2.0		ug/L
Bromoform	< 0.5		ug/L
1,1,2,2-Tetrachloroethane	< 1.0	<b> </b>	ug/L
1,2,3-Trichloropropane	< 1.0		ug/l
n-Propylbenzene	< 2.0		ug/L
Bromobenzene	< 1.0		ug/L
2-Chlorotoluene	< 2.0		ug/L
4-Chlorotoluene	< 2.0		ug/L
1,3,5-Trimethylbenzene	< 2.0	<b>(</b>	ug/L
tert-Butylbenzene	< 2.0	<u> </u>	ug/L
1,2,4-Trimethylbenzene	< 1.0	<b>∦</b>	ug/L
sec-Butylbenzene	< 2.0		ug/L
p-isopropyltoluene	< 2.0		ug/L
1,3-Dichlorobenzene	< 1.0		ug/L
1,4-Dichlorobenzene	< 0.5	75.0	ug/L
n-Butylbenzene	< 2.0		ug/L
1,2-Dichlorobenzene	< 0.5	600	ug/L
1,2-Dibromo-3-Chlorobenz	< 5.0	70.0	ug/L
1,2,4-Trichlorobenzene	< 0.5	70.0	ug/L
Hexachlorobutadiene	< 1.0	1	ug/L
Naphthalene	< 2.0		ug/L
1,2,3-Trichlorobenzene	< 2.0		ug/L

MCL = Maximum Contaminant Level

-- = Not Applicable

The analysis of this sample was performed in accordance with procedures approved or recognized by the U.S. Environmental Protection Agency. If you have any questions, please contact Mr. Terry Timmons at 573/751-1188.

James H. Long, Director Environmental Services Program Division of Environmental Quality

c: TERRY TIMMONS, PDWP

## DEPARTMENT OF NATURAL RESOURCES

DIVISION OF ENVIRONMENTAL QUALITY P.O. Box 176 Jefferson City, MO 65102-0176

#### ENVIRONMENTAL SERVICES PROGRAM

BOB MARSHALL CITY HALL P.O. BOX 1048

CAMDENTON, MO 65020

Lab Number: 97-A4822

Sample Number: 97-F101

\*\*\* QUARTERLY MONITORING \*\*\*

#### RESULTS OF SAMPLE ANALYSES FOR PUBLIC WATER SUPPLIES

Report Date:

June 13, 1997

PWS County: CAMDEN PWS ID: MO3010130

Date Collected: June 3, 1997

Sample Location: MULBERRY WELL HOUSE

PWS Name:

Analysis Performed	Results	MCL	Units
VOC Results:			
Dichlorodifluoromethane	< 20.0	ll l	ug/L
Chloromethane	< 2.5		ug/L
Vinyl Chloride	< 0.5	2.0	ug/L
Bromomethane	< 9.0	l l	ug/L
Chloroethane	< 2.5		ug/L
Trichlorofluoromethane	< 2.5	\	ug/L
1,1-Dichloroethene	< 0.5	7.0	ug/L
Methylene Chloride	< 0.5	5.0	ug/L
Methyl-tert-butyl ether	< 5.0	J	ug/L
trans-1,2-Dichloroethene	< 0.5	100	ug/L
1,1-Dichloroethane	< 1.0	<b>!</b>	ug/L
	< 1.0		ug/L
cis-1,2-Dichloroethene	< 0.5	70.0	ug/L
Chloroform	< 0.5		ug/L
Bromochloromethane	< 1.0	<b>[</b>	ug/L
1,1,1-Trichloroethane	< 0.5	200	ug/L
1,1-Dichloropropene	< 1.0		ug/L
Carbon Tetrachloride	< 0.5	5.0	ug/L
Benzene	< 0.5	5.0	ug/L
1,2-Dichloroethane	< 0.5	5.0	ug/L
Trichloroethene	4.5	5.0	ug/L
1,2-Dichloropropane	< 0.5	5.0	ug/L
Bromodichloromethane	< 0.5		ug/L
Dibromomethane	< 1.0	<b> </b>	ug/L
cis-1,3-Dichloropropane	< 2.0	<b> </b>	ug/L
Toluene	< 0.5	1000	ug/L

Page: 2
Report Date: June 13, 1997

Lab Number: 97-A4822 Sample Number: 97-F101

Analysis Performed	Results	MCL	Units
trans-1,3-Dichloropropane	< 1.0		ug/L
1,1,2-Trichloroethane	< 0.5	5.0	ug/L
Tetrachloroe <b>thene</b>	< 0.5	5.0	ug/L
1,3-Dichloropropane	< 2.0	<b></b>	ug/L
Dibromochloromethane	< 0.5		ug/L
1,2-Dibromoethane	< 2.0		ug/L
Chlorobenzene	< 0.5	100	ug/L
Ethylbenzene	< 0.5	700	ug/L
1,1,1,2-Tetrachloroethane	< 1.0		ug/L
Total Xylenes	< 0.5	10000	ug/L
Styrene	< 0.5	100	ug/L
Isopropylbenzene	< 2.0		ug/L
Bromoform	< 0.5		ug/L
1,1,2,2-Tetrachloroethane	< 1.0	<b> </b>	ug/L
1,2,3-Trichloropropane	< 1.0		ug/l
n-Propylbenzene	< 2.0		ug/L
Bromobenzene	< 1.0	.∥	ug/L
2-Chlorotoluene	< 2.0		ug/L
4-Chlorotoluene	< 2.0		ug/L
1,3,5-Trimethylbenzene	< 2.0	<b></b>	ug/L
tert-Butylbenzene	< 2.0		ug/L
1,2,4-Trimethylbenzene	< 1.0		ug/L
sec-Butylbenzene	< 2.0		ug/L
p-isopropyltoluene	< 2.0		ug/L
1,3-Dichlorobenzene	< 1.0		ug/L
1,4-Dichlorobenzene	< 0.5	75.0	ug/L
n-Butylbenzene	< 2.0		ug/L
1,2-Dichlorobenzene	< 0.5	600	ug/L
1,2-Dibromo-3-Chlorobenz	< 5.0	<b>⊩</b>	ug/L
1,2,4-Trichlorobenzene	< 0.5	70.0	ug/L
Hexachlorobutadiene	< 1.0	<b></b>	ug/L
Naphthalene	< 2.0	<b> </b>	ug/L
1,2,3-Trichlorobenzene	< 2.0	<b> </b>	ug/L

MCL = Maximum Contaminant Level

-- = Not Applicable

The analysis of this sample was performed in accordance with procedures approved or recognized by the U.S. Environmental Protection Agency. If you have any questions, please contact Mr. Terry Timmons at 573/751-1188.

James H. Long, Director
Environmental Services Program
Division of Environmental Quality

Mel Camahan, Governor + David A. Shorr, Director

## ENT OF NATURAL RESOURCES

- DIVISION OF ENVIRONMENTAL OF ALITY -P.O. Box 176 Jefferson City MO 65102-0176

#### ENVIRONMENTAL SERVICES PROGRAM

BOB MARSHALL CITY HALL P.O. BOX 1048 CAMDENTON, MO 65020

Lab Number:

PWS ID:

97-A7751

MO3010130

Sample Number: 97-1658

QUARTERLY MONITORING

#### RESULTS OF SAMPLE ANALYSES FOR PUBLIC WATER SUPPLIES

Report Date:

September 4, 1997

Date Collected: August 26, 1997

Sample Location: MULBERRY WELL HOUSE

PWS Name: CAMDENTON

		<del></del>
Vinyl Chloride Bromomethane Chloroethane Trichlorofluoromethane 1,1-Dichloroethene Methylene Chloride Methyl-tert-butyl ether trans-1,2-Dichloroethene 1,1-Dichloroethane 2,2-Dichloropropane cis-1,2-Dichloroethene Chloroform Bromochloromethane 1,1,1-Trichloroethane 1,1-Dichloropropene Carbon Tetrachloride Benzene 1,2-Dichloroethane 1,2-Dichloroethane 1,2-Dichloropropane Sromodichloromethane 1,2-Dichloropropane Bromodichloromethane  1,2-Dichloropropane Scarbon Tetrachloride Chloroethane Chloroethane Chloroethane Chloroethane Chloroethane Chloroethane Chloromethane	0.5       7.0         0.5       5.0         5.0          0.5       100         1.0          0.5       70.0         0.5          1.0          0.5       200         1.0          0.5       5.0         0.5       5.0         4.3       5.0	ug/L ug/L ug/L ug/L ug/L ug/L ug/L ug/L

Page: 2 Lab Number: 97-A7751 Report Date: September 4, 1997 Sample Number: 97-I658

Analysis Performed	Results	MCL	Units
trans-1,3-Dichloropropane	< 1.0		1 - / 7
1,1,2-Trichloroethane	< 0.5	5.0	ug/L
Tetrachloroethene	< 0.5	5.0	ug/L
1,3-Dichloropropane	< 2.0		ug/L ug/L
Dibromochloromethane	< 0.5	<b>∦</b>	ug/L ug/L
1,2-Dibromoethane	< 2.0		ug/L ug/L
Chlorobenzene	< 0.5	100	ug/L
Ethylbenzene	< 0.5	700	ug/L
1,1,1,2-Tetrachloroethane	< 1.0	/	ug/L
Total Xylenes	< 0.5	10000	ug/L
Styrene	< 0.5	100	ug/L
Isopropylbenzene	< 2.0	100	ug/L
Bromoform	< 0.5	li	ug/L
1,1,2,2-Tetrachloroethane	< 1.0	<b> </b>	ug/L
1,2,3-Trichloropropane	< 1.0		ug/L ug/l
n-Propylbenzene	< 2.0		ug/L
Bromobenzene	< 1.0		ug/L
2-Chlorotoluene	< 2.0	<b> </b>	ug/L ug/L
4-Chlorotoluene	< 2.0	∥	ug/L
1,3,5-Trimethylbenzene	< 2.0		ug/L
tert-Butylbenzene	< 2.0	<b>!</b>	ug/L
1,2,4-Trimethylbenzene	< 1.0		ug/L
sec-Butylbenzene	< 2.0	J	ug/L ug/L
p-isopropyltoluene	< 2.0	1	ug/L
1,3-Dichlorobenzene	< 1.0	<b>1</b>	ug/L ug/L
1,4-Dichlorobenzene	< 0.5	75.0	ug/L
n-Butylbenzene	< 2.0		ug/L
1,2-Dichlorobenzene	< 0.5	600	ug/L ug/L
1,2-Dibromo-3-Chlorobenz	< 5.0	000	ug/L ug/L
1,2,4-Trichlorobenzene	< 0.5	70.0	ug/L
Hexachlorobutadiene	< 1.0	/0.0	ug/L ug/L
Naphthalene	< 2.0		ug/L
1,2,3-Trichlorobenzene	< 2.0		ug/L ug/L

MCL = Maximum Contaminant Level

-- = Not Applicable

The analysis of this sample was performed in accordance with procedures approved or recognized by the U.S. Environmental Protection Agency. If you have any questions, please contact Mr. Terry Timmons at 573/751-1188.

James H. Long, D (rector

Environmental Services Program Division of Environmental Quality

## McCamabas Governor \* Divid A Short Director ;

Lab Number: 97-A7752

PWS ID:

MO3010130

## DEPARTMENT OF NATURAL RESOURCES

- DIVISION OF UNVIRONMENTAL QUALITY -P.O. Box 176 Jefferson City, MO 65102-0176

#### ENVIRONMENTAL SERVICES PROGRAM

VINCENT COSTA 112 COURT CIRCLE - CITY HALL P.O. BOX 1048

CAMDENTON, MO 65020

Sample Number: 97-1659

QUARTERLY MONITORING

#### RESULTS OF SAMPLE ANALYSES FOR PUBLIC WATER SUPPLIES

Report Date:

September 4, 1997 August 26, 1997

Date Collected:

Sample Location: MULBERRY WELL HOUSE

PWS Name:

Analysis Performed	Results	MCL	Units
VOC Results:			
Dichlorodifluoromethane	< 20.0		ug/L
Chloromethane	< 2.5		ug/L
Vinyl Chloride	< 0.5	2.0	ug/L
Bromomethane	< 9.0		ug/L
Chloroethane	< 2.5		ug/L
Trichlorofluoromethane	< 2.5		ug/L
1,1-Dichloroethene	< 0.5	7.0	ug/L
Methylene Chloride	< 0.5	5.0	ug/L
Methyl-tert-butyl ether	< 5.0		ug/L
trans-1,2-Dichloroethene	< 0.5	100	ug/L
1,1-Dichloroethane	< 1.0		ug/L
2,2-Dichloropropane	< 1.0		ug/L
cis-1,2-Dichloroethene	< 0.5	70.0	ug/L
Chloroform	< 0.5		ug/L
Bromochloromethane	< 1.0		ug/L
1,1,1-Trichloroethane	< 0.5	200	ug/L
1,1-Dichloropropene	< 1.0		ug/L
Carbon Tetrachloride	< 0.5	5.0	ug/L
Benzene	< 0.5	5.0	ug/L
1,2-Dichloroethane	< 0.5	5.0	ug/L
Trichloroethene	4.3	5.0	ug/L
1,2-Dichloropropane	< 0.5	5.0	ug/L
Bromodichloromethane	< 0.5		ug/L
Dibromomethane	< 1.0	<b> </b>	ug/L
cis-1,3-Dichloropropane	< 2.0	1000	ug/L
Toluene	< 0.5	1000	ug/L

Page: 2 Lab Number: 97-A7752 Report Date: September 4, 1997 Sample Number: 97-1659

Analysis Performed	Results	MCL	Units
trans-1,3-Dichloropropane	< 1.0		ug/L
1,1,2-Trichloroethane	< 0.5	5.0	ug/L
Tetrachloroethene	< 0.5	5.0	ug/L
1,3-Dichloropropane	< 2.0		ug/L
Dibromochloromethane	< 0.5	<b> </b>	ug/L
1,2-Dibromoethane	< 2.0		ug/L
Chlorobenzene	< 0.5	100	ug/L
Ethylbenzene	< 0.5	700	ug/L
1,1,1,2-Tetrachloroethane	< 1.0		ug/L
Total Xylenes	< 0.5	10000	ug/L
Styrene	< 0.5	100	ug/L
Isopropylbenzene	< 2.0		ug/L
Bromoform	< 0.5		ug/L
1,1,2,2-Tetrachloroethane	< 1.0		ug/L
1,2,3-Trichloropropane	< 1.0	∥	ug/l
n-Propylbenzene	< 2.0	]	ug/L
Bromobenzene	< 1.0	l	ug/L
2-Chlorotoluene	< 2.0	<b>)</b>	ug/L
4-Chlorotoluene	< 2.0		ug/L
1,3,5-Trimethylbenzene	< 2.0		ug/L
tert-Butylbenzene	< 2.0		ug/L
1,2,4-Trimethylbenzene	< 1.0	1	ug/L
sec-Butylbenzene	< 2.0	<b> </b>	ug/L
p-isopropyltoluene	< 2.0	<b></b>	ug/L
1,3-Dichlorobenzene	< 1.0	∥	ug/L
1,4-Dichlorobenzene	< 0.5	75.0	ug/L
n-Butylbenzene	< 2.0		ug/L
1,2-Dichlorobenzene	< 0.5	600	ug/L
1,2-Dibromo-3-Chlorobenz	< 5.0		ug/L
1,2,4-Trichlorobenzene	< 0.5	70.0	ug/L
Hexachlorobutadiene	< 1.0		ug/L
Naphthalene	< 2.0		ug/L
1,2,3-Trichlorobenzene	< 2.0		ug/L

MCL = Maximum Contaminant Level

-- = Not Applicable

The analysis of this sample was performed in accordance with procedures approved or recognized by the U.S. Environmental Protection Agency. If you have any questions, please contact Mr. Terry Timmons at 573/751-1188.

James H. Long, D(rector

Environmental Services Program

### DEPARTMENT OF NATURAL RESOURCES

- DIVISION OF ENVIRONMENTAL QUALITY -P.O. Box 176 Jefferson City, MO 65102-0176

#### ENVIRONMENTAL SERVICES PROGRAM

VINCENT COSTA

Lab Number:

PWS ID:

97-A11630

MO3010130

112 COURT CIRCLE, CITY HALL P.O. BOX 1048 CAMDENTON, MO 65020

Sample Number: 97-L708

QUARTERLY MONITORING

RESULTS OF SAMPLE ANALYSES FOR PUBLIC WATER SUPPLIES

Report Date:

December 18, 1997

Date Collected: December 1, 1997

Sample Location: MULBERRY WELL HOUSE

PWS Name:

Analysis Performed	Results	MCL	Units
VOC Results:			. ,_
Dichlorodifluoromethane	< 20.0	] ]	ug/L
Chloromethane	< 2.5		ug/L
Vinyl Chloride	< 0.5	2.0	ug/L
Bromomethane	< 9.0		ug/L
Chloroethane	< 2.5		ug/L
Trichlorofluoromethane	< 2.5		ug/L
1,1-Dichloroethene	< 0.5	7.0	ug/L
Methylene Chloride	< 0.5	5.0	ug/L
Methyl-tert-butyl ether	< 5.0		ug/L
trans-1,2-Dichloroethene	< 0.5	100	ug/L
1,1-Dichloroethane	< 1.0		ug/L
2,2-Dichloropropane	< 1.0	<b></b>	ug/L
cis-1,2-Dichloroethene	< 0.5	70.0	ug/L
Chloroform	< 0.5	(l	ug/L
Bromochloromethane	< 1.0	¶	ug/L
1,1,1-Trichloroethane	< 0.5	200	ug/L
1,1-Dichloropropene	< 1.0	<b> </b>	ug/L
Carbon Tetrachloride	< 0.5	5.0	ug/L
Benzene	< 0.5	5.0	ug/L
1,2-Dichloroethane	< 0.5	5.0	ug/L
Trichloroethene	4.4	5.0	ug/L
1,2-Dichloropropane	< 0.5	5.0	ug/L
Bromodichloromethane	< 0.5	l	ug/L
Dibromomethane	< 1.0		ug/L
cis-1,3-Dichloropropane	< 2.0		ug/L
Toluene	< 0.5	1000	ug/L

Page: 2 Lab Number: 97-A11630 Report Date: December 18, 1997 Sample Number: 97-L708

Analysis Performed	Results	MCL	Units
trans-1,3-Dichloropropane	< 1.0		ug/L
1,1,2-Trichloroethane	< 0.5	5.0	ug/L
Tetrachloroethene	< 0.5	5.0	ug/L
1,3-Dichloropropane	< 2.0		ug/L
Dibromochloromethane	< 0.5		ug/L
1,2-Dibromoethane	< 2.0	∦	ug/L
Chlorobenzene	< 0.5	100	ug/L
Ethylbenzene	< 0.5	700	ug/L
1,1,1,2-Tetrachloroethane	< 1.0	<b> </b>	ug/L
Total Xylenes	< 0.5	10000	ug/L
Styrene	< 0.5	100	ug/L
Isopropylbenzene	< 2.0		ug/L
Bromoform	< 0.5	<del></del>	ug/L
1,1,2,2-Tetrachloroethane	< 1.0		ug/L
1,2,3-Trichloropropane	< 1.0	<b>∥</b>	ug/l
n-Propylbenzene	< 2.0	∦	ug/L
Bromobenzene	< 1.0	<b></b>	ug/L
2-Chlorotoluene	< 2.0		ug/L
4-Chlorotoluene	< 2.0	<b> </b>	ug/L
1,3,5-Trimethylbenzene	< 2.0		ug/L
tert-Butylbenzene	< 2.0		ug/L
1,2,4-Trimethylbenzene	< 1.0		ug/L
sec-Butylbenzene	< 2.0	<b>∥</b>	ug/L
p-isopropyltoluene	< 2.0	<b> </b>	ug/L
1,3-Dichlorobenzene	< 1.0	<b>∥</b>	ug/L
1,4-Dichlorobenzene	< 0.5	75.0	ug/L
n-Butylbenzene	< 2.0		ug/L
1,2-Dichlorobenzene	< 0.5	600	ug/L
1,2-Dibromo-3-Chloroprop	< 5.0		ug/L
1,2,4-Trichlorobenzene	< 0.5	70.0	ug/L
Hexachlorobutadiene	< 1.0	<b> </b>	ug/L
Naphthalene	< 2.0	1	ug/L
1,2,3-Trichlorobenzene	< 2.0		ug/L

MCL = Maximum Contaminant Level

-- = Not Applicable

The analysis of this sample was performed in accordance with procedures approved or recognized by the U.S. Environmental Protection Agency. If you have any questions, please contact Mr. Terry Timmons at 573/751-1188.

James H. Long, Director Environmental Services Program



## 

- DIVISION OF ENVIRONMENTAL QUALITY WHAL NEURONGELS P.O. Box 176 Jefferson City, MO 65102-0176

#### ENVIRONMENTAL SERVICES PROGRAM

VINCENT COSTA 112 COURT CIRCLE, CITY HALL P.O. BOX 1048 CAMDENTON, MO 65020

Lab Number: 98-A896

Sample Number: 98-B383

#### RESULTS OF SAMPLE ANALYSES FOR PUBLIC WATER SUPPLIES

Report Date:

February 18, 1998

Date Collected: February 2, 1998

PWS ID: MO3010130

Sample Location: MULBERRY WELL, SPECIAL REQUEST

PWS Name:

Analysis Performed	Results	MCL	Units
VOC Results:			
Dichlorodifluoromethane	< 20.0	}	ug/L
Chloromethane	< 2.5		ug/L
Vinyl Chloride	< 0.5	2.0	ug/L
Bromomethane	< 9.0	∦	ug/L
Chloroethane	< 2.5	ļ	ug/L
Trichlorofluoromethane	< 2.5	<b> </b>	ug/L
1,1-Dichloroethene	< 0.5	7.0	ug/L
Methylene Chloride	< 0.5	5.0	ug/L
Methyl-tert-butyl ether	< 5.0	1	ug/L
trans-1,2-Dichloroethene	< 0.5	100	ug/L
1,1-Dichloroethane	< 1.0	<b>∥</b>	ug/L
2,2-Dichloropropane	< 1.0	<b>∥</b>	ug/L
cis-1,2-Dichloroethene	< 0.5	70.0	ug/L
Chloroform	< 0.5		ug/L
Bromochloromethane	< 1.0	<b> </b>	ug/L
1,1,1-Trichloroethane	< 0.5	200	ug/L
1,1-Dichloropropene	< 1.0	<b> </b>	ug/L
Carbon Tetrachloride	< 0.5	5.0	ug/L
Benzene	< 0.5	5.0	ug/L
1,2-Dichloroethane	< 0.5	5.0	ug/L
Trichloroethene	6.3	5.0	ug/L
1,2-Dichloropropane	< 0.5	5.0	ug/L
Bromodichloromethane	< 0.5	<b> </b>	ug/L
Dibromomethane	< 1.0		ug/L
cis-1,3-Dichloropropane	< 2.0		ug/L
Toluene	< 0.5	199ECE	II V BOOK
trans-1,3-Dichloropropane	< 1.0	KDU L	The Tarket
1,1,2-Trichloroethane	< 0.5	1.35.0 FER	ug/L i 0 1907

Page: 2
Report Date: February 18, 1998

Lab Number: 98-A896 Sample Number: 98-B383

Analysis Performed	Results	MCL	Units
Tetrachloroethene	< 0.5	5.0	ug/L
1,3-Dichloropropane	< 2.0	<b></b>	ug/L
Dibromochloromethane	< 0.5		ug/L
1,2-Dibromoethane	< 2.0	<b></b>	ug/L
Chlorobenzene	< 0.5	100	ug/L
Ethylbenzene	< 0.5	700	ug/L
1,1,1,2-Tetrachloroethane	< 1.0		ug/L
Total Xylenes	< 0.5	10000	ug/L
Styrene	< 0.5	100	ug/L
Isopropylbenzene	< 2.0	<b>∥</b>	ug/L
Bromoform	< 0.5		ug/L
1,1,2,2-Tetrachloroethane	< 1.0		ug/L
1,2,3-Trichloropropane	< 1.0	<b> </b>	ug/l
n-Propylbenzene	< 2.0	<b></b>	ug/L
Bromobenzene	< 1.0		ug/L
2-Chlorotoluene	< 2.0	∦	ug/L
4-Chlorotoluene	< 2.0		ug/L
1,3,5-Trimethylbenzene	< 2.0		ug/L
tert-Butylbenzene	< 2.0	<b></b>	ug/L
1,2,4-Trimethylbenzene	< 1.0		ug/L
sec-Butylbenzene	< 2.0		ug/L
p-isopropyltoluene	< 2.0	<b></b>	ug/L
1,3-Dichlorobenzene	< 1.0		ug/L
1,4-Dichlorobenzene	< 0.5	75.0	ug/L
n-Butylbenzene	< 2.0		ug/L
1,2-Dichlorobenzene	< 0.5	600	ug/L
1,2-Dibromo-3-Chloroprop	< 5.0		ug/L
1,2,4-Trichlorobenzene	< 0.5	70.0	ug/L
Hexachlorobutadiene	< 1.0	<b> </b>	ug/L
Naphthalene	< 20.0	<b>—</b>	ug/L
1,2,3-Trichlorobenzene	< 2.0		ug/L

MCL = Maximum Contaminant Level

-- = Not Applicable

The analysis of this sample was performed in accordance with procedures approved or recognized by the U.S. Environmental Protection Agency. If you have any questions, please contact Mr. Terry Timmons at 573/751-1188.

James H. Long, Derector

Environmental Services Program Division of Environmental Quality

Markette to the transfer of the Sales of the

McCamahan Governor • Stephen M Militard Ductors 2.6 1008

DEPARTMENT OF NATURAL RESOURCES

DIVISION OF ENVIRONMENTAL OF PARTMENT OF P.O. Box 176 Jefferson City. MONATURAL RESOURCES

#### ENVIRONMENTAL SERVICES PROGRAM

VINCENT COSTA

Lab Number: 98-A1807

PWS ID: MO3010130

112 COURT CIRCLE, CITY HALL P.O. BOX 1048

CAMDENTON, MO 65020

Sample Number: 98-C482

OUARTERLY MONITORING

#### RESULTS OF SAMPLE ANALYSES FOR PUBLIC WATER SUPPLIES

Report Date:

March 11, 1998

Date Collected: February 17, 1998 Sample Location: MULBERRY WELL HOUSE

PWS Name:

Analysis Performed	Results	MCL	Units
VOC Results:			
Dichlorodifluoromethane	< 20.0		ug/L
Chloromethane	< 2.5		ug/L
Vinyl Chloride	< 0.5	2.0	ug/L
Bromomethane	< 9.0		ug/L
Chloroethane	< 2.5		ug/L
Trichlorofluoromethane	< 2.5	<b></b> 1	ug/L
1,1-Dichloroethene	< 0.5	7.0	ug/L
Methylene Chloride	< 0.5	5.0	ug/L
Methyl-tert-butyl ether	< 5.0		ug/L
trans-1,2-Dichloroethene	< 0.5	100	ug/L
1,1-Dichloroethane	< 1.0	<b></b>	ug/L
2,2-Dichloropropane	< 1.0		ug/L
cis-1,2-Dichloroethene	< 0.5	70.0	ug/L
Chloroform	< 0.5	<b> </b>	ug/L
Bromochloromethane	< 1.0		ug/L
1,1,1-Trichloroethane	< 0.5	200	ug/L
1,1-Dichloropropene	< 1.0		ug/L
Carbon Tetrachloride	< 0.5	5.0	ug/L
Benzene	< 0.5	5.0	ug/L
1,2-Dichloroethane	< 0.5	5.0	ug/L
Trichloroethene	5.2	5.0	ug/L
1,2-Dichloropropane	< 0.5	5.0	ug/L
Bromodichloromethane	< 0.5		ug/L
Dibromomethane	< 1.0		ug/L
cis-1,3-Dichloropropane	< 2.0		ug/L
Toluene	< 0.5	1000	ug/L

Page: 2 Lab Number: 98-A1807 Report Date: March 11, 1998 Sample Number: 98-C482

Analysis Performed	Results	MCL	Units
trans-1,3-Dichloropropane	< 1.0		ug/L
1,1,2-Trichloroethane	< 0.5	5.0	ug/L
Tetrachloroethene	< 0.5	∥ 5.0	ug/L
1,3-Dichloropropane	< 2.0		ug/L
Dibromochloromethane	< 0.5		ug/L
1,2-Dibromoethane	< 2.0		ug/L
Chlorobenzene	< 0.5	100	ug/L
Ethylbenzene	< 0.5	700	ug/L
1,1,1,2-Tetrachloroethane	< 1.0	<b></b>	ug/L
Total Xylenes	< 0.5	10000	ug/L
Styrene	< 0.5	100	ug/L
Isopropylbenzene	< 2.0		ug/L
Bromoform	< 0.5		ug/L
1,1,2,2-Tetrachloroethane	< 1.0		ug/L
1,2,3-Trichloropropane	< 1.0		ug/l
n-Propylbenzene	< 2.0		ug/L
Bromobenzene	< 1.0	<b></b> .	ug/L
2-Chlorotoluene	< 2.0	<b></b>	ug/L
4-Chlorotoluene	< 2.0	Ŋ	ug/L
1,3,5-Trimethylbenzene	< 2.0		ug/L
tert-Butylbenzene	< 2.0		ug/L
1,2,4-Trimethylbenzene	< 1.0		ug/L
sec-Butylbenzene	< 2.0		∥ ug/L
p-isopropyltoluene	< 2.0		ug/L
1,3-Dichlorobenzene	< 1.0		ug/L
1,4-Dichlorobenzene	< 0.5	75.0	ug/L
n-Butylbenzene	< 2.0	<b></b>	ug/L
1,2-Dichlorobenzene	< 0.5	600	ug/L
1,2-Dibromo-3-Chloroprop		<b></b>	ug/L
	< 0.5	70.0	ug/L
Hexachlorobutadiene	< 1.0		ug/L
Naphthalene	< 20.0	<b></b>	ug/L
1,2,3-Trichlorobenzene	< 2.0	<b></b>	ug/L


MCL = Maximum Contaminant Level

-- = Not Applicable

The analysis of this sample was performed in accordance with procedures approved or recognized by the U.S. Environmental Protection Agency. If you have any questions, please contact Mr. Terry Timmons at 573/751-1188.

James H. Long, Derector

Environmental Services Program



APR 15 1998

STATE OF MISSOURI

Mel Camalian Concernor + Septien M. Mahippoly Incerton. Securities of the Concernor of the Society of the Concernor of the Co

## DEPARTMENT OF NATURAL RESCURCES

- DIVISION OF ENVIRONMENTAL QUALITY -P.O. Box 176 Jefferson City, MO 65102-0176

#### ENVIRONMENTAL SERVICES PROGRAM

VINCENT COSTA 112 COURT CIRCLE, CITY HALL P.O. BOX 1048 CAMDENTON, MO 65020

Lab Number: 98-A3749

Sample Number: 98-B784

RESULTS OF SAMPLE ANALYSES FOR PUBLIC WATER SUPPLIES

Report Date: March 31, 1998 Date Collected: March 25, 1998

PWS County: CAMDEN PWS ID: MO3010130

Sample Location: MULBERRY WELL

PWS Name:

Analysis Performed	Results	MCL	Units
VOC Results:			
Dichlorodifluoromethane	< 20.0		ug/L
Chloromethane	< 2.5		ug/L
Vinyl Chloride	< 0.5	2.0	ug/L
Bromomethane	< 9.0	<b> </b>	ug/L
Chloroethane	< 2.5		ug/L
Trichlorofluoromethane	< 2.5		ug/L
1,1-Dichloroethene	< 0.5	7.0	ug/L
Methylene Chloride	< 0.5	5.0	ug/L
Methyl-tert-butyl ether	< 5.0		ug/L
trans-1,2-Dichloroethene	< 0.5	100	ug/L
1,1-Dichloroethane	< 1.0		ug/L
2,2-Dichloropropane	< 1.0	<b></b>	ug/L
cis-1,2-Dichloroethene	< 0.5	70.0	ug/L
Chloroform	< 0.5		ug/L
Bromochloromethane	< 1.0		ug/L
1,1,1-Trichloroethane	< 0.5	200	ug/L
1,1-Dichloropropene	< 1.0	<b></b>	ug/L
Carbon Tetrachloride	< 0.5	5.0	ug/L
Benzene	< 0.5	5.0	ug/L
1,2-Dichloroethane	< 0.5	5.0	ug/L
Trichloroethene	3.6	5.0	ug/L
1,2-Dichloropropane	< 0.5	5.0	ug/L
Bromodichloromethane	< 0.5	<b> </b>	ug/L
Dibromomethane	< 1.0		ug/L
cis-1,3-Dichloropropane	< 2.0		ug/L
Toluene	< 0.5	1000	ug/L
trans-1,3-Dichloropropane	< 1.0		ug/L
1,1,2-Trichloroethane	< 0.5	5.0	ug/L

Page: 2 Lab Number: 98-A3749
Report Date: March 31, 1998 Sample Number: 98-B784

Analysis Performed	Results	MCL	Units
Tetrachloroethene	< 0.5	5.0	ug/L
1,3-Dichloropropane	< 2.0	<b></b>	ug/L
Dibromochloromethane	< 0.5	<b></b>	ug/L
1,2-Dibromoethane	< 2.0	<b></b>	ug/L
Chlorobenzene	< 0.5	100	ug/L
Ethylbenzene	< 0.5	700	ug/L
1,1,1,2-Tetrachloroethane	< 1.0		ug/L
Total Xylenes	< 0.5	10000	ug/L
Styrene	< 0.5	100	ug/L
Isopropylbenzene	< 2.0	<b></b>	ug/L
Bromoform	< 0.5	<b> </b>	ug/L
1,1,2,2-Tetrachloroethane	< 1.0	(	ug/L
1,2,3-Trichloropropane	< 1.0		ug/l
n-Propylbenzene	< 2.0		ug/L
Bromobenzene	< 1.0	<b></b>	ug/L
2-Chlorotoluene	< 2.0	<b> </b>	ug/L
4-Chlorotoluene	< 2.0		ug/L
1,3,5-Trimethylbenzene	< 2.0		ug/L
tert-Butylbenzene	< 2.0		ug/L
1,2,4-Trimethylbenzene	< 1.0		ug/L
sec-Butylbenzene	< 2.0		ug/L
p-isopropyltoluene	< 2.0		ug/L
	< 1.0	<b>)</b>	ug/L
1,4-Dichlorobenzene	< 0.5	75.0	ug/L
n-Butylbenzene	< 2.0	∦	ug/L
1,2-Dichlorobenzene	< 0.5	600	ug/L
	< 5.0		ug/L
	< 0.5	70.0	ug/L
Hexachlorobutadiene	< 1.0	·	ug/L
Naphthalene	< 20.0		ug/L
1,2,3-Trichlorobenzene	< 2.0		ug/L

MCL = Maximum Contaminant Level

-- = Not Applicable

The analysis of this sample was performed in accordance with procedures approved or recognized by the U.S. Environmental Protection Agency. If you have any questions, please contact Mr. Terry Timmons at 573/751-1188.

James H. Long, D(rector

Environmental Services Program Division of Environmental Quality

MIN 0 2 1998

STATE OF MISSOURI

# DEPARTMENT OF NATURAL RESOURCES

41 41

- DIVISION OF ENVIRONMENTAL QUALITY CONTROL CO P.O. Box 176 Jefferson City MO 65192-0176

#### ENVIRONMENTAL SERVICES PROGRAM

VINCENT COSTA

Lab Number: 98-A4982

112 COURT CIRCLE, CITY HALL P.O. BOX 1048

CAMDENTON, MO 65020

Sample Number: 98-F440

RESULTS OF SAMPLE ANALYSES FOR PUBLIC WATER SUPPLIES

Report Date:

May 7, 1998

PWS County: CAMDEN

Date Collected: April 23, 1998
Sample Location: MULBERRY WELL HOUSE

PWS ID: MO3010130

PWS Name:

Analysis Performed	Results	MCL	Units
VOC Results:			
Dichlorodifluoromethane	< 20.0		ug/L
Chloromethane	< 2.5		ug/L
Vinyl Chloride	< 0.5	2.0	ug/L
Bromomethane	< 9.0		ug/L
Chloroethane	< 2.5	<b></b>	ug/L
Trichlorofluoromethane	< 2.5		ug/L
1,1-Dichloroethene	< 0.5	7.0	ug/L
Methylene Chloride	< 0.5	5.0	ug/L
Methyl-tert-butyl ether	< 5.0		ug/L
trans-1,2-Dichloroethene	< 0.5	100	ug/L
1,1-Dichloroethane	< 1.0		ug/L
2,2-Dichloropropane	< 1.0		ug/L
cis-1,2-Dichloroethene	< 0.5	70.0	ug/L
Chloroform	< 0.5	∥	ug/L
Bromochloromethane	< 1.0		ug/L
1,1,1-Trichloroethane	< 0.5	200	ug/L
1,1-Dichloropropene	< 1.0	1	ug/L
Carbon Tetrachloride	< 0.5	5.0	ug/L
Benzene	< 0.5	5.0	ug/L
1,2-Dichloroethane	< 0.5	5.0	ug/L
Trichloroethene	4.1	5.0	ug/L
1,2-Dichloropropane	< 0.5	5.0	ug/L
Bromodichloromethane	< 0.5		ug/L
Dibromomethane	< 1.0		ug/L
cis-1,3-Dichloropropane	< 2.0		ug/L
Toluene	< 0.5	1000	ug/L
trans-1,3-Dichloropropane	< 1.0		ug/L
1,1,2-Trichloroethane	< 0.5	5.0	ug/L

Page: 2 Lab Number: 98-A4982 Report Date: May 7, 1998 Sample Number: 98-F440

Analysis Performed	Results	MCL	Units
Tetrachloroethene	< 0.5	5.0	ug/L
1,3-Dichloropropane	< 2.0	<b> </b>	ug/L
Dibromochloromethane	< 0.5	<b></b>	ug/L
1,2-Dibromoethane	< 2.0	<b></b>	ug/L
Chlorobenzene	< 0.5	100	ug/L
Ethylbenzene	< 0.5	700	ug/L
1,1,1,2-Tetrachloroethane	< 1.0	<b></b>	ug/L
Total Xylenes	< 0.5	10000	ug/L
Styrene	< 0.5	100	ug/L
Isopropylbenzene	< 2.0		ug/L
Bromoform	< 0.5	<b></b>	ug/L
1,1,2,2-Tetrachloroethane	< 1.0		ug/L
1,2,3-Trichloropropane	< 1.0		ug/l
n-Propylbenzene	< 2.0		ug/L
Bromobenzene	< 1.0	i	ug/L
2-Chlorotoluene	< 2.0		ug/L
4-Chlorotoluene	< 2.0		ug/L
1,3,5-Trimethylbenzene	< 2.0		ug/L
tert-Butylbenzene	< 2.0		ug/L
1,2,4-Trimethylbenzene	< 1.0	- <del>-</del>	ug/L
sec-Butylbenzene	< 2.0		ug/L
p-isopropyltoluene	< 2.0	<b></b>	ug/L
1,3-Dichlorobenzene	< 1.0		ug/L
1,4-Dichlorobenzene	< 0.5	75.0	ug/L
n-Butylbenzene	< 2.0		ug/L
1,2-Dichlorobenzene	< 0.5	600	ug/L
	< 5.0	<b>-</b> -	ug/L
1,2,4-Trichlorobenzene	< 0.5	70.0	ug/L
Hexachlorobutadiene	< 1.0		ug/L
Naphthalene	< 20.0		ug/L
1,2,3-Trichlorobenzene	< 2.0		ug/L

MCL = Maximum Contaminant Level

-- = Not Applicable

The analysis of this sample was performed in accordance with procedures approved or recognized by the U.S. Environmental Protection Agency. If you have any questions, please contact Mr. Terry Timmons at 573/751-1188.

James H. Long, Director Environmental Services Program Division of Environmental Quality

RECEIVED

NOV 0 2 1998

STATE OF MISSOURI

McCamalian Covernor - Supplier M. Mahakat Dineston

## DEPARTMENT OF NATURAL RESOURCES

 DIVISION OF ENVIRONMENTAL QUALITY = P.O. Box 176 Jefferson City. MO 65102-0176

#### ENVIRONMENTAL SERVICES PROGRAM

VINCENT COSTA

Lab Number: 98-A6299

112 COURT CIRCLE, CITY HALL

P.O. BOX 1048

CAMDENTON, MO 65020

Sample Number: 98-H069

OUARTERLY MONITORING \*\*\*

RESULTS OF SAMPLE ANALYSES FOR PUBLIC WATER SUPPLIES

Report Date:

June 9, 1998

Date Collected: May 21, 1998

PWS ID: MO3010130

Sample Location: MULBERRY WELL PWS Name:

Analysis Performed	Results	MCL	Units
VOC Results:	<del></del>		
Dichlorodifluoromethane	< 20.0		ug/L
Chloromethane	< 2.5	∦	ug/L
Vinyl Chloride	< 0.5	2.0	ug/L
Bromomethane	< 9.0		ug/L
Chloroethane	< 2.5	jj	ug/L
Trichlorofluoromethane	< 2.5		ug/L
1,1-Dichloroethene	< 0.5	7.0	ug/L
Methylene Chloride	< 0.5	5.0	ug/L
Methyl-tert-butyl ether	< 5.0		ug/L
trans-1,2-Dichloroethene	< 0.5	100	ug/L
1,1-Dichloroethane	< 1.0		ug/L
2,2-Dichloropropane	< 1.0	∥	ug/L
cis-1,2-Dichloroethene	< 0.5	70.0	ug/L
Chloroform	< 0.5		ug/L
Bromochloromethane	< 1.0	}	ug/L
1,1,1-Trichloroethane	< 0.5	200	ug/L
l,l-Dichloropropene	< 1.0	<b></b>	ug/L
Carbon Tetrachloride	< 0.5	5.0	ug/L
Benzene	< 0.5	5.0	ug/L
1,2-Dichloroethane	< 0.5	∬ 5.0	ug/L
Trichloroethene	11.8	5.0	ug/L
1,2-Dichloropropane	< 0.5	5.0	ug/L
Bromodichloromethane	< 0.5	∦	ug/L
Dibromomethane	< 1.0	<b></b>	ug/L
cis-1,3-Dichloropropane	< 2.0		ug/L
Toluene	< 0.5	ECEIVE 1000	ug/L
	<del></del>		<u> </u>

Page: 2 Report Date: June 9, 1998 Lab Number: 98-A6299 Sample Number: 98-H069

Analysis Performed	Results	MCL	Units
trans-1,3-Dichloropropane	< 1.0		ug/L
1,1,2-Trichloroethane	< 0.5	5.0	ug/L
Tetrachloroethene	< 0.5	5.0	ug/L
1,3-Dichloropropane	< 2.0		ug/L
Dibromochloromethane	< 0.5		ug/L
1,2-Dibromoethane	< 2.0	<b> </b>	ug/L
Chlorobenzene	< 0.5	100	ug/L
Ethylbenzene	< 0.5	700	ug/L
1,1,1,2-Tetrachloroethane	< 1.0		ug/L
Total Xylenes	< 0.5	10000	ug/L
Styrene	< 0.5	100	ug/L
Isopropylbenzene	< 2.0		ug/L
Bromoform	< 0.5	<b> </b>	ug/L
1,1,2,2-Tetrachloroethane	< 1.0	<b></b>	ug/L
1,2,3-Trichloropropane	< 1.0		ug/l
n-Propylbenzene	< 2.0	<b>-</b>	ug/L
Bromobenzene	< 1.0		ug/L
2-Chlorotoluene	< 2.0		ug/L
4-Chlorotoluene	< 2.0	<b>  -</b> -	ug/L
1,3,5-Trimethylbenzene	< 2.0	)	ug/L
tert-Butylbenzene	< 2.0		ug/L
1,2,4-Trimethylbenzene	< 1.0	]	ug/L
sec-Butylbenzene	< 2.0	<b> </b>	ug/L
p-isopropyltoluene	< 2.0	<b> </b>	ug/L
1,3-Dichlorobenzene	< 1.0		ug/L
1,4-Dichlorobenzene	< 0.5	75.0	ug/L
n-Butylbenzene	< 2.0		ug/L
1,2-Dichlorobenzene	< 0.5	600	ug/L
1,2-Dibromo-3-Chloroprop	< 5.0		ug/L
1,2,4-Trichlorobenzene	< 0.5	70.0	ug/L
Hexachlorobutadiene	< 1.0	<b> </b>	ug/L
Naphthalene	< 20.0	<b>}</b>	ug/L
1,2,3-Trichlorobenzene	< 2.0		ug/L

MCL = Maximum Contaminant Level

-- = Not Applicable

The analysis of this sample was performed in accordance with procedures approved or recognized by the U.S. Environmental Protection Agency. If you have any questions, please contact Mr. Terry Timmons at 573/751-1188.

James H. Long, Director Environmental Services Program

NOV 0 2 1998

STATE OF MISSOURI

Mel Camalian Governor • Stephen M. Militood. Director

## DEPARTMENT OF NATURAL RESOURCES

--- DIVISION OF ENVIRONMENTAL QUALITY -P O. Box 176 Jefferson City, MO 65102-0176

Lab Number: 98-A6820

PWS County: CAMDEN

PWS ID: MO3010130

#### ENVIRONMENTAL SERVICES PROGRAM

VINCENT COSTA 112 COURT CIRCLE, CITY HALL P.O. BOX 1048 CAMDENTON, MO 65020

#### RESULTS OF SAMPLE ANALYSES FOR PUBLIC WATER SUPPLIES

Sample Number: 98-F519

Report Date: Date Collected: June 8, 1998

June 18, 1998

Sample Location: MULBERRY WELL

PWS Name:

Analysis Performed	Results	MCL	Units
VOC Results:			
Dichlorodifluoromethane	< 20.0		ug/L
Chloromethane	< 2.5		ug/L
Vinyl Chloride	< 0.5	2.0	ug/L
Bromomethane	< 9.0		ug/L
Chloroethane	< 2.5		ug/L
Trichlorofluoromethane	< 2.5		ug/L
1,1-Dichloroethene	< 0.5	7.0	ug/L
Methylene Chloride	< 0.5	5.0	ug/L
Methyl-tert-butyl ether	< 5.0		ug/L
trans-1,2-Dichloroethene	< 0.5	100	ug/L
1,1-Dichloroethane	< 1.0	¶	ug/L
2,2-Dichloropropane	< 1.0		ug/L
cis-1,2-Dichloroethene	< 0.5	70.0	ug/L
Chloroform	< 0.5		ug/L
Bromochloromethane	< 1.0		ug/L
1,1,1-Trichloroethane	< 0.5	200	ug/L
1,1-Dichloropropene	< 1.0	<u> </u>	ug/L
Carbon Tetrachloride	< 0.5	5.0	ug/L
Benzene	< 0.5	5.0	ug/L
1,2-Dichloroethane	< 0.5	5.0	ug/L
Trichloroethene	5.1	5.0	ug/L
1,2-Dichloropropane	< 0.5	5.0	ug/L
Bromodichloromethane	< 0.5		ug/L
Dibromomethane	< 1.0		ug/L
cis-1,3-Dichloropropane	< 2.0		ug/L
Toluene	< 0.5	1000	ug/L
trans-1,3-Dichloropropane			ug/L
1,1,2-Trichloroethane	< 0.5	5.0	ug/L

Page: 2 Lab Number: 98-A6820 Report Date: June 18, 1998 Sample Number: 98-F519

Analysis Performed	Results	MCL	Units
Tetrachloroethene	< 0'.5	5.0	ug/L
1,3-Dichloropropane	< 2.0	<b> </b>	ug/L
Dibromochloromethane	< 0.5		ug/L
1,2-Dibromoethane	< 2.0		ug/L
Chlorobenzene	< 0.5	100	ug/L
Ethylbenzene	< 0.5	700	ug/L
1,1,1,2-Tetrachloroethane	< 1.0	<b> </b>	ug/L
Total Xylenes	< 0.5	10000	ug/L
Styrene	< 0.5	100	ug/L
Isopropylben <b>zene</b>	< 2.0	<b> </b>	ug/L
Bromoform	< 0.5	1	ug/L
1,1,2,2-Tetrachloroethane	< 1.0		ug/L
	< 1.0	<b></b>	ug/l
n-Propylbenzene	< 2.0	<b> </b>	ug/L
Bromobenzene	< 1.0		ug/L
2-Chlorotoluene	< 2.0	<b> </b>	ug/L
4-Chlorotoluene .	< 2.0		ug/L
1,3,5-Trimethylbenzene	< 2.0		ug/L
tert-Butylbenzene	< 2.0		ug/L
1,2,4-Trimethylbenzene	< 1.0		ug/L
sec-Butylbenzene	< 2.0		ug/L
p-isopropyltoluene	< 2.0	<b> </b>	ug/L
1,3-Dichlorobenzene	< 1.0		ug/L
1,4-Dichlorobenzene	< 0.5	75.0	ug/L
n-Butylbenzene	< 2.0		ug/L
1,2-Dichlorobenzene	< 0.5	600	ug/L
1,2-Dibromo-3-Chloroprop	< 5.0		ug/L
1,2,4-Trichlorobenzene	< 0.5	70.0	ug/L
Hexachlorobutadiene	< 1.0		ug/L
Naphthalene	< 20.0		ug/L
1,2,3-Trichlorobenzene	< 2.0		ug/L

MCL = Maximum Contaminant Level

-- = Not Applicable

The analysis of this sample was performed in accordance with procedures approved or recognized by the U.S. Environmental Protection Agency. If you have any questions, please contact Mr. Terry Timmons at 573/751-1188.

James H. Long, Derector

Environmental Services Program

## DEPARTMENT OF NATURAL RESOURCES 1998

-DIVISION OF EXVIRONMENTAL QUALITY = PO Box 176 Jefferson Circ. MO 6840240176 AL SERVICES PROGRAM

Lab Number: 98-A14822

PWS ID: MO3010130

#### ENVIRONMENTAL SERVICES PROGRAM

VINCENT COSTA 112 COURT CIRCLE - CITY HALL P.O. BOX 1048 CAMDENTON, MO 65020

Sample Number: 98-U834

QUARTERLY MONITORING

#### RESULTS OF SAMPLE ANALYSES FOR PUBLIC WATER SUPPLIES

Report Date: September 9, 1998

Date Collected: August 25, 1998

Sample Location: MULBERRY WELL

PWS Name:

Analysis Performed	Results	MCL	Units
VOC Results: Dichlorodifluoromethane Chloromethane Vinyl Chloride Bromomethane Chloroethane Trichlorofluoromethane 1,1-Dichloroethene Methylene Chloride	< 200 < 2.5 < 0.5 < 9.0 < 2.5 < 2.5 < 0.5 < 0.5 < 0.5	MCL  2.0 7.0 5.0 100 70.0 200 5.0 5.0 5.0 5.0	ug/L ug/L ug/L ug/L ug/L ug/L ug/L ug/L
cis-1,3-Dichloropropane Toluene	< 2.0 < 1.0	1000	ug/L ug/L ug/L

Page: 2 Lab Number: 98-A14822 Report Date: September 9, 1998 Sample Number: 98-U834

Analysis Performed	Results	MCL	Units
trans-1,3-Dichloropropane	< 1.0		ug/L
1,1,2-Trichloroethane	< 0.5	5.0	ug/L
Tetrachloroethene	< 0.5	5.0	ug/L
1,3-Dichloropropane	< 2.0		ug/L
Dibromochloromethane	< 0.5		ug/L
1,2-Dibromoethane	< 2.0		ug/L
Chlorobenzene	< 0.5	100	ug/L
Ethylbenzene	< 0.5	700	ug/L
1,1,1,2-Tetrachloroethane	< 1.0		ug/L
Total Xylenes	< 0.5	10000	ug/L
Styrene	< 0.5	100	ug/L
Isopropylbenzene	< 2.0		ug/L
Bromoform	< 0.5		ug/L
1,1,2,2-Tetrachloroethane	< 1.0		ug/L
1,2,3-Trichloropropane	< 1.0	i	ug/l
n-Propylbenzene	< 2.0		ug/L
Bromobenzene	< 1.0		ug/L
2-Chlorotoluene	< 2.0		ug/L
4-Chlorotoluene	< 2.0	<b></b>	ug/L
1,3,5-Trimethylbenzene	< 2.0	<b></b>	ug/L
tert-Butylbenzene	< 2.0		ug/L
1,2,4-Trimethylbenzene	< 1.0		ug/L
sec-Butylbenzene	< 2.0	i	ug/L
p-isopropyltoluene	< 2.0		ug/L
1,3-Dichlorobenzene	< 1.0		ug/L
1,4-Dichlorobenzene	< 0.5	75.0	ug/L
n-Butylbenzene	< 2.0		ug/L
1,2-Dichlorobenzene	< 0.5	600	ug/L
1,2-Dibromo-3-Chloroprop	< 5.0		ug/L
1,2,4-Trichlorobenzene	< 0.5	70.0	ug/L
Hexachlorobutadiene	< 1.0		ug/L
Naphthalene	< 20.0		ug/L
1,2,3-Trichlorobenzene	< 2.0		ug/L

MCL = Maximum Contaminant Level

-- = Not Applicable

The analysis of this sample was performed in accordance with procedures approved or recognized by the U.S. Environmental Protection Agency. If you have any questions, please contact Mr. Terry Timmons at 573/751-1188.

James H. Long, Director Environmental Services Program Division of Environmental Quality



#### Missouri Department of Natural Resources



E-mail is for official department use only. Copies of messages may be archived indefinitely and reviewed as appropriate.

From Dianne Holtmeyer on 01/25/99 03:30:50 PM

To: Valerie Wilder/HWP/DEQ/MODNR@MODNR

cc: TERRY TIMMONS@NetTalk @ MODNR

Subject: Camdenton

Fourth quarter TCE results for samples collected on 12/2/98 at Camdenton (MO3010130) were:

Blair Well - <0.50 ug/L (No detect)
Rodeo Well - <0.50 ug/L (No detect)

Mulberry Well - 4.40 ug/L

Hickory Well - <0.50 ug/L (No detect)

Dianne Holtmeyer
Missouri Department of Natural Resources
Public Drinking Water Program
P.O. Box 176
Jefferson City, MO 65102

Phone: (573) 526-3479/Fax: (573) 751-3110

Internet mail: nrholtd@mail.dnr.state.mo.us

## RECEIVED

MAR 2 2 1999



Mel Carnahan Governor - Stephen M. Mahlood Director

TOF NATURAL RESOURCES TENDENT OF DIVISION OF ENVIRONMENTAL QUALITY THE SUURCES

P.O. Box 176 Jefferson City, MO 65102-0176

ENVIRONMENTAL SERVICES PROGRAM

VINCENT COSTA

Lab Number: 99-A402

112 COURT CIRCLE, CITY HALL P.O. BOX 1048

CAMDENTON, MO 65020

Sample Number: 9901502

#### RESULTS OF SAMPLE ANALYSES FOR PUBLIC WATER SUPPLIES

Report Date:

March 10, 1999

PWS ID: MO3010130

Date Collected: January 13, 1999 PV Sample Location: MULBERRY WELL, SPECIAL REQUEST

PWS Name:

Analysis Performed	Results	MCL	Units
VOC Results:			
Dichlorodifluoromethane	< 2.5		ug/L
Chloromethane	< 2.5		ug/L
Vinyl Chloride	< 0.5	2.0	ug/L
Bromomethane	< 9.0		ug/L
Chloroethane	< 2.5		ug/L
Trichlorofluoromethane	< 2.5		ug/L
1,1-Dichloroethene	< 0.5	7.0	ug/L
Methylene Chloride	< 0.5	5.0	ug/L
Methyl-tert-butyl ether	< 5.0		ug/L
trans-1,2-Dichloroethene	< 0.5	100	ug/L
1,1-Dichloroethane	< 1.0		ug/L
2,2-Dichloropropane	< 1.0		ug/L
cis-1,2-Dichloroethene	1.3	70.0	ug/L
Chloroform	< 0.5	<b> </b>	ug/L
Bromochloromethane	< 1.0		ug/L
1,1,1-Trichloroethane	< 0.5	200	ug/L
1,1-Dichloropropene	< 1.0		ug/L
Carbon Tetrachloride	< 0.5	5.0	ug/L
Benzene	< 0.5	5.0	ug/L
1,2-Dichloroethane	< 0.5	5.0	ug/L
Trichloroethene	26.2	5.0	ug/L
1,2-Dichloropropane	< 0.5	5.0	ug/L
Bromodichloromethane	< 0.5		ug/L
Dibromomethane	< 1.0		ug/L
cis-1,3-Dichloropropane	< 2.0		ug/L
Toluene	< 0.5	1000	ug/L
trans-1,3-Dichloropropane	< 1.0		ug/L
1,1,2-Trichloroethane	< 0.5	5.0	ug/L

Page: 2

Lab Number: 99-A402 Report Date: March 10, 1999 Sample Number: 9901502

Analysis Performed	Results	MCL	Units
Tetrachloroethene	< 0.5	5.0	ug/L
1,3-Dichloropropane	< 2.0		ug/L
Dibromochloromethane	< 0.5		ug/L
1,2-Dibromoethane	< 2.0	\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\	ug/L
Chlorobenzene	< 0.5	100	ug/L
Ethylbenzene	< 0.5	700	ug/L
1,1,1,2-Tetrachloroethane	< 1.0	)	ug/L
Total Xylenes	< 0.5	10000	ug/L
Styrene	< 0.5	100	ug/L
Isopropylbenzene	< 2.0		ug/L
Bromoform	< 0.5		ug/L
1,1,2,2-Tetrachloroethane	< 1.0		ug/L
1,2,3-Trichloropropane	< 1.0		ug/l
n-Propylbenzene	< 20.0		ug/L
Bromobenzene	< 1.0		ug/L
2-Chlorotoluene	< 2.0		ug/L
4-Chlorotoluene	< 2.0		ug/L
1,3,5-Trimethylbenzene	< 5.0		ug/L
tert-Butylbenzene	< 2.0		ug/L
1,2,4-Trimethylbenzene	< 1.0		ug/L
sec-Butylbenzene	< 2.0	<b> </b>	ug/L
p-isopropyltoluene	< 2.0	<b></b>	ug/L
1,3-Dichlorobenzene	< 1.0	}	ug/L
1,4-Dichlorobenzene	< 0.5	75.0	ug/L
n-Butylbenzene	< 2.0		ug/L
1,2-Dichlorobenzene	< 0.5	600	ug/L
1,2-Dibromo-3-Chloroprop	< 0.5		ug/L
1,2,4-Trichlorobenzene	< 0.5	70.0	ug/L
Hexachlorobutadiene	< 1.0		ug/L
Naphthalene	< 2.0	<b> </b>	ug/L
1,2,3-Trichlorobenzene	< 2.0	<b> </b>	ug/L


MCL = Maximum Contaminant Level

-- = Not Applicable

The analysis of this sample was performed in accordance with procedures approved or recognized by the U.S. Environmental Protection Agency. If you have any questions, please contact Mr. Terry Timmons at 573/751-1188.

James H. Long, Director

Environmental Services Program



## DEPARTMENT OF NATURAL RESOURCES

DIVISION OF ENVIRONMENTAL QUALITY –
 P.O. Box 176 Jefferson City, MO 65102-0176

## ENVIRONMENTAL SERVICES PROGRAM RESULT OF SAMPLE ANALYSIS

Sample No. 94-C603

Reported to: TERRY TIMMONS

Affiliation: PDW

Date: 5/13/94

Project Code: 3404/3000

Sample Description:

CAMDENTON, BLAIR WELL

MO3010130

Collected by: BOB MARSHALL

Affiliation: MISC

Date: 04/27/94

#### **PARAMETERS**

#### RESULTS

VOC Results:	
Benzene	<0.5 ug/L
Bromobenzene	<1.0 ug/L
Bromochloromethane	<1.0 ug/L
Bromodichloromethane	<1.0 ug/L
Bromoform	< 2.5  ug/L
Bromomethane	<2.5 ug/L
n-Butylbenzene	< 2.0  ug/L
sec-Butylbenzene	<2.0 ug/L
tert-Butylbenzene	<2.0 ug/L
Carbon tetrachloride	<0.5 ug/L
Chlorobenzene	<0.5 ug/L
Chloroethane	<2.5 ug/L
Chloroform	<1.0 ug/L
Chloromethane	<2.5 ug/L
2-Chlorotoluene	<2.0 ug/L
4-Chlorotoluene	<2.0 ug/L
Dibromochloromethane	<1.0 ug/L
1,2-Dibromo-3-chloropropane	<5.0 ug/L
1,2-Dibromoethane	<2.0 ug/L
Dibromomethane	<1.0 ug/L

Mel Camahan, Governor • David A. Shorr, Director :

## DEPARTMENT OF NATURAL RESOURCES

-- DIVISION OF ENVIRONMENTAL QUALITY -P O. Box 176 Jefferson City, MO 65102-0176

Page 2 Sample no. 94-C603 Date 5/13/94

PARAMETERS		RESULTS
1,2-Dichlorobenzene	<0.5	ug/L
1,3-Dichlorobenzene	<1.0	ug/L
1,4-Dichlorobenzene	<0.5	ug/L
Dichlorodifluoromethane		ug/L
1,1-Dichloroethane		ug/L
1,2-Dichloroethane	<0.5	ug/L
1,1-Dichloroethene	<0.5	ug/L
cis-1,2-Dichloroethene		ug/L
trans-1,2-Dichloroethene	<0.5	ug/L
1,2-Dichloropropane	<0.5	ug/L
1,3-Dichloropropane	<2.0	ug/L
2,2-Dichloropropane	<1.0	ug/L
1,1-Dichloropropene	<1.0	ug/L
cis-1,3-Dichloropropene	<2.0	ug/L
trans-1,3-Dichloropropene	<1.0	ug/L
Ethylbenzene		ug/L
Hexachlorobutadiene	<1.0	ug/L
Isopropylbenzene	<2.0	ug/L
p-Isopropyltoluene	<2.0	ug/L
Methylene Chloride	<0.5	ug/L
Naphthalene	<2.0	ug/L
n-Propylbenzene	<2.0	ug/L
Styrene	<0.5	ug/L
1,1,1,2-Tetrachloroethane	<1.0	ug/L
1,1,2,2-Tetrachloroethane		ug/L
Tetrachloroethene	<0.5	ug/L
Toluene	<0.5	ug/L
1,2,3-Trichlorobenzene		ug/L
1,2,4-Trichlorobenzene		ug/L
1,1,1-Trichloroethane	<0.5	ug/L

Mel Camahan, Governor • David A. Shorr, Director

## DEPARTMENT OF NATURAL RESOURCES

1 7 1

- DIVISION OF ENVIRONMENTAL QUALITY -P.O. Box 176 Jefferson City. MO 65102-0176

Page 3 Sample no. 94-C603 Date 5/13/94

<u>PARAMETERS</u>	RESULTS
1,1,2-Trichloroethane	<0.5 ug/L
Trichloroethene	<0.5 ug/L
Trichlorofluoromethane	<2.5 ug/L
1,2,3-Trichloropropane	<1.0 ug/L
1,2,4-Trimethylbenzene	<1.0 ug/L
1,3,5-Trimethylbenzene	<2.0 ug/L
Vinyl Chloride	<0.5 ug/L
o-Xylene	<0.5 ug/L
m&p-xylene	<0.5 ug/L

The analysis of this sample was performed in accordance with procedures approved or recognized by the U.S. Environmental Protection Agency.

James H. Long Director Environmental Services Program

### DEPARTMENT OF NATURAL RESOURCES

- DIVISION OF ENVIRONMENTAL QUALITY -P.O. Box 176 Jefferson City, MO 65102-0176

#### ENVIRONMENTAL SERVICES PROGRAM

BOB MARSHALL CITY HALL P.O. BOX 1048

CAMDENTON, MO 65020

Lab Number: 97-A759

Sample Number: 97-A467

#### RESULTS OF SAMPLE ANALYSES FOR PUBLIC WATER SUPPLIES

Report Date: Date Collected:

February 24, 1997 January 29, 1997

PWS County: CAMDEN PWS ID: MO3010130

Sample Location: BLAIR ST WELL HOUSE

PWS Name:

Analysis Performed	Results	MCL	Units
VOC Results:			
Dichlorodifluoromethane	< 20.0		ug/L
Chloromethane	< 2.5		ug/L
Vinyl Chloride	< 0.5	2.0	ug/L
Bromomethane	< 9.0		ug/L
Chloroethane	< 2.5		ug/L
Trichlorofluoromethane	< 2.5		ug/L
1,1-Dichloroethene	< 0.5	7.0	ug/L
Methylene Chloride	< 0.5	5.0	ug/L
Methyl-tert-butyl ether	< 5.0		ug/L
trans-1,2-Dichloroethene	< 0.5	100	ug/L
1,1-Dichloroethane	< 1.0	( ·	ug/L
2,2-Dichloropropane	< 1.0	1	ug/L
cis-1,2-Dichloroethene	< 0.5	70.0	ug/L
Chloroform	< 0.5		ug/L
Bromochloromethane	< 1.0		ug/L
1,1,1-Trichloroethane	< 0.5	200	ug/L
1,1-Dichloropropene	< 1.0		ug/L
Carbon Tetrachloride	< 0.5	5.0	ug/L
Benzene	< 0.5	5.0	ug/L
1,2-Dichloroethane	< 0.5	5.0	ug/L
Trichloroethene	< 0.5	5.0	ug/L
1,2-Dichloropropane	< 0.5	5.0	ug/L
Bromodichloromethane	< 0.5		ug/L
Dibromomethane	< 1.0		ug/L
cis-1,3-Dichloropropane	< 2.0		ug/L
Tcluene	< 0.5	1000	ug/L
trans-1,3-Dichloropropane	< 1.0		ug/L
1,1,2-Trichloroethane	< 0.5	5.0	ug/L

Page: 2 Lab Number: 97-A759

Sample Number: 97-A467 Report Date: February 24, 1997

Analysis Performed	Results	MCL	Units
Tetrachloroethene	< 0.5	5.0	ug/L
1,3-Dichloropropane	< 2.0		ug/L
Dibromochloromethane	< 0.5		ug/L
1,2-Dibromoethane	< 2.0	<b> </b>	ug/L
Chlorobenzene	< 0.5	100	ug/L
Ethylbenzene	< 0.5	700	ug/L
1,1,1,2-Tetrachloroethane	< 1.0		ug/L
Total Xylenes	< 0.5	10000	ug/L
Styrene	< 0.5	100	ug/L
Isopropylbenzene	< 2.0		ug/L
Bromoform	< 0.5		ug/L
1,1,2,2-Tetrachloroethane	< 1.0		ug/L
1,2,3-Trichloropropane	< 1.0		ug/l
n-Propylbenzene	< 2.0	<b> </b>	ug/L
Bromobenzene	< 1.0		ug/L
2-Chlorotoluene	< 2.0	<b></b>	ug/L
4-Chlorotoluene	< 2.0	<b></b>	ug/L
1,3,5-Trimethylbenzene	< 2.0	<b></b>	ug/L
tert-Butylbenzene	< 2.0	<b>∦</b>	ug/L
1,2,4-Trimethylbenzene	< 1.0	1	ug/L
sec-Butylbenzene	< 2.0	∥	ug/L
p-isopropyltoluene	< 2.0	<b> </b>	ug/L
1,3-Dichlorobenzene	< 1.0	∦	ug/L
1,4-Dichlorobenzene	< 0.5	75.0	ug/L
n-Butylbenzene	< 2.0		ug/L
1,2-Dichlorobenzene	< 0.5	600	ug/L
1,2-Dibromo-3-Chlorobenz	< 5.0	1	ug/L
1,2,4-Trichlorobenzene		70.0	ug/L
Hexachlorobutadiene	< 1.0		ug/L
Naphthalene	< 2.0		ug/L
1,2,3-Trichlorobenzene	< 2.0		ug/L


MCL = Maximum Contaminant Level

-- = Not Applicable

The analysis of this sample was performed in accordance with procedures approved or recognized by the U.S. Environmental Protection Agency. If you have any questions, please contact Mr. Terry Timmons at 573/751-1188.

James H. Long, Director Environmental Services Program

Division of Environmental Quality



STATE OF MISSOURI

McCarnalian concernor • Stephen M. Mahlood, Director

TEB 23 1998

## DEPARTMENT OF NATURAL RESOURCES

- DIVISION OF ENVIRONMENTAL QUALITY SOURCE FAR MEET OF P.O. Box 176 Jefferson City, MO 65102-01 CATURAL RESOURCES

#### ENVIRONMENTAL SERVICES PROGRAM

VINCENT COSTA 112 COURT CIRCLE, CITY HALL P.O. BOX 1048 CAMDENTON, MO 65020

Lab Number: 98-A898

Sample Number: 98-B385

RESULTS OF SAMPLE ANALYSES FOR PUBLIC WATER SUPPLIES

Report Date:

February 10, 1998

PWS ID:

MO3010130

Date Collected: February 2, 1998 Sample Location: BLAIR WELL, SPECIAL REQUEST

PWS Name:

Analysis Performed	Results	MCL	Units
VOC Results:	<del></del>		
Dichlorodifluoromethane	< 20.0		ug/L
Chloromethane	< 2.5	<b>-</b> -	ug/L
Vinyl Chloride	< 0.5	2.0	ug/L
Bromomethane	< 9.0	<b> </b>	ug/L
Chloroethane	< 2.5		ug/L
Trichlorofluoromethane	< 2.5		ug/L
1,1-Dichloroethene	< 0.5	7.0	ug/L
Methylene Chloride	< 0.5	5.0	ug/L
Methyl-tert-butyl ether	< 5.0	∦	ug/L
trans-1,2-Dichloroethene	< 0.5	100	ug/L
1,1-Dichloroethane	< 1.0		ug/L
2,2-Dichloropropane	< 1.0	<b> </b>	ug/L
cis-1,2-Dichloroethene	< 0.5	70.0	ug/L
Chloroform	< 0.5		ug/L
Bromochloromethane	< 1.0	_~	ug/L
l,1,1-Trichloroethane	< 0.5	200	ug/L
1,1-Dichloropropene	< 1.0	<b>∥</b>	ug/L
Carbon Tetrachloride	< 0.5	¶ 5.0	ug/L
Benzene	< 0.5	5.0	ug/L
1,2-Dichloroethane	< 0.5	5.0	ug/L
Trichloroethene	< 0.5	5.0	ug/L
1,2-Dichloropropane	< 0.5	5.0	ug/L
Bromodichloromethane	< 0.5		ug/L
Dibromomethane	< 1.0		ug/L
cis-1,3-Dichloropropane	< 2.0	<b> </b>	ug/L
Toluene	< 0.5	1000	ug/L
trans-1,3-Dichloropropane	< 1.0		ug/L
1,1,2-Trichloroethane	< 0.5	5.0	ug/L

'.Page: 2

Lab Number: 98-A898 Report Date: February 10, 1998 Sample Number: 98-B385

Analysis Performed	Results	мÇL	Units
Tetrachloroethene	< 0.5	5.0	ug/L
1,3-Dichloropropane	< 2.0		ug/L
Dibromochloromethane	< 0.5	·	ug/L
1,2-Dibromoethane	< 2.0		ug/L
Chlorobenzene	< 0.5	100	ug/L
Ethylbenzene	< 0.5	700	ug/L
1,1,1,2-Tetrachloroethane	< 1.0		ug/L
Total Xylenes	< 0.5	10000	ug/L
Styrene	< 0.5	100	ug/L
Isopropylbenzene	< 2.0	<b>-</b> -	ug/L
Bromoform	< 0.5	<u>-</u> -	ug/L
	< 1.0		ug/L
1,2,3-Trichloropropane	< 1.0		ug/l
n-Propylbenzene	< 2.0 < 1.0	₩	ug/L
Bromobenzene			ug/L
2-Chlorotoluene	< 2.0	<b></b>	ug/L
4-Chlorotoluene	< 2.0		ug/L
1,3,5-Trimethylbenzene	< 2.0	]	ug/L
tert-Butylbenzene	< 2.0	<b></b>	ug/L
1,2,4-Trimethylbenzene	< 1.0	1	ug/L
sec-Butylbenzene	< 2.0	]	ug/L
p-isopropyltoluene	< 2.0		ug/L
1,3-Dichlorobenzene	< 1.0	75.0	ug/L
1,4-Dichlorobenzene	< 0.5	75.0	ug/L
n-Butylbenzene	< 2.0	600	ug/L
1,2-Dichlorobenzene	< 0.5 < 5.0	600	ug/L
1,2-Dibromo-3-Chloroprop		70.0	ug/L
1,2,4-Trichlorobenzene Hexachlorobutadiene	< 1.0	70.0	ug/L
	< 20.0		ug/L
Naphthalene			ug/L
1,2,3-Trichlorobenzene	< 2.0		ug/L

MCL = Maximum Contaminant Level

-- = Not Applicable

The analysis of this sample was performed in accordance with procedures approved or recognized by the U.S. Environmental Protection Agency. If you have any questions, please contact Mr. Terry Timmons at 573/751-1188.

James H. Long, Derector

Environmental Services Program

Division of Environmental Quality

MARGINGS - CO - CONTRACTOR NATURAL MEDICALES

FED 23 1998

MAZINERUMS PROSES TRUGGRAM

W. 181 CH. 1914 C. 17. 50681W

אשלוט מצט שליוט אילוע אילוע

Date:

2/18/98

To:

Terry Timmons, PDWP

From:

Mary King, ESP

Subject: Samples with Results Greater than PDWP Monitoring Trigger

Sample MO ID Number	Supplyname Analyte	Results	MCL	Trigger
98-B383 MO3010130	CAMDENTON Trichloroethene	6.3 ug/L	5.0	0.5

1 1

#### STATE OF MISSOURI

### DEPARTMENT OF NATURAL RESOURCES

DIVISION OF ENVIRONMENTAL QUALITY —
 P.O. Box 176 Jefferson City, MO 65102-0176

Lab Number:

98-A3751

MO3010130

PWS County: CAMDEN

PWS ID:

#### ENVIRONMENTAL SERVICES PROGRAM

VINCENT COSTA 112 COURT CIRCLE, CITY HALL P.O. BOX 1048 CAMDENTON, MO 65020

Sample Number: 98-B786

RESULTS OF SAMPLE ANALYSES FOR PUBLIC WATER SUPPLIES

Report Date: March 31, 1998 Date Collected: March 25, 1998

Sample Location: BLAIR WELL PWS Name: CAMDENTON

Analysis Performed	Results	MCL	Units
VOC Results:			
Dichlorodifluoromethane	< 20.0	<b></b>	ug/L
Chloromethane	< 2.5	<b></b>	ug/L
Vinyl Chloride	< 0.5	2.0	ug/L
Bromomethane	< 9.0	<b> </b>	ug/L
Chloroethane	< 2.5	∦	ug/L
Trichlorofluoromethane	< 2.5	1	ug/L
1,1-Dichloroethene	< 0.5	7.0	ug/L
Methylene Chloride	< 0.5	5.0	ug/L
Methyl-tert-butyl ether	< 5.0	<u></u>	ug/L
trans-1,2-Dichloroethene	< 0.5	100	ug/L
1,1-Dichloroethane	< 1.0	<b></b>	ug/L
2,2-Dichloropropane	< 1.0	l	ug/L
cis-1,2-Dichloroethene	< 0.5	70.0	ug/L
Chloroform	< 0.5	<b> </b>	ug/L
Bromochloromethane	< 1.0	<b> </b>	ug/L
1,1,1-Trichloroethane	< 0.5	200	ug/L
1,1-Dichloropropene	< 1.0	1	ug/L
Carbon Tetrachloride	< 0.5	5.0	ug/L
Benzene	< 0.5	5.0	ug/L
1,2-Dichloroethane	< 0.5	5.0	ug/L
Trichioroethene	< 0.5	<b>§</b> 5.0	ug/L
1,2-Dichloropropane	< 0.5	∬ 5.0	ug/L
Bromodichloromethane	< 0.5	1	ug/L
Dibromomethane	< 1.0	<b></b>	ug/L
cis-1,3-Dichloropropane	< 2.0		ug/L
Toluene	< 0.5	1000	ug/L
trans-1,3-Dichloropropane	< 1.0		ug/L
1,1,2-Trichloroethane	< 0.5	5.0	ug/L

Page: 2 Lab Number: 98-A3751
Report Date: March 31, 1998 Sample Number: 98-B786

Analysis Performed	Results	MCL	Units
Tetrachloroethene	< 0.5	5.0	ug/L
1,3-Dichloropropane	< 2.0	<b>)</b>	ug/L
Dibromochloromethane	< 0.5	<b> </b>	ug/L
1,2-Dibromoethane	< 2.0		ug/L
Chlorobenzene	< 0.5	100	ug/L
Ethylbenzene	< 0.5	700	ug/L
1,1,1,2-Tetrachloroethane	< 1.0		ug/L
Total Xylenes	< 0.5	10000	ug/L
Styrene	< 0.5	∥ 100	ug/L
Isopropylbenzene	< 2.0		ug/L
Bromoform	< 0.5	1	ug/L
1,1,2,2-Tetrachloroethane	< 1.0	<u> </u>	ug/L
1,2,3-Trichloropropane		<b>  </b>	ug/l
n-Propylbenzene	< 2.0	<b> </b>	ug/L
Bromobenzene	< 1.0		ug/L
2-Chlorotoluene	< 2.0		ug/L
4-Chlorotoluene	< 2.0	<b></b>	ug/L
1,3,5-Trimethylbenzene	< 2.0	<b>∥</b>	ug/L
tert-Butylbenzene	< 2.0	l	ug/L
1,2,4-Trimethylbenzene	< 1.0	<b></b>	ug/L
sec-Butylbenzene	< 2.0	i	ug/L
p-isopropyltoluene	< 2.0	<b> </b>	ug/L
1,3-Dichlorobenzene	< 1.0	1	ug/L
1,4-Dichlorobenzene	< 0.5	75.0	ug/L
n-Butylbenzene	< 2.0		ug/L
1,2-Dichlorobenzene	< 0.5	600	ug/L
1,2-Dibromo-3-Chloroprop	< 5.0		ug/L
1,2,4-Trichlorobenzene	< 0.5	70.0	ug/L
Hexachlorobutadiene	< 1.0	<b></b>	ug/L
Naphthalene	< 20.0		ug/L
1,2,3-Trichlorobenzene	< 2.0	<b></b>	ug/L

MCL = Maximum Contaminant Level

-- = Not Applicable

The analysis of this sample was performed in accordance with procedures approved or recognized by the U.S. Environmental Protection Agency. If you have any questions, please contact Mr. Terry Timmons at 573/751-1188.

James H. Long, Derector

Environmental Services Program Division of Environmental Quality

MU + 0 2 1998

#### STATE OF MISSOURI

## DEPARTMENT OF NATURAL RESOURCES OF OF

---- DIVISION OF ENVIRONMENTAL OF METY P.O. Box 176 - Jefferson City MO 65102-0176

#### ENVIRONMENTAL SERVICES PROGRAM

VINCENT COSTA

Lab Number: 98-A4981

112 COURT CIRCLE, CITY HALL

P.O. BOX 1048

CAMDENTON, MO 65020

Sample Number: 98-F439

#### RESULTS OF SAMPLE ANALYSES FOR PUBLIC WATER SUPPLIES

PWS County: CAMDEN

Report Date: May 7, 1998
Date Collected: April 23, 1998

PWS ID: MO3010130

Sample Location: BLAIR STREET

PWS Name:

Analysis Performed	Results	MCL	Units
VOC Results:			
Dichlorodifluoromethane	< 20.0		ug/L
Chloromethane	< 2.5	<b> </b>	ug/L
Vinyl Chloride	< 0.5	2.0	ug/L
Bromomethane	< 9.0	∥	ug/L
Chloroethane	< 2.5		ug/L
Trichlorofluoromethane	< 2.5		ug/L
1,1-Dichloroethene	< 0.5	7.0	ug/L
Methylene Chloride	< 0.5	5.0	ug/L
Methyl-tert-butyl ether	< 5.0		ug/L
trans-1,2-Dichloroethene	< 0.5	100	ug/L
1,1-Dichloroethane	< 1.0		ug/L
2,2-Dichloropropane	< 1.0		ug/L
cis-1,2-Dichloroethene	< 0.5	70.0	ug/L
Chloroform	< 0.5	∦	ug/L
Bromochloromethane	< 1.0	<b> </b>	ug/L
1,1,1-Trichloroethane	< 0.5	200	ug/L
1,1-Dichloropropene	< 1.0	\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \	ug/L
Carbon Tetrachloride	< 0.5	5.0	ug/L
Benzene	< 0.5	5.0	ug/L
1,2-Dichloroethane	< 0.5	5.0	ug/L
Trichloroethene	< 0.5	5.0	ug/L
1,2-Dichloropropane	< 0.5	5.0	ug/L
Bromodichloromethane	< 0.5	<b>-</b> -	ug/L
Dibromomethane	< 1.0		ug/L
cis-1,3-Dichloropropane	< 2.0		ug/L
Toluene	< 0.5	1000	ug/L
trans-1,3-Dichloropropane	< 1.0		ug/L
1,1,2-Trichloroethane	< 0.5	5.0	ug/L

Page: 2 Lab Number: 98-A4981 Report Date: May 7, 1998 Sample Number: 98-F439

Analysis Performed	Results	MCL	Units
Tetrachloroethene	< 0.5	5.0	ug/L
1,3-Dichloropropane	< 2.0		ug/L
Dibromochloromethane	< 0.5	<b></b>	ug/L
1,2-Dibromoethane	< 2.0	1	ug/L
Chlorobenzene	< 0.5	∥ 100	ug/L
Ethylbenzene	< 0.5	<b>∥</b> 700	ug/L
1,1,1,2-Tetrachloroethane	< 1.0		ug/L
Total Xylenes	< 0.5	10000	ug/L
Styrene	< 0.5	∥ 100	ug/L
Isopropylbenzene	< 2.0		ug/L
Bromoform	< 0.5	i	ug/L
1,1,2,2-Tetrachloroethane	< 1.0	<b> </b>	ug/L
1,2,3-Trichloropropane	< 1.0	[	ug/l
n-Propylbenzene	< 2.0		ug/L
Bromobenzene	< 1.0	∥	ug/L
2-Chlorotoluene	< 2.0		ug/L
4-Chlorotoluene	< 2.0		ug/L
1,3,5-Trimethylbenzene	< 2.0		ug/L
tert-Butylbenzene	< 2.0		ug/L
1,2,4-Trimethylbenzene	< 1.0		ug/L
sec-Butylbenzene	< 2.0		ug/L
p-isopropyltoluene	< 2.0	<b> </b>	ug/L
1,3-Dichlorobenzene	< 1.0		ug/L
1,4-Dichlorobenzene	< 0.5	75.0	ug/L
n-Butylbenzene	< 2.0		ug/L
1,2-Dichlorobenzene	< 0.5	600	ug/L
1,2-Dibromo-3-Chloroprop	< 5.0		ug/L
1,2,4-Trichlorobenzene	< 0.5	70.0	ug/L
Hexachlorobutadiene	< 1.0		ug/L
Naphthalene	< 20.0		ug/L
1,2,3-Trichlorobenzene	< 2.0		ug/L

MCL = Maximum Contaminant Level

-- = Not Applicable

The analysis of this sample was performed in accordance with procedures approved or recognized by the U.S. Environmental Protection Agency. If you have any questions, please contact Mr. Terry Timmons at 573/751-1188.

James H. Long, Derector

Environmental Services Program Division of Environmental Quality

RECEIVED

MOV 0 2 1998

STATE OF MISSOURI

# DEPARTMENT OF NATURAL RESOURCES

- DIVISION OF ENVIRONMENTAL QUALITY -P.O. Box 176 Jefferson City. MO 65102-0176

#### ENVIRONMENTAL SERVICES PROGRAM

VINCENT COSTA

Lab Number: 98-A6300

112 COURT CIRCLE, CITY HALL

P.O. BOX 1048

CAMDENTON, MO 65020

Sample Number: 98-H070

QUARTERLY MONITORING

#### RESULTS OF SAMPLE ANALYSES FOR PUBLIC WATER SUPPLIES

Report Date:

June 8, 1998

Date Collected: May 21, 1998

PWS ID: MO3010130

Sample Location: BLAIR WELL PWS Name:

Analysis Performed	Results	MCL	Units
VOC Results:	<del> </del>		
Dichlorodifluoromethane	< 20.0		ug/L
Chloromethane	< 2.5	<b>∦</b>	ug/L
Vinyl Chloride	< 0.5	2.0	ug/L
Bromomethane	< 9.0		ug/L
Chloroethane	< 2.5		ug/L
Trichlorofluoromethane	< 2.5		ug/L
1,1-Dichloroethene	< 0.5	7.0	ug/L
Methylene Chloride	< 0.5	5.0	ug/L
Methyl-tert-butyl ether	< 5.0		ug/L
trans-1,2-Dichloroethene	< 0.5	100	ug/L
1,1-Dichloroethane	< 1.0		ug/L
2,2-Dichloropropane	< 1.0	<b></b>	ug/L
cis-1,2-Dichloroethene	< 0.5	70.0	ug/L
Chloroform	< 0.5		ug/L
Bromochloromethane	< 1.0		ug/L
1,1,1-Trichloroethane	< 0.5	200	ug/L
1,1-Dichloropropene	< 1.0	<b>\</b>	ug/L
Carbon Tetrachloride	< 0.5	5.0	ug/L
Benzene	< 0.5	5.0	ug/L
1,2-Dichloroethane	< 0.5	5.0	ug/L
Trichloroethene	< 0.5	5.0	ug/L
1,2-Dichloropropane	< 0.5	5.0	ug/L
Bromodichloromethane	< 0.5		ug/L
Dibromomethane	< 1.0		ug/L
cis-1,3-Dichloropropane	< 2.0		ug/L
Toluene	< 0.5	1000	ug/L

Page: 2 Lab Number: 98-A6300 Report Date: June 8, 1998 Sample Number: 98-H070

Analysis Performed	Results	MCL	Units
trans-1,3-Dichloropropane	< 1.0		ug/L
1,1,2-Trichloroethane	< 0.5	5.0	ug/L
Tetrachloroethene	< 0.5	5.0	ug/L
1,3-Dichloropropane	< 2.0	<b> </b>	ug/L
Dibromochloromethane	< 0.5	<b>∦</b>	ug/L
1,2-Dibromoethane	< 2.0	1	ug/L
Chlorobenzene	< 0.5	100	ug/L
Ethylbenzene	< 0.5	700	ug/L
1,1,1,2-Tetrachloroethane	< 1.0	1	ug/L
Total Xylenes	< 0.5	10000	ug/L
Styrene	< 0.5	100	ug/L
Isopropylbenzene	< 2.0	∥	ug/L
Bromoform	< 0.5	∥	ug/L
1,1,2,2-Tetrachloroethane	< 1.0	<b> </b>	ug/L
1,2,3-Trichloropropane	< 1.0	)	ug/l
n-Propylbenzene	< 2.0	<b>∥</b>	ug/L
Bromobenzene	< 1.0	(	ug/L
2-Chlorotoluene	< 2.0	<b>∥</b>	ug/L
4-Chlorotoluene	< 2.0	}	ug/L
1,3,5-Trimethylbenzene	< 2.0	<b> </b>	ug/L
tert-Butylbenzene	< 2.0	<b>∥</b> i	ug/L
1,2,4-Trimethylbenzene	< 1.0	<b> </b>	ug/L
sec-Butylbenzene	< 2.0	ii	ug/L
p-isopropyltoluene	< 2.0	<b>∦</b>	ug/L
1,3-Dichlorobenzene	< 1.0	∥	ug/L
1,4-Dichlorobenzene	< 0.5	75.0	ug/L
n-Butylbenzene	< 2.0		ug/L
1,2-Dichlorobenzene	< 0.5	600	ug/L
1,2-Dibromo-3-Chloroprop	< 5.0	<b></b>	ug/L
1,2,4-Trichlorobenzene	< 0.5	70.0	ug/L
	< 1.0		ug/L
Naphthalene	< 20.0		ug/L
1,2,3-Trichlorobenzene	< 2.0		ug/L

MCL = Maximum Contaminant Level

-- = Not Applicable

The analysis of this sample was performed in accordance with procedures approved or recognized by the U.S. Environmental Protection Agency. If you have any questions, please contact Mr. Terry Timmons at 573/751-1188.

James H. Long, Director Environmental Services Program Division of Environmental Quality

NOV 0 2 1998

STATE OF MISSOURI

# DEPARTMENT OF NATURAL RESOURCES TO THE OF MATURAL RESOURCES

P.O. Box 176 Jefferson City MO 65102-0176

#### ENVIRONMENTAL SERVICES PROGRAM

VINCENT COSTA 112 COURT CIRCLE, CITY HALL P.O. BOX 1048 CAMDENTON, MO 65020

Lab Number: 98-A6822

Sample Number: 98-F521

#### RESULTS OF SAMPLE ANALYSES FOR PUBLIC WATER SUPPLIES

Report Date: June 15, 1998 Date Collected: June 8, 1998

PWS County: CAMDEN PWS ID: MO3010130

Sample Location: BLAIR WELL PWS Name:

Analysis Performed	Results	MCL	Units
VOC Results:			
Dichlorodifluoromethane	< 20.0		ug/L
Chloromethane	< 2.5		ug/L
Vinyl Chloride	< 0.5	2.0	ug/L
Bromomethane	< 9.0		ug/L
Chloroethane	< 2.5		ug/L
Trichlorofluoromethane	< 2.5		ug/L
1,1-Dichloroethene	< 0.5	7.0	ug/L
Methylene Chloride	< 0.5	5.0	ug/L
Methyl-tert-butyl ether	< 5.0		ug/L
trans-1,2-Dichloroethene	< 0.5	100	ug/L
1,1-Dichloroethane	< 1.0		ug/L
2,2-Dichloropropane	< 1.0		ug/L
cis-1,2-Dichloroethene	< 0.5	70.0	ug/L
Chloroform	< 0.5	<b> </b>	ug/L
Bromochloromethane	< 1.0		ug/L
1,1,1-Trichloroethane	< 0.5	200	ug/L
1,1-Dichloropropene	< 1.0		ug/L
Carbon Tetrachloride	< 0.5	5.0	ug/L
Benzene	< 0.5	5.0	ug/L
1,2-Dichloroethane	< 0.5	5.0	ug/L
Trichloroethene	< 0.5	5.0	ug/L
1,2-Dichloropropane	< 0.5	5.0	ug/L
Bromodichloromethane	< 0.5	<u> </u>	ug/L
Dibromomethane	< 1.0	)	ug/L
cis-1,3-Dichloropropane	< 2.0	∥	ug/L
Toluene	< 0.5	1000	ug/L
trans-1,3-Dichloropropane	< 1.0		ug/L
1,1,2-Trichloroethane	< 0.5	5.0	ug/L

Page: 2 Lab Number: 98-A6822 Report Date: June 15, 1998 Sample Number: 98-F521

Analysis Performed	Results	MCL	Units
Tetrachloroethene	< 0.5	5.0	ug/L
1,3-Dichloropropane	< 2.0	ļ	ug/L
Dibromochloromethane	< 0.5		ug/L
1,2-Dibromoethane	< 2.0	<b></b>	ug/L
Chlorobenzene	< 0.5	100	ug/L
Ethylbenzene	< 0.5	700	ug/L
1,1,1,2-Tetrachloroethane	< 1.0	1	ug/L
Total Xylenes	< 0.5	10000	ug/L
Styrene	< 0.5	100	ug/L
Isopropylbenzene	< 2.0	]	ug/L
Bromoform	< 0.5	<b>∫</b>	ug/L
1,1,2,2-Tetrachloroethane	< 1.0	[	ug/L
1,2,3-Trichloropropane		<b> </b>	ug/l
n-Propylbenzene	< 2.0	<b></b>	ug/L
Bromobenzene	< 1.0	<b> </b>	ug/L
2-Chlorotoluene	< 2.0		ug/L
4-Chlorotoluene	< 2.0	<b></b>	ug/L
1,3,5-Trimethylbenzene	< 2.0	<b></b>	ug/L
tert-Butylbenzene	< 2.0	<b> </b>	ug/L
1,2,4-Trimethylbenzene	< 1.0		ug/L
sec-Butylbenzene	< 2.0		ug/L
p-isopropyltoluene	< 2.0		ug/L
1,3-Dichlorobenzene	< 1.0		ug/L
1,4-Dichlorobenzene	< 0.5	75.0	ug/L
n-Butylbenzene	< 2.0		ug/L
1,2-Dichlorobenzene	< 0.5	600	ug/L
1,2-Dibromo-3-Chloroprop			ug/L
	< 0.5	70.0	ug/L
Hexachlorobutadiene	< 1.0		ug/L
Naphthalene	< 20.0		ug/L
1,2,3-Trichlorobenzene	< 2.0	))	ug/L


MCL = Maximum Contaminant Level

-- = Not Applicable

The analysis of this sample was performed in accordance with procedures approved or recognized by the U.S. Environmental Protection Agency. If you have any questions, please contact Mr. Terry Timmons at 573/751-1188.

James H. Long, Director

Environmental Services Program Division of Environmental Quality



STATE OF MISSOURI

### DEPARTMENT OF NATURAL RESOURCES

-DIVISION OF ENVIRONMENTAL QUALITY "----P.O. Box 176 Jefferson Cirv. MO 65102-0176

Lab Number: 98-A14824

PWS ID: MO3010130

#### ENVIRONMENTAL SERVICES PROGRAM

VINCENT COSTA 112 COURT CIRCLE - CITY HALL P.O. BOX 1048 CAMDENTON, MO 65020

Sample Number: 98-U836

QUARTERLY MONITORING

RESULTS OF SAMPLE ANALYSES FOR PUBLIC WATER SUPPLIES

Report Date:

September 9, 1998

Date Collected: August 25, 1998

Sample Location: BLAIR WELL

PWS Name:

Analysis Performed	Results	MCL	Units
VOC Results:    Dichlorodifluoromethane    Chloromethane    Vinyl Chloride    Bromomethane    Chloroethane    Trichlorofluoromethane    1,1-Dichloroethene    Methylene Chloride    Methyl-tert-butyl ether    trans-1,2-Dichloroethene    1,1-Dichloroethane    2,2-Dichloropropane    cis-1,2-Dichloroethene    Chloroform    Bromochloromethane    1,1-Trichloroethane    1,1-Trichloroethane    1,1-Dichloropropene    Carbon Tetrachloride    Benzene    1,2-Dichloroethane    Trichloroethene    1,2-Dichloropropane    Bromodichloromethane	< 200	MCL  2.0 7.0 5.0 100 70.0 200 5.0 5.0 5.0 5.0	ug/L ug/L ug/L ug/L ug/L ug/L ug/L ug/L
Dibromomethane cis-1,3-Dichloropropane Toluene	< 1.0 < 2.0 < 1.0	  1000	ug/L ug/L ug/L

Page: 2 Lab Number: 98-A14824 Report Date: September 9, 1998 Sample Number: 98-U836

Analysis Performed	Results	MCL	Units
trans-1,3-Dichloropropane	< 1.0		ug/L
1,1,2-Trichloroethane	< 0.5	5.0	ug/L
Tetrachloroethene	< 0.5	5.0	ug/L
1,3-Dichloropropane	< 2.0		ug/L
Dibromochloromethane	< 0.5		ug/L
1,2-Dibromoethane	< 2.0		ug/L
Chlorobenzene	< 0.5	100	ug/L
Ethylbenzene	< 0.5	∥ 700	ug/L
1,1,1,2-Tetrachloroethane	< 1.0	ļ i	ug/L
Total Xylenes	< 0.5	10000	ug/L
Styrene	< 0.5	100	ug/L
Isopropylbenzene	< 2.0	<b>∥</b> '	ug/L
Bromoform	< 0.5	[	ug/L
1,1,2,2-Tetrachloroethane	< 1.0		ug/L
1,2,3-Trichloropropane	< 1.0		ug/l
n-Propylbenzene	< 2.0	<b>}</b>	ug/L
Bromobenzene	< 1.0		ug/L
2-Chlorotoluene	< 2.0		ug/L
4-Chlorotoluene	< 2.0		ug/L
1,3,5-Trimethylbenzene	< 2.0		ug/L
tert-Butylbenzene	< 2.0		ug/L
1,2,4-Trimethylbenzene	< 1.0	∥ –– l	ug/L
sec-Butylbenzene	< 2.0		ug/L
p-isopropyltoluene	< 2.0	<b>∥</b> ––	ug/L
1,3-Dichlorobenzene	< 1.0		ug/L
1,4-Dichlorobenzene	< 0.5	75.0	ug/L
n-Butylbenzene	< 2.0		ug/L
1,2-Dichlorobenzene	< 0.5	600	ug/L
1,2-Dibromo-3-Chloroprop	< 5.0	1	ug/L
	< 0.5	70.0	ug/L
Hexachlorobutadiene	< 1.0		ug/L
Naphthalene	< 20.0		ug/L
1,2,3-Trichlorobenzene	< 2.0		ug/L

MCL = Maximum Contaminant Level

-- = Not Applicable

The analysis of this sample was performed in accordance with procedures approved or recognized by the U.S. Environmental Protection Agency. If you have any questions, please contact Mr. Terry Timmons at 573/751-1188.

James H. Long, Director Environmental Services Program

Division of Environmental Quality

### **STATE OF MISSOURI**

Mel Camahan, Governor • David A. Shorr, Director

### DEPARTMENT OF NATURAL RESOURCES

- DIVISION OF ENVIRONMENTAL QUALITY -P.O. Box 176 Jefferson City, MO 65102-0176

#### ENVIRONMENTAL SERVICES PROGRAM RESULT OF SAMPLE ANALYSIS

Sample No. 94-C601

Reported to: TERRY TIMMONS Affiliation: PDW

Date: 5/13/ 1

Project Code: 3404/300)

Sample Description:

CAMDENTON, RODEO WELL

MO3010130

Collected by: BOB MARSHALL

Affiliation: MISC

Date: 04/27/94

### **PARAMETERS**

#### RESULTS

VOC Results:	
Benzene	<0.5 ug/L
Bromobenzene	< 1.0~ ug/L
Bromochloromethane	<1.0 ug/L
Bromodichloromethane	<1.0 ug/L
Bromoform	<2.5 ug/L
Bromomethane	<2.5 ug/L
n-Butylbenzene	<2.0 ug/L
sec-Butylbenzene	<2.0 ug/L
tert-Butylbenzene	<2.0 ug/L
Carbon tetrachloride	< 0.5  ug/L
Chlorobenzene	< 0.5  ug/L
Chloroethane	<2.5 ug/L
Chloroform	<1.0 ug/L
Chloromethane	<2.5 ug/L
2-Chlorotoluene	<2.0 ug/L
4-Chlorotoluene	<2.0 ug/L
Dibromochloromethane	<1.0 ug/L
1,2-Dibromo-3-chloropropane	<5 0 ug/L
1,2-Dibromoethane	<2.0 ug/L
Dibromomethane	<1.0 ug/L

## DEPARTMENT OF NATURAL RESOURCES

— DIVISION OF ENVIRONMENTAL QUALITY – PO Box 176 Jefferson City, MO 65102-0176

Page 2 Sample no. 94-C601 Date 5/13/94

PARAMETERS		RESULTS
1,2-Dichlorobenzene	<0.5	ug/L
1,3-Dichlorobenzene	<1.0	ug/L
1,4-Dichlorobenzene	<0.5	ug/L
Dichlorodifluoromethane	<2.5	ug/L
1,1-Dichloroethane	<1.0	ug/L
1,2-Dichloroethane	<0.5	ug/L
1,1-Dichloroethene		ug/L
cis-1,2-Dichloroethene	<0.5	ug/L
trans-1,2-Dichloroethene	<0.5	ug/L
1,2-Dichloropropane	<0.5	ug/L
1,3-Dichloropropane		ug/L
2,2-Dichloropropane	<1.0	ug/L
1,1-Dichloropropene	<1.0	ug/L
cis-1,3-Dichloropropene	<2.0	ug/L
trans-1,3-Dichloropropene		ug/L
Ethylbenzene	<0.5	ug/L
Hexachlorobutadiene	<1.0	ug/L
Isopropylbenzene	<2.0	ug/L
p-Isopropyltoluene	<2.0	ug/L
Methylene Chloride	<0.5	
Naphthalene	<2.0	ug/L
n-Propylbenzene	<2.0	ug/L
Styrene	<0.5	ug/L
1,1,1,2-Tetrachloroethane	<1.0	ug/L
1,1,2,2-Tetrachloroethane	<1.0	ug/L
Tetrachloroethene	<0.5	ug/L
Toluene	<0.5	ug/L
1,2,3-Trichlorobenzene		ug/L
1,2,4-Trichlorobenzene		ug/L
l, l, l-Trichloroethane	<0.5	

### EPARTMENT OF NATURAL RESOURCES

— DIVISION OF ENVIRONMENTAL QUALITY — ———— P.O Box 176 Jefferson City, MO 65102-0176

Page 3 Sample no. 94-C601 Date 5/13/94

PARAMETERS		RESULTS
1,1,2-Trichloroethane Trichloroethene Trichlorofluoromethane 1,2,3-Trichloropropane 1,2,4-Trimethylbenzene 1,3,5-Trimethylbenzene	<0.5 <0.5 <2.5 <1.0 <1.0 <2.0	ug/L ug/L ug/L ug/L
Vinyl Chloride	<0.5	ug/L
o-Xylene m&p-xylene	<0.5 <0.5	_

The analysis of this sample was performed in accordance with procedures approved or recognized by the U.S. Environmental Protection Agency.

James H. Long, Director Environmental Services Program Division of Environmental Quality

### DEPARTMENT OF NATURAL RESOURCES

 DIVISION OF ENVIRONMENTAL QUALITY — P.O. Box 176 Jefferson City, MO 65102-0176

#### ENVIRONMENTAL SERVICES PROGRAM

BOB MARSHALL CITY HALL

P.O. BOX 1048

CAMDENTON, MO 65020

Lab Number:

97-A760

Sample Number: 97-A468

#### RESULTS OF SAMPLE ANALYSES FOR PUBLIC WATER SUPPLIES

Report Date: February 24, 1997 Date Collected: January 29, 1997

PWS County: CAMDEN PWS ID: MO3010130

Sample Location: RODEO WELL HOUSE

PWS Name:

Analysis Performed	Results	MCL	Units
VOC Results:			
Dichlorodifluoromethane	< 20.0		ug/L
Chloromethane	< 2.5	l	ug/L
Vinyl Chloride	< 0.5	2.0	ug/L
Bromomethane	< 9.0	∦	ug/L
Chloroethane	< 2.5		ug/L
Trichlorofluoromethane	< 2.5		ug/L
1,1-Dichloroethene	< 0.5	7.0	ug/L
Methylene Chloride	< 0.5	5.0	ug/L
Methyl-tert-butyl ether	< 5.0		ug/L
trans-1,2-Dichloroethene	< 0.5	100	ug/L
1,1-Dichloroethane	< 1.0	<u> </u>	ug/L
2,2-Dichloropropane	< 1.0	<b> </b>	ug/L
cis-1,2-Dichloroethene	< 0.5	70.0	ug/L
Chloroform	< 0.5	<u> </u>	ug/L
Bromochloromethane	< 1.0	<b>∥</b>	ug/L
1,1,1-Trichloroethane	< 0.5	200	ug/L
1,1-Dichloropropene	< 1.0		ug/L
Carbon Tetrachloride	< 0.5	5.0	ug/L
Benzene	< 0.5	∬ 5.0	ug/L
1,2-Dichloroethane	< 0.5	∯ 5.0	ug/L
Trichloroethene	3.9	5.0	ug/L
1,2-Dichloropropane	< 0.5	∫ 5.0	ug/L
Bromodichloromethane	< 0.5	<b> </b>	ug/L
Dibromomethane	< 1.0		ug/L
cis-1,3-Dichloropropane	< 2.0	<b> </b>	ug/L
Toluene	< 0.5	1000	ug/L
trans-1,3-Dichloropropane	< 1.0		ug/L
1,1,2-Trichloroethane	< 0.5	5.0	ug/L

Page: 2 Lab Number: 97-A760 Sample Number: 97-A468 Report Date: February 24, 1997

Analysis Performed	Results	MCL	Units
Tetrachloroethene	< 0.5	5.0	ug/L
1,3-Dichloropropane	< 2.0	<b> </b>	ug/L
Dibromochloromethane	< 0.5		ug/L
1,2-Dibromoethane	< 2.0	<u> </u>	ug/L
Chlorobenzene	< 0.5	100	ug/L
Ethylbenzene	< 0.5	700	ug/L
1,1,1,2-Tetrachloroethane	< 1.0		ug/L
Total Xylenes	< 0.5	10000	ug/L
Styrene	< 0.5	100	ug/L
Isopropylbenzene	< 2.0		ug/L
Bromoform	< 0.5		ug/L
-,-, ,	< 1.0		ug/L
1,2,3-Trichloropropane	< 1.0	<b>—</b>	ug/l
n-Propylbenzene	< 2.0	<b> </b>	ug/L
Bromobenzene	< 1.0	<b></b>	ug/L
2-Chlorotoluene	< 2.0		ug/L
4-Chlorotoluene	< 2.0		ug/L
1,3,5-Trimethylbenzene	< 2.0		ug/L
tert-Butylbenzene	< 2.0		ug/L
1,2,4-Trimethylbenzene	< 1.0		ug/L
sec-Butylbenzene	< 2.0		ug/L
p-isopropyltoluene	< 2.0		ug/L
1,3-Dichlorobenzene	< 1.0		ug/L
1,4-Dichlorobenzene	< 0.5	75.0	ug/L
n-Butylbenzene	< 2.0		ug/L
1,2-Dichlorobenzene	< 0.5	600	ug/L
1,2-Dibromo-3-Chlorobenz	< 5.0		ug/L
1,2,4-Trichlorobenzene	< 0.5	70.0	ug/L
Hexachlorobutadiene	< 1.0		ug/L
Naphthalene	< 2.0		ug/L
1,2,3-Trichlorobenzene	< 2.0		ug/L

MCL = Maximum Contaminant Level

-- = Not Applicable

The analysis of this sample was performed in accordance with procedures approved or recognized by the U.S. Environmental Protection Agency. If you have any questions, please contact Mr. Terry Timmons at 573/751-1188.

James H. Long, Director Environmental Services Program

Division of Environmental Quality

### DEPARTMENT OF NATURAL RESOURCES

 DIVISION OF ENVIRONMENTAL QUALITY = P.O. Box 176 Jefferson City, MO 65102-0176

Report Date:

Date Collected:

3/17/97

3/12/97

3/12/97

#### ENVIRONMENTAL SERVICES PROGRAM

#### RESULTS OF SAMPLE ANALYSES FOR PUBLIC WATER SUPPLIES

Sample Number: 97-0487 Lab Number: 97-A2243

Reported To: JIM HOULIHAN

Affiliation: JCRO Project Code: 3404/3000

Date Received:

Sample Collected by:

PWS Supply Name: PWS Identification:

PWS County: Sampling Location:

Sample Description:

JIM HOULIHAN, JCRO CAMDENTON

MO3010130 CAMDEN

RODEO WELL CONFIRMATION SAMPLE

Page: 2 Lab Number: 97-A2243 Report Date: March 17, 1997 Sample Number: 97-0487

Analysis Performed	Results	MCL	Units
cis-1,3-Dichloropropane	< 2.0		ug/L
Toluene	< 0.5	1000	ug/L
trans-1,3-Dichloropropane		<b></b>	ug/L
1,1,2-Trichloroethane	< 0.5	∬ 5.0	ug/L
Tetrachloroethene	< 0.5	5.0	ug/L
1,3-Dichloropropane	< 2.0	<b> </b>	ug/L
Dibromochloromethane	< 0.5	₩	ug/L
1,2-Dibromoethane	< 2.0	)) ——	ug/L
Chlorobenzene	< 0.5	∥ 100	ug/L
Ethylbenzene	< 0.5	700	ug/L
1,1,1,2-Tetrachloroethane	< 1.0	∦	ug/L
Total Xylenes	< 0.5	10000	ug/L
Styrene	< 0.5	∬ 100	ug/L
Isopropylbenzene	< 2.0	₩	ug/L
Bromoform	< 0.5	<b>∦</b> ~−	ug/L
1,1,2,2-Tetrachloroethane	< 1.0	₩	ug/L
1,2,3-Trichloropropane	< 1.0	<b>)</b>	ug/l
n-Propylbenzene	< 2.0	<b> </b>	ug/L
Bromobenzene	< 1.0	<b>∥</b>	ug/L
2-Chlorotoluene	< 2.0	₩	ug/L
4-Chlorotoluene	< 2.0	}	ug/L
1,3,5-Trimethylbenzene	< 2.0	₩	ug/L
tert-Butylbenzene	< 2.0	<b>  </b>	ug/L
1,2,4-Trimethylbenzene	< 1.0	∦	ug/L
sec-Butylbenzene	< 2.0	<del></del>	ug/L
p-isopropyltoluene	< 2.0		ug/L
1,3-Dichlorobenzene	< 1.0	ll	ug/L
1,4-Dichlorobenzene	< 0.5	75.0	ug/L
n-Butylbenzene	< 2.0		ug/L
1,2-Dichlorobenzene	< 0.5	600	ug/L
1,2-Dibromo-3-Chlorobenz	< 5.0	<b> </b>	ug/L
1,2,4-Trichlorobenzene	< 0.5	70.0	ug/L
Hexachlorobutadiene	< 1.0	<b></b>	ug/L
Naphthalene	< 2.0	<b></b>	ug/L
1,2,3-Trichlorobenzene	< 2.0		ug/L


MCL = Maximum Contaminant Level

-- = Not Applicable

The analysis of this sample was performed in accordance with procedures approved or recognized by the U.S. Environmental Protection Agency. If you have any questions, please contact Mr. Terry Timmons at 573/751-1188.

James H. Long Director Environmental Services Program Division of Environmental Quality

c: TERRY TIMMONS, PDWP



FFB 23 1998

STATE OF MISSOURI

Mel can dem Concernor & Stephen M. Mahlood, Directory

## DEPARTMENT OF NATURAL RESOURCES OF PROGRAM OF THE P

─ DIVISION OF ENVIRONMENTAL QUALIFY UTVAL HEUDURCES P.O. Box 176 Jefferson City, MO 65102-0176

#### ENVIRONMENTAL SERVICES PROGRAM

VINCENT COSTA 112 COURT CIRCLE, CITY HALL P.O. BOX 1048 65020 CAMDENTON, MO

Lab Number: 98-A897

Sample Number: 98-B384

#### RESULTS OF SAMPLE ANALYSES FOR PUBLIC WATER SUPPLIES

Report Date:

PWS Name:

February 10, 1998

Date Collected:

February 2, 1998

PWS ID: MO3010130

Sample Location: RODEO WELL, SPECIAL REQUEST

CAMDENTON

Units Analysis Performed Results MCL VOC Results: Dichlorodifluoromethane < 20.0 ug/L Chloromethane < 2.5 ug/L Vinyl Chloride < 0.5 2.0 uq/L ug/L Bromomethane < 9.0 ug/L Chloroethane < 2.5 Trichlorofluoromethane < 2.5 ug/L 1,1-Dichloroethene < 0.5 7.0 uq/L Methylene Chloride < 0.5 5.0 ug/L Methylene Chloride Methyl-tert-butyl ether trans-1,2-Dichloroethene < 5.0 ug/L < 0.5 ug/L 100 1,1-Dichloroethane < 1.0 \_\_\_ ug/L 2,2-Dichloropropane ug/L < 1.0 \_\_\_ cis-1,2-Dichloroethene < 0.5 70.0 ug/L Chloroform < 0.5 ug/L Bromochloromethane < 1.0 \_\_\_ ug/L 1,1,1-Trichloroethane < 0.5 ug/L 200 1,1-Dichloropropene < 1.0 ug/L Carbon Tetrachloride < 0.5 5.0 ug/L Benzene < 0.5 5.0 ug/L 1,2-Dichloroethane < 0.5 5.0 uq/L Trichloroethene < 0.5 5.0 ug/L 1,2-Dichloropropane Bromodichloromethane < 0.5 5.0 ug/L < 0.5 ug/L Dibromomethane < 1.0 ug/L cis-1,3-Dichloropropane < 2.0 ug/L Toluene < 0.5 1000 uq/L trans-1,3-Dichloropropane < 1.0 1,1,2-Trichloroethane < 0.5 ug/L 5.0 ug/L

Page: 2
Report Date: February 10, 1998

Lab Number: 98-A897 Sample Number: 98-B384

Analysis Performed	Results	MCL	Units
Tetrachloroethene	< 0.5	5.0	ug/L
1,3-Dichloropropane	< 2.0	<b> </b>	ug/L
	< 0.5		ug/L
1,2-Dibromoethane	< 2.0		ug/L
Chlorobenzene	< 0.5	100	ug/L
Ethylbenzene	< 0.5	700	ug/L
1,1,1,2-Tetrachloroethane	< 1.0		ug/L
Total Xylenes	< 0.5	10000	ug/L
Styrene	< 0.5	100	ug/L
Isopropylbenzene	< 2.0		ug/L
Bromoform	< 0.5	<b>"</b>	ug/L
, ,	< 1.0	_ <del>_</del>	ug/L
1,2,3-Trichloropropane	< 1.0		ug/l
n-Propylbenzene	< 2.0		ug/L
Bromobenzene	< 1.0	<del></del>	ug/L
2-Chlorotoluene	< 2.0		ug/L
4-Chlorotoluene	< 2.0	<b>—</b>	ug/L
1,3,5-Trimethylbenzene	< 2.0		ug/L
tert-Butylbenzene	< 2.0		ug/L
1,2,4-Trimethylbenzene	< 1.0	<b> </b>	ug/L
sec-Butylbenzene	< 2.0		ug/L
p-isopropyltoluene	< 2.0		ug/L
1,3-Dichlorobenzene	< 1.0		ug/L
1,4-Dichlorobenzene	< 0.5	75.0	ug/L
n-Butylbenzene	< 2.0		ug/L
1,2-Dichlorobenzene	< 0.5	600	ug/L
1,2-Dibromo-3-Chloroprop	< 5.0		ug/L
1,2,4-Trichlorobenzene	< 0.5	70.0	ug/L
Hexachlorobutadiene	< 1.0		ug/L
Naphthalene	< 20.0		ug/L
1,2,3-Trichlorobenzene	< 2.0		ug/L

MCL = Maximum Contaminant Level

-- = Not Applicable

The analysis of this sample was performed in accordance with procedures approved or recognized by the U.S. Environmental Protection Agency. If you have any questions, please contact Mr. Terry Timmons at 573/751-1188.

James H. Long, D(rector

Environmental Services Program

Division of Environmental Quality

1993 1993

MODELLE CONTRACTOR STANDARD

RECEIVED

MOV 0 2 1998

STATE OF MISSOURI

## DEPARTMENT OF NATURAL RESOURCES

– DIVISION OF ENVIRONMENTAL QUALITY (\*\*\* P.O. Box 176 Tefferson City MO 65102-0176

#### ENVIRONMENTAL SERVICES PROGRAM

VINCENT COSTA

Lab Number: 98-A4983

112 COURT CIRCLE, CITY HALL

P.O. BOX 1048

CAMDENTON, MO 65020

Sample Number: 98-F441

#### RESULTS OF SAMPLE ANALYSES FOR PUBLIC WATER SUPPLIES

PWS County: CAMDEN

Report Date: May 7, 1998
Date Collected: April 23, 1998

PWS ID: MO3010130

Sample Location: RODEO WELL PWS Name:

Analysis Performed	Results	MCL	Units
VOC Results:			
Dichlorodifluoromethane	< 20.0		ug/L
Chloromethane	< 2.5	<b>∥</b> ––	ug/L
Vinyl Chloride	< 0.5	2.0	ug/L
Bromomethane	< 9.0		ug/L
Chloroethane	< 2.5		ug/L
Trichlorofluoromethane	< 2.5		ug/L
1,1-Dichloroethene	< 0.5	7.0	ug/L
Methylene Chloride	< 0.5	5.0	ug/L
Methyl-tert-butyl ether	< 5.0		ug/L
trans-1,2-Dichloroethene	< 0.5	100	ug/L
1,1-Dichloroethane	< 1.0	<b> </b>	ug/L
2,2-Dichloropropane	< 1.0	l	ug/L
cis-1,2-Dichloroethene		70.0	ug/L
Chloroform	< 0.5	∥	ug/L
Bromochloromethane	< 1.0		ug/L
1,1,1-Trichloroethane	< 0.5	200	ug/L
1,1-Dichloropropene	< 1.0		ug/L
Carbon Tetrachloride	< 0.5	5.0	ug/L
Benzene	< 0.5	5.0	ug/L
1,2-Dichloroethane	< 0.5	5.0	ug/L
Trichloroethene	< 0.5	5.0	ug/L
1,2-Dichloropropane	< 0.5	5.0	ug/L
Bromodichloromethane	< 0.5		ug/L
Dibromomethane	< 1.0	)	ug/L
cis-1,3-Dichloropropane	< 2.0		ug/L
Toluene	< 0.5	1000	ug/L
trans-1,3-Dichloropropane	< 1.0		ug/L
1,1,2-Trichloroethane	< 0.5	5.0	ug/L

Page: 2 Report Date: May 7, 1998 Lab Number: 98-A4983 Sample Number: 98-F441

Analysis Performed	Results	MCL	Units
Tetrachloroethene	< 0.5	5.0	ug/L
1,3-Dichloropropane	< 2.0		ug/L
Dibromochloromethane	< 0.5	<b>-</b> -	ug/L
1,2-Dibromoethane	< 2.0	<b> </b>	ug/L
Chlorobenzene	< 0.5	100	ug/L
Ethylbenzene	< 0.5	700	ug/L
1,1,1,2-Tetrachloroethane	< 1.0	<b>!</b>	ug/L
Total Xylenes	< 0.5	10000	ug/L
Styrene	< 0.5	100	ug/L
Isopropylbenzene	< 2.0	∦	ug/L
Bromoform	< 0.5	<b> </b>	ug/L
-,-,-,-	< 1.0		ug/L
1,2,3-Trichloropropane	< 1.0		ug/l
n-Propylbenzene	< 2.0	<u> </u>	ug/L
Bromobenzene	< 1.0		ug/L
2-Chlorotoluene	< 2.0	I	ug/L
4-Chlorotoluene	< 2.0	<b> </b>	ug/L
1,3,5-Trimethylbenzene	< 2.0	<b>.</b>	ug/L
tert-Butylbenzene	< 2.0	<b></b>	ug/L
1,2,4-Trimethylbenzene	< 1.0	<del></del>	ug/L
sec-Butylbenzene	< 2.0	1	ug/L
p-isopropyltoluene	< 2.0	<b> </b>	ug/L
1,3-Dichlorobenzene	< 1.0	<del></del>	ug/L
1,4-Dichlorobenzene	< 0.5	75.0	ug/L
n-Butylbenzene	< 2.0		ug/L
1,2-Dichlorobenzene	< 0.5	600	ug/L
1,2-Dibromo-3-Chloroprop	< 5.0	<del></del>	ug/L
1,2,4-Trichlorobenzene	< 0.5	70.0	ug/L
Hexachlorobutadiene	< 1.0		ug/L
Naphthalene	< 20.0		ug/L
1,2,3-Trichlorobenzene	< 2.0	<b> </b>	ug/L


MCL = Maximum Contaminant Level

-- = Not Applicable


The analysis of this sample was performed in accordance with procedures approved or recognized by the U.S. Environmental Protection Agency. If you have any questions, please contact Mr. Terry Timmons at 573/751-1188.

James H. Long, Director Environmental Services Program

Division of Environmental Quality



STATE OF MISSOURI Mel Canadian Concerns - Stephen M. Wildling Director



### DEPARTMENT OF NATURAL RESOURCES

--- DIVISION OF ENVIRONMENTAL QUALITY P.O. Box 176 Jefferson City, MO 65102-0176

#### ENVIRONMENTAL SERVICES PROGRAM

VINCENT COSTA 112 COURT CIRCLE, CITY HALL P.O. BOX 1048 CAMDENTON, MO 65020

Lab Number: 98-A6301

PWS ID: MO3010130

Sample Number: 98-H071

QUARTERLY MONITORING

#### RESULTS OF SAMPLE ANALYSES FOR PUBLIC WATER SUPPLIES

Report Date:

June 8, 1998

Date Collected: May 21, 1998

Sample Location: RODEO WELL

PWS Name:

Analysis Performed	Results	MCL	Units
VOC Results:			
Dichlorodifluoromethane	< 20.0		ug/L
Chloromethane	< 2.5	<b>-</b> -	ug/L
Vinyl Chloride	< 0.5	2.0	ug/L
Bromomethane	< 9.0		ug/L
Chloroethane	< 2.5		ug/L
Trichlorofluoromethane	< 2.5	<b></b>	ug/L
1,1-Dichloroethene	< 0.5	7.0	ug/L
Methylene Chloride	< 0.5	5.0	ug/L
Methyl-tert-butyl ether	< 5.0		ug/L
trans-1,2-Dichloroethene	< 0.5	100	ug/L
1,1-Dichloroethane	< 1.0	<b></b>	ug/L
2,2-Dichloropropane	< 1.0		ug/L
cis-1,2-Dichloroethene	< 0.5	70.0	ug/L
Chloroform	< 0.5		ug/L
Bromochloromethane	< 1.0	<del>-</del>	ug/L
1,1,1-Trichloroethane	< 0.5	200	ug/L
1,1-Dichloropropene	< 1.0		ug/L
Carbon Tetrachloride	< 0.5	5.0	ug/L
Benzene	< 0.5	5.0	ug/L
1,2-Dichloroethane	< 0.5	5.0	ug/L
Trichloroethene	< 0.5	5.0	ug/L
1,2-Dichloropropane	< 0.5	5.0	ug/L
Bromodichloromethane	< 0.5		ug/L
Dibromomethane	< 1.0		ug/L
cis-1,3-Dichloropropane	< 2.0		ug/L
Toluene	< 0.5	1000	ug/L

Page: 2 Report Date: June 8, 1998 Lab Number: 98-A6301 Sample Number: 98-H071

Analysis Performed	Results	MCL	Units
trans-1,3-Dichloropropane	< 1:0		ug/L
1,1,2-Trichloroethane	< 0.5	5.0	ug/L
Tetrachloroethene	< 0.5	5.0	ug/L
1,3-Dichloropropane	< 2.0		ug/L
Dibromochloromethane	< 0.5		ug/L
1,2-Dibromoethane	< 2.0		ug/L
Chlorobenzene	< 0.5	100	ug/L
Ethylbenzene	< 0.5	700	ug/L
	< 1.0	\	ug/L
Total Xylenes	< 0.5	10000	ug/L
Styrene	< 0.5	100	ug/L
Isopropylbenzene	< 2.0	<b> </b>	ug/L
Bromoform	< 0.5		ug/L
1,1,2,2-Tetrachloroethane	< 1.0		ug/L
1,2,3-Trichloropropane	< 1.0	<b>1</b>	ug/l
n-Propylbenzene	< 2.0	<b>∥</b> −−	ug/L
Bromobenzene	< 1.0	∦	ug/L
2-Chlorotoluene	< 2.0	)	ug/L
4-Chlorotoluene	< 2.0	₩	ug/L
1,3,5-Trimethylbenzene	< 2.0		ug/L
tert-Butylbenzene	< 2.0	1	ug/L
1,2,4-Trimethylbenzene	< 1.0	∦	ug/L
sec-Butylbenzene	< 2.0	<b> </b>	ug/L
p-isopropyltoluene	< 2.0	<b>-</b> -	ug/L
1,3-Dichlorobenzene	< 1.0	1	ug/L
1,4-Dichlorobenzene	< 0.5	75.0	ug/L
n-Butylbenzene	< 2.0		ug/L
1,2-Dichlorobenzene	< 0.5	600	ug/L
	< 5.0	<b>_</b>	ug/L
1,2,4-Trichlorobenzene	< 5.0 < 0.5 < 1.0	70.0	ug/L
Hexachlorobutadiene	< 1.0		ug/L
Naphthalene	< 20.0	<b></b> _	ug/L
1,2,3-Trichlorobenzene	< 2.0		ug/L

MCL = Maximum Contaminant Level

-- = Not Applicable

The analysis of this sample was performed in accordance with procedures approved or recognized by the U.S. Environmental Protection Agency. If you have any questions, please contact Mr. Terry Timmons at 573/751-1188.

James H. Long, Director Environmental Services Program Division of Environmental Quality

MOV 0 2 1998

-1513/11. MAR

STATE OF MISSOURI

## DEPARTMENT OF NATURAL RESOURCES

- DIVISION OF ENVIRONMENTAL QUALITY -P.O. Box 176 Tellerson City, MO 65102-0176

#### ENVIRONMENTAL SERVICES PROGRAM

VINCENT COSTA

Lab Number: 98-A6821

112 COURT CIRCLE, CITY HALL

P.O. BOX 1048

CAMDENTON, MO 65020

Sample Number: 98-F520

#### RESULTS OF SAMPLE ANALYSES FOR PUBLIC WATER SUPPLIES

PWS County: CAMDEN

Report Date: June 15, 1998 Date Collected: June 8, 1998 Sample Location: RODEO WELL

PWS ID: MO3010130

PWS Name:

Analysis Performed	Results	MCL	Units
VOC Results:			
Dichlorodifluoromethane	< 20.0		ug/L
Chloromethane	< 2.5		ug/L
Vinyl Chloride	< 0.5	2.0	ug/L
Bromomethane	< 9.0		ug/L
Chloroethane	< 2.5	<b>}</b>	ug/L
Trichlorofluoromethane	< 2.5		ug/L
1,1-Dichloroethene	< 0.5	7.0	ug/L
Methylene Chloride		5.0	ug/L
Methyl-tert-butyl ether	< 5.0		ug/L
trans-1,2-Dichloroethene	< 0.5	100	ug/L
1,1-Dichloroethane	< 1.0	∥	ug/L
2,2-Dichloropropane	< 1.0	<b> </b>	ug/L
cis-1,2-Dichloroethene	< 0.5	70.0	ug/L
Chloroform	< 0.5	∦ '	ug/L
Bromochloromethane	< 1.0	∥	ug/L
1,1,1-Trichloroethane	< 0.5	200	ug/L
1,1-Dichloropropene	< 1.0		ug/L
Carbon Tetrachloride	< 0.5	5.0	ug/L
Benzene	< 0.5	5.0	ug/L
1,2-Dichloroethane	< 0.5	5.0	ug/L
Trichloroethene	< 0.5	5.0	ug/L
1,2-Dichloropropane	< 0.5	5.0`	ug/L
Bromodichloromethane	< 0.5		ug/L
Dibromomethane	< 1.0		ug/L
cis-1,3-Dichloropropane	< 2.0		ug/L
Toluene	< 0.5	1000	ug/L
trans-1,3-Dichloropropane	< 1.0	<b></b>	ug/L
1,1,2-Trichloroethane	< 0.5	5.0	ug/L

Page: 2 Lab Number: 98-A6821 Report Date: June 15, 1998 Sample Number: 98-F520

Analysis Performed	Results	MCL	Units
Tetrachloroethene	< 0.5	5.0	ug/L
1,3-Dichloropropane	< 2.0		ug/L
Dibromochloromethane	< 0.5	<b> </b>	ug/L
1,2-Dibromoethane	< 2.0	<b>  </b>	ug/L
Chlorobenzene	< 0.5	100	ug/L
Ethylbenzene	< 0.5	∥ 700	ug/L
1,1,1,2-Tetrachloroethane	< 1.0	<b> </b>	ug/L
Total Xylenes	< 0.5	∥ 10000	ug/L
Styrene	< 0.5	∥ 100	ug/L
Isopropylbenzene	< 2.0	í	ug/L
Bromoform	< 0.5	<del></del>	ug/L
1,1,2,2-Tetrachloroethane	< 1.0	)	ug/L
1,2,3-Trichloropropane	< 1.0	//	ug/l
n-Propylbenzene	< 2.0	<b>∥</b>	ug/L
Bromobenzene	< 1.0	[	ug/L
2-Chlorotoluene	< 2.0		ug/L
4-Chlorotoluene	< 2.0	<b> </b>	ug/L
1,3,5-Trimethylbenzene	< 2.0		ug/L
tert-Butylbenzene	< 2.0		ug/L
1,2,4-Trimethylbenzene	< 1.0	<b> </b>	ug/L
sec-Butylbenzene	< 2.0		ug/L
p-isopropyltoluene	< 2.0	₩ ~-	ug/L
1,3-Dichlorobenzene	< 1.0	<b> </b>	ug/L
1,4-Dichlorobenzene	< 0.5	75.0	ug/L
n-Butylbenzene	< 2.0	)	ug/L
1,2-Dichlorobenzene	< 0.5	600	ug/L
1,2-Dibromo-3-Chloroprop	< 5.0		ug/L
1,2,4-Trichlorobenzene	< 0.5	70.0	ug/L
Hexachlorobutadiene	< 1.0	∥	ug/L
Naphthalene	< 20.0	<b> </b>	ug/L
1,2,3-Trichlorobenzene	< 2.0		ug/L

MCL = Maximum Contaminant Level

-- = Not Applicable

The analysis of this sample was performed in accordance with procedures approved or recognized by the U.S. Environmental Protection Agency. If you have any questions, please contact Mr. Terry Timmons at 573/751-1188.

James H. Long, Director Environmental Services Program Division of Environmental Quality

#### STATE OF MISSOURI

## DEPARTMENT OF NATURAL RESOURCES 0.3.1998

-DIVISION OF FNVIRONMENTAL QUANTIES PO Box 176 lefferson City, MO 65102-01-6

#### ENVIRONMENTAL SERVICES PROGRAM

VINCENT COSTA 112 COURT CIRCLE - CITY HALL P.O. BOX 1048 CAMDENTON, MO 65020

Sample Number: 98-U835

QUARTERLY MONITORING

#### RESULTS OF SAMPLE ANALYSES FOR PUBLIC WATER SUPPLIES

Report Date:

September 9, 1998

Date Collected: August 25, 1998

Sample Location: RODEO WELL

PWS ID:

Lab Number: 98-A14823

MO3010130

PWS Name:

Analysis Performed	Results	MCL	Units
VOC Results:			
Dichlorodifluoromethane	< 200	i	ug/L
Chloromethane	< 2.5	<b> </b>	ug/L
Vinyl Chloride	< 0.5	2.0	ug/L
Bromomethane	< 9.0	<u> </u>	ug/L
Chloroethane	< 2.5		ug/L
Trichlorofluoromethane	< 2.5	₩	ug/L
1,1-Dichloroethene	< 0.5	7.0	ug/L
Methylene Chloride	< 0.5	5.0	ug/L
Methyl-tert-butyl ether	< 5.0		ug/L
trans-1,2-Dichloroethene	< 0.5	100	ug/L
1,1-Dichloroethane	< 1.0	<b> </b>	ug/L
2,2-Dichloropropane	< 1.0	<b> </b>	ug/L
cis-1,2-Dichloroethene	< 0.5	70.0	ug/L
Chloroform	< 0.5	∜	ug/L
Bromochloromethane	< 1.0	<b> </b>	ug/L
1,1,1-Trichloroethane	< 0.5	200	ug/L
1,1-Dichloropropene	< 1.0		ug/L
Carbon Tetrachloride	< 0.5	5.0	ug/L
Benzene	< 0.5	5.0	ug/L
1,2-Dichloroethane	< 0.5	5.0	ug/L
Trichloroethene	< 0.5	5.0	ug/L
1,2-Dichloropropane	< 0.5	5.0	ug/L
Bromodichloromethane	< 0.5		ug/L
Dibromomethane	< 1.0		ug/L
cis-1,3-Dichloropropane	< 2.0		ug/L
Toluene	< 1.0	1000	ug/L

Page: 2 Lab Number: 98-A14823 Report Date: September 9, 1998 Sample Number: 98-U835

Analysis Performed	Results	MCL	Units
	< 1.0		
trans-1,3-Dichloropropane	< 1.0 < 0.5		ug/L
1,1,2-Trichloroethane Tetrachloroethene		5.0	ug/L
	< 0.5	5.0	ug/L
1,3-Dichloropropane	< 2.0		ug/L
Dibromochloromethane	< 0.5	ii	ug/L
1,2-Dibromoethane	< 2.0		ug/L
Chlorobenzene	< 0.5	100	ug/L
Ethylbenzene	< 0.5	700	ug/L
1,1,1,2-Tetrachloroethane	< 1.0		ug/L
Total Xylenes	< 0.5	10000	ug/L
Styrene	< 0.5	100	ug/L
Isopropylbenzene	< 2.0	<b> </b>	ug/L
Bromoform	< 0.5		ug/L
1,1,2,2-Tetrachloroethane	< 1.0		ug/L
1,2,3-Trichloropropane	< 1.0		ug/l
n-Propylbenzene	< 2.0		ug/L
Bromobenzene	< 1.0	<b> </b>	ug/L
2-Chlorotoluene	< 2.0		ug/L
4-Chlorotoluene	< 2.0		ug/L
1,3,5-Trimethylbenzene	< 2.0		ug/L
tert-Butylbenzene	< 2.0		ug/L
1,2,4-Trimethylbenzene	< 1.0	<b> </b>	ug/L
sec-Butylbenzene	< 2.0		ug/L
p-isopropyltoluene	< 2.0		ug/L
1,3-Dichlorobenzene	< 1.0	<b>!</b>	ug/L
1,4-Dichlorobenzene	< 0.5	75.0	ug/L
n-Butylbenzene	< 2.0		ug/L
1,2-Dichlorobenzene	< 0.5	600	ug/L
1,2-Dibromo-3-Chloroprop	< 5.0		ug/L
	< 0.5	70.0	ug/L
	< 1.0		ug/L
Naphthalene	< 20.0		ug/L
1,2,3-Trichlorobenzene	< 2.0		ug/L
1,2,5 ilitoliobelizelle	~ 2.0		ا مراک

MCL = Maximum Contaminant Level

-- = Not Applicable

The analysis of this sample was performed in accordance with procedures approved or recognized by the U.S. Environmental Protection Agency. If you have any questions, please contact Mr. Terry Timmons at 573/751-1188.

James H. Long, Director Environmental Services Program

Environmental Services Program Division of Environmental Quality

contamination from an industrial-type cleaning chemical known as trichlethylene. So far, levels of TCE have stayed below those considered acceptable by

By Joyce L. Miller CAMDENTON - A Camdenton manufacturing plant is under the the gun to comply continues to show traces of of chemical contamination in the city's water supply. DNR says Camdenton's water with an order from the Missouri Department of Natural Resources after being identified as a potential source

to people or the environment.
Modine has 30 days to comply.
Failure to do so could force
DNR to take legal action against the company.

Modine engineer Bob King
said the DNR order was come up with a plan to address Manufacturing Company to headquarters in Racine, forwarded to corporation facility that may pose a threat contamination at the

According to King, the order was vague and didn't contain Continued on page 4, col. 1)

federal and state standards.

Former Hulett Lagoon Site Combined PA/SI Reference 51

(Continued from page 1)

any specific course of action.

DNR says the order will establish a regulatory time frame and schedule for the manufacturing plant to follow, in order to deal with potential contamination at the plant's location on Sunset Drive. The plan will be negotiated between DNR and Modine.

DNR and city officials believe the chemical was probably spilled more than a decade ago by Modine's predecessor. The plant is located across from the Mulberry Street well which, up until now, has supplied most of the city's water.

Modine contends chemical has never been used in the manufacturing process at the Camdenton plant.

Increased levels of TCE have been showing up in the city's water system over the last year. Traces started appearing as early as last summer. Since that time, city officials have determined the contamination was entering the water supply at the Mulberry Street well.

The city is in the process of putting together a deal for a new well on Hickory Street. The well, property and engineering is expected to run the city about \$250,000. In the meantime, the Mulberry Street well is being used as little as possible, according to Public Works Director Vince Costa.

TCE is considered to be a human carcinogen by the International Agency for Research on cancer and the Environmental Protection Agency, depending on levels of exposure, duration and amounts.

DNR engineer Chris Kump

said the consent order is the first step in the process of determining the nature and of TCE extent the contamination. Based on what is found, clean-up measures may recommended.

"The order requires Modine to determine the nature and extent of contamination, groundwater, including resulting from past waste handling practices at the facility." DNR spokesman Connie Patterson said "The order also requires Modine to perform a corrective measure study and detail a final remedy to be applied at the

TCE is considered to be a human carcinogen by the International Agency for Research on cancer and the Environmental Protection Agency, depending on levels of exposure, duration and amounts.

site. The public will be asked for review and comment on the proposed final remedy prior to approval by DNR and implementation by Modine"

Modine Manufacturing Company has operated the Camdenton facility since October, 1990. Modine manufactures conditioning coils and feeder parts from aluminum and copper tubing. The facility was previously owned by Sunstrand Tubular Products from 1974 to 1990.

Kump said Modine has been very willing to work with DNR to get the TCE problem corrected.

Former Hulett Lagoon Site Combined PA/SI Reference 52

MAY 2 1 1998

HAZARDOUS WASTE PROGRAM MISSOURI DEPARTMENT OF NATURAL RESOURCES

### RCRA Sampling Investigation Report

### Modine Site - Burnau Private Well Camdenton, Missouri

April 23, 1998

Prepared For:

Missouri Department of Natural Resources
Division of Environmental Quality
Hazardous Waste Program

Prepared By:

Missouri Department of Natural Resources
Division of Environmental Quality
Environmental Services Program

### Table of Contents

<u>Sect</u>	ion																					F	ag	<u>e</u>
1.0	Intro	oductio	on				•	•	•	•	•		•	•	•	•	•	•	•	•	•	•	•	1
2.0	2.1 2.2	Descri Site I Site I	Loca( Desci	tior ript	ı . Lior	 1 .			•		•	•	•	•	•	•	•	•			•	•		1 1
3.0	3.1 3.2 3.3	ods . Field Chain Analys Quali	Prod of-G	cedu Cust Requ	res cody rest	s . ⁄ · ced	•	•	•	•	•		•				•	•	•			•	•	2 2 3
4.0	Inves	stigat:	ion I	Deri	ive	1 Wa	ste	es	•	•				•	•			•	•		•	•		3
5.0	Obsei	rvatio	ns							•			•	•							•	•		3
6.0	Data	Repor	ting	•			•	•	•	•	•	•	•	•	•		•	•	•	•	•	•	•	3
Anne	ndices	3						_				T	OC	a t	ed	l a	t.	er	าส	οf	. 1	cer	o	rt.

RCRA Sampling Investigation Report Modine Site - Burnau Private Well Camdenton, Missouri April 23, 1998 Page 1

#### 1.0 Introduction

At the request of the Hazardous Waste Program (HWP) a sampling investigation was conducted on April 23, 1998, by Eric Sappington of the Environmental Services Program (ESP). The purpose of the investigation was to collect a water sample from a private well located at the Dave Burnau residence, 178 Sunset Drive in Camdenton, Missouri. The Burnau home is located across the street from the Modine Heat Transfer, Inc. facility. Information obtained from previous investigations raised concerns that organic solvent contaminants, known to exist in the soils and groundwater at the Modine site, may have migrated to the nearby Burnau well.

The private well at the Burnau residence is a secondary water source, the primary drinking water source being the Camdenton public water supply. There were no samples collected from the Camdenton public water supply during this investigation.

#### 2.0 Site Description and History

#### 2.1 Site Location

The Burnau residence is located at 178 Sunset Drive, Camdenton, Missouri. The Modine Heat Transfer, Inc. facility is located at 179 Sunset Drive, directly across the street from the Burnau residence.

#### 2.2 Site Description

The Burnau home is located in a residential neighborhood adajcent to the Modine facility.

#### 2.3 Site History/Contaminants of Concern

Previous investigations conducted at the Modine site found evidence of organic solvent contamination in both soils and groundwater in the vicinity of the manufacturing plant. Trichloroethylene (trichloroethene), tetrachloroethylene, 1,1,1-trichloroethane, and vinyl chloride are among the contaminants that have been detected in the soils and/or groundwater at the site.

Further historical or background information regarding the Modine site can be found in the ESP and HWP files.

RCRA Sampling Investigation Report Modine Site - Burnau Private Well Camdenton, Missouri April 23, 1998 Page 2

#### 3.0 Methods

#### 3.1 Field Procedures

Sample 98-4702 was collected from an outside spigot located at the rear of the Burnau residence. Sample 98-4703 was collected from the same location as a duplicate to 98-4702. Prior to sample collection, the spigot was turned on and allowed to flow for 12 minutes in order to purge the stagnant water from the pressure tank. According to Mr. Burnau, the pressure tank has a capacity of 30 to 40 gallons. Using a stop watch and a graduated bucket, the flow rate was calculated at four gallons per minute. Thus, 48 gallons were purged prior to sample collection. The water was discharged into a storm drain on the Burnau property.

In order to minimize agitation and aeration at the spigot, the flow rate was reduced to a thin stream for sample collection. The vials for volatile organic parameters were filled first, then the flow rate was increased slightly to facilitate filling the one-liter sample containers for semi-volatile organic parameters.

The sample vials for the volatile organic parameters were prepreserved with a few drops of hydrochloric acid. The containers for semi-volatile organic parameters required no chemical preservatives. Upon collection, all sample containers were labelled and placed immediately on ice in a cooler.

Clean nitrile gloves were worn for sample collection.

Modine was contacted prior to the investigation and offered the opportunity to collect split samples from the Burnau well. The company was initially interested in collecting samples, but then declined the offer.

#### 3.2 Chain-of-Custody

Each sample container received a numbered label upon collection. A chain-of-custody form was then completed which recorded the sample number assigned to each container, the description of the location of the sample collected, the date and time collected, and the parameters to be analyzed.

The ESP representative maintained custody of the samples and hand delivered the samples to the Environmental Services Program in Jefferson City where they were relinquished to a sample custodian.

RCRA Sampling Investigation Report Modine Site - Burnau Private Well Camdenton, Missouri April 23, 1998 Page 3

### 3.3 Analyses Requested

All samples were analyzed for volatile organic and semi-volatile organic parameters.

### 3.4 Quality Assurance/Quality Control (QA/QC)

All samples were analyzed in accordance with the general requirements and standard operating procedures described in the Fiscal Year 1998 Generator/TSD Quality Assurance Project Plan.

Sample 98-4701 was collected as a trip blank and analyzed for the same parameters as the groundwater samples.

### 4.0 Investigation Derived Wastes

All disposable personal protective equipment generated by the ESP representative was returned to the ESP laboratory for proper disposal.

### 5.0 Observations

The samples collected from the Burnau private well were clear, colorless and had no discernable odor.

When asked at the time of the investigation, Mr. Burnau was not aware of the well characteristics (e.g. total well depth, static water level, casing depth, or depth of pump). The ESP did not open up the well and made no attempt to measure the well characteristics.

Mr. Burnau stated that he used the private well primarily for watering his lawn and that he did not use the well as a source of drinking water. There was nothing unusual noted regarding the lawn and there were no obvious signs of stressed vegetation observed.

The weather on the day of sampling was sunny and warm.

### 6.0 Data Reporting

The analytical results of the sampling investigation are attached to this report.

RCRA Sampling Investigation Report Modine Site - Burnau Private Well Camdenton, Missouri April 23, 1998 Page 4

In response to a request made by Mr. Burnau at the time of the investigation, Eric Sappington provided the sample results to Mr. Burnau during a telephone conversation that took place on May 18, 1998. Mr. Burnau was informed that the level of trichloroethene (TCE) in his private well exceeded the Maximum Contaminant Level (MCL) for public drinking water supplies. The MCL for TCE is 5 parts per billion (ug/L). Mr. Burnau was advised not to drink the water and was provided with a contact at the Missouri Department of Health (Randy Maley) should he have any questions regarding the health effects of TCE.

Submitted by:

Eric Sappington

Environmental Specialist Field Services Section

Environmental Services Program

Date:

5/20/98

Approved by:

ames H. Long

Director

Environmental (Services Program

ES:

c: Chris Kump, HWP

Bob Hentges, Regional Director, JCRO

### Appendix A

RCRA Sampling Investigation Report Modine Site - Burnau Private Well Camdenton, Missouri April 23, 1998

Analytical Results

### STATE OF MISSOURI

# DEPARTMENT OF NATURAL RESOURCES

– DIVISION OF ENVIRONMENTAL QUALITY – P.O Box 176 Jefferson City, MO 65102-0176

### ENVIRONMENTAL SERVICES PROGRAM

### RESULTS OF SAMPLE ANALYSES

Sample Number: 98-4701 Lab Number: 98-D933

Reported To: ERIC SAPPINGTON 5/ 6/98 4/23/98 Report Date: Date Collected: Affiliation: ESP Project Code: 3735/3000 4/24/98 Date Received:

Sample Collected by: ERIC SAPPINGTON, ESP
Sampling Location: MODINE SITE, CAMDENTON, MO,
Sample Description: TRIP BLANKS Sample Description:

Analysis Performed	Results		Analyzed	Method
VOA Results:				
Chloromethane	< 5.0	ug/L	4/28/98	8260
Vinyl Chloride	< 5.0	ug/L	4/28/98	8260
Bromomethane	< 5.0	ug/L	4/28/98	8260
Chloroethane	< 5.0	ug/L	4/28/98	8260
1,1-Dichloroethene	< 5.0	ug/L	4/28/98	8260
Acetone	< 20.0	ug/L	4/28/98	8260
Carbon Disulfide	< 5.0	ug/L	4/28/98	8260
Methylene Chloride	< 20.0	ug/L	4/28/98	8260
Methyl Tert-Butyl Ether	< 5.0	ug/L	4/28/98	8260
trans-1,2-Dichloroethene	< 5.0	ug/L	4/28/98	8260
1,1-Dichloroethane	< 5.0	ug/L	4/28/98	8260
2-Butanone	< 20.0	ug/L	4/28/98	8260
cis-1,2-Dichloroethene	< 5.0	ug/L	4/28/98	8260
Chloroform	< 5.0	ug/L	4/28/98	8260
1,1,1-Trichloroethane	< 5.0	ug/L	4/28/98	8260
Carbon Tetrachloride	< 5.0	ug/L	4/28/98	8260
Benzene	< 5.0	ug/L	4/28/98	8260
1,2-Dichloroethane	< 5.0	ug/L	4/28/98	8260
Trichloroethene	< 5.0	ug/L	4/28/98	8260
1,2-Dichloropropane	< 5.0	ug/L	4/28/98	8260
Bromodichloromethane	< 5.0	ug/L	4/28/98	8260
2-Hexanone	< 20.0	ug/L	4/28/98	8260
Trans-1,3-Dichloropropene	< 5.0	ug/L	4/28/98	8260
Toluene	< 5.0	ug/L	4/28/98	8260
CIS-1,3-Dichloropropene	< 5.0	ug/L	4/28/98	8260

Page 2 Lab Number: 98-D933 Sample Number: 98-4701 May 6, 1998

Analysis Performed	Results		Analyzed	Method
1,1,2-Trichloroethane	< 5.0	ug/L	4/28/98	8260
4-Methyl-2-Pentanone	< 20.0	ug/L	4/28/98	8260
Tetrachloroethene	< 5.0	ug/L	4/28/98	8260
Dibromochloromethane	< 5.0	ug/L	4/28/98	8260
Chlorobenzene	< 5.0	ug/L	4/28/98	8260
Ethylbenzene	< 5.0	ug/L	4/28/98	8260
Total Xylenes	< 5.0	ug/L	4/28/98	8260
Styrene	< 5.0	ug/L	4/28/98	8260
Bromoform	< 5.0	ug/L	4/28/98	8260
1,1,2,2-Tetrachloroethane	< 5.0	ug/L	4/28/98	8260
1,3-Dichlorobenzene	< 5.0	ug/L	4/28/98	8260
1,4-Dichlorobenzene	< 5.0	ug/L	4/28/98	8260
1,2-Dichlorobenzene	< 5.0	ug/L	4/28/98	8260
BNA Results:		37	, ,	
Phenol	< 2.0	ug/L	4/30/98	8270
bis(-2-Chloroethyl)Ether	< 2.0	ug/L	4/30/98	8270
2-Chlorophenol	< 5.0	ug/L	4/30/98	8270
1,3-Dichlorobenzene	< 2.0	ug/L	4/30/98	8270
1,4-Dichlorobenzene	< 2.0	ug/L	4/30/98	8270
N-nitrosodimethylamine	< 2.0	ug/L	4/30/98	8270
1,2-Dichlorobenzene	< 2.0	ug/L	4/30/98	8270
2-Methylphenol	< 2.0	ug/L	4/30/98	8270
bis(2-Chloroisopropyl)Eth	< 2.0	ug/L	4/30/98	8270
4-Methylphenol	< 2.0	ug/L	4/30/98	8270
N-Nitro-Di-n-Propylamine	< 2.0	ug/L	4/30/98	8270
Hexachloroethane	< 2.0	ug/L	4/30/98	8270
Nitrobenzene	< 2.0	ug/L	4/30/98	8270
Isophorone	< 2.0	ug/L	4/30/98	8270
2-Nitrophenol	< 2.0	ug/L	4/30/98	8270
2,4-Dimethylphenol	< 2.0	ug/L	4/30/98	8270
Benzoic Acid	< 2.0	ug/L	4/30/98	8270
bis(2-Chloroethoxy)Methan	< 2.0	ug/L	4/30/98	8270
2,4-Dichlorophenol	< 2.0	ug/L	4/30/98	8270
1,2,4-Trichlorobenzene	< 2.0	ug/L	4/30/98	8270
Naphthalene	< 2.0		4/30/98	8270
<b>←</b>	< 5.0	ug/L	4/30/98	8270
4-Chloroaniline	< 2.0	ug/L	4/30/98	8270
Hexachlorobutadiene		ug/L		8270
4-Chloro-3-Methylphenol	< 5.0	ug/L	4/30/98	8270
2-Methylnaphthalene	< 2.0	ug/L	4/30/98	8270
Hexachlorocyclopentadiene	< 2.0	ug/L	4/30/98	8270
2,4,6-Trichlorophenol	< 2.0	ug/L	4/30/98	8270
2,4,5-Trichlorophenol	< 5.0 < 2.0	ug/L	4/30/98	8270
2-Chloronaphthalene		ug/L	4/30/98	8270
2-Nitroaniline	< 5.0	ug/L	4/30/98	8270
Dimethylphthalate	< 2.0	ug/L	4/30/98	
Acenaphthylene	< 2.0	ug/L	4/30/98	8270
2,6-Dinitrotoluene	< 2.0	ug/L	4/30/98	8270
3-Nitroaniline	< 5.0	ug/L	4/30/98	8270

Page 3

Lab Number: 98-D933 Sample Number: 98-4701

May 6, 1998

Analysis Performed	Results		Analyzed	Method
Acenaphthene	< 2.0	ug/L	4/30/98	8270
2,4-Dinitrophenol	< 5.0		4/30/98	8270
4-Nitrophenol	< 5.0.		4/30/98	8270
Dibenzofuran	< 2.0	ug/L	4/30/98	8270
2,4-Dinitrotoluene	< 2.0	ug/L		8270
Diethylphthalate	< 2.0	ug/L		8270
4-Chlorophenyl-phenylethe	< 2.0	ug/L	4/30/98	8270
Fluorene	< 2.0	ug/L	4/30/98	8270
4-Nitroaniline	< 5.0	ug/L	4/30/98	8270
4,6-Dinitro-2-Methylpheno	< 5.0	ug/L	4/30/98	8270
N-Nitrosodiphenylamine	< 2.0	ug/L	4/30/98	8270
4-Bromophenyl-phenylether	< 2.0	ug/L	4/30/98	8270
Hexachlorobenzene	< 2.0	ug/L	4/30/98	8270
Pentachlorophenol	< 5.0	ug/L	4/30/98	8270
Phenanthrene	< 2.0	ug/L	4/30/98	8270
Anthrancene	< 2.0	ug/L	4/30/98	8270
Di-n-Butylphthalate	< 5.0	ug/L	4/30/98	8270
Fluoranthene	< 2.0	ug/L	4/30/98	8270
Pyrene	< 2.0	ug/L	4/30/98	8270
Butylbenzylphthalate	< 2.0	ug/L	4/30/98	8270
3-3'-Dichlorobenzidine	< 5.0	ug/L	4/30/98	8270
Benzo(a)anthracene	< 2.0	ug/L	4/30/98	8270
Chrysene	< 2.0	ug/L	4/30/98	8270
bis(2-ethylhexyl)phthalat	< 5.0	ug/L	4/30/98	8270
Di-n-Octylphthalate	< 2.0	ug/L	4/30/98	8270
Benzo(b)fluoranthene	< 2.0	ug/L	4/30/98	8270
Benzo(k)fluoranthene	< 2.0	ug/L	4/30/98	8270
Benzo(a)pyrene	< 2.0	ug/L	4/30/98	8270
Indeno(1,2,3-cd)pyrene	< 2.0	ug/L	4/30/98	8270
Dibenz(a,h)anthracene	< 2.0	ug/L	4/30/98	8270
Benzo(g,h,i)perylene	< 2.0	ug/L	4/30/98	8270

The analysis of this sample was performed in accordance with procedures approved or recognized by the U.S. Environmental Protection Agency.

James H. Long, Director

Environmental Services Program

Division of Environmental Quality

C: KATHY FLIPPIN, HWP

### STATE OF MISSOURI

# DEPARTMENT OF NATURAL RESOURCES

– DIVISION OF ENVIRONMENTAL QUALITY -PO Box 176 Jefferson City, MO 65102-0176

### ENVIRONMENTAL SERVICES PROGRAM

### RESULTS OF SAMPLE ANALYSES

Sample Number: 98-4702 Lab Number: 98-D935

Reported To: ERIC SAPPINGTON Affiliation:

5/ 6/98 4/23/98 Report Date: ESP Date Collected:

Project Code: 3735/3000

4/24/98 Date Received:

Sample Collected by:

ERIC SAPPINGTON, ESP

Sampling Location: Sample Description:

MODINE SITE, CAMDENTON, MO, BURNAU RESIDENCE, GROUNDWATER,

PRIVATE WELL

Analysis Performed	Results		Analyzed	Method
VOA Results:				
Chloromethane	< 5.0	ug/L	4/28/98	8260
Vinyl Chloride	< 5.0	ug/L	4/28/98	8260
Bromomethane	< 5.0	ug/L	4/28/98	8260
Chloroethane	< 5.0	ug/L	4/28/98	8260
1,1-Dichloroethene	< 5.0	ug/L	4/28/98	8260
Acetone	< 20.0	ug/L	4/28/98	8260
Carbon Disulfide	< 5.0	ug/L	4/28/98	8260
Methylene Chloride	< 20.0	ug/L	4/28/98	8260
Methyl Tert-Butyl Ether	< 5.0	ug/L	4/28/98	8260
trans-1,2-Dichloroethene	< 5.0	ug/L	4/28/98	8260
1,1-Dichloroethane	< 5.0	ug/L	4/28/98	8260
2-Butanone	< 20.0	ug/L	4/28/98	8260
cis-1,2-Dichloroethene	12.0	ug/L	4/28/98	8260
Chloroform	< 5.0	ug/L	4/28/98	8260
1,1,1-Trichloroethane	< 5.0	ug/L	4/28/98	8260
Carbon Tetrachloride	< 5.0	ug/L	4/28/98	8260
Benzene	< 5.0	ug/L	4/28/98	8260
1,2-Dichloroethane	< 5.0	ug/L	4/28/98	8260
Trichloroethene	210	ug/L	4/28/98	8260
1,2-Dichloropropane	< 5.0	ug/L	4/28/98	8260
Bromodichloromethane	< 5.0	ug/L	4/28/98	8260
2-Hexanone	< 20.0	ug/L	4/28/98	8260
Trans-1,3-Dichloropropene	< 5.0	ug/L	4/28/98	8260
Toluene	< 5.0	ug/L	4/28/98	8260

Page 2 Lab Number: 98-D935 Sample Number: 98-4702 May 6, 1998

Analysis Performed	Results		Analyzed	Method
CIS-1,3-Dichloropropene.	< 5.0	ug/L	4/28/98	8260
1,1,2-Trichloroethane	< 5.0	ug/L	4/28/98	8260
4-Methyl-2-Pentanone	< 20.0	ug/L	4/28/98	8260
Tetrachloroethene	< 5.0	ug/L	4/28/98	8260
Dibromochloromethane	< 5.0	ug/L	4/28/98	8260
Chlorobenzene	< 5.0	ug/L	4/28/98	8260
Ethylbenzene	< 5.0	ug/L	4/28/98	8260
Total Xylenes	< 5.0	ug/L	4/28/98	8260
Styrene	< 5.0	ug/L	4/28/98	8260
Bromoform	< 5.0	ug/L	4/28/98	8260
1,1,2,2-Tetrachloroethane	< 5.0	ug/L	4/28/98	8260
1,3-Dichlorobenzene	< 5.0	ug/L	4/28/98	8260
1,4-Dichlorobenzene	< 5.0	ug/L	4/28/98	8260
1,2-Dichlorobenzene	< 5.0	ug/L	4/28/98	8260
BNA Results:			, .	
Phenol	< 2.0	ug/L	4/30/98	8270
bis(-2-Chloroethyl)Ether	< 2.0	ug/L	4/30/98	8270
2-Chlorophenol	< 5.0	ug/L	4/30/98	8270
1,3-Dichlorobenzene	< 2.0	ug/L	4/30/98	8270
1,4-Dichlorobenzene	< 2.0	ug/L	4/30/98	8270
N-nitrosodimethylamine	< 2.0	ug/L	4/30/98	8270
1,2-Dichlorobenzene	< 2.0	ug/L	4/30/98	8270
2-Methylphenol	< 2.0	ug/L	4/30/98	8270
bis(2-Chloroisopropyl)Eth	< 2.0	ug/L	4/30/98	8270
4-Methylphenol	< 2.0	ug/L	4/30/98	8270
N-Nitro-Di-n-Propylamine	< 2.0	ug/L	4/30/98	8270
Hexachloroethane	< 2.0	ug/L	4/30/98	8270
Nitrobenzene	< 2.0	ug/L	4/30/98	8270
Isophorone	< 2.0	ug/L	4/30/98	8270
2-Nitrophenol	< 2.0	ug/L	4/30/98	8270
2,4-Dimethylphenol	< 2.0	ug/L	4/30/98	8270
Benzoic Acid	< 2.0	ug/L	4/30/98	8270
bis(2-Chloroethoxy)Methan	< 2.0	ug/L	4/30/98	8270
2,4-Dichlorophenol	< 2.0	ug/L	4/30/98	8270
1,2,4-Trichlorobenzene	< 2.0	ug/L	4/30/98	8270
Naphthalene	< 2.0	ug/L	4/30/98	8270
4-Chloroaniline	< 5.0	ug/L	4/30/98	8270
Hexachlorobutadiene	< 2.0	ug/L	4/30/98	8270
4-Chloro-3-Methylphenol	< 5.0	ug/L	4/30/98	8270
2-Methylnaphthalene	< 2.0	ug/L	4/30/98	8270
Hexachlorocyclopentadiene	< 2.0	ug/L	4/30/98	8270
2,4,6-Trichlorophenol	< 2.0	ug/L	4/30/98	8270
2,4,5-Trichlorophenol	< 5.0	ug/L	4/30/98	8270
2-Chloronaphthalene	< 2.0	ug/L	4/30/98	8270
2-Nitroaniline	< 5.0	ug/L	4/30/98	8270
Dimethylphthalate	< 2.0	ug/L	4/30/98	8270
Acenaphthylene	< 2.0	ug/L	4/30/98	8270
2,6-Dinitrotoluene	< 2.0	ug/L	4/30/98	8270
a, o bilitorocordono	- 2.0	-3/ -	., 50, 50	

Page 3

Lab Number: 98-D935 Sample Number: 98-4702

May 6, 1998

Analysis Performed	Results		Analyzed	Method
3-Nitroaniline	< 5.0	ug/L	4/30/98	8270
Acenaphthene	< 2.0	ug/L	4/30/98	8270
2,4-Dinitrophenol	< 5.0	ug/L	4/30/98	8270
4-Nitrophenol	< 5.0	ug/L	4/30/98	8270
Dibenzofuran	< 2.0	ug/L	4/30/98	8270
2,4-Dinitrotoluene	< 2.0	ug/L	4/30/98	8270
Diethylphthalate	< 2.0	ug/L	4/30/98	8270
4-Chlorophenyl-phenylethe	< 2.0	ug/L	4/30/98	8270
Fluorene	< 2.0	ug/L	4/30/98	8270
4-Nitroaniline	< 5.0	ug/L	4/30/98	8270
4,6-Dinitro-2-Methylpheno	< 5.0	ug/L	4/30/98	8270
N-Nitrosodiphenylamine	< 2.0	ug/L	4/30/98	8270
4-Bromophenyl-phenylether	< 2.0	ug/L	4/30/98	8270
Hexachlorobenzene	< 2.0	ug/L	4/30/98	8270
Pentachlorophenol	< 5.0	ug/L	4/30/98	8270
Phenanthrene	< 2.0	ug/L	4/30/98	8270
Anthrancene	< 2.0	ug/L	4/30/98	8270
Di-n-Butylphthalate	< 5.0	ug/L	4/30/98	8270
Fluoranthene	< 2.0	ug/L	4/30/98	8270
Pyrene	< 2.0	ug/L	4/30/98	8270
Butylbenzylphthalate	< 2.0	ug/L	4/30/98	8270
3-3'-Dichlorobenzidine	< 5.0	ug/L	4/30/98	8270
Benzo(a)anthracene	< 2.0	ug/L	4/30/98	8270
Chrysene	< 2.0	ug/L	4/30/98	8270
bis(2-ethylhexyl)phthalat	< 5.0	ug/L	4/30/98	8270
Di-n-Octylphthalate	< 2.0	ug/L	4/30/98	8270
Benzo(b)fluoranthene	< 2.0	ug/L	4/30/98	8270
Benzo(k)fluoranthene	< 2.0	ug/L	4/30/98	8270
Benzo(a)pyrene	< 2.0	ug/L	4/30/98	8270
Indeno(1,2,3-cd)pyrene	< 2.0	ug/L	4/30/98	
Dibenz(a,h)anthracene	< 2.0	ug/L	4/30/98	8270
Benzo(g,h,i)perylene	< 2.0	ug/L	4/30/98	8270

The analysis of this sample was performed in accordance with procedures approved or recognized by the U.S. Environmental Protection Agency.

James H. Long, Director Environmental Services Program Division of Environmental Quality

C: KATHY FLIPPIN, HWP

### STATE OF MISSOURI

# DEPARTMENT OF NATURAL RESOURCES

— DIVISION OF ENVIRONMENTAL QUALITY -P.O. Box 176 Jefferson City, MO 65102-0176

Report Date:

Date Collected:

Date Received:

5/13/98

4/23/98

4/24/98

### ENVIRONMENTAL SERVICES PROGRAM

### RESULTS OF SAMPLE ANALYSES

Sample Number: 98-4703 Lab Number: 98-D936

ERIC SAPPINGTON Reported To:

ESP

Affiliation:

Sample Collected by:

Project Code: 3735/3000

ERIC SAPPINGTON, ESP

Sampling Location: MODINE SITE, CAMDENTON, MO, Sample Description: BURNAU RESIDENCE, GROUNDWATER,

PRIVATE WELL (DUPLICATE)

Analysis Performed	Results		Analyzed	Method
VOA Results:				
Chloromethane	< 5.0	ug/L	4/29/98	8260
Vinyl Chloride	< 5.0	ug/L	4/29/98	8260
Bromomethane	< 5.0	ug/L	4/29/98	8260
Chloroethane	< 5.0	ug/L	4/29/98	8260
1,1-Dichloroethene	< 5.0	ug/L	4/29/98	8260
Acetone	< 20.0	ug/L	4/29/98	8260
Carbon Disulfide	< 5.0	ug/L	4/29/98	8260
Methylene Chloride	< 20.0	ug/L	4/29/98	8260
Methyl Tert-Butyl Ether	< 5.0	ug/L	4/29/98	8260
trans-1,2-Dichloroethene	< 5.0	ug/L	4/29/98	8260
1,1-Dichloroethane	< 5.0	ug/L	4/29/98	8260
2-Butanone	< 20.0	ug/L	4/29/98	8260
cis-1,2-Dichloroethene	13.0	ug/L	4/29/98	8260
Chloroform	< 5.0	ug/L	4/29/98	8260
1,1,1-Trichloroethane	< 5.0	ug/L	4/29/98	8260
Carbon Tetrachloride	< 5.0	ug/L	4/29/98	8260
Benzene	< 5.0	ug/L	4/29/98	8260
1,2-Dichloroethane	< 5.0	ug/L	4/29/98	8260
Trichloroethene	170	ug/L	4/29/98	8260
1,2-Dichloropropane	< 5.0	ug/L	4/29/98	8260
Bromodichloromethane	< 5.0	ug/L	4/29/98	8260
2-Hexanone	< 20.0	ug/L	4/29/98	8260
Trans-1,3-Dichloropropene	< 5.0	ug/L	4/29/98	8260
Toluene	< 5.0	ug/L	4/29/98	8260

Page 2

Lab Number: 98-D936 Sample Number: 98-4703

May 13, 1998

Analysis Performed	Results		Analyzed	Method
CIS-1,3-Dichloropropene	< 5.0	ug/L	4/29/98	8260
1,1,2-Trichloroethane	< 5.0	ug/L	4/29/98	8260
4-Methyl-2-Pentanone	< 20.0	ug/L	4/29/98	8260
Tetrachloroethene	< 5.0	ug/L	4/29/98	8260
Dibromochloromethane	< 5.0	ug/L	4/29/98	8260
Chlorobenzene	< 5.0	ug/L	4/29/98	8260
Ethylbenzene	< 5.0	ug/L	4/29/98	8260
Total Xylenes	< 5.0	ug/L	4/29/98	8260
Styrene Styrene	< 5.0	ug/L	4/29/98	8260
Bromoform	< 5.0	ug/L	4/29/98	8260
1,1,2,2-Tetrachloroethane	< 5.0	ug/L	4/29/98	8260
1,3-Dichlorobenzene	< 5.0	ug/L	4/29/98	8260
1,4-Dichlorobenzene	< 5.0	ug/L	4/29/98	8260
1,2-Dichlorobenzene	< 5.0	ug/L	4/29/98	8260
BNA Results:		-,	• •	
Phenol	< 2.0	ug/L	4/30/98	8270
bis(-2-Chloroethyl)Ether	< 2.0	ug/L	4/30/98	8270
2-Chlorophenol	< 5.0	ug/L	4/30/98	8270
1,3-Dichlorobenzene	< 2.0	ug/L	4/30/98	8270
1,4-Dichlorobenzene	< 2.0	ug/L	4/30/98	8270
N-nitrosodimethylamine	< 2.0	ug/L	4/30/98	8270
1,2-Dichlorobenzene	< 2.0	ug/L	4/30/98	8270
2-Methylphenol	< 2.0	ug/L	4/30/98	8270
bis(2-Chloroisopropyl)Eth	< 2.0	ug/L	4/30/98	8270
4-Methylphenol	< 2.0	ug/L	4/30/98	8270
N-Nitro-Di-n-Propylamine	< 2.0	ug/L	4/30/98	8270
Hexachloroethane	< 2.0	ug/L	4/30/98	8270
Nitrobenzene	< 2.0	ug/L	4/30/98	8270
Isophorone	< 2.0	ug/L	4/30/98	8270
2-Nitrophenol	< 2.0	ug/L	4/30/98	8270
2,4-Dimethylphenol	< 2.0	ug/L	4/30/98	8270
Benzoic Acid	< 2.0	ug/L	4/30/98	8270
bis(2-Chloroethoxy)Methan	< 2.0	ug/L	4/30/98	8270
2,4-Dichlorophenol	< 2.0	ug/L	4/30/98	8270
1,2,4-Trichlorobenzene	< 2.0	ug/L	4/30/98	8270
Naphthalene	< 2.0	ug/L	4/30/98	8270
4-Chloroaniline	< 5.0	ug/L	4/30/98	8270
Hexachlorobutadiene	< 2.0	ug/L	4/30/98	8270
4-Chloro-3-Methylphenol	< 5.0	ug/L	4/30/98	8270
2-Methylnaphthalene	< 2.0	ug/L	4/30/98	8270
Hexachlorocyclopentadiene	< 2.0	ug/L	4/30/98	8270
2,4,6-Trichlorophenol	< 2.0	ug/L	4/30/98	8270
2,4,6 Trichlorophenol	< 5.0	ug/L	4/30/98	8270
2-Chloronaphthalene	< 2.0	ug/L	4/30/98	8270
2-Nitroaniline	< 5.0	ug/L	4/30/98	8270
Dimethylphthalate	< 2.0		4/30/98	8270
	< 2.0	ug/L	4/30/98	8270
Acenaphthylene	< 2.0	ug/L		8270
2,6-Dinitrotoluene	× 2.0	ug/L	4/30/98	0270

Page 3

Lab Number: 98-D936 Sample Number: 98-4703

May 13, 1998

Analysis Performed	Results		Analyzed	Method
3-Nitroaniline	< 5.0	ug/L	4/30/98	8270
Acenaphthene	< 2.0	ug/L	4/30/98	8270
2,4-Dinitrophenol	< 5.0	ug/L	4/30/98	8270
4-Nitrophenol	< 5.0	ug/L	4/30/98	8270
Dibenzofuran	< 2.0	ug/L	4/30/98	8270
2,4-Dinitrotoluene	< 2.0	ug/L	4/30/98	8270
Diethylphthalate	< 2.0	ug/L	4/30/98	8270
4-Chlorophenyl-phenylethe	< 2.0	ug/L	4/30/98	8270
Fluorene	< 2.0	ug/L	4/30/98	8270
4-Nitroaniline	< 5.0	ug/L	4/30/98	8270
4,6-Dinitro-2-Methylpheno	< 5.0	ug/L	4/30/98	8270
N-Nitrosodiphenylamine	< 2.0	ug/L	4/30/98	8270
4-Bromophenyl-phenylether	< 2.0	ug/L	4/30/98	8270
Hexachlorobenzene	< 2.0	ug/L	4/30/98	8270
Pentachlorophenol	< 5.0	ug/L	4/30/98	8270
Phenanthrene	< 2.0	ug/L	4/30/98	8270
Anthrancene	< 2.0	ug/L	4/30/98	8270
Di-n-Butylphthalate	< 5.0	ug/L	4/30/98	8270
Fluoranthene	< 2.0	ug/L	4/30/98	8270
Pyrene	< 2.0	ug/L	4/30/98	8270
Butylbenzylphthalate	< 2.0	ug/L	4/30/98	8270
3-3'-Dichlorobenzidine	< 5.0	ug/L	4/30/98	8270
Benzo(a)anthracene	< 2.0	ug/L	4/30/98	8270
Chrysene	< 2.0	ug/L	4/30/98	8270
bis(2-ethylhexyl)phthalat	< 5.0	ug/L	4/30/98	8270
Di-n-Octylphthalate	< 2.0	ug/L	4/30/98	8270
Benzo(b)fluoranthene	< 2.0	ug/L	4/30/98	8270
Benzo(k)fluoranthene	< 2.0	ug/L	4/30/98	8270
Benzo(a)pyrene	< 2.0	ug/L	4/30/98	8270
Indeno(1,2,3-cd)pyrene	< 2.0	ug/L	4/30/98	8270
Dibenz(a,h)anthracene	< 2.0	ug/L	4/30/98	8270
Benzo(g,h,i)perylene	< 2.0	ug/L	4/30/98	8270
	= • •	J, -	, , , ,	

The analysis of this sample was performed in accordance with procedures approved or recognized by the U.S. Environmental Protection Agency.

James H. Long, Director

Environmental Services Program
Division of Environmental Quality

c: KATHY FLIPPIN, HWP

JOHN ASHCROFT



Former Hulett Lagoon Site Combined PA/SI Reference 53

Acting Director

# STATE OF MISSOURI DEPARTMENT OF NATURAL RESOURCES

DIVISION OF GEOLOGY AND LAND SURVEY P.O. Box 250 111 Fairgrounds Rd. Rolla, MO 65401

### MONITORING WELL INSTALLATION FOR SUNDSTRAND PA/SI

On July 22-29, 1992, two monitoring wells were drilled at the Sundstrand site in Camdenton. This site is located in Section 26, T. 38 N., R. 17 W., in Camden County. These two wells are an upgradient well and a downgradient well for the site. Both monitor the water table which was encountered at depths of 160 to 175 feet. The locations of these wells are indicated on an attached map.

In the downgradient well, bedrock was encountered at a much greater depth than anticipated, and nominal 8 inch steel surfacing casing was installed to a depth of 94 feet. This casing was grouted full length with a 2% CaCl cement. No surface casing was used in the upgradient well. Both wells are completed in the Gasconade Dolomite.

In both wells schedule 80 PVC screen with a size 10 slot, 12-20 sand, and 2" schedule 40 PVC riser pipe was used.

Edith Starbuck, Geologist
Environmental Geology Section
Geology & Land Survey
August 7, 1992

ES/dsb

Post-It® Fax Note 7671	Date 11-9-94 pages 4
To Jim Tucholski	From Edie Starbuck
Co /Dept. H.W.P DEQ	CO DGLS-Rolla
Phone # 314-751 - 2674	Phone # 314-368 - 2136
Fax # 314-751-7869	Fax # 314-368-2111



		<del>-</del>	,					•
GEOLO	GIC D	RILI	. LC	)G	<u>Sun</u>	d:	strand PA/SI, Candenton	PAGE NO. HOLE NO
SIAKI _	LIMIZH	DRILL	ER		10	RILL	METHOD I HOMEHOLE DIAMETER IVELL DIAMETER	TOTAL DEPTH
7/28	7/29	1000	y n	NG ELE	V. G	2 i v	TOTATY 84" 2" DECENTION DEPTH/ELEVATION CROWNDWATER - DATE HE	19-
1	buck		,				COSSI	hly No.
upa				100		'	C The	y recharge
		2110					tenced area, east of bu	uilding
TYPE	3 × E	I	L00	WELL CONSTRUCTION	CLASS- IFICATION	ni 독		, 6
SCE LE	ELOUS.	DEPTH		7.00	PAS	SAMPLE NIERVA	DESCRIPTION	NOTES
SAMPLE TO SAMPLE TO RECOVERY	7 65	ū	GRAPHIC	3.6	PE	r H		
0) 0) 12	•		9	<del></del> -			8.0	
		12	<b>तरा</b>	1 1		1	fill material to about 5,	
	1		<u></u>			-	thin sandstones in sandy red clay with chent	].
1 1 1		24'					7	
		21		1			much chert.	
			<b>*</b>					
		37	<del>7</del>					
			1		]		•	
			7		1 1			
		-	_/	11		'	· w · · · ·	
1 1 1 1			$\coprod$		]	ł	medium gray dolomite	
1 1 1 1	'] ]			11	1		with chert, often	
1	1		7				medium gray dolomite with chert, often sandy	
1111	·		11				Sartay	
			7				•	
			77	11			•	slightly
111		123	77	11		'		moist tuttin
1 1		145	<b>-</b>	-		ı	•	,
		157	7			, [		
1			77				_	
			I	1	ļ	{		W.L. 176'
			_⊈∷	<u>:</u> []::	}		•	
				目			<u>.</u>	v. wet
		197	4				÷	1 _
			1				<u>.</u>	2' seal 52' sand 40' screen
							Aug 9 1995 15952	52 sand
							Aug 9 1995 159.53 below T.O.C.	40 screen
			}				below 7.0.(.	
- A 2711 A 440 A 7								
ASTH BYSES SS = SPLIT D = DENNISH	SPOON C	= CON	BT [U	CS = C	ONITH	hõñs	SANDLER	PACE NO. HOLF NO
- ALMAU A		<del> </del>	·m·	. na -5U				<u> </u>

FIGURE 3-1 FIELD DRILL LOG

Not to scale

GEOLOGIC DOLL LOG PROJE		PAGE NO. HOLE NO.
GEOLOGIC DRILL LOG SU	ndstrand PA/SI, Camdenton	of
	air rotary 84" 2"	197
LOGGER TOP OF CASING ELEV.	GROUND ELEVATION / DEPTH/ELEVATION GROUNDWATER - DATE ME	SURED
Starbuck	approx. 350 176, 7/29/92 (Pass	by recharge
upgradient - insi	de fenced area, east of bu	hilding
والمراجع والمنافع والمناف والمنافع والأنتفاق المنافع المراجع المراجع المراجع المراجع المراجع المراجع	¥	1
T   P   &   T &	ALE RUE	
SAMPLE TO SAMPLE TO SAMPLE BECOVERY BELOWS A CHASS-CLASS-CLASS-CLASS-CLASS-	TRICALLA BANFICE NOITHINDSBD NOITHINDSBD	NOTES
SON GRA	# <u>[</u>	
	fill material to about 5;	
12	thin sandstones in sandy red clay with chert	}
	rea city with there	}.
29'		
	much chert	{
37' 7	, <u> </u>	
	•	}
	medium gray dolomite with chert, often sandy	
	with chert, often	-
	Sandy	
	11	1
		slightly
123//	<b>!</b>	moist fulling
1		
		V. wet .
In Tell		176
		2' seal
		2' seal 52'sand 40'screen
		40 screen
		ļ <sub>i</sub>
*ASTH DTS86 ST = SHELBY TUBE		
*ASTH DISSO ST = SHELBY TUBE  SS = SPLIT SPOON C = CORE CS = CONT  O = DENNISON CT = CUTTINGS BA =BUCKE	INUOUS SAMPLER	PAGE NO. HOLE NO
THE THE PARTY OF T	I AVI	<u> </u>

FIGURE 3-1 FIELD DRILL LOG

PACE NO. THOLE NO.

GEOLOGIC DRILL LOG MOSundstrand Camdenton up 128 FINISH 128 7/29 WELL DIAMETER TOTAL DEPTH TOP of CASING ELEV. DEPTH/ELEVATION GROUNDUATER - DATE MEASURED 176-7/29/92 140 schol 40 pipe 10 slot (16 bags) screen Laa DELL SAMPLE BLOWS\* OEPTH BRAPHIC DESCRIPTION NOTES 0 a commercing gravel in [ 1:11] 5 10-12 15-16 broken olk gray theit enacted clay w/24 20-Z 24 some dolo-little sandy. 30 "good bed somedkand 40' micro xln dolomite 50 60 some med gray chet 70 fine xIn dolomite 80 dolomite - little gray ch 90 sandy dolomite-little with the 100 110 moist :20 123 tan-gray elolomite w/ little chest 127 noisture 132 11 · w/ lots of gray chest -slaghtly -013t 730 143 145. dry 147 sandy dolomite 157 h - V.V. little water ד ו buff-colored dolomite 183 little moist 185 is some chert 190 v. wet v. wet- a respectable amount 196

Floyd said damp @ 163 FIELD DRILL LOG

# CONTINUOUS SAMPLER

MO DNR/DGLS

GEOLOGIC DRILL LOG Sundstrand PA/SI, Camdenton PAGE NO. MOLE NO													
311	RT		माम		DRILL					N C	<u></u>		MW-1
L	7/-	22	7	/27	ì	-	1e	_	la	ai c	rotary 81/2" 2"	1	78 7
								LEV.			SURED	<u>,                                    </u>	
H	7 950 101 . 7 20 /										192		
-	L L		<u>37</u>	900	791		,		50	) ·	west of west parking lo	+	
SAMPLE NO.	SAMPLE TYPE	RECOUERY "	SAMPLE	ELEV	DEPTH	GRAPHIC LOG	WELL CONSTRUCTYON		CLASS- IFICATION	SAMPLE INTERVAL	DESCRIPTION	ТОН	'ES
			•			-					silty red clay with chert.	Sur	مرو
					25						the zone from 10-20 had little chert	casin 94	a to
						6 6					boulders or relict bedding of chert and dolomite		
			•		<b>.80</b>	H					much chent		
					90	出		-	•				
			:		100						sandy dolomite with chert	mois cut	.t tina
					120		-				medium gray dolomite	1	·
						山					with very little chert	w.c.1	61'
					178	4					•	2'5 50's	
			•								÷ .		scree
			•								Aug 9 '95 147.28		
				-							· bebu T.O.C.		
2X°	TH C	5158 PL11	SPO	ST C	= SHE	CBY T	UBE 1	. COI	HTIM	السا الافتاح	SAMPLER	PAGE NO.	HOLE .
œ_	<u>- 0</u> 1	ENNI	<u> 1002</u>	<u> </u>	= CUT	CUUGS	بتقب	<b>AUC</b>	KEL.	ÁÚG.		af	

FIGURE 3-1 FIELD DRILL LOG

Not to scale

PACE NO.

HOLF NO

3-24	<b>1</b> –1	999	3 1	0:48			MO DNF	R∕DGL	.5	573 368 2111	P.07/09.
STA LOGI	/2 ER 5+	22	7	/a7	L	LER 2-y of C	OG   N e_ ISTHE ELI	Su Ev.	RILLI Zi C ROUI A P	AND LOCATION ASTrand PA/SI, Camdenton HETHOD BOREHOLE DIAMETER WELL DIAMETER TOTALY 8/2"/12" DEPTH/ELEVATION GROUNDWATER - DATE HEA Prox 97000000000000000000000000000000000000	TOTAL BEPTH
۲Ö.	TYPE	2				18 6v	Ö	T	T	west of west parking lo	+
	SAMPLE 1	RECOVERY	SAMPL	ELEV	DEFTH	GRAPHIC	WELL	CLASS- IFICATION	SAMPL INTERU	DESCRIPTION	HOTES
					25 80 100 120	サローローロー				silty red clay with chert.  the zone from 10-20 had little chert  boulders or relict bedding of chert and dolomite  much chert.  sandy dolomite with chert  medium gray dolomite  with very little chert	

FIGURE 3-1
FIELD DRILL LOG

TUBE CONTINUOUS SAMPLER
GS BA =BUCKET AUG

ASTH DISSO ST = SHELBY TO SS = SPLIT SPOON C = CORE D = DENNISON CT = CUTTINGS

G	iΕ(	)L	OG	IC D	RILI	 L L	OG	OJECI	NAH	E AND LOCATION	_		<del></del> _	PAGE		OLE NO
	12	2	FIN.		DRILL			- 1		. METHOD	BOREHOLE DI		VELL DIAMETER		TOTAL	
_	CER			·	105		ZING ELE	V.	GROUN	O ELEVATION	DEPTH/ELEVA	TION GROU	7/28	EASURED		
_		0	<u></u>	روح	+		nd	16	0	' sout	hol	NW	corner	of	10	ᡛ
SAMPLE NO.	SAMPLE TYPE	RECOVERY "	SAMPLE Blows*	ELEU	Бертж	GRAPHIC LOG	NEEL CONSTRUCTION	CLASS- IFICATION	SAMPLE		DESCRI	et colo	~		NOTE	
				100 120 130 140 150 170 178		D	M: 1[1] [1] [1] [1]			gray dolo "1	domite " lomite do lami - whin	t chei less ch w smal te - n le & gra 11	t (Hgray) lest o chest	+c		dep
* X 3 S S	TM S	5758 PL 11	SPO	ST	= SHE	BY	18E	ONTI	d mus	SAMPLER				PACE	NO.	HOLE NO

SS = SPLIT SPOON C = CORE CS = CONTINUOUS SAMPLER

DENNISON CT = CUITINGS BA = BUCKET AUG.


FICTOR CLUST IN 80-94 FIELD

FIGURE 3-1 FIELD DRILL LOG

O tan tred silty day 5' - ns - sitty red clay w/ much chert Stiff red clay wicket tragments. 10-12 00 1 Stiff red day w gray che and sandy dolomite tragments - 15-17: " (chert in 3' zone ~ 16'2) 20-20.5'- Stiff red clay w/ small on chest -3 Frech beciding (dolo & chert) 80'- bedrock 12" hole to 94 tremie pipe to 85

Former Hulett Lagoon Site Combined PA/SI Reference 54

# COMPREHENSIVE GROUNDWATER MONITORING EVALUATION MODINE MANUFACTURING COMPANY MISSOURI



### Conducted by

# MISSOURI DEPARTMENT OF NATURAL RESOURCES HAZARDOUS WASTE PROGRAM GROUNDWATER UNIT

CHRIS KUMP ENVIRONMENTAL ENGINEER

**JANUARY, 1998** 

# COMPREHENSIVE MONITORING EVALUATION REPORT MODINE MANUFACTURING COMPANY CAMDENTON, MISSOURI

Prepared by

Chris Kump Environmental Engineer

MDNR HAZARDOUS WASTE PROGRAM

JANUARY, 1998

# **EXECUTIVE SUMMARY**

Modine Manufacturing Company, Camdenton, Missouri produces air-conditioning coils and feeder parts from aluminum and copper tubing. The facility was originally owned and operated by Dawson Metal Products form 1967 to 1974. Sundstrand Tubular products purchased the facility in 1974, and continued operating until 1990. In October 1990 the facility was purchased by Modine Heat Transfer, Inc., now Modine Manufacturing Company. Modine is the current owner/operator of the facility.

Before Modine purchased the facility, Sundstrand submitted a closure plan in September 1990 to terminate interim status and hold generator status only. The closure plan, with approval from MDNR, was implemented in July 1993. Results from the closure plan revealed a release of hazardous waste beneath the facility. Therefore, clean closure could not be granted. As a result, Modine became subject to groundwater monitoring requirements contained in 40 CFR 265. Subpart F. This included the requirement that a groundwater monitoring system be installed to determine whether groundwater contamination has occurred due to the storage of hazardous waste at the facility.

This Comprehensive Groundwater Monitoring Evaluation (CME) was prepared as part of Missouri's authorization under RCRA, on behalf of EPA and under the Missouri Hazardous Waste Management Law and Regulations to determine the regulatory and technical adequacy of Modine's RCRA groundwater monitoring system. As a result of this evaluation MDNR has determined that:

- 1 Modine must draft and submit a Sampling and Analysis Plan that adequately defines the sampling procedures to be followed by sampling personnel.
- The existing groundwater monitoring wells do not adequately determine the rate and extent of groundwater contamination at the facility Therefore, Modine must install additional monitoring wells
- Modine must submit an annual groundwater monitoring report that documents the sampling results and activities, operation and maintenance of the groundwater monitoring system and the adequacy of the monitoring system at the facility for the year

# TABLE OF CONTENTS

I.	<b>OBJE</b>	CTIVE AND SCOPE	1								
II.	SITE DESCRIPTION AND BACKGROUND										
	A. ]	Facility Location	4								
		Site and Regulatory History	4								
		Regulated Unit Description	6								
	<b>D</b> . (	Compliance History	10								
III.	ENVIRONMENTAL SETTING										
	$\overline{\mathbf{A}}$ .	Regional Geology	17								
		Site-Specific Geology	21								
		Site-Specific Hydrogeology	23								
IV.	OPERATION AND MAINTENANCE INSPECTION										
	A	Sampling and Analysis Plan									
		Field Sampling and Analysis Procedures	30								
		Physical Well Integrity Inspection	31								
		Split-Sampling Results	32								
V.	TECHNICAL GROUNDWATER MONITORING EVALUATION										
		ssessment of Hydrogeological Characterization									
		Assessment of Monitoring Well Network	34								
		Annual Groundwater Monitoring Report Content	37								
VI.	CONCLUSIONS										
	A. S	Sampling and Analysis Plan	39								
		Field Sampling and Analysis Procedures	39								
		sical Well Integrity Inspection									
		Split-Sampling Results	40 41								
		Hydrogeological Characterization	41								
		Assessment of Monitoring Well Network	42								
		Annual Groundwater Monitoring Report	43								
VII.	<u>REFEI</u>	RENCES	44								
TAB	LES INC	CLUDED IN REPORT TEXT									
	Table 1	Bedrock Elevation and Thickness	23								
	Table 2		25								

# **TABLE OF CONTENTS (CONTINUED)**

ij

### **APPENDICES**

Appendix A - Location and Site Maps

Appendix B - Operation and Maintenance Inspection Worksheets

Appendix C - Sampling and Analysis Plan Worksheet
Appendix D - Boring/Monitoring Well Construction Logs

Appendix E - Laboratory Analytical Data
Appendix F - Modine Potentiometric Maps

Appendix G - Annual Groundwater Monitoring Report Review Worksheets

Appendix H - MDNR/Modine Correspondence

TABLE 2

ı	MONITORING WELL COMPLETION DATA										
WELL NUMBER	DATE INSTALLED	CASING MATERIAL	CASING DIAMETER	DEPTH TO SCREEN	SCREENED INTERVAL	TOC ELEVATION (bgs)	TOTAL DEPTH (bgs)				
MW-1	7/92	PVC	2"	NR	NR	186.61'	161'				
MW-2	7/92	PVC	2"	NR	NR	204.26'	197'				
MW-3	8/9/95	Steel Surface Casing to 64', Open Hole 64' to 167'	5"* 4-3/4"	None	Open Hole 64' to 167' bgs	193.74'	167'				
MW-4	8/11/95	Steel Surface Casing to 44', Open Hole 44' to 158'	5"* 4-3/4"	None	Open Hole 44' to 158' bgs	192.24'	158'				

bgs - below ground surface

NR - Not Known

\* - Surface Casing Diameter

... T 3

Groundwater monitoring wells MW-3 and MW-4, have shown chronic "insufficient well volume" during sampling events. Both wells have shown detectable levels of VOC contamination during past sampling events, and it is not clear why they are chronically dry If Modine cannot obtain samples from these wells, then a remedy must be sought (i e, redevelopment, well replacement, deepening, etc.) to enable collection at these wells

Special consideration should be given to Modine's close proximity (i.e., within a 4 mile radius) to at least 130 private and at least 1 public drinking water well. It is important that Modine look at the groundwater situation very seriously since any potential groundwater contamination could have a direct affect on the health of groundwater users in the area. It is for this reason that additional monitoring wells to define the limits of potential contamination must be installed in a timely manner.



Former Hulett Lagoon Site Combined PA/SI Reference 55

> 721 Emerson Road, Suite 220 Saint Louis, Missouri 63141-6748 314 993 4599 Tel 314 993 4895 Fax

October 19, 1998

Mr. Thomas S. Sanicola Environmental Engineer Modine Manufacturing Company 1500 DeKoven Avenue Racine, Wisconsin 53403

Re: Fin

Final Letter Report Subsurface Investigation

Monitoring Well Installation - Former Hulett Lagoon

Camdenton, Missouri

Dames & Moore Project No. 27397-035-045

RECEIVED

OCT 21 1998

HAZARDOUS WASTE FHOGRAM MISSOURI DEPARTMENT OF NATURAL RESOURCES

Dear Mr. Sanicola:

Dames & Moore is pleased to submit this letter report summarizing activities relative to the installation of monitoring well MW-5, at the former Hulett Lagoon in Camdenton, Missouri for the Modine Manufacturing Company (Modine). The former Hulett Lagoon is located approximately 1,000 feet northeast of the Modine facility and appears, based upon the results of a previous field fracture survey, to be the source of the observed trichloroethylene (TCE) impact to groundwater. The purpose of this investigation was to determine the presence or absence of volatile organic compounds (VOCs), in particular, TCE in the groundwater underlying the former Hulett Lagoon.

It is our understanding that the Hulett Lagoon is owned and was operated by the City of Camdenton. The lagoon reportedly received wastewater from a number of commercial and industrial facilities; including Sundstrand Tubular Products (Sundstrand), the former owners and operators of the current Modine facility.

The subsurface investigation field activities were conducted from July 7, 1998, through July 16, 1998. A project specific health and safety plan was developed for Dames & Moore personnel and a health and safety briefing was held prior to initiation of the work.

### 1.0 MONITORING WELL INSTALLATION AND GROUNDWATER SAMPLING

Layne-Western Company, Inc. of St. Louis, Missouri was subcontracted by Dames & Moore for drilling services. The monitoring well was drilled using a truck-mounted hollow stem auger drilling rig and an air rotary drilling rig. Following completion, the monitoring well was

Mr. Thomas S. Sanicola Modine Manufacturing Company Dames & Moore Project No. 27397-035-045 October 19, 1998 Page -2-

surveyed for location and elevation relative to the existing monitoring wells at the Modine facility by Robert F. Arnold & Associates of Camdenton, Missouri.

The shallow, non-lithified material was drilled utilizing a hollow stem auger drilling rig. Soil samples were continuously collected with a two and one half foot long split spoon sampler advanced ahead of the augers with a hydraulic hammer. The soil samples were logged by Dames & Moore personnel in accordance with the Unified Soil Classification System (USCS).

Each soil sample collected was stored in a Zip-loc® bag. A photoionization detection (PID) reading was taken of the headspace gas in each of the bagged samples by puncturing the plastic with the tip of the PID probe. The headspace reading is used to approximate organic vapor concentrations. The PID, a Thermo-Environmental OVM Model 580-B, was calibrated daily to a 100 parts per million (ppm) isobutlyene standard. There was no field evidence of impact to the soil based on the PID readings and olfactory indications in the monitoring well; therefore, no soil samples were submitted to the laboratory for analysis. PID readings are presented on the monitoring well log.

Once bedrock was encountered, a temporary casing was set at a depth of 10.5 feet below ground surface (bgs) and the hole was re-entered and diamond cored (NX core) to a depth of approximately 104 feet bgs. The purpose of the temporary casing was to ensure that water used in the coring operation could be recovered and recirculated. Potable water from the City of Camdenton public water supply was used as the coring fluid.

The bedrock was continuously cored using a ten foot NX core barrel. All core material was appropriately marked, logged according to standard logging methods, and stored in NX core boxes. As each core run was removed from the barrel, the bedrock was field screened using the PID. The probe of the PID was run along the length of the core to determine the presence of organic vapors. There was no evidence of impact to the bedrock based on the PID readings and olfactory indications. A well log is attached to this letter report.

The original intent had been to core the well to total depth. However, water loss was encountered during the drilling process beginning at a depth of approximately 22 feet bgs. Water loss appears to have occurred due to the presence of open fractures and void spaces. The water loss problem increased as the boring was deepened, so that the coring operation was terminated at a depth of 104 feet bgs. A total of approximately 5,000 gallons of potable water was lost to the formation.

Mr. Thomas S. Sanicola Modine Manufacturing Company Dames & Moore Project No. 27397-035-045 October 19, 1998 Page -3-

Following coring activities, the hole was re-entered and reamed out to a depth of approximately 118 feet bgs. Groundwater was encountered at an approximate depth of 105 feet bgs.

Permanent surface casing was installed in competent bedrock to a depth of approximately 37 feet bgs. This depth was chosen in order to case off several void spaces which had been encountered during the drilling, notably the void space from 35.0 to 36.5 feet bgs. The monitoring well was constructed with schedule 80, two-inch inside diameter, polyvinyl chloride (PVC) casing with a 0.010 inch slotted screen in accordance with "Missouri Well Construction Rules, June 1996". The well is completed with a screen length of thirty feet and contains a filter pack that extends approximately four feet above the top of the screen. Approximately five feet of bentonite pellets were placed above the filter pack to serve as an annular seal, and were hydrated. Bentonite grout was placed in the hole to approximately 10 feet bgs. The remaining depth was completed with bentonite pellets to approximately one foot below the top of PVC casing. The well was completed approximately two and one half feet above surface grade with a 6-inch diameter protective casing surrounded by a two foot square concrete surface pad. A locking cap was placed on the protective casing to ensure the integrity of the well.

Prior to sampling, the well was gauged to assess the groundwater level and determine the volume of water to be purged. An attempt was made to air lift the water out during development; however, due to the limited water column and the low recharge rate, the procedure was unsuccessful. In order to develop the well, approximately 10 well volumes of groundwater were removed (approximately 30 gallons). The monitoring well was purged in accordance with RCRA Ground-Water Monitoring TEGD guidelines. Purging was done with a dedicated, disposable, polyethylene bailer and new poly-rope. The purged water was containerized in an on-site 55-gallon drum.

The well was sampled using a dedicated disposable bailer and new poly-rope. The bailer was slowly lowered into the water to minimize agitation. Samples were transferred from the bailer to the sample containers in a manner as to minimize agitation and aeration. Personnel conducting the groundwater sampling wore a new pair of clean disposable latex gloves. A duplicate sample was also collected from the well. The samples were shipped, under proper Chain-of-Custody, in an iced cooler by overnight delivery service to Specialized Assays, Inc. and were analyzed for volatile organic compounds (VOCs) by EPA Method 8260.

Measures were taken to reduce the possibility of cross contamination between sampled intervals. After each use, the soil samplers were decontaminated with a high pressure wash. Personnel who handled tools and collected samples were a new pair of disposable latex gloves for each sample

Mr. Thomas S. Sanicola Modine Manufacturing Company Dames & Moore Project No. 27397-035-045 October 19, 1998 Page -4-

acquisition. A decontaminated set of augers, barrel rods, and air rotary rods were used for the installation of the monitoring well.

Investigation-derived waste was segregated according to waste type. The purged water was stored in a 55-gallon drum which remains stored near MW-5 for future use. The water used in the air rotary process and the reamed bedrock material were stored in 55-gallon drums. The drums were properly labeled and staged at the facility in a fenced in area on the west side of the building. Modine is responsible for the proper disposal of these investigation-derived waste.

### 2.0 ANALYTICAL RESULTS

Soil samples were not submitted to the laboratory for analysis. A groundwater sample and a duplicate sample were collected from MW-5 for analysis. Additionally, a water sample was collected from the decontamination water holding tank and the coring water holding tank. The results obtained for each of the samples are summarized below:

- Monitoring Well MW-5: The groundwater sample collected from MW-5 exhibited a concentration of TCE at 484.1 ppb and cis-1,2-dichloroethene at 28.0 ppb. A duplicate sample was collected from MW-5 which exhibited a concentration of TCE of 458.5 ppb and cis-1,2-dichloroethene of 28.2 ppb.
- Core Holding Tank: The water collected from the core holding tank originated at the facility and exhibited a TCE concentration of 3.0 ppb.
- Decontamination Holding Tank: The water collected from the decontamination holding tank originated at the facility and exhibited a TCE concentration of 3.2 ppb.

### 3.0 GROUNDWATER ELEVATIONS

Groundwater depths relative to top of casing were determined for all five monitor wells on July 31, 1998. Groundwater depths were determined using a decontaminated Solinst® electronic water level indicator. This indicator was decontaminated between each use. The resulting groundwater elevations, along with the surveyed elevations of the casing tops are shown in Table 1.

The groundwater elevations (Figure 1) confirm the generally trough-like configuration of the groundwater potentiometric surface, which has been observed in previous gauging events. MW-1

Mr. Thomas S. Sanicola Modine Manufacturing Company Dames & Moore Project No. 27397-035-045 October 19, 1998 Page -5-

is approximately in the center of the trough-like surface. Data from MW-5 demonstrate that groundwater is flowing generally to the southwest, in the direction of the Modine facility. This flow direction is parallel to the direction of the primary fracture set identified in the 1996 Fracture System Investigation. These data strongly suggest that TCE in groundwater beneath the former Hulett lagoon is the source for TCE-impacted groundwater at MW-4.

### 4.0 GEOPHYSICAL LOGGING

Dames & Moore contracted with Century Geophysical Corporation (Century) to perform geophysical logging of MW-5. This logging was accomplished on July 31. 1998 and was witnessed by Ms. Miesche Francis of Dames & Moore.

The suite of logs run in this well included induction resistivity, gamma ray, and neutron. The 2-inch diameter casing size prevented running the density tool. Since the well contained water only at the base, acoustic and spontaneous potential logs were not run. Copies of the geophysical logs are included as Appendix B.

The results of the logging are discussed below. All depths discussed in this section are depth below top of casing, except as noted.

The resistivity log for MW-5 indicates metallic casing installed to a depth of 40 feet. Rock beneath this casing is shown to be fairly high in resistivity, which is consistent with carbonate rock, and fairly uniform. Both the resistivity and the gamma ray curves do not support major changes in lithology. A conspicuous gamma ray peak, which corresponds to a resistivity low, occurs at 84 feet. This appears to be the same feature observed in all four of the other wells and was referred to in the 1996 fracture system report as the "gamma marker". In all five wells, this feature marks the upper boundary of an increase in resistivity. The gamma marker is estimated to be approximately three feet thick in MW-5. The neutron response increases for nearly 20 feet below the gamma marker, indicating less porous rock. According to the core log, the gamma marker corresponds approximately with a fractured, vuggy crystalline limestone, which overlies a relatively nonporous grainstone. The structural elevation of the gamma marker is 95.44 feet, approximately 30 feet higher relative to the marker at the Modine plant. Therefore, any stratigraphic component of flow in the unsaturated zone may be in the direction of the Modine facility (Figure 2).



Mr. Thomas S. Sanicola Modine Manufacturing Company Dames & Moore Project No. 27397-035-045 October 19, 1998 Page -6-

### 6.0 FUTURE TASKS

Dames & Moore has begun the procedures to conduct a groundwater tracing event at the facility. The proper documents have been completed and submitted to the Missouri Department of Natural Resources (MDNR) to obtain permission to conduct this trace. As of the date of this letter report, Dames & Moore has not received a response from the MDNR. However, dye bugs consisting of activated charcoal were placed in all of the on-site monitoring wells (MW-1, MW-2, MW-3, and MW-4) for the purpose of background sampling to determine if fluorescein dye exists in the groundwater beneath the facility. The dye bugs were lowered in the well column approximately half way into the groundwater and left in place for one week. The dye bugs along with a grab groundwater sample were collected from all of the on-site wells and a grab groundwater sample was also collected from the City of Camdenton Mulberry Well. The samples were placed in appropriate containers and shipped via overnight courier to Ozark Underground Laboratory, Inc. to determine the presence, if any, of fluorescein.

### 7.0 SUMMARY AND CONCLUSIONS

TCE was detected in the groundwater sample collected from MW-5 located near the former Hulett Lagoon. The concentration of TCE significantly exceeds the Drinking Water Standards and Health Advisories level of 5 ppb for TCE. Groundwater appears to flow southwest from the former Hulett Lagoon towards the Modine facility. Based upon these results, it is Dames & Moore's opinion that the source of the TCE in the groundwater beneath the Modine facility is the former Hulett Lagoon.

>•3**3**(**3**(3)300<

Mr. Thomas S. Sanicola Modine Manufacturing Company Dames & Moore Project No. 27397-035-045 October 19, 1998 Page -7-

Dames & Moore is pleased to present this letter report summarizing the activities associated with the installation of MW-5 at the former Hulett Lagoon and additional tasks associated with the subsurface investigation at the Modine facility in Camdenton, Missouri. If you have any questions or comments regarding the contents of this report, please contact either of the undersigned at (314) 993-4599.

Very truly yours,

Dames & Moore

Daniel J. Price, R.G. Managing Principal

St. Louis Office

J. Ronald Sides, Ph. D.

Senior Geologist

DJP/JRS:nkh

P \045\10-OCT98\MISC\_JOB\CORRSPND\SANI\_19.JRS






### TABLE 1

# Groundwater Elevations July 31, 1998 Modine Heat Transfer Facility Camdenton, Missouri

	Casing Elevation	Depth to Water	Groundwater Elevation
MW-1	186.61	153.75	32.86
MW-2	204.26	166.46	37.80
MW-3	193.74	154.78	38.96
MW-4	192.24	159.46	32.78
MW-5	179.44	104.19	75.25

<sup>\*</sup> Elevation references a coordinate system previously established for this project.



NOTE: VERTICAL DATUM IS PROJECT SPECIFIC, NOT USGS.

CONTOUR INTERVAL IS IO FEET. EXCEPT WHERE DASHED (5 FEET). MODINE HEAT TRANSFER, INC. CAMDENTON, MISSOURI

DATE: Aug. 20, 1998 JOB NO.: 27397-035-05 DRAWN BY CHK'D BY

SCALE:

JRS


JMS



DAMES & MOORE

721 EMERSON ROAD, SUITE 220 ST. LOUIS, MISSOURI 63141 PHONE: 314-993-4599

R:\ENV\27397.035\MODINEFI.DWG 08/20/98



NOTE: VERTICAL DATUM IS PROJECT SPECIFIC, NOT USGS.

CONTOUR INTERVAL IS IO FEET, EXCEPT WHERE DASHED (5 FEET).

# FIGURE 2 SUBSURFACE STRUCTURE ELEVATION OF GAMMA MARKER

MODINE HEAT TRANSFER, INC. CAMDENTON, MISSOURI

DATE:
Aug. 20, 1998
JOB NO.:
27397-035-05
DRAWN BY CHK'D BY
JMS JRS
SCALE:

DATE:

Aug. 20, 1998
GROUP

YC CHUMN

DAMES & MOORI

GROUP A DAMES & MOORE GROUP COMPANY
721 EMERSON ROAD, SUITE 220
ST. LOUIS, MISSOURI 63141
PHONE: 314-993-4599

R:\ENV\27397.035\MODINEF2.DWG 08/20/98

## PROJECT MADINE SUBSURFACE INVESTIGATION

Hole No. MW-5 Feature Former Hult Lagann	Angle (from Horizontal) VELTICAL Bearing	Ground Elevation
Coordinates: N	Date Started 7-9-98	Rock Elevation Overburden Thickness 10.5
E	Date Completed 7-10-98	Ground-Water Elevation 1CH.2. (7-16-95
Core Sizes	Total Depth 104	Logged by M.M. FEALLS

	Core Sizes			.			0990	ed b	y .	M.M. FRANCIS
	, Te	- 1	aph Log			ohic	×			Para-la
	Depth (Elevation)	Lithology	Structure	Attitude	Classification and Physical Condition	C.RGrap	Core Rec. %	RaD %		Remarks (Sample Data, Water Levels, Drilling Characteristics etc.)
	- 1 - 2				ML BROWN SILTY CLAY WHIT brownish yellow strangers, soft dry, with trace charte gravel and its to BROWNEH TELLOW.	2	5	5	11	50% Reserving
	- - 3 - 4				CL YELLOWISH RED CLAY with brown Statement, hard, mest, etiff, with Charly grave!		4	7	8	50% Recovery -
J 1	- 5 - 5 - 7	1.				ч	6	10	ic	75% Resource
	-7 - -9				1"chat kirs at 1.0"	3	4	9	10	ovm 16.2 # 4 6.8"
$\oplus$	- 5 - 70 - 10	_/.v			Weathered Immesters, H. Ireur, over+ beauting	7.	E	: 1	5%	50% Recovery -
	— 11 - — 12 -	LS	1 11. 1. 1	00000	Top of Rock at 10.5'  Xtalline Linxelone, Gircinstone, Light Eray, thin layers of more Sincly Xtalling rach porous	THE STATE OF THE PARTY.	4	4		Core#1 Start 3:55 P _ Start 4:25 P _ Fradure not open _
	-13 - -14 - 15			0 0 00	Vuggy and Chatbeaung 14.51-15.0' Bedding Plane Jonts	1	,001	56%		0VM7 0.0
718/95			, / in :	00.	Linvestono, profestono. Hi gray, perous vuony Mudding granzion in a filed gray and town			53% ×1		Corce D. Benet DIE IA. Str. a. II A Fracture not open.
	- 18 - 18 - 18		·		If our bearing, 18.27-18.57  Limestone grounston on Hi gray of co-theory	44.	X	X		No PID reading  Const 3 Claum 1:21 A  Claum 9:57 A

#### GEOLOGIC LOG

## PROJECT MODINE STESSILEACE INVESTIGATION

Hole No Feature FOV Coordinates: Core Sizes	N.	C.F.	hu l	Angle (from Horizontal) Net ICA  Lett Lagran Bearing  Date Started 7-7-98  Date Completed 7-10-98  Total Depth 104'	. Ro	ock rert	Ele	vati en	ration ion Thickness 10.5 ter Elevation
Depth (Elevation)		Structure & d	_	Classification and Physical Condition	C.RGraphic	Core Rec. %	Rab %		Remarks (Sample Data, Water Levels, Drilling Characteristics etc.)
- - 21 - - 22 - - 23	<u>9</u>	-	000	21.2 Too Fracture.  Linus 1. Construction of the construction of t		43%	34%		Fractionics not open I'Mould loss [48"x96"Arough]
-24 -25 -26				Limestone, promiser is the company of the company o				٠	Core# 4 Start 10:14/ Stop 11:14/
- 77 - 75 - 73	LS	6	0	2011) Coch fragiens		0/200)	.tl2,%		Clay SAMI
-30 - -31 - -32				Salidio Postra					2" fluid Ices in a line in
-33 -34 -35		7+	45°	VOID 32.19 - 83.59 Chartegray and Property of Agencians	4444	· 	Σ		6"-1"   6"   6"   6"   6"   6"   6"   6"
-36 -37 -38	re		26.70	VOID 35.01-33.57  Limeters producting clay dups, the state of the stat		%c9.			No enventation 100% Thirdies (pen-involution)

## PROJECT MONNE SUPSUL FACE HIVESTIGATION

	Feature TOY Coordinates:	N N	Angle (from Horizontal) VCITICAL  THUICH AQQQC Bearing  Date Started 7-7-95  Date Completed 7-10-05  Total Depth 10-1						Ground Elevation  Rock Elevation  Overburden Thickness  Ground-Water Elevation  Logged by M.M. FRAINCS						
	Depth Elevation)		Structure & de	_	Classification and Physical Condition	-Graphic	re Rec. %	RaD %		Remarks (Sample Data, Water Levels,					
		불	Stru	Att		C.R.	8			Drilling Characteristics etc.)					
	- 40 - 41 - 12		スー	0	Ho.6' 45 estacture Chart, gray to light gray barded	HI 0000				-					
	— 42 - — 43		-	4	42.0-42.8° Chert, rubtle, with elaucenite fractured	20	% JUI	30 %							
	- 백 - - 박5		- \	00	Limestone rubble, It. brown w/sandstone. Limestone, grainstone, brown 14.5' Open fractures	<b>开打</b> [htt	1/2	`^ !		Corest 7 Start 5:10P					
,	- - 40 - :-	LS	,	65	45.3° 65° fracture Limestone, mildstone, Itbrown to beige, mothed Limestone, grainstone, banded, it brown to					- - -					
	- 32 - 32 - 33				tergo, vuiggy 48.3° Limostone, mudstone to grainstone It brown	丑	3/2	V		- -					
$\oplus$	- 50 - 50 -		~/	35 c	49.8° 35° fracture		· 99	19		-					
	-51 		<b>≋</b> :	٥											
-9-98			イミ	C	52.2° 75° fracture	Δ <sub>Δ</sub>				0VM 0.0 Stop 6:10p.					
	-: # -: #		7	0 00 75	53.5' 70° fracture 53.8' 75° fracture	STHIP :	Σ	X		Numerous offer the made to complete step 12:475					
					that, Hearce, Vugosi Limestone, grainstene, Itbrown, chest bearing	ΔΔ				Strp 1:26 p_					
			1	10	son goo open fracture. chert, rubble, aray limestone, midstone, It brown, mottled chert bearing (beige)	44	%u0	-9609		ONW C.S					
			-	c	chert, gray, vuggy	۵۵				-					
	F		2	0	59.0' 45° open-fracture	۵ ۵	X	X		Core+ ? Start 1:35p					

## PROJECT MODINE SUBSURFACE INVESTIGATION


Hole No. MW-5 Feature Former Huk # Lancon	Angle (from Horizontal)  Bearing  Date Started 7-7-98	Ground Elevation
Coordinates: N	Date Started 7-7-98	Overburden Thickness 10.5
Ε	Date Completed 7-10-98	Ground-Water Elevation
Core Sizes	Date Completed 7-10-98 Total Depth 104	Logged by M.M. FRATICIS

Core Sizes				Date Completed 7-10-98 Total Depth 104	c.		۰ م	u/-	ter Elevation M.M. FRANCIS
Depth (Elevation)		Structure 80 de		Classification and Physical Condition	C.RGraphic	Core Rec. %	Rap 🛪		Remarks (Sample Data, Water Levels, Drilling Characteristics etc.)
- 62 - 63 - 64 - 65 - 66	Ŋ	~= X ~ ~	070	60.0' openfracture Chert, rubble gray 61.2' Limostone, H brown 61.4' Chert 51.6' Limostone, grainstone, H brown banded, Vuggy, mottled 62.0' open fractures 62.5' Limostone, H brown, chert bearing Limostone, grainstone, chert bearing, vuggy, mottled, banded 1+ beige	444	% × × ×	:	•	OVM. 0.0
-67 -68 -69 -70 -71 -73	LS	( )	೦ ಇಂ	chert, Higray to med. gray bands with limesions vuos 68.2-68.60 vertical open fracture 69.2' umestone, grainstone, H. brown to base banded, motified, vuogy (chert-filled) porous		Σ			OVM 0.0  Core#   Start 4 50 = 5:11 p
-73 -16-98 -74/7/ - -75 -76	<i>77.</i>	7/	\.\.\.\.\.\.\.\.\.\.\.\.\.\.\.\.\.\.\.	Limestone, mudstone, juggy, cher bearing /Focines, icss of c.5° ////////// Limestone, gravistone, it brown, banded, vuggy, chert bearing Open fractures		Σ Ζ	У. У	7;	Core#12. star+11.32 7-10-98 stop 1.45
-77 -78 -79		~	0	open-fracture chert, H. peige, motiled with gray bands onen-fracture.	111111111111111111111111111111111111111	<i>48</i> %	%\%		

#### GEOLOGIC LOG

				PROJECT MODINE SUBSURFAC	E	-11	JE	S	MEATION			
Hole No. Feature FOT Coordinates: Core Sizes	N. E.	••••		Angle (from Horizontal)  CH LAQON Bearing  Date Started 7-10-08  Date Completed 7-10-08  Total Depth 104	Rock Elevation Overburden Thickness 10.5							
		aphi	С		<u>.</u>	•	Г	Г				
Depth (Elevation)	Lithology	Structure &	Attitude	Classification and Physical Condition	C.RGraphic	Core Rec. %	RaD %		Remarks (Sample Data, Water Levels, Drilling Characteristics etc.)			
-81 -81 -82 -83 -84 -85 -87 -88 -90 -91 -95 -97			०००० ०४५० ० ० <del>४</del> ० ००५० ०	Chert, gray to med. gray banded Lime stone, brown, xystalline Chert, gray, motilled, vuggy Limestone, it brown Chert, gray banded Limestone, brown, vuggy 83.6' 45° fracture  Chert, gray to ltgray banded Open vertical fracture Limestone, it brown Chert (86.0') Limestone, grainstone, clart bearing, rugg, motiled Limestone, percus, gravistore chert, med. gray motiled, vuggy Limestone, it brown, gravistore Chert, med. gray motiled, vuggy		× × × × × × × × × × × × × × × × × × ×	20/ M N		Core#14 240 = 317F - Step 3:50 F.			
-98				konded		48	75%		-			

				PROJECT JYIUDINY, SUBSURFAC	5	N	UE	5	TIGHTIUIU								
Coordinates:	N.			Angle (from Horizontal)  TT LKGON Bearing  Date Started 7-7-98  Date Completed 7-10-98  Total Depth 104	. 0	Ground Elevation  Rock Elevation  Overburden Thickness 10.57  Ground-Water Elevation  Logged by M.M.+RHNUS											
Depth (Elevation)		Structure & d		Classification and Physical Condition	C.RGraphic	Core Rec. %	RaD %		Remarks (Sample Data, Water Levels, Drilling Characteristics etc.)								
100		~	^	Limestrue Harail paraula agun	3/	T	1										
- 101	is	$\sim$	U	Limestone, Harry, porous grain- Stone Chert, Harry with dark gray					-								
-				VUOS					-								
- 103 -		_	_	Limestone, grainstone, H. brown banded. Motiled, chait beauting													
- 104		~	<u>U</u>	END OF CORE	中	V	V.	-									
F				2.00													
-									-								
F																	
F									-								
									-								
F 1									-								
									-								
-				*					]								
E																	
-																	
									-								
-																	
<u> </u>									-								
F																	
-									_								
F																	
-																	
-																	
-																	
									-								



721 Emerson Road, Sume 220 Same Louis, Missouri 63141-6748 314 993 4599 Tel 314 993 4895 Fax

TO CHRIS KUMP

MONR

Fex Number

573-526-5268

From

RON 51055

Date

11/9/98

Subject

MODINE

No. of pages

7

ANALYTICAL REPORTS, MW-5

- 1) GAMPLE
- DI SAMPLE DUP
- 3) TRIP BLANK

CALL WIHANY QUESTIONS

This message is intended only for the use of the individual or entity to which it is addressed, and may contain information that is privileged, confidential, and exempt from disclosure under applicable law. If the reader of the message is not the intended tecipient, or the employee or agent responsible for delivering the message, you are hereby notified that any dissemination, distribution or copying of the communication is strictly prohibited. If you have received this communication in error, please notify us immediately by telephone and return the original message to us at the above address via the U.S. Postal Service.

#### ANALYTICAL REPORT

DAMES & MOORE 7378
DEBORAH Y. WHITAKER
2135 E. SUNSHINE, SUITE 105
SPRINGFIELD, MO 65804

Leb Number: 98-A83247 Sample ID: MW05-GW1-Q1-98 Sample Type: Ground water

Site ID:

Project: 27397-035-045

Project Name: MODINE SUBSURFACE INVEST

7 1 0000701000 AN /60 01 10 /00 01 00 00 11 /01111

Sampler: MIESCHE FRANCIS

Date Collected: 7/16/98
Time Collected: 12:52
Date Received: 7/17/98
Time Received: 9:00

Analyte	Result	Onits	Peport Limit	Quan Livit	Dil Factor	Data	Time	Analyst	Method	Batch
*AUTSLIFE ONEVAICE*								# Mankan	an(An	199
Acetone	<b>T</b> D	<b>15/</b> 1	0.0100	0,0100	1	7/18/98	1:15	6. Norton	8260B 8260B	199
Bensaur	ND	<b>ag/</b> ]	0.0020	0.0020	1	7/38/98	1:15	G.Noztoa		
Broschensens	MD.	<b>25</b> /1	5,5820	6.0020	1	7/18/98	1:15	G. Forton	8260B	199
Bromochloromethane	TD .	<b>1</b> 9/1	0.0020	0.0020	1	7/18/98	1:15	C. Norton	82608	199
Bronofers	RD	<b>mg/1</b>	0.0020	0.0030	1	7/18/98	1:15	G. Martos	5260B	199
Stononethere	ND CN	<b>ag/</b> 1	0.0020	0.0020	1	7/18/98	1:15	G. Nortoz	82608	195
2-Butanose	#D	<b>Eq/1</b>	0.0166	0.9100	1	7/18/98	1:15	6. Forton	8750B	155
a-Batylbensene	yd	<b>29/3</b>	0.0020	9.0028	1	7/18/98	1:15	G.Borton	8260B	199
sec-Butylbanssas	TO	<b>sg/l</b>	0.0020	8.0020	1	7/18/98	1:15	6.Bortom	82608	199
t-Butylbensene	TD .	<b>ag/</b> 1	0.0020	0.0020	1	7/18/58	1:15	G. Morton	B2603	197
Carbon dissifide	3D	mg/l	0.0020	0.0020	1	7/18/98	1:15	6. Porton	8260B	199
Carbos tetrachlorida	ND	19/1	0.0029	6.0020	1	7/18/98	1:15	G. Horton	82603	199
Chlorobensens	AD	mq/l	0.0020	9.0026	1	7/38/98	1:15	6.Norton	6240B	199
Chlorosthans	10	mq/1	0.0020	0.0020	1	7/18/98	1:15	G. Norton	826¢B	199
1-Chlorosthylvinylether	TD.	ng/l	0.0020	0.0020	1	7/18/98	1;15	G. Vorton	8260B	199
Chlorofors	MD	<b>mg/l</b>	0.0020	0.0020	1	7/18/98	1:15	G. Fortes	82658	399
Chlorosethene	KD.	mg/1	0.0020	0.0078	1	7/18/98	1:15	6. Norton	62603	199
7-Chlorotolyene	#D	<b>mg/1</b>	0.0020	0.0020	1	7/18/98	1:15	6. Norton	8260B	199
4-Chlorotolnene	ND.	<b>89/</b> )	0.0020	0.0020	1	7/18/98	1:15	6.Vorton	82603	199
1,2-Dibroso-3-chloropropane	<b>PD</b>	<b>e</b> g/1	0.0100	0.0100	1	7/18/98	1:15	6.Nortos	8260B	199
Dibrosechloromethens	50	mg/1	0.0020	0.0028	1	7/18/98	1:15	6. Forton	82663	199
1.2-Dibromoethame	ED.	ng/i	0.0020	0.6020	1	7/18/98	1:15	6. Norton	82603	199
dibrosomethane	TD.	<b>eq/</b> ]	0.8026	0.0820	1	1/38/98	1:15	6.Morton	1260B	199
1,2-Dichlorobeasene	¥D	<b>Bq/l</b>	0.0020	0.0020	1	7/18/98	1:15	G. Forton	82683	199
1,3-Dichlorobeasese	173	mg/1	0.0020	0.0020	1	7/18/98	1:15	G. Morton	9260B	199
1,4-Dichlorobensene	nd	mg/I	0.0020	0.0020	1	7/12/98	1:15	C.Nortos	82608	199
Dirhlorodifluoromethane	XD	<b>ag/</b> 1	0.0020	0.0020	1	7/18/98	1:15	E. Norton	8760B	199
1,1-Dichloroethase	KD.	<b>mg</b> /1	0.0020	0.0026	1	7/18/98	1:13	6. Norton	8760B	199
1,1-Dichloronthane	#D	M/)	0.0020	0.8020	1	7/18/98	1:15	G. Norton	8760B	199
1,1-Dichloroethene	WD	<b>ag/1</b>	0.0020	0.0070	1	7/18/98	1:15	6. Norton	8260B	199
cis-1,2-Dichloroethene	0.0280	<b>ag/1</b>	0.0020	0.0026	1	7/18/98	1:15	G. Forton	6260B	199
trans-1,2-Dichloroethess	ND D	mg/1	0.0020	0.0020	1	7/18/98	1:15	G. Jorton	8260B	19"
1,2-Dichloropropane	ND	eg/l	0 0020	0.0020	1	7/15/98	1:15	G. Nortes	8260B	1/

#### ANALYTICAL REPORT

Laboratory Number: 98-A83247 Sample ID: MWO5-GW1-Q1-98

Page 2

Analyte	Resolt	Units	Report Limit	goar Limit	gil Factor	Data	Time	Analyst	Hethod	Batch
1.3-Dichloropropane	¥D	mg/l	6.0020	0.0028	1	7/18/98	1:15	G.Morton	\$260B	199
2,2-Dichloropropane	ED .	<b>ag/</b> ]	0.0020	0.0020	1	7/18/98	1:15	E. Horton	8260B	199
1,1-Dichloropropess	ND	mg/]	0.0020	0.0020	1	7/18/98	1:15	6.Portob	8260B	199
cia-1,3-Dichloropropose	MD	mg/1	8,0020	0.0020	1	7/18/98	1:15	G.Nortos	82608	199
trans-1,3-Dichloropropess	<b>VD</b>	mg/l	0.0029	D. 0020	1	7/18/98	1:15	6. lorton	<b>8</b> 1608	199
Sthylbessens	XD	<b>9</b> 9/1	0.0020	0.0020	1	7/18/98	1:15	G. Norton	8260B	199
Hezachlorobutadiane	XD	<b>199</b> /3	0.0820	0.0026	1	7/18/98	1:15	G. Forton	6260B	199
2-lezanone	N)	mg/l	0.0100	0.0100	1	7/18/98	1:15	C.Nortes	\$2609	199
Isopropylbensene	ND	mg/l	0.0020	0.0020	1	7/18/98	1:15	6. Mortos	82608	199
4-leopropyitoluana	10	ag/1	0.0010	0.0020	1	7/18/98	1:15	6. Morton	8260B	199
f-Mathyl-2-pentanose	10	<b>29/1</b>	0.0100	0.0100	1	7/18/98	1:15	5. Sorton	82503	199
Methylene chloride	FD	mg/1	0.0020	0.0020	1	7/18/98	1:15	6.Nortos	8260B	199
Taphthelens	FD	<b>24/</b> }	0.0020	0.0020	1	7/18/98	1:15	6. Norton	82603	195
n-Propylbenzene	ND	<b>mg/1</b>	0.0020	0.0020	1	7/18/98	1:15	6.Nortes	8260B	199
Styrale	YD	BQ/1	0.0020	0.0020	1	7/18/98	1:15	G.Nortos	82608	199
1,1,1,2-Tetrachloroethame	m	mg/l	0.8020	0.0020	1	7/18/98	1:15	G. Norton	8260B	199
1,1,2,7-Yetrachloroethane	10	<b>ag/1</b>	0.0020	0.0020	1	1/18/98	1:15	6. Norton	8250B	199
Tetrachloroethens	RD	<b>84/1</b>	0.0029	0.0020	1	7/18/98	1:15	6.Norton	B260B	199
Toluese	ND	<b>19</b> /1	0.0020	0.0020	ì	7/18/98	1:15	G.Nortoz	8260B	159
1,2,3-frichlorobensene	19	sq/1	0.0020	0.0028	i	7/18/98	1:15	C. Borton	8260B	199
1,2,4-Trichlorobeasese	ND .	mg/1	0.0020	0.0020	ī	7/18/98	1:15	G.Mortes	8260B	199
1,1,1-Trichlorosthaue	FD.	Bg/)	0.0020	8.0020	1	7/18/98	1:15	G. Norton	82693	199
1.1.2-Trichlorosthess	n)	M()	0.0020	0.0020	i	7/18/98	1:15	E.Norton	82608	199
Trichloroethese	0.4841	mg/l	0.0200	0.0020	10	7/20/98	16:39	C.Norton	8260B	199
1,2,3-Trichloropropass	10	mg/1	0.0020	0.0020	i	7/18/98	1:15	G.Morton	\$260B	199
			0.0020	0.0020	1	7/18/98	1:15	G. Norton	8250B	199
1,2,4-Primethylbeatene	¥Ď	<b>BQ</b> /1	0.8620	0.0010	i	7/18/98	1:15	G. Forton	8260B	199
1,3,5-Trinethylbensene	<b>10</b>	mg/1	0.9020 0.0020	0.0020	1	7/18/98	1:15	5. Fostor	82603	199
Vieyl chloride	ND	#9/1 == (1	•	0.0020	1	7/18/98	1:15	6. Vorton	82603	199
lylenea	10	<b>34/1</b>	0.0020		1	•	1:15	G. Norton	82603	199
Browdichloromethane	ND	<b>8</b> g/1	0.0028	0.0020	-	7/18/98			82608	199
Trichlorofluoromothass	#D	<b>mg/l</b>	0.0020	0.0020	1	7/18/98	1:15	g. Nostob	410nD	123

ND = Not detected at the report limit.

Surrogate	t Recovery	Target Range
VOA Burrogate, 1,2-Dichloroethane, d4	77.	70 131.
VOA Surrogate, Toluene de	90.	83 115.
VOB Eurrogate, 4-Eronofluorobensens	88.	73 119.
VOA Socrogate, Dibromofluoromethase	82.	72 130,

#### ANALYTICAL REPORT

DAMES & MOORE 7378
DEBORAH Y. WHITAKER
2135 E, SUNSHINE, SUITE 105
SPRINGFIELD, MO 65804

Project: 27397-035-045

Project Name: MODINE SUBSURFACE INVEST

H - 1 0000701000 1011/60 01 10/00 01 00 00 11/4++1

Sampler: MIESCHE FRANCIS

Lab Number: 98-A83248

Sample ID: MM05-GW1-Q1-98-D Sample Type: Ground water

Site ID:

Date Collected: 7/16/98
Time Collected: 12:52
Date Received: 7/17/98
Time Received: 9:00

Laslyte	Result	Opits	Report Limit	Quan Limit	Dil factor	Date	Tipe	Analyst	Nethod	Betch
•VOLATILE ORGANICS4										
Acetose	<b>I</b> D	<b>59/</b> 1	0.0150	9.0100	1	7/18/98	1:51	6. Horton	8260B	159
Benzeze	KD	<b>14</b> /1	0.0020	0.0026	1	7/18/98	1:51	g.Morton	8260B	199
Bronobensene	HD	<b>29/1</b>	0.0020	0.0020	1	7/18/98	1:51	G.Bozton	5260B	199
Bronochloromethane	ND	<b>B</b> 9/1	0.0020	D.0020	1	7/18/98	1:51	6. Horton	87683	199
Bronoform	ND	mg/1	0.6020	0.0020	1	7/18/98	1:51	6. Norton	82500	199
Broncusthane	XD	<b>eg/</b> ]	0.0020	0.0020	1	7/18/98	1:51	g.Wortes	6260D	199
2-Butarose	10	mg/1	0.0100	0.0100	1	7/18/98	1:51	6.Nortoz	#260B	199
n-Butylbanene	10	mg/l	0.9020	0.0020	1	7/18/98	1:51	G.Noston	8260B	199
sec-Buty)beasene	ND	<b>39/1</b>	0.0020	0.0020	1	7/18/98	1:51	C. Varton	82609	199
t-Butylbansene	10	11g/l	0.0020	0.0025	1	7/18/98	1:51	6. Forton	8260B	199
Carbon displfide	13	<b>89/1</b>	0.0020	0.0020	1	7/18/58	1:51	6.Norton	8260B	199
Carbon tetrachloride	10	<b>99/1</b>	0,0020	0.5020	1	7/18/98	1:51	\$.Norton	82609	199
Chlorobessens	173	mg/l	0.0020	0.0020	1	7/18/98	1:51	G. Norton	82608	199
Chlorpethans	FD FD	ag/l	8.0020	0.0020	1	1/18/98	1:51	G.Roston	826QB	199
2-Chloroethylvinylether	n	mg/l	0.0020	0.8020	ĭ	7/15/98	1:51	G.Norton	82603	199
Chloroform	10	eg/3	0.0020	8.00ZD	i	7/18/98	1:51	6.Norton	8260B	199
Chlorosethans	ער. מנ	ag/1	0.0020	0.0020	ī	7/18/98	1:51	6.Vorten	82608	199
1-Chlorotolnese	10	E9/1	0.0020	0.0020	i	7/16/98	1:51	6.Vortes	8260B	199
4-Chlorotolesse	10	ed/7	0.0020	8.0028	i	7/18/98	1:51	6.Borton	82609	199
	ND NA	8g/l	0.0010	0.0100	i	7/18/98	1:51	C.Fortes	82603	199
1,2-Dibroso-3-chloropropase	-		0.0020	6.0020	i	7/18/98	1:51	G. Forton	8260B	195
Dibranochloroset bane	AD CX	<b>ag/1</b>	0.6020	8.0020	i	1/18/98	1:51	G. Borton	8260B	199
1,2-Dibromoethame		<b>119/1</b>	0.0020	0.0020	1	7/18/98	1:51	E.Rorton	82503	199
Dibrementhans	#D	<b>99/1</b>	0.0020	0.0020	i	T/18/98	1:51	6. Norton	826QB	199
1,2-Dichlorobensene	BD	mg/1	0.0028	D.0020	1	7/18/98	1:51	G. Norton	8260B	199
1,3-Dichlorobensene	ND	<b>aq/1</b>	0.0020 0.0020	0.0020	1	7/18/98	1:51	G. Warton	82608	199
1,4-Dichlorobensess	)D	<b>eg/</b> ]	0.0020	0.0020	i	7/18/98	1:51	G. Norton	8260B	199
Dichlorodillapromethane	MD OR	<b>Bg/l</b>			-	7/10/98	1:51	S. Norton	82603	199
1,1-Dichlorosthane	ND .	<b>sg/l</b>	0.0020	0.0028 0.0020	1	7/18/98	1:51	C. Norten	8250B	199
1,1-Dicklorosthams	TB	<b>05/1</b>	0.0920	0.0020	1	7/18/98	1:51	6. Norton	8266B	199
1,1-Dichloroethops	ND	mg/1	0.0020	•	1		1:51	G. Horton	8260B	199
cie-1,2-Dichlorcethane	0.0287	<b>mg/1</b>	0.0020	0.8020 6.0020	1	7/10/98 7/18/98	1:51	G. Nortes	82608	199
trans-1,2-Dichloroethene	ND	<b>sg/1</b>	0.5020	-	-		1:51	G. Horton	8260B	199
1,2-Dichloropropade	KD.	<b>ag/l</b>	0.0020	0.0020	1	7/16/95	1:21	o.Pyi Lui	41014	477

## ANALYTICAL REPORT

Laboratory Number: 98-A83248 Sample ID: MW05-GW1-Q1-98-D

Page 2

Assiyts	Result	Units	Report Limit	Quan Limit	Dil Vactor	Date	Tire	laalyst	Method	Batch
1,3-Dichloropropane	ND	<b>sy</b> /l	0.0020	0.0020	1	7/18/98	1:51	C. Forton	82603	195
2.2-Dichloropropane	KD.	99/1	0.9020	0.0020	1	7/18/98	1:51	C. Norten	8260B	199
1,1-Dichloropropess	ND .	<b>s</b> g/l	0.0020	0.0020	1	7/18/98	1:51	0. Norton	52603	199
cis-1,3-Dichloropropene	ND	<b>89/1</b>	0.0020	0.0020	1	7/18/96	1:51	6.Nortos	8260B	199
trans-1,3-Biebloropropens	10	mg/1	0.0020	0.0020	1	7/18/98	1:51	6.Vortos	82601	199
Riphipersese	ND	29/1	0.0020	8.0020	1	1/18/98	1:51	6.Norton	82609	199
Mexachlorobutadiese	rd	<b>3</b> 9/1	0.0820	0.0020	1	7/18/98	1:51	G.Mortos	1250B	199
J-16391046	AD.	mg/]	0.0100	0.0100	ĺ	1/18/98	1:51	C. Norton	8760B	199
Isopropylbessese	10	<b>19/1</b>	0,0020	0.6620	1	7/18/98	1:51	6.Norton	1260D	199
4-laopropyitoliese	n	8g/1	0.0028	0.0020	1	7/18/98	1:51	G. Nortas	8250B	199
	ND	ag/1	0.0100	9.0100	1	7/18/98	1:51	G. Borton	8260B	199
4-Hethyl-2-pentanone	KD MD	#9/1 #9/1	0.0020	0.0020	i	7/18/98	1:51	C. Morton	82608	199
Nethylene chloride	FD OF	eg/1	0.0020	0.0020	i	7/18/98	1:51	G. Mostos	8260B	199
Waphthalene	ND	<b>8</b> g/1	0.8020	0.6020	ī	7/18/98	1:51	G. Marton	8260B	199
a-Propylbessese	ND	mg/l	0.0020	0.0020	i	7/18/98	1:51	G. Mortos	8260B	199
Styrens	10 10	mg/1 mg/1	0.0020	0.0020	1	7/18/98	1:51	G.Nortos	82603	199
1,1,1,1-Yetrachloroethane	10 10	29/l	0.0020	0.0020	î	7/18/98	1:51	6. Marton	8260 <del>9</del>	199
1,1,2,2-Tetrachioroethane		85/1	0.0020	₹.0020	i	7/18/98	1:51	G. Warton	82608	199
Tetrachloroethese	ed Ed	mg/l	0.0020	0.0020	i	7/18/98	1:51	E. Nortos	8260B	199
Toluene	עפ סא		0.0020	0.0020	i	7/18/98	1:51	G. Kortan	4260B	199
1,2,3-frichlorobenzene		<b>eq/</b> 1	0.0020	0.0020	1	7/18/98	1:51	G. Vorton	B260B	199
1,2,4-Trichlorobensess	TD	<b>BQ/</b> 1	0.0020	0.0020	i	7/18/98	1:51	G.Norton	8250B	199
1,1,1-frichlorostheme	ND	mg/l		9.0020	i	7/18/98	1:51	G. Mortos	87508	199
1,1,2-Trichloroethana	ND .	<b>29/1</b>	0.0010				11:57	G. Roztoz	8260B	199
Trichloroethene	0.4585	mg/1	8.0256	0.0020	10	7/20/98	1:51	6. 301 tob	82503	Ì99
1,2,3-trichloropeopase	M	<b>85</b> /3	0.0020	0.0020	1	7/18/98		-	82603	199
1,7,4-Trimethylbeoseme	ND	<b>19/1</b>	0.0020	9.8020	1	7/18/98	1:51	6. Morton	82608	199
1,3,5-Trimetbylbensena	AD.	14/1	0.0020	0.0020	1	1/18/98	1:51	6.Forton	82603	199
Vinyl chloride	ND.	<b>mg/l</b>	9.0020	0.0020	1	7/18/98	1:57	G. Norton		-
Tylenes	HD	<b>24</b> /]	0.0020	0.0020	1	7/18/98	1:51	6. Forton	82608	199
Brosodichloromethane	KD	<b>24/</b> ]	0.0020	9 9020	1	7/38/98	1:51	G. Nortos	8250B	195
Trichlorofluorosethane	AD.	<b>9</b> g/1	0.0020	8.0020	1	7/18/98	1:51	6. Norton	82603	199

ND = Not detected at the report limit.

Burrogate	1 Pacovery	Target Range
VOA Burrogate, 1,2-Dichloroethane, d4	62.	70 131.
VOA Syrrogate, Tolorne de	89.	<b>83.</b> - 115.
VOA Surrogate, 4-Bromoflyorobenseme	50.	<b>73 119</b> .
VOR Surrogate, Dibrosofluoromethame	85.	72 130.

ANT STAAR TO WOOT WATER

٠. ٠ .

#### ANALYTICAL REPORT

DAMES & MOORE 7378 DEBORAH Y. WHITAKER 2135 E. SUNSHINE, SUITE 105 SPRINGPIELD, MO 65804

Lab Number: 98-A83249 Sample ID: TRIP BLANK Sample Type: Ground water

Site ID:

Project: 27397-035-045

Date Collected: Time Collected:

Project Name: MODINE SUBSURFACE INVEST Date Received: 7/17/98

Time Received: 9:00

Sampler: MIESCHE FRANCIS

laziyte	Besult	Vaits	Peport Limit	Ques Limit	Dil Pactor	Pate	Time	Asalyst	Method	Batch
+POLATILE ORGANICS+									88785	***
lcetone .	IJ	呵/1	0.0100	9.0100	ì	7/18/98	0:03	6.Porton	82508	199
Bensene	ND.	<b>sg/l</b>	8.0020	6.0020	1	7/18/98	6:01	G.Norton	8260B	199
Brozobensene	ND .	<b>89/1</b>	0.0020	0.0070	1	7/19/94	6:61	6. Verton	82603	199
Bromochlo/gmethans	YD	<b>eg/1</b>	0.0020	6.0020	1	7/18/98	0:01	G. Forton	8260B	199
Brazofors	vd	19/I	0.0028	0.0020	1	7/18/98	0:61	6.Norton	82603	195
Bromomethane	ND	mg/1	0.0020	0.0020	1	7/18/98	0:01	6. Norton	8260B	199
2-Brtanope	M	<b>9</b> 5/1	9-0100	0.0100	1	7/18/98	0:01	C. Norton	6260B	199
n-Butylbensene	ND	mg/1	0.0020	<b>8.00</b> 26	1	7/18/98	0:01	G. Norton	8260B	199
sec-Botylbeasene	ND	<b>3</b> 9/1	9.0020	9.0020	1	7/18/98	0:61	6.Norton	82603	199
t-Butylbansane	KD	<b>39/1</b>	0.6020	9.0020	1	7/18/98	0:01	6. Norton	8260B	199
Carbon disulfide	ND	跨/1	0.6020	0.0020	1	7/18/98	0:01	G. Morton	62688	199
Carbon tetrachloride	#D	<b>ag/1</b>	8.0020	0.0020	1	7/18/98	8:01	6.Vortan	8260B	199
Chlorobansane	AD .	09/1	0.0020	0.0020	1	7/18/98	0:01	6.Norton	8260B	159
Chloroethade	ND ON	<b>8</b> 4/1	0.0010	0.0020	1	7/18/98	0:01	C.Norton	8260B	199
2-Chloroethylvisylether	ND	m/1	0.0020	0.0020	1	7/16/98	0:01	6. Nortos	82608	199
Chlorofors	n	8g/l	0.8020	0.0020	i	7/18/95	8:01	G.Norton	8260B	199
Chlorosethane	<b>ID</b>	BQ/1	0.0020	0.0020	ì	7/18/98	0:01	6. Norten	8250D	199
2-Chlorotolneme	ND N	<b>39/1</b>	6.0020	0.0020	1	7/18/98	0:61	G. Morten	<b>82608</b>	199
4-Chloratoluene	53	mg/l	0.6020	0.0020	ì	7/18/98	0:01	G. Norton	82608	199
1.3-Dibrono-3-chloropropess	ND	<b>89/</b> 1	0.8100	0.0100	ì	7/18/98	0:01	G. Nortos	B260B	199
Diptomochloremethane	RD	5q/l	0.0020	0.0020	i	7/18/98	0:01	G. Serton	82608	199
	RD	19/1 19/1	0.0020	0.0020	î	7/18/98	0:01	6.Forton	8260B	199
1,2-Dibromoethane	ND		0.0026	0.0020	i	7/18/98	0.01	G.Norten	8250B	199
Dibrosomethane		<b>39/1</b>	0.0020 0.0020	0.0020	i	7/18/98	0:01	C. Morton	8260B	199
1,2-Dichlorobensese	ND	mg/1	0.0020	0.0020	1	7/18/98	0:01	C. Nortos	8260B	199
1,3-Dichlorobenzane	ID .	mg/1			-	7/18/98	0:01	6. Nortos	8260B	199
1,4-Dichlorobensese	#D	mg/]	0.0026	0.5026	1		0:01	G. Norton	9260B	199
Dichlorodifluoromethane	VB	#g/1	0.0020	0.0029	1	7/18/98	0:01	G. Norton	8260B	199
1,1-Dichloroethane	<b>ID</b>	<b>■</b> 9/1	0.0020	0.0070	1	7/18/98			8250B	199
1,2-Dichloroethane	nd	<b>ug/1</b>	0.0020	0-0020	1	7/18/98	D:01	G. Forton	8260B	199
1.1-Dichloroethene	M	<b>11</b> 9/3	0.0020	0.0020	1	7/18/96	0:01	6. Norton		199
cis-1,1-Dichloroethene	PD	mg/l	0.0020	0.0020	1	7/18/98	0:01	6. Norton	8260B	199
trans-1,2-Dichloroethead	ND .	<b>ag/3</b>	0.0020	0.0020	1	7/18/98	0:01	G. Norton	8260B	
1,2-Dichluropropane	HD	<b>1</b> 9/1	0.0020	0.0020	1	7/16/98	0:01	6.Forten	82603	199

(a) (b) (b) (b) (b) (c)

## ANALYTICAL REPORT

Laboratory Number: 98-A83249 Sample ID: TRIP BLANK

Page 2

Lelyte	Result	Units	Apport Limit	Quan Lisit	Dil Factor	Date	Ties	Analyst	Nethod	Batch
1.3-Dichloropropane	ND	mg/1	0.0020	0.0020	1	7/18/98	0:01	G. Mortos	826DB	199
1,2-Dichleropropana	ND	mg/1	0.0028	0.0020	1	7/18/98	8:01	C.Norton	6260B	199
1,1-Dichleropropene	ad .	<b>ag/1</b>	0.0020	0.0028	1	7/14/98	0:01	6. Nortes	82608	199
cis-1,3-Dichloropropses	10	<b>39</b> /1	0.0020	0.0020	1	7/16/98	0:01	6. Forton	8260B	199
trans-1, 3-Dichloropropese	ID	mg/l	0.0020	8,0020	1	7/18/98	0:01	6. lortor	8260B	199
Bthylbensene	ND	mg/1	0.0020	0.0020	1	7/18/98	0:01	G. Morton	87609	199
Resachiprobutadiene	W	<b>eg/</b> ]	0.0020	0.0020	1	7/18/98	0:01	6.Norton	8260B	199
Z-Zerabons	ND OK	<b>29/1</b>	0.0100	0.0100	1	7/18/98	0:01	C. Mortos	8260B	199
Lappropylbensese	ND	<b>1</b> 9/1	0.0020	8.0020	1	7/18/98	0:01	G. Norton	\$260B	199
4-Isoprepyltolasme	<b>F</b> D	<b>ag/1</b>	0.0020	0.0020	1	7/18/98	0:01	G. Mortes	0260B	199
4-Methyl-2-pentanose	10	mg/1	0.0100	0.0100	1	7/18/98	0:01	G. Morton	8260B	199
Mathylane chloride	סע	ag/)	0.0020	4.0028	1	7/18/98	0:01	6.Yortes	82608	199
Paphthelene	10	89/1	0.0020	0.0020	1	7/18/98	0:01	C. Verten	8260B	199
n-franklyssere	RD	mg/1	0.0028	0.0820	1	7/18/98	0:01	G. Norton	8260B	159
Styrane	NO	<b>3</b> 1/1	0.0820	0.0028	1	7/18/98	0:01	6.Nortos	82609	199
1,1,1,2-Tetrachloroothass	מנ	<b>ug/</b> )	0.0020	0.0020	1	7/18/98	0:01	G. Martos	8260B	199
1,1,2,2-Tetrachloroethane	ID .	#9/1	0.9020	0.0020	1	7/18/98	0:01	G. Forton	8260B	199
Tetrachlorosthans	ND	=g/l	p.0020	0.0020	i	7/18/98	0:01	6. Fortos	8260B	199
Tolvese	ND	ag/1	0.0020	0.0020	ì	7/18/98	0:01	G. Morton	5260B	199
1,2,3-Trichlorobensese	XB	<b>8g/l</b>	0.0020	0.0020	1	7/18/98	0:01	5.Worten	82608	199
1,2,4-Tricklorobensane	ND	<b>ag/1</b>	0.0020	0.0020	1	7/18/98	0:01	C. Barton	82608	155
1,1,1-Trichloroethane	BD	#g/]	0.0025	D.0020	ì	7/18/98	0:01	G. Norton	8260 <b>u</b>	199
1,1,2-Trichloroethane	ND	eg/l	0.0020	0.0020	i	7/10/98	0:01	C.Forton	82608	199
richlorpathene	45	8g/)	0.0020	0.9826	i	7/18/98	0:61	C. Morten	8250B	195
	ND 40	<b>s</b> g/l	8.0020	0.0020	i	7/18/98	0:01	6. Torton	B260B	199
1,2,3-Trichleropropage	ND ND	<b>8</b> g/l	0.0020	0.0020	1 .	7/18/98	0:01	G. Norton	8260B	199
1,2,4-Trimethylbensese	<b>ND</b>	mg/1	0.0020	0.0020	i	7/18/98	0:01	G. Norton	8260B	199
1,3,5-trisethylbensene			0.0020	0.0020	i	7/18/98	0:01	G. Forton	\$250B	199
Vanyl chloride	ji) Ti	mg/l	0.0020	0.0020	i	7/18/98	0:01	6.Vortes	9760B	199
lyleaes	Ð	<b>mg/l</b>		0.0020	1	7/18/98	0:01	6.Borton	82609	199
Bresedichloromethane	<b>FD</b>	<b>=g/</b> }	0.0020		1	7/18/98	0:01	G. Forten	92603	199
Trichlorofluoromethane	ID	mg/l	0.0020	8.0DZO	1	1170120	4.47	A . AAT COD	45400	• • •

ND = Not detected at the report limit.

1 Recovery	Target Range		
	********		
100.	10 131.		
87.	83 115.		
94	73 119.		
95.	72 130.		
	100. 87. 94		



## MISSOURI DEPARTMEN

Former Hulett Lagoon Site Combined PA/SI Reference 57

Headqu

2901 West Truman Boulevard, P.O. Box 180, Jefferson City, Missouri 65102-0180 Telephone 573/751-4115 ◆ Missouri Relay Center. 1-800-735-2966 (TDD)

**IERRY M CONLEY, Director** 



RECEIVED

DEC 1 5 1998

Ms. Julie Kelsey
Department of Natural Resources
P. O. Box 176
Jefferson City, MO 65102-0176

HAZARDOUS WASTE PROGRAM MISSOURI DEPARTMENT OF NATURAL RESOURCES

Re: Herculaneum Smelter; Faerber Farm

AFormer Hulett Lagoon; Highway AF Wells

Dear Ms. Kelsey:

Thank you for your letter of November 2, 1998 regarding rare, threatened and endangered species within the proposed project area.

Review of our records show that public lands, sensitive species or communities are known to exist on or near the above referenced sites. Please refer to the enclosed Heritage Database report for details. This report reflects information we currently have in our database. We provide this information for planning purposes only; it should not be regarded as a definitive statement as to the presence or absence of rare/endangered species or high-quality natural communities. Additional on-site inspections may be needed to verify the presence or absence of such species or communities.

Thank you for the opportunity to review and comment.

Sincerely,

MARY LYON
POLICY ANALYST

ML:klm Enclosure

COMMISSION




### MO DEPARTMENT OF NATURAL RESOURCES P.O. BOX 176 JEFFERSON CITY, MO 65102-0176

#### FORMER HULETT LAGOON

#### The following species and/or natural communities are known to occur on or in the vicinity of the project site:

Scientific Name	Common Name	Federal <u>Status</u>	State Status	State Rank	Size/ Acres	Township/ <u>Range</u>	Sec.	<u>Ownership</u>
4-mile radius - source #1 and #2								
SPIRANTHES OVALIS VAR EROSTELLATA	OVAL LADIES' TRESSES			S2	0	037N017W	01	DNR
AMBYSTOMA ANNULATUM	RINGED SALAMANDER			S3	0	038N017W	27	PRIVATE
CHERT SAVANNA				S2	45	037N017W	02	DNR
DOLOMITE GLADE				S3	17	037N017W	11	DNR
CHERT SAVANNA				S2	50	037N017W	14	DNR
TYPHLICHTHYS SUBTERRANEUS	SOUTHERN CAVEFISH			S2S3	0	037N017W	02	DNR
DOLOMITE GLADE				S3	24	038N017W	35	DNR
DOLOMITE GLADE				S3	12	037N017W	10	DNR
MOIST LIMESTONE/DOLOMITE CLIFF				S4S5	0	037N017W	01	DNR
ARDEA HERODIAS	GREAT BLUE HERON			S5	0	037N017W	03	DNR
DOLOMITE GLADE				S3	13	037N017W	12	DNR
DRYOPTERIS CARTHUSIANA	SPINULOSE SHIELD FERN			S1	0	037N017W	01	DNR
DOLOMITE GLADE				S3	21	037N017W	11	DNR
HEMIDACTYLIUM SCUTATUM	FOUR-TOED SALAMANDER			S3	0	037N017W	02	DNR
MYOTIS GRISESCENS	GRAY BAT	E	E	S3	0	037N017W	02	DNR
LIMESTONE/DOLOMITE TALUS				S4S5	3	037N017W	01	DNR
DOLOMITE GLADE				S3	20	037N017W	11	DNR
MESIC FOREST				S3	5	037N017W	01	DNR
DRYOPTERIS GOLDIANA	GOLDIE'S FERN			S2	0	037N017W	01	DNR
DOLOMITE GLADE				S3	14	037N017W	10	DNR
DOLOMITE GLADE				S3	12	037N017W	01	DNR
DOLOMITE GLADE				S3	10	037N016W	18	PRIVATE
15 river miles, source #1								
MYOTIS GRISESCENS	GRAY BAT	E	E	S3	0	038N018W	02	PRIVATE





#### MO DEPARTMENT OF NATURAL RESOURCES

#### FORMER HULETT LAGOON

#### Additional in formation for planning purposes:

Gray bats are likely to occur in the project area, as they forage over streams, rivers, and reservoirs in this part of Missouri.

Pallid sturgeons are big river fish that may range widely in the Mississippi River and Missouri River system. Because the preferred habitat and range of the species are unknown, any project that modifies big river habitat or impacts water quality should consider the possible impact to pallid sturgeon populations.

Overwintering bald eagles may occur in the project area, as they are common winter residents in big river habitats and major lakes where they feed on fish.

#### Public land in the 4-mile radius, source #1 and #2:

Camdenton Conservation Service Center

Missouri Depratment of Conservation

Ha Ha Tonka State Park

Missouri Department of Natural Resources

Ha Ha Tonka Savanna Natural Area

Missouri Department of Natural Resources

#### Public land along 15 river miles, source #1:

Larry Gale Access

Missouri Department of Conservation

FEDERAL STATUS - The federal status is derived from the provisions of the federal Endangered Species Act, which is administered by the U.S. Fish and Wildlife Service. The Endangered Species Act provides federal protection for plants and animals listed as Endangered or Threatened. E = Endangered, T = Threatened, C = Candidate for Federal listing.

STATE STATUS (E) - the state status is determined by the Department of Conservation under constitutional authority. <u>Rule 3CSR10-4.111Endangered Species</u> of the *Wildlife Code of Missouri* and certain state statutes apply to state Endangered species

STATE RANK - A numeric rank of relative endangement based primarily on the number of occurrences of the species within the state of Missouri. S1 = Critically imperiled in the state, S2 = Imperiled in the state, S3 = Rare and uncommon in the state

Heron rookeries, eastern collared lizard populations, natural communities and geologic features are recognized as sensitive biological resources and may also appear on this report



# Former Hulett Lagoon Site Combined PA/SI United States Department of the Treference 58

14 }-

#### FISH AND WILDLIFE SERVICE

Ecological Services Columbia Field Office 608 East Cherry Street, Room 200 Columbia, Missouri 65201 Tel: 573/876-1911 Fax: 573/876-1914

FWS/AES-CMFO

DEC | 8 1998

Ms. Julie B. Kelsey
Department of Natural Resources
Hazardous Waste Program
P.O. Box 176
Jefferson City, Missouri 65102-0176

Dear Ms. Kelsey:

This letter is in response to your November 2, 1998 letter asking the U.S. Fish and Wildlife Service (Service) for information on the presence of federally-listed threatened and endangered species, sensitive environments, and wetlands which may be present at or near the Herculaneum Smelter in Johnson County (Township 41N, Range 5E, Section 29), the Faerber Farm in Gasconade County (Township 45N, Range 4W, Section 6), the former Hulett Lagoon in Camden County (Township 38N, Range 17W, Section 24), and the Highway AF Wells in Franklin County (Township 40N, Range 2W, Section 5). This response is provided by the Service under the authority of the Fish and Wildlife Coordination Act (16 U.S.C. 661 et seq.), the National Environmental Policy Act of 1969 (42 U.S C. 4321-4327), and the Endangered Species Act of 1973, as amended (16 U.S.C. 1531-1543).

None of the sites being investigated appear to impact State or Federal fish and wildlife lands or facilities, nor do they impact lands which were acquired or are managed with Federal grant-in-aid assistance under the Wildlife Restoration Act (Pittman-Robertson Act, Public Law 75-415) or the Fish Restoration Act (Dingell-Johnson Act, Public Law 81-681).

#### Herculaneum Smelter and Faerber Farm

Both the Herculaneum Smelter and the Faerber Farm are in close proximity to the Missouri and Mississippi Rivers and habitats associated with the federally-listed endangered pallid sturgeon (Scaphirhynchus albus), threatened Bald Eagle (Haliaeetus leucocephalus), endangered Interior Least Tern (Sterna antillarum athalassos), and endangered Piping Plover (Charadrius melodius), which occur along either river during certain times of the year. Due to the proximity of the Faerber Farm to the Missouri River and the proximity of the Herculaneum site to Jefferson County, the federally-listed endangered Indiana bat (Myotis sodalis) might also occur

#### Pallid Sturgeon

The federally-listed pallid sturgeon is widely distributed in the Missouri River and also occurs in the Mississippi River south of St. Louis, downstream from the mouth of the Missouri. These fish are well adapted to the bottoms of large, turbid, free-flowing rivers with swift water.

Julie B. Kelsey

Major threats to this species include habitat destruction, over harvest, and pollution. Though more research is necessary, it is suspected that pollution of the Missouri River by organic wastes coming from cities, livestock impoundments, industrial areas, and packing houses have negatively affected populations as sites such as these have increased over time and occur in nearly 45% of the pallid sturgeon's range.

In addition, elevated polychlorinated biphenyls (PCB's), cadmium, mercury, and selenium have been detected in tissue samples collected from pallid sturgeon in the Missouri River. Other contaminants, such as chlordane, DDE, DDT, and dieldrin have also been detected. Abandoned landfills, mines, sewage treatment plants, and industries all have high potential to contaminate pallid sturgeon habitat.

#### Bald Eagle

The federally-listed threatened Bald Eagle frequently winters in forested habitat along the Missouri and Mississippi Rivers. Bald Eagles generally prefer the largest trees (> 12 inches diameter at breast height) for perching and roosting. They generally forage on fish, dead and dying waterfowl, and carrion. Wintering populations have been increasing in Missouri, although counts fluctuate widely from year to year dependent upon ice over in the northern part of the eagle's range. Nesting Bald Eagles are also increasing, but to date, no nest sites are near either the Herculaneum or Faerber sites.

Eagles can be adversely affected by heavy metals, bacteria, and other contaminants. Due to the scavenger behaviors of the eagle, they often feed on dead or dying prey which may have been poisoned in some way or may have elevated bacterial levels. In such cases, eagles can be affected through a secondary pathway in the food chain which could harm or kill individuals. Direct toxic effects of organochlorines such as dieldrin, endrin and DDT have also contributed significantly to declines in eagle populations.

#### Interior Least Tern

The federally-listed endangered Interior Least Tern currently nests in the Bootheel region of Missouri along the Mississippi River. Terns presently use the Missouri River as a migration corridor from nesting sites in Nebraska and the Dakotas. During these times, May and between August and early September, birds are seen more frequently. They may use shallow, seasonal wetlands located in the Missouri River floodplain to rest and forage. The primary cause of decline for Interior Least Terns is habitat destruction and predation, though elevated levels of heavy metals have been found in egg tissue taken from the bootheel nesting grounds (Charbonneau, pers. comm).

#### Piping Ployer

The federally-listed threatened Piping Plover occur in Missouri as transients during migrational periods to wintering grounds on the Gulf Coast and are predominantly from the Northern Great Plains population. Piping Plovers do not nest in Missouri, and historical records do not indicate they ever did (Fish and Wildlife Service, 1988). Birds only occur very rarely between April and May and August through September during migrational flights. Mud flats, sand bars, and wet open fields on or near the Missouri River floodplain may be utilized during this period for rest and foraging. The primary cause for

Julie B. Kelsey

Piping Plover decline is habitat destruction, predation, and human disturbance.

#### Indiana bat

The federally-listed endangered Indiana bat may also occur near these two sites. Indiana bats spend the winter hibernating in caves in the Ozarks. During April and May, females migrate north and establish small maternity colonies in suitable sites within wooded riparian areas, floodplain forests, or upland woodlots. Maternity roost sites tend to be in dead or dying trees greater than 9 inches in diameter at breast height and with loose or exfoliating bark. Trees most likely to have loose or exfoliating bark are dead oaks, hickories, elms, green and white ash, silver maple, and eastern cottonwood, or living shagbark hickory. Preferred roost sites are located in forest openings, at the forest edge, or where tree canopy is sparse, and within 1 km (0.6 mi.) of water where they forage on flying insects. Indiana bats continue to decline in parts of its range, including Missouri. Reasons for decline are habitat disturbance/destruction, deforestation, stream channelization, and pesticides.

Finally, both the sturgeon chub (Macrhybopsis gelida) and sicklefin chub (M. meeki) have been proposed as Candidates for listing and occur in the Mississippi and Missouri Rivers. To date, they have no protection under the Endangered Species Act, and are provided here for your information only. Both the sicklefin and the sturgeon chub are close associates, occupying the open channels of swift, large, turbid rivers over sand and fine gravel. Neither species have ever been abundant in the Missouri River but are more common in the lower 300 miles of the river.

#### Former Hulett Lagoon

No federally-listed threatened or endangered species occur directly on this site, however, Bald Eagles do winter at the Lake of the Ozarks. Please see our comments above regarding habitat and life history traits of wintering Bald Eagles.

#### Highway AF Wells

The federally-listed endangered Indiana bat has been documented at Meramec State Park. The three creeks listed are not within the same watershed as the Meramec, however, during the summer roosting period, Indiana bats may utilize habitats along each creek as they migrate north. See our comments above regarding Indiana bat habitat and life history traits.

The federally-listed endangered gray bat (Myotis grisescens) also has been documented in cave habitats at Meramec State Park. The gray bat occupies a limited geographic range in limestone karst areas of the southeastern United States, including Missouri. With rare exception, the gray bat roosts in caves year-round. In winter, most gray bats hibernate in vertical (pit) caves with cool, stable temperatures below 10 degrees Celsius. Summer caves, especially those used by maternity colonies, are nearly always located within a kilometer (0.6 mile) of rivers or reservoirs over which bats feed. The summer caves are warm with dome ceilings that trap body heat. Most gray bats migrate seasonally between hibernating and maternity caves, and both types of caves are located in Missouri. Gray bats are active at night, foraging for insects

Julie B. Kelsey

over water or along shorelines, and they need a corridor of forest riparian cover between roosting caves and foraging areas. They can travel as much as 20 kilometers (12 miles) from their roost caves to forage.

We are concerned about the water quality of Spring Creek, Winsel Creek, and the Bourbouse River due to the presence of many mussel "species of concern". The sheepnose (Plethobasus cyphyus), snuffbox (Plagiola triquetra), and scaleshell (Leptodea leptodon) all occur in the Bourbeuse river near the Highway AF Wells. Mussels are extremely sensitive to pollutants and heavy metals, including pesticides, runoff from agricultural fields, livestock wastes, mine tailings, industrial pollutants, and heavy organic loads from sewage. Again, each of these mussel species currently have no protection under that Endangered Species Act and they are provided here for your information.

If you have not already done so, please contact the Missouri Department of Conservation regarding Missouri species of conservation concern (Planning Division, P.O. Box 180, Jefferson City, Missouri 65102).

#### Wetlands

Because your letter did not identify the specific site locations, we can only comment on wetlands in general. There are numerous small farm impoundments within the sections identified in your letter. Though these may have wetland characteristics, the Service is primarily concerned with naturally occurring wetlands. Most wetland habitat near these sites can be found along streams and within the floodplains of major rivers. The Service's National Wetland Inventory (NWI) maps are available for all of Missouri and may help you identify wetlands and other aquatic habitats near each site. NWI maps for approximately the northern two-thirds of Missouri are available free of charge in digital form over the Internet at: <a href="http://www.nwi.fws.gov">http://www.nwi.fws.gov</a>. You can also order paper NWI maps through the U.S. Geological Survey's Earth Science Information Center (ESIC). For information and NWI map availability, call ESIC's toll free number 1-800-USA-MAPS. Orders and payment for NWI maps in Missouri should be sent to:

USGS/ESIC Mid Continent Mapping Center 1400 Independence Road, Mail Stop 231 Rolla, Missouri 65401 (573) 308-3500

Thank you for contacting the Service for the opportunity to review this project. Please contact Ms. Kelly Srigley Werner of my staff at (573) 876-1911 ext. 112 if you have further questions or need additional assistance.

Sincerely,

R. Mark Wilson Field Supervisor





# WELCOME! MABLE/Geocorr Geographic Correspondence Engine Version 3.01



[OSEDA Mirror] | [SEDAC Mirror] | [CENSUS Mirror]

This application allows you to access the MABLE geographic data base and to generate custom "correlation lists" as reports and/or files.

#### Help | Examples | Usage Notes Output Samples | New in V3 | Articles | Future

This form has 5 main sections. Only the first 2 are required.

Input | Output | Point & Distance | Bounding Box | Geographic Filter

Note: In most of the select-list boxes below you can make multiple selections. Some browsers require that you hold down the ctrl key while clicking before it will recognize multiple selections.

#### Input Options

Select state(s) to process. (Limit of 5 states on weekdays, 7 AM - 6 PM) (Required Option)

Random Pick
ALABAMA
ALASKA
ARIZONA
ARKANSAS
CALIFORNIA
COLORADO
CONNECTICUT
DELAWARE


For background information and help with any of the geographic codes used in the MABLE database (source/target geocodes) consult the file:

MAGGOT

(Master Area Geographic Glossary Of Terms)

Select "SOURCE" Geocode(s)

Select "TARGET" Geocode(s)



• Digits of Hydrological Unit Codes to keep: C 2 C 4 C 6 @ 8

Weighting Variable:	
Specify the weighting variable to use for determining the portion of the source geocodes corresponding to the target geocodes:	☐ Ignore Census Blocks with
Population (1990 census)  Land Area (square km)  Housing Units (1990 census)	a value of 0 for the weighting variable.

\*\*\* Hydrologic Unit Codes are normally 8 digits, but you can specify keeping only the first 2, 4 or 6

(region, subregion and accounting units). These codes not available for Alaska and Hawaii.

#### Output Options

Have weighted centroids calculated and kept on the output file(s)	Generate 2nd allocation factor (AFACT2): portion of <i>target</i> geocodes in <i>source</i> geocodes	Sort by target geocodes, then source geocodes (default is by source, then target)

You have your choice of 2 output formats: a comma-separated-value (".csv") file **and/or** a report format (".lst") file. For each file you can specify whether you want just the geographic codes, or the codes *and* the names associated with them (where applicable), or just the names.

Generate a CSV file	Generate a listing file
Just Codes (No Names) Codes and Names Just Names (No Codes)	Just Codes (No Names) Codes and Names Just Names (No Codes)

9	Process	time	for	large	areas	may	be	several	minutes.
	1 100000	CILIA	***	D-	er en		~ ~		**********

Reset I	Defaults	Run Requ	iest
following o	options furthe	r limit criteria	set above

#### Point-and-Distance Options

Specify	a point (location) and distance to b	e
used as	filter:	

Value for radius of Circ	ele or radius of largest	(III IIIIIes, u		here to specify
Ring: 4		kilometers.	)	
(See just below for link	s to help find coordinate	ates.)		
Coordinates of Point: longitude.	38.01143	degrees latitude,	92.75471	degrees
Label of Point:		(opt	tional)	

### Define Ring criteria specifying only one of the following two options:

**Either:** # of equi-distant rings (integer value between 1 and 10). Radius specified above will be divided by this to derive width of each Ring.

**Or:** Specify your own custom list of up to 10 ring radii values in ascending order (values must be greater than zero, may be fractional, and largest should equal the radius of the Circle specified above):

Links are provided here to facilitate obtaining coordinates for your location. See the HELP file

for more detailed information.

- The <u>ETAK Eagle geocoder</u> site lets you enter a street address or street intersection. It displays the coordinates as well as a long list of geographic codes (and will also draw you a map of the area about the point.)
- To get the coordinates of any ZIP code or city use Chris Stuber's Gazetteer
- To view the region of interest try his <u>Tiger Map Server</u> page.
- An alternate site for street addresses or street intersections is the Yahoo Map Server (but you'll need to see the help to find lat-long coordinates).
- View county names on state level maps, check the Census Bureau's Map Stats

**Note:** If you specify a lat-long location the variable "distance" will be added to your output. This requires that weighted centroids also be calculated (set automatically). The "distance" variable will be between the weighted centroid and the specified Point. If you specify Ring Pseudo-Geocodes then distance and weighted centroid values will *not* be calculated or stored (because weighted centroids of donuts are misleading).

#### Bounding Box Filter Option

If you want to limit processing to blocks with center points that fall in a specified rectangular area you can enter the coordinates for such a "bounding box" next.

Define the "bounding	ng box" coordinates in decin	nal degrees:	
	Northern-most		Southern-most
Latitude		Latitude	
	Western-most		Eastern-most
Longitude		Longitude	

Process time for large areas may be several minutes.

Reset	Defaults	Run Request

**NOTE:** The rest of this form allows you to specify options that will limit the geographic universe to be processed. If you just want to process the entire state(s) that you have selected then you can ignore the rest of this form and submit your request now.

### Geographic Filtering Options

You can specify any or all of 3 types of geography to limit the universe to be processed. You may, for example, only want to see a file with geography for a set of counties, or for a specific metro area (or areas), or possibly for a city (place). You can do so by entering the appropriate FIPS (Federal Information Processing Standard) codes in the text entry boxes that follow. If you need to "look up" the codes you can click on the links to the code-list files in each section.


By default, if you specify more than one kind of geography here then the application assumes that you want to "and" the selections, keeping only areas that satisfy all criteria. For example, if you specified three counties and a metro area, you would only get data based on blocks that were in **both** the counties and the metro area (i.e. the intersection of the selected areas.) To override this default and

choose geographies that satisfy $any$ (rather than $all$ ) of your select criteria CLICK HERE:
All selections made below are in addition to the state-level or distance-based filtering which you specified above
<u>County codes</u> . Enter 5-digit FIPS county codes with leading zeroes separated by blanks. You may enter 3-digit codes if you selected only one state. Your output will be limited to the counties specified.  Examples:
<ul> <li>29189 29510 17163 17119 (selects 4 counties in 2 states)</li> <li>005 017 049 (selects 3 counties from the single state selected)</li> </ul>
Metro Area codes. Enter 4-digit FIPS metro area codes with leading zeroes separated by blanks. MSA, CMSA and PMSA codes may be used (4-digit only). The 1990 definitions will be used. Your output will be limited to the metro areas specified. New England NECMA codes can <b>not</b> be used. Examples:
<ul> <li>3760 1602 (Selects Kansas City MSA and Chicago CMSA)</li> </ul>
5700 1002 (Sciects Railsas City WISA and Chicago CIVISA)
Place codes. Enter 7-digit FIPS place codes with leading zeroes separated by blanks. You can enter 5-digit codes if only one state has been selected. Your output will be limited to the official city limits of these cities as of the 1990 census.  Examples:
<ul> <li>70520 70545 70550 53780 06020 (Saginaw City, Saginaw Township North and South, Midland, Bay City, MI)</li> </ul>
Process time for large areas may be several minutes.  Reset Defaults Run Request
Top   SEDAC   UMSL UIC   FTP Archive   DDViewer   Credits   Comments and Suggestions
Last Update: 09-22-98

.....

geocorr3 3.03 Rev. 99/01/15 / Process: 23822 (OSEDA/UIC, U. of Missouri) - Run 0
Listing of Geographic Correlations


Listing	of Geograph	ic Corre	lations	
COUNTY	TRACT	RING	POP	AFACT
29029	9505.00	0.25	180 696	0.053 0.204
		0.50	696	0.204
29029	9504.00	1.00	0	0.000
29029	9505.00	1.00	1267	0.371
29029	9504.00	2.00	117	0.167
29029	9505.00	2.00	983	0.288
29029	9508.00	2.00	0	0.000
29029	9503.00	3.00	83	0.311
29029	9504.00	3.00	134	0.191
29029	9505.00	3.00	283	0.083
29029	9506.00	3.00	198	0.391
29029	9508.00	3.00	582	0.561
29029	9503.00	4.00	184	0.689
29029	9504.00	4.00	451	0.642
29029	9505.00	4.00	6	0.002
29029	9506.00	4.00	308	0.609
29029	9508.00	4.00	456	0.439



## Windsor Estates Nursing Home 3069006 1 well

The information below represents the data currently associated with the water supply layers. The well/intake number corresponds to the well/intake numbers depicted on the accompanying map. Blanks indicate missing data. This table is subject to change as additional information is acquired. Source: Missouri Department of Natural Resources, Public Drinking Water Program. Production Date: October 02, 1996

Temporary DGLS well number	. The correct well number is requested.		Production	Date: October 02	1990
Well Number	Wi				
Extended PWS #	3069006101.				
Local Well Name					
DGLS Well #	40392				
Latitude	38 1 42.1 N	WAR A STATE OF THE	TOOLSER MOVER - FOR TO TORK ART SOME LIVE SERVICE	agraphia Africania in Constitution (Constitution)	e and a state of the second
Longitude	92 46 4.6 W		*		
USGS 7.5 Quadrangle	Green Bay Terrace				
County	Camden				
DNR Region	Jefferson City				
Date Drilled	1969				
Material (C/U)	Consolidated		A Comment of the Comm		
Total Depth (ft)	600.000				
Casing Depth (ft)	400.0			M	
Casing Size (in)	6.				
Casing Type					
Screen Length (ft)					
Screen Size (in)		· 一一			
Static Water Level (ft)	165.0				
Well Yield (gpm)					
Draw Down Level					
Determination Date		, *			
Yielding Strata					
Pump Type					
Pump Level (ft)					
Capacity (gpm)					
Pump Meter (Y/N)					
Standby Power (Y/N)					
Date Abandoned					
Date Plugged				all land	
VOC detections (Y/N)	N				
Nitrate-N Level (mg/l)	N				
Chlorination (Y/N)	N				
Filtration (Y/N)	N				
GWUDISW (Y/N)					
State Approved (Y/N)			terior de A. M.	erani Paran	a salarine ful




## Linn Creek 3010471 1 well

The information below represents the data currently associated with the water supply layers. The well/intake number corresponds to the well/intake numbers depicted on the accompanying map. Blanks indicate missing data. This table is subject to change as additional information is acquired. Source: Missouri Department of Natural Resources, Public Drinking Water Program. Production Date: October 02, 1996

Well Number W2 Extended PWS # 3010471102. Local Well Name Well #2 DGLS Well# 28620 Latitude 38 2 3.7 N Longitude 92 42 36.2 W USGS 7.5 Quadrangle Camdenton County Camden **DNR** Region Jefferson City Date Drilled 1984 Material (C/U) Consolidated Total Depth (ft) 860.000 Casing Depth (ft) 528.0 Casing Size (in) Casing Type Steel Screen Length (ft) Screen Size (in) Static Water Level (ft) 104.0 Well Yield (gpm) 70 Draw Down Level 125.0 Determination Date 1983 **Yielding Strata** Pump Type Pump Level (ft) 294 Capacity (gpm) 10 Pump Meter (Y/N) Standby Power (Y/N) Date Abandoned Date Plugged VOC detections (Y/N) Nitrate-N Level (mg/l) N Chlorination (Y/N) Filtration (Y/N) GWUDISW (Y/N)

State Approved (Y/N)



## Southway Terrace MHP 3048141 I well

The information below represents the data currently associated with the water supply layers. The well/intake number corresponds to the well/intake numbers depicted on the accompanying map. Blanks indicate missing data. This table is subject to change as additional information is acquired. Source: Missouri Department of Natural Resources, Public Drinking Water Program. Production Date: October 02, 1996

to describe the street of the last	
Well Number	WI Comment of the Com
Extended PWS #	304814[10]
Local Well Name	
DGLS Well#	26629
Latitude	37 59 35.2 N
Longitude	92 42 56.5 W
USGS 7.5 Quadrangle	Decaturville
County	Camden
DNR Region	Jefferson City
Date Drilled	1970
Material (C/U)	Consolidated
Total Depth (ft)	550.000
Casing Depth (ft)	350.0
Casing Size (in)	
Casing Type	Steel e.g.
Screen Length (ft)	
Screen Size (in)	
Static Water Level (ft)	175.0
Well Yield (gpm)	
Draw Down Level	
Determination Date	
Yielding Strata	
Pump Type	Submersible
Pump Level (ft)	
Capacity (gpm)	
Pump Meter (Y/N)	
Standby Power (Y/N)	
Date Abandoned	
Date Plugged	
VOC detections (Y/N)	N
Nitrate-N Level (mg/l)	N
Chlorination (Y/N)	N
Filtration (Y/N)	N
GWUDISW (Y/N)	$\mathcal{M}_{\mathcal{M}}$